
# GOVERNMENT OF INDIA DEPARTMENT OF ARCHAEOLOGY CENTRAL ARCHAEOLOGICAL LIBRARY CLASS New Acc. 34731 CALL No. 330.934 Das





# ECONOMIC HISTORY OF ANCIENT INDIA.



34731

BY

# SANTOSH KUMAR DAS, M. A. (Hist & Econ.)

PROFESSOR, NARASINHA DUTT COLLEGE, HOWRAH, AUTHOR OF "THE EDUCATIONAL SYSTEM OF THE ANCIENT HINDUS" AND "THE LEAGUE OF NATIONS".

Ref 734:01

SECOND EDITION

CALCUTTA 1944.

# Opinions on Prof. S. K. DAS'S

# THE ECONOMIC HISTORY OF ANCIENT INDIA

#### FIRST EDITION

- 1. Professor J. W. GARNER, PH. D., D.L., of the University of Illinois, U.S.A.: "A work of unusual scholarship and of great historical value."
- 2. Dr. JULIUS JOLLY of the University of Wurzburg, Germany :-

"Valuable work .. The numerous Sanskrit quotations show perfect acquaintance with Sanskrit literature ..... The book contains a very thorough and a very lively account of the economic development of Ancient India."

- 3. Professor E. WASHBURN HOPKINS, Yale University, U. S. A.;—
  "An excellent resume of what can be gleaned from the Ancient texts."
- 4. Dr. V. LESNEY of the Czech University of Prauge, Czecho-Slovakia:—
  "The book is written in a nice methodical way and the Western Indologists should welcome such Indian competition in the field. From start to finish it is evident that the author has thoroughly mastered his subject."
  - 5. Dr. SNOCH HUR GRONZE of the University of Leiden, Holland :"A valuable contribution to the elucidation of a difficult historical problem."
  - 6 Dr. RUDOLF OTTO of the University of Marburg, Germany: -- "Extra-ordinarily interesting work."
  - 7. Dr. ADOLPHE FERRIERE of the University of Geneva, Switzerland :- "Beautiful work."
- 8. Dr. A. B KEITH of the Edinburg University, Scotland :—
  "It contains much valuable material, carefully collected and presented in an interesting and clear manner."
  - 9. Dr. H. JACOBI of the University of Bonn, Germany :-
- 10. The AMRITA BAZAR PATRIKA: -Prof. Das has exhibited an uncommon degree of critical and analytical skill and the result has been the production of a book of rare worth, sure to prove interesting as well to the University students as to the general public."

#### DEDICATED

TO

THE SACRED MEMORY OF

THE LATE SIR ASHUTOSH MUKHERJI

IN HUMBLE APPRECIATION OF

ALL THAT HE HAS DONE

FOR THE CAUSE OF

ANCIENT INDIAN HISTORY AND CULTURE.

water atyra BSI-11-3-53

CENTRAL ARCHAEOLOGIGAL
LIBRARY, NEW DELAN.
Acc. No. 34731...
Date. 25 9 195.8...
Call No. 330: 934

# New AC 34731

Date No. 934 P.DE.

## CONTENTS

Introduction	- ***	***	-	IX
Chapter I.		100		
The Palæolithic Age	***	-0.0	***	1
Chapter II.				
The Neolithic Age	***	***	***	3
Chapter III.				
The Copper Age			***	7
Chapter IV.				
The Rgvedic Age	400	***		22
Chapter V.				
The Brahmana Period	***	***		81
Chapter VI.				
The Age of Gautama Buddha				179
		***	***	119
Index I. Sources with the Subjects	***			281
	***	***	***	201
Index II. Subjects				994
	***	***	***	324
Index III. Proper Names				995
Title I Toper Names	***	0.00	***	335

#### PREFACE

At the beginning of the session 1922-23 I delivered a series of lectures on "The Economic History of Ancient India" to the students of the Kalikātā Vidyāpīṭha and as a token of my humble connection with that noble institution I published those lectures in January 1925.

In bringing out this second edition I have necessarily to make substantial additions and alterations so much so that the work has to be published in two volumes. I have avoided on principle all theoretical disquisitions throughout this work. It has been my aim rather simply to present the facts in a connected manner with a view to illustrate, as far as possible, the gradual development of economic progress from the earliest times. I have always indicated the sources of my information in order that my conclusions may be tested with reference to the authorities on which they are based. In this connection I beg to acknowledge the invaluable help and guidance I have received from the researches of Professors Zimmer, Macdonell and Keith, Drs. Fick and Rhys Davids and Professor Hopkins who have dealt with the economic data on the basis respectively of the Vedas, the Jātakas and the Epics.

I take this opportunity of expressing publicly my thanks to those savants and scholars who have favoured me with critical appreciation of the first edition of this work and to the authorities of the Benares Hindu University and the University of Calcutta who immediately after its publication kindly recommended it for introduction into their Post-graduate classes in Ancient Indian History and Culture.

Prafulla Chandra College
Bagerhat
The 3rd July 1937.

SANTOSH KUMAR DAS.

# 3 12 11 83

a faction of the seasons with the season in par James Markey is the

#### INTRODUCTION

The starting point of all human activity is the existence of wants. To satisfy hunger and thirst, to obtain shelter and to provide clothing were the chief aims of primitive man and constitute even to-day the motor-forces of all society. As man develops, his wants grow in number and refinement. However civilised he becomes, his material welfare is the foundation on which the entire structure of his larger life is built up. Ever since his creation man has waged an unceasing struggle not only to tree himself from the vagaries of Nature but also to modify and utilise the lorces of Nature to his own account. Any one, therefore, who wishes to engage in the study of human society can hardly neglect man's relations to his material environment, so essential to his life and progress. A study of this material basis will also enable him to disclose the influence of forces of the moulding of the future.

Yet strangely enough this material or economic basis of human exisence hardly drew the attention of historians except incidentally. With ongenital human weakness for the uncommon and the extraordinary, they enerally emphasised the cataclysmic factors in society like war and exagerated the importance of the Supermen, the Heroes of History. As Dr. Price says " Political changes and constitutional developments, the rise and all of dynasties and statesmen, the vicissitudes of military and naval onflict filled the canvas and presented tempting opportunities for able raftmanship and rich contrasted colouring." Thus the normal and actual levelopment of human society, through the arts of peace and co-operation has been overshadowed by the lurid clouds of war and political strife. If, herefore, we want to re-establish History on her only true pedestal of truth and humanity, every individual writer and teacher of history must mmediately start the work of expiation and search into the intimate relation that subsisted between Man and the surrounding Nature which excrted the most powerful influence on the evolution of human life and thought.

As regards this material environment we must take into account the physical features of a country, its geographical position and climate, the

nature of its soil, its productive capacity, the conditions of its food supply etc., and before we proceed to a study of the economic history of Ancient India a consideration of these with special reference to India must engage our attention so that we may see to what extent man in Ancient India was permanently affected by the material basis of his existence.

According to Geologists India was represented in Palæozoic times by the central plateau and the northern fringe of the Aravalli mountains. To its north lay a shallow sea covering the area of modern Afganisthan, Rajputna and the Himalayan regions. In Tertiary times the Gondwana beds were formed extending over Assam and the Eastern Himalayas and this nucleus of India was connected with the continent of Africa by a stretch of dry land. At this time as a result of volcanic cataclysms the Gondwana continent was broken up and an area of 200,000 square miles was covered with lava, thus resulting in the formation of the Deccan. In the Pliocene period due to volcanic activity there commenced the great upheaval to the north, resulting in the formation of the Himalayas. The deterioration of rock on both sides due to the action of rain and glaciers, the collected alluvium of ages brought down by the hill-torrents filled up in course of time the shallow gap and thus gradually the river systems of the Indus and the Ganges were formed and India attained roughly her present shape.

Thus formed India became remarkable for her natural boundaries, being surrounded on all sides by mountains and seas. In ancient times the sea was a formidable barrier against foreign invasions. Crafts from Egypt or Mesopotamia, from China or Java could come with favourable wind to trade with India but the idea of conquest could not be conceived. For the Arabian Sea or the Bay of Bengal was not very easy to cross and there was no country in the East or the West which had a sufficiently strong fleet to undertake the conquest of India. The mountains no doubt contained passes but they could be crossed with difficulty, as most of them were very narrow, high and therefore covered with snow during greater part of the year. The narrowness of these passes made it impossible for barbaric hordes to come in sufficient numbers to overwhelm, far less to obliterate, the settled civilisation of previous ages. Thus her natural boundaries which

made India virtually immune from foreign invasions not only rendered the Indian civilisation at once original and unique in character but also allowed time to her socio-economic institutions to become deep-rooted and in a great measure able to withstand the modifying influences of later invaders.

The socio-economic life of man is equally influenced by the climate and configuration of his habitat. His food supply, which depends on the climate and soil influences him directly and regulates his efforts. Moreover, climate influences his capacity for labour. People of warmer regions are less active and vigorous than men of cooler regions. The Indo-Aryans of the Vedic Age when they lived in the cooler climate of the Punjab and U. P. were famous for their martial prowess and spirit of adventure which were for a long time kept alive by the necessity of holding their own against the non-Aryans. But when after the resistance of the non-Aryans was broken they had settled in the Gangetic plain for a certain amount of time the enervating influence of the warm climate told upon them and made them languid and fond of repose and thus unable to follow habitually any standard of good workmanship or to soar always the height of workmanship of which they were capable. In warmer latitudes early marriages are always universal and hence the rate of birth is very high and consequently we find 'a low respect for human life'. For this reason Indo-Aryan society of the Vedic Age is not marked by early marriage which grew up along with the pernicious custom of infanticide in the warmer parts of the country. Men of warmer regions require simple food, clothing and housing while people of cooler regions require strong drink and nourishing food to sustain them and such clothing and dwelling house as may protect them against weather. Hence in the comparatively drier regions the entrance and enclosure aspects of the dwelling house were more prominent and the references to these features and their figurative use accordingly occur in texts like the Rgveda which were mainly of Midlandic origin. With the march of Aryan arms into the rainflooded lower Gangetic valley the roof naturally had to be built up carefully and we therefore find much care bestowed on the construction of the thatched roof in the house-construction outlined in the Atharvaveda, which is pre-eminently a book of the Angirasas, who are definitely located in and

associated with the very same lower Gangetic provinces in Pauranic tradition. For similar reasons the Vedic Aryans who lived in the cooler climate of the Punjab and U. P. wore dress mostly made of wool and ate food in which wheat, wine and meat formed a principal part. With the progress of Aryan arms into the warmer eastern parts of the country we find a growing dislike for wine and meat, specially beef and the substitution of rice for wheat as food and of linen, cotton and silk for woolen dress.

Owing to the rigours of climate, however, the realms of snow in the Himalayan regions long remained devoid of culture and economic progress while in the rainless and very hot climate of the sandy desert of Rajputna man long remained a semi-nomad moving from place to place in search of good pasturage for his flock. In the Indo-Gangetic plains, on the other hand, the genial climate (which is 'milder than the climate of most other countries in the same latitude'), the rich soil and the large navigable rivers have produced their natural effects. Progress of agriculture became rapid and settled life began very early with all its concommitants-land system, village system, etc. Prosperous cities sprang up on banks of rivers which afforded every facility for trade and communication while the abundance of agricultural and mineral wealth led to an early growth of industry, and the navigability of the rivers coupled with a long coast-line gave birth to maritime and trading activity. Under the glaring tropical Sun the moist soil became fertile beyond imagination, producing for man in lavish abundance all that he needs for life. But it also subdued the mind with the overwhelming force of its fecundity. It could not have been otherwise than that the exuberance of tropical Nature should have captivated the mind of man, stirring up his imagination, filling it with brilliant designs or patterns for his handiwork and fostering in him a love of contemplation and luxurious case. Indeed the genial climate and the rich soil bringing the means of subsistence within easy reach left men sufficiently at leisure to develop the higher arts of civilisation.

Climate determines not only the productive activity and standard of living of man but also the productivity of his fields and the nature and amount of his harvests. Wheat, for instance, which requires a cool climate

is the principal crop of the Panjab while rice which flourishes in warm but damp regions is the chief crop of the lower valley of the Ganges. Cotton, hemp etc., have likewise their localised area in keeping with climatic causes. Climate thus exercises a direct influence on agriculture and an indirect one on industry.

India has been blessed with different varieties of soil which combined with the great variety of physical features, climate and rainfall enable her to produce almost every kind of vegetable life, so that agriculture naturally became the mainstay of her people from time immemorial. Among the four important varieties of soil in India the alluvial soil is usually rich in phosphoric acid, potash, lime and magnesia and is suitable for the growth of kharif and rabi crops. The trap soils which occupy the next place of honour produce, when porous and light as on uplands and hill-slopes, millets and pulses and when thick and more fertile as in the low lands, cotton and wheat besides millets and pulses. Regar or black cotton soil, supposed to be of volcanic origin is highly compact, tenscious and retentive of moisture and is therefore particularly favourable to the growth of cotton and rabi crops though kharif crops also are conveniently grown in many cases. Crystalline soils which widely differ in different provinces agree in being generally deficient in nitrates and phosphoric acids. "The clayey and brownish loams of the low lands are however fertile" and favourable to the growth of a great variety of crops, principal among them being rice.

India is equally famous for her vast forest areas. The Vedas speak of forests repeatedly. The Rāmāyaṇa describes at length the forest region to the east and south of Mithilā and speaks of the Paāchavaṭī forest and the celebrated Daṇdakāraṇya. In the Buddhist literature we read of the Andhavana of Kośala, the Sitāvana of Magadha, Pacīnavaṇṣa-dāya of the Sākiya territory and of the Mahākalinga forest. Besides helping the progress of agriculture by storing up rain-water in the soil and by keeping the atmosphere sufficiently cool so as to cause the fall of rain when rain-bearing clouds pass over them, these forests supplied an essential part of the economic needs of the people. They provided them with wild rice (nīvāra), esculent vegetables, fuel and with the materials for the construction of houses, chariots, boats, domestic furniture, sacrificial implements and

animals. They were a constant source of supply of medicinal herbs and plants as well as of sacrificial grass. They also supplied the people with aloe, bdellium, spikenard, resin, comphor, sandalwood, lac, hides, fruits and honey.

India is also blessed with the soil and climate capable of bearing animals useful to man. From the economic point of view the domestic animals are more useful than wild ones. Of the former horses and elephants were used for riding and transport purposes, both in peace and war; asses, mules, bullocks and buffaloes were used as beasts of burden or in drawing waggons while the horse and the bullock helped in the cultivation of the soil. The cow, sheep and goat supplied the people with milk or with flesh and hides. The cow-dung was used as manure or as fuel in the form of cow-dung cakes while the wool of the sheep and the goat was made into blankets. The people obtained a supply of musk from the musk-deer, chamaras from the tail of the yak and skins from the wild boar, the wild deer and the black antelope. The tusks of wild elephants, skins of the tiger and the lion and the horn and bones of some of the animals were also used for various purposes.

The Greeks when they came to India were struck with the mineral wealth of India whose importance in the economic development of the country could never be exaggerated. Gold was obtained by Indians even in prehistoric times not only from river-washings but also from gold-bearing quartz and by the end of the Vedic period they became familiar with zinc, lead and iron in addition to gold, silver, copper and tim. In the words of Megasthenes "The soil too has underground numerous veins of all sorts of metals, for it contains much gold, silver, copper and iron in no small quantity and even tin and other metals which are employed in making articles of ornament and of use as well as the implements and accountrements of war" (Bk. I. Fragment 1. Cf. Diodorus II. 36). Diamond and salt mines existed and varieties of precious stones and oyster pearls from pearl-beds on the sea-coast fetched a high price in the western markets.

To crown all, India occupied a position of great advantage, almost at the centre of the Eastern Hemisphere and at the head of the Indian Ocean, so that her trade-routes radiated in all directions—westwards for Arabia and Egypt, s ath for Ceylon, south-west for south Africa, and south-east for the Malaya Archipelago and the Far East. No doubt the Indian coast-line is very poor in identations and land-locked bays but in ancient times when the size of trading vessels was not so large as in our days a large number of fair weather anchorages were available as is proved by the later evidence of the Periplus of the Erythrean Sea. The ancient mariners took advantage not only of the monsoons but also of the surface currents or drifts which even now affect the coasts of India. Thus both the East and the West came to be the theatre of Indian commercial activity and gave scope to her artisans and merchants. As Sir William Hunter well remarks " From the earliest days India has been a trading country. The industrial genius of her inhabitants even more than her natural wealth and her extensive sea-board, distinguished her from other Asiatic lands. In contrast with the Arabian peninsula on the west, with the Malaya peninsula on the east or with the equally fertile empire of China, India has always maintained an active intercourse with Europe" (Indian Empire, third edition, p. 958). As a consequence she had the balance of trade clearly in her favour, a balance which could only be settled by the export of precious metals from the countries, commercially indebted to her. For a genial climate and a fertile soil, coupled with the industrial genius of her people and a judicious distribution of land among all classes made India virtually independent of foreign nations in respect of necessaries of life while the ideal of simple living and high thinking must have rendered the secondary wants of the mass of the people very limited in number. Thus has she been for many centuries the final depository of a large portion of the metallic wealth of the world. It was this flow or "drain" of gold into India which so far back as the first century A. D. was the cause of alarm and regret to Pliny. It was probably also the same flow of gold into the country that even earlier still in the fifth century B. C. enabled the small Indian satrapy of Darius to pay him 360 Eubolic talents of gold, worth fully £ 1,290,000 and constituting about one-third of the total bullion revenue of the Asiatic provinces (Herodotus III).

animals. They were a constant source of supply of medicinal herbs and plants as well as of sacrificial grass. They also supplied the people with aloe, bdellium, spikenard, resin, comphor, sandalwood, lac, hides, fruits and honey.

India is also blessed with the soil and climate capable of bearing animals useful to man. From the economic point of view the domestic animals are more useful than wild ones. Of the former horses and elephants were used for riding and transport purposes, both in peace and war; asses, mules, bullocks and buffaloes were used as beasts of burden or in drawing waggons while the horse and the bullock helped in the cultivation of the soil. The cow, sheep and goat supplied the people with milk or with flesh and hides. The cow-dung was used as manure or as fuel in the form of cow-dung cakes while the wool of the sheep and the goat was made into blankets. The people obtained a supply of musk from the musk-deer, chamaras from the tail of the yak and skins from the wild boar, the wild deer and the black antelope. The tusks of wild elephants, skins of the tiger and the lion and the horn and bones of some of the animals were also used for various purposes.

The Greeks when they came to India were struck with the mineral wealth of India whose importance in the economic development of the country could never be exaggerated. Gold was obtained by Indians even in prehistoric times not only from river-washings but also from gold-bearing quartz and by the end of the Vedic period they became familiar with zinc, lead and iron in addition to gold, silver, copper and tin. In the words of Megasthenes "The soil too has underground numerous veins of all sorts of metals, for it contains much gold, silver, coppor and iron in no small quantity and even tin and other metals which are employed in making articles of ornament and of use as well as the implements and accountrements of war" (Bk. I. Fragment I. Cf. Diodorus II. 36). Diamond and salt mines existed and varieties of precious stones and oyster pearls from pearl-beds on the sea-coast fetched a high price in the western markets.

To crown all, India occupied a position of great advantage, almost at the centre of the Eastern Hemisphere and at the head of the Indian Ocean, so that her trade-routes radiated in all directions—westwards for Arab'a and Egypt, s uth for Ceylon, south-west for south Africa, and south-east for the Malaya Archipelago and the Far East. No doubt the Indian coast-line is very poor in identations and land-locked bays but in ancient times when the size of trading vessels was not so large as in our days a large number of fair weather anchorages were available as is proved by the later evidence of the Periplus of the Erythrean Sea. The ancient mariners took advantage not only of the monsoons but also of the surface currents or drifts which even now affect the coasts of India. Thus both the East and the West came to be the theatre of Indian commercial activity and gave scope to her artisans and merchants. As Sir William Hunter well remarks " From the earliest days India has been a trading country. The industrial genius of her inhabitants even more than her natural wealth and her extensive sea-board, distinguished her from other Asiatic lands. In contrast with the Arabian peninsula on the west, with the Malaya peninsula on the east or with the equally fertile empire of China, India has always maintained an active intercourse with Europe" (Indian Empire, third edition, p. 958). As a consequence she had the balance of trade clearly in her favour, a balance which could only be settled by the export of precious metals from the countries, commercially indebted to her. For a genial climate and a fertile soil, coupled with the industrial genius of her people and a judicious distribution of land among all classes made India virtually independent of foreign nations in respect of necessaries of life while the ideal of simple living and high thinking must have rendered the secondary wants of the mass of the people very limited in number. Thus has she been for many centuries the final depository of a large portion of the metallic wealth of the world. It was this flow or "drain" of gold into India which so far back as the first century A. D. was the cause of alarm and regret to Pliny. It was probably also the same flow of gold into the country that even earlier still in the fifth century B. C. enabled the small Indian satrapy of Darius to pay him 360 Eubolic talents of gold, worth fully £ 1,290,000 and constituting about one-third of the total bullion revenue of the Asiatic provinces (Herodotus III).



# THE ECONOMIC HISTORY OF ANCIENT INDIA.

#### CHAPTER I.

# The Palceolithic Age.

"The pleasant belief of poets that primitive man enjoyed in an earthly paradise a golden age free from sin, sorrow, want and death finds no support from the researches of sober, matter-of-fact science. On the contrary, abundant and conclusive evidence proves that the earliest man whether in India, Europe or elsewhere were rude savages, cowering for shelter under rocks or trees or roughly housed in Caves and huts."1 He does not know how to pasture cattle or to cultivate the land. He does not know private property in land and division of labour. He was ignorant of any metal and even of pottery. He was dependent for tools or weapons of all kinds on sticks, stones and bones. The sticks of course have perished and the bones have mostly shared the same fate on account of the white ants. The stone implements laboriously shaped by chipping into forms suitable for hammering, cutting, boring and scrapping are found in large numbers in many parts of India. Apart from the Burma find containing stone implements "showing distinct traces of having been worked by man" the Godavari flake furnishes "evidence in India of the existence of man at a much earlier peried than Europe."8 According to Obermaier the Godavari flake was probably used in scraping the bark from branches and smoothing them down into poles; while the rough Coup-de-poing type as we get in Nerbada is well adapted to dividing flesh and dressing hides. The Godavari and Nerbada finds are generally accepted as Pre-Chellean to indicate their Chronological Correlation with Europe.

Dr. Keith in the Records of the Geological Survey, Vol. XXXVII. p. 102.

<sup>1</sup> Oxford History of India - Vincent A. Smith. p. 1.

<sup>&</sup>quot; Mr. H. F. Blanford in the Proceedings of the Asiatic Society of Bengal, 1867, p. 144.

Osborn in his Men of the Old Stone Age, 1918, pp. 129-30 dates the Pre-Chellean industry at 125,000 years.

At the outset the occurrence of rocks suitable for fashioning tools and weapons no doubt played a great part in the selection of habitation sites by early Palœolithic Indians. Quartzine stone is specially suitable for the making of tools and weapons and therefore they mustered strong in the Cuddapah, Guntur and Nellore districts and the neighbouring tracts of Madras where quartzite abounds. As large migrations ceased and comparatively settled life began, they developed cesthetic instincts in the choice of colours and progressed in craftmanship. A distinct progress is discernible from the Burma find to the Godavari flake which is "formed from a compact light-coloured agate"s and the more southern the find the better the finish. The proximity of rivers to rocks highly suitable for implements also helped them in the selection of habitation sites. The palceoliths obtained from Dhenkenal, Angul, Talchir, Sambalpur, Chakradharpur, Nuagardh, Ghatsila, Morhana Pahar, Partabgunj and Jubbalpur unmistakably prove that the banks of the Suvarnarekha, the Sangai, the Bijnai and their affluents flowing eastwards as well as other rivers draining into the Ganges or its affluents north-eastwards from high plateaux were as much centres of palœolithic culture as the South Indian rivers. Probably also in some cases Palœolithic settlements sprang up near by lakes. At Heera and Chik Mulungi, about twenty miles above Kaira a large variety of weapons has been found which belong to this age.

In the Billa Surgam Caves of Karnaul at least two hundred bone weapons and implements have been found. Awls, many kinds of arrowheads, small daggers, scrapers, chisels, gough, wedges, axe-heads etc., form part of the various kinds of things which bear definite traces of being worked up by man. Definite proof exists of the use of stones as well by these Cave-dwellers. Thus in the Cathedral Cave of Billa Surgam 'two or three bones were found showing distinct traces of having been scraped with a hard and sharp implement the marks being such as would be made by a might have been smoked before being taken as the presence of the cinder plainly brings out the existence of fire.

Dr. Oldham in the record of the Geological Survey of India, Vol. I. p. 65.

### CHAPTER II.

# The Neolithic Age.

In the next stage of human advance, men were for a long time still ignorant of metals except gold and were consequently obliged to continue using stone tools and weapons. The stone implements and weapons were ground, grooved and polished and thus converted into highly finished objects adapted to diverse purposes. Their main types are: (1) grooved axe with pecked groove; (2) celt with (a) blade thick near edge, (b) with long slender form, (c) with nearly round section, with nearly diamond section, with nearly rectangular section; (3) wedge-form; (4) chisel-form; (5) chipped shade; (6) pestle; and (7) hammer-stone. These can be studied to special advantage in the Bellary district where Fraser discovered in 1872 the north Bellary and Kapgallu Neolithic remains. The north-east slope of the hill here was apparently a Neolithic factory-site and the largest manufacturing industry of polished stones with tools in every stage of manufacture flourished there.

The Neolithic Indians were no longer mere hunters but cultivators as well, as the abundant varieties of mealing stones, corn-crushers and pounding stones prove. In fact, the people were rather vegetarian than carnivorous like the preceding men of the Old Stone Age, as the peaceful implements far out-number the weapons for war.

By this time many of them learnt to live in thatched primitive huts as the presence of straw in the cinder-mounds clearly prove. In their articles for domestic use they showed great fascination for colour. Their knives, saws, drills and lancets were made of beautiful chert, agate chalcedony, blood-stone and rock-crystal and went to make up the comforts of their economic household.

The Neolithic Indians used pottery which was "dull-coloured and rough-surfaced with but little decoration." The finds are distributed

Bruce-Foote in Notes on the Ages and Distribution of the Foote Collection of Indian Pre-historic and Prote-historic Antiquities, Madras, 1216, p. 34.

through the district of Anantapur, Cuddapah, Kurnool, Tinnevelly, Baroda, Kathiwar, Beluchisthan and other regions. Some of the Bellary potteries were "impressed with finger-tips five or four or two in number. A note worthy form is vessels pierced with a certain number of holes in two pieces of grey pottery from the same place four or ten in number. Closely associated with these are forms analogous to the fabric-marked pottery of which one has been reported in Travancore stape and to which class may be assigned a large number of those described as impressed with fillets of the simplest type which appear to have been so common in Neolithic India. An equally common form is the grooved pattern, two, three or sometimes even fourteen lines incised which is often varied by impressed or raised ring designs ,"7

Gold is obtained directly from quartz veins and it is well knewn that Palceolithic Indians were very fond of milk-white quartz. "Many old workings have been met with along with outcrops of the veins in Chota Nagpur with large number of grooved stones which had been used for crushing and grinding the quartz."8 The remains of ancient workings are also found in the Wynaad district of Malabar, Nilgiri and in Mysore. A Neolethic settlement of gold miners existed at Maski in the modern state of Hyderabad where the gold-miners' shafts were the deepest in the world. Its yellow colour was the cause of its early use and a like case is of several finely coloured gem-stones used in the making of beads which were used for ornamental as well as ritual purposes. 10

These primitive peoples were not altogether devoid of the artistic sense as the rock paintings near Singanpur in the Raigarh district of the Central Provinces seem to prove. "The pigment was probably applied by means of bamboo or reed brushes, the implement most likely

<sup>\*</sup> Professor Panchanan Mitra in Pre-historic India, Second edition, 1927, pp. 399-400.

La Touche, Bibliography of Indian Geology, Article on " Gold ."

<sup>·</sup> Gowland on Metals in Antiquity in the Journal of the Royal Anthropological Institute, Vol. XVIII. p. 260.

To Bruce-Poote has pointed out that the Neolithic settlement in the Bellary district gradually acquired the knowledge of iron-making industry as some small pottery (tuyere) suitable for protection against direct flame action of the nozzle of a small bellows was found in the Neolithic stratum.

used being a stiff blunt point, rather than a brush and the treatment of some of the painted surfaces seems to prove this ... The drawings are mostly executed in flat washes of one colour, although there are certain traces of shading and modelling, but these are very indistinct and barely discernible. The soft effect of the outline of the paintings may be due to age, or to the porous nature of the rock having absorbed the pigment. The subjects are (a) hunting scenes, (b) groups of figures, (c) picture-writing or hieroglyphics and (d) drawings of animals, reptiles, etc ...... The chief artistic feature of these Raigarh paintings lies in their spirited expression and spontaneity of treatment. A strong family likeness may be noticed between these cave paintings and the patterns on what is called the "cross-lined" pottery of pre-historic Egypt. In these the men are reprensented in the "triangular style", a method of drawing adopted by many primitive races of ancient and modern times."11 Equally interesting are the no less than twenty groups of figures of birds and beasts executed on rocks in the Neolithic site of Kapgallu in the Bellary district found by H. Knox18 and the cave-paintings in the Kymore ranges discovered by John Cockburn, 18

No less striking are the series of sculptures occurring in the Edakal Cave, Wynaad. "The most interesting features of the sculpture are the frequent human figures with peculiar headdress. There are several rather indistinct figures of animals. The usual Indian symbols are of frequent occurrence, s.g., the swastika and specimens of the familiar circular 'sunsymbols'. There is evidence also of magic squares." That they belonged to the Neolithic times may be judged from the find of a fragment of a well-shaped and polished celt from the place. To the same cultural horizon, at least so far as the style was concerned, belonged a group of rock-carvings discovered by Professor Panchanan Mitra and party in the

<sup>11</sup> Mr. Percy Brown's Notes on the prehistoric care paintings at Raigarh in Prof.
Panchanan Mitra's Prehistoric India, pp. 464-65, 467-68.

<sup>22</sup> Bruce-Foote in Notes on the Ages, etc. pp. 87-89.

<sup>18</sup> Journal of the Royal Asiatic Society, 1889, New Series, Vol. XXXI, pp. 89-97

<sup>14</sup> F. Fawcett in Indian Antiquary, Vol. XXX (1901) p. 413.

Maubhandar village of Singhbhum. 15 That they belonged to Neolithic times may be judged from the find of a Neolithic axe from the place.

The Neolithic Indians learnt the use of graves which have been discovered by John Cockburn in the Mirzapur district, U. P. 16 The tombs were surrounded by stone circles. Many pre-historic cemetries exist in the Tinnevelly district along the coast of the Tāmraparņī river, the most ancient seat of the pearl and conch-shell industry. This connection between the early settlements on the Tāmraparņī river and the pearl-fishery is not an isolated fact. Professor Elliot Smith 17 rightly observes: "Ancient miners in search of metals or precious stones or in other cases pearlfishers had in every case established camps to exploit these varied sources of wealth and the megalithic monuments represent their tombs and temples."

<sup>15</sup> Professor Panchanan Mitra's Prehistoric India pp. 201-202.

<sup>14</sup> Imperial Gazetser, Vol. II. pp. 95-96.

<sup>18</sup> Manchester Memoirs, Vol. LX. Part I, 1915, p. 29 of reprint.

## CHAPTER III.

# The Copper Age.

As the Neolithic Age gradually passed away in Northern India, it appears to have given place not to an Age of Bronze as it did in most parts of Europe but to one of Copper. In Southern India on the other hand, stone tools were superseded directly by iron without any intermediate step.18 Six bronze weapons of which three are harpoons, one a celt, one a spearhead and the last a sword have been noticed by Vincent Smith and no less than 123 bronze objects are recorded by Mr. Rea and we find not quite a small number in the Patna Museum. But all these were used as adornments or mere exotics. Among the Copper Age antiquities are bare and shouldered celts, harpoons, spear heads both plain and barbed, axe-heads, swords and an object suggestive of the human shape. The last mentioned as well as some of the swords which are remarkable for their excessive weight and the form of their handles may have been used for cult purposes. One hoard of these implements which came from Gungeria in the Central Provinces contained as many as 424 specimens of almost pure metal, weighing in all 829 pounds besides 102 ornamental laminal of silver. Such a collection comprising as it did, a variety of implements intended for domestic and other purposes affords evidence enough, as Dr. Smith has remarked, that their manufacture was conducted in India on an extensive scale; while the distinctive types that have been evolved and are represented both in this and other finds connote a development that must already have extended over a long period, though at the same time, the barbed spear-heads and harpoons and flat celts manifestly copied from neolithic prototypes bespeak a relatively high antiquity. The presence of silver ornaments in the Gungeria hoard has suggested doubts as to its remote date but there seems little reason for assuming that a race familiar with the difficult metallurgical processes by which copper is extracted from its ores were incapable of smelting silver from the rich argintiferous galenas which occur in various localities.

The Copper Age and the Pre-historic Bronze Implements of India by V. A. Smith in the Indian Antiquary, Vol. XXXIV, p. 229f and Vol. XXXVI, p. 53f.

Information of equally fascinating interest to the student of economic history is furnished by the sepulchral remains found in the Tinnevelly, Kurnool, Coimbatore and Anantapur districts as well as in the Nizam's dominions. The smaller earthen vessels found in the burial sites at Adichanallur in Tinnevelly elosely resemble objects of pre-historic pottery found in Egypt and many exhibit a characteristic red and black polished surface, which was the result of friction and not of a true fused glaze. It is interesting to find rice husks in many of these earthen utensils. The iron articles include swords, daggers, spear-heads, agricultural implements resembling the modern "mammutti", tridents, peculiar "hangers" probably used fer the suspension of iron saucer lamps of which several have been found. Though much fewer in number the bronze articles are executed with higher skill than those in iron and comprise objects like scent-bottles, rings, bangles and bracelets. There are sieves in bronze in the form of perforated cups fitted into small basins. The only objects discovered in any of the precious metals are oval front lets of gold leaf. In Kurnool burial sites 20 no stone or metal implements or weapons or beads or jewelleries have been found. The only objects obtained are domestic vessels made of a buff-coloured pottery, neatly turned on a wheel and well-baked. There are also large food and water jars of a deep red colour, glazed and ornamented with incised lines and a few simple raised mouldings. The sepulchral remains in Coimbatore 1 contain pottery, domestic vessels, a few beads , corroded iron implements such as knives and spear blades. Most of the tombs of the Anantapur district are provided with circular ring of stones all round and are of the usual rectangular shape, with four stone-sides and a heavy capstone above. A circular hole laboriously cut through one of the solid side-slabs was possibly intended as a passage for the soul on its return to earth. Though the Egyptian process of embalming appears to have been unknown, similar care was taken to preserve the remains of the

<sup>19</sup> Mr. A. Rea's Report of the Archeological Survey of India, Southern Circle, 1902—1903 pp. 111—140.

Longhurst's Report of the Archœlogical Survey of India, Madras, 1914-1915 pp. 39-41.

N. J. Walbouse's Notes on the Megalithic monuments of Coimbatore district,
Madrae in J. R. A. S., New series, Vol. VII.

dead by placing them in earthen jars or urns, carefully sealed with clay; while the almost cyclopean nature of the construction of some of the tombs rival those of Egypt in point of durability. It is equally worthy of note that tombs of this kind are only found in Southern and Western India which seems to point to western influence.<sup>22</sup> The sepulchral remains discovered by Dr. Hunt in the Nizam's dominions<sup>23</sup> include potteries, some of which bear marks closely resembling early forms of the "ka" mark of Egypt, dishes, bells and ornaments made of copper as well as weapons, arrow-heads, knives, spears, axes, sickles and tridents made of iron.

Having regard to this development of industry it seems desirable to say a few words with regard to the condition of currency that may have prevailed in this country before the advent of the Aryans. "I can quite imagine some doubt crossing the minds of most of my readers" says Professor D. R. Bhandarkar "as to how I could even surmise the state of currency in pre-vedic India. But what Professor Ridgeway has done in regard to the pre-historic or proto-historic currency of Greece can also be attempted on a modest scale in regard to India, provided we follow his method which is typically the anthropological method." It is possible to study the various kinds of currency in use among the savage tribes of various stages of civilisation and compare them to the similar ones that were prevalent in India. Now the earliest stage of civilisation is taken to be the Hunting stage. No form of currency belonging to this stage, such as skins of hunting animals is known to us from any composition of the Vedic period or from any other source. As the Hunting age passes to the Pastoral and animals are domesticated, the animal itself, not its skin, becomes the unit of value. The most common of such animals in India is the cow which is found mentioned in the Rigveda. Thus there is a hymn in this Veda 24 where Indra i.e., his image is offered as a fetish

Longhurst's Report of the Archeeological Survey of India, Madras, 1912—1913, pp. 57L

<sup>\*\*</sup> E. H. Hunt's Hyderabad Cairn barials and their significance in the Journal of the Royal Anthropological Institute, Vol. LIV. 1925, pp. 140—156; F. J. Richards' Note on some Iron Age graves in North Arcot district, Ibid, pp. 157—165.

<sup>\*\*</sup> IV. 24, 10.

for ten cows and another<sup>25</sup> where Indra is considered to be so invaluable that not a hundred, a thousand or a myriad of cows is thought to be a proper price. As the Pastoral develops into the Agricultural stage, a number of agricultural products come to be used as currency. It is in this agricultural stage that commerce is found to develop itself and a greater number of objects are found capable of being used as measures of value, such as garments, coverlets and goat-skins which were so employed in the time of the Athava-veda.<sup>26</sup> Thus we see that traces of the various circulating media of these various stages of civilisation are clearly found in the Samhitā portion of the Vedas and they must have survived down to the Vedic epoch from previous stages of civilisation.

We may also note here that there are not one or two but many pre-historic symbols to be found on the punch-marked coins.27 Mr. Theobald has observed not less than fourteen symbols engraved on the sculptured stones of Scotland. There was a time when Fergusson and archeologists of his kind relegated the rude stone implements of Great Britain to the post-Roman period but to-day no archeeologist of any repute disputes its pre-historic chareter. When therefore we find so many pre-historic symbols occurring on the punch-marked coins, it is difficult to avoid the conclusion that Karstpana coins must have been handed down to us from pre-historic times. If any further evidence is required, it is furnished by the fact, first brought to our notice by Elliot that these punch-marked coins " have been discovered along the ashes of the men who constructed the primitive tombs known as Pandukulis of the south and uncarthed from the ruins of buried cities in excavating the head-waters of the Ganges Canal."28 "A large horde of these coins" says he elsewhere "was discovered in September 1807 at the opening of one of the ancient tombs known by the name of Pandukulis near the village of Chavadipaleiyam in Coimbatore, thus identifying the employment of this kind of money with the aboriginal race whose places of sepulchure are scattered over every part of Southern India,"29

<sup>98</sup> VIII. 1. 5.

<sup>24</sup> IV. 7. 6.

us ef. J. B. O. R. S. 1920, p. 400.

as INO. cs L 45.

<sup>20</sup> Madras Journal of Literature and Science, 1858. p. 227.

# The Chalcolithic Civilisation of the Indus Valley.

The surprising discoveries by Rai Bahadur Dayaram Sahni at Harappa in the Mont-gomery district of the Punjab and by Babu Rakhaldas Bannerji at Mohenzo Daro in the Larkana district of Sindh have proved the existence of a new kind of coins and have established beyond doubt the fact that five thousand years ago the people of the Punjab and Sind were living in well-built cities and were in possession of a relatively mature civilisation with a high standard of art and craftmanship and a developed system of writing-a civilisation as highly developed and seemingly as widespread as the Sumerian culture of Mesopotamia with conclusive evidence of a close contact between the two.30 The recent discoveries by Mr. N. G. Mazumdar<sup>31</sup> of a remarkable series of pre-historic sites in western Sind between the Indus and the Khirthar range reveal a wider diffusion of this Indus culture and link up the zone of Chalcolithic civilisation of Sind with the area surveyed by Sir Anrid Stein in Southern Beluchisthan; and there is evidence to show that it extended over Cutch and Kathiawar towards the Deccan.

Like the Egyptians of the Nile valley or the Sumerians and Babylonians of the Tigris-Euphrates valley the Indus people were provided by Nature with ample opportunities for agriculture on a flat plain subjected to floods. There are strong reasons for inferring that Sind was then watered by two large rivers instead of one and was, as a consequence, at once more fertile and less subject to floods. The two rivers are the Indus and the old great Mihran, otherwise known as the Hakra or Wahindah which once received the waters of the Sutlej and flowed well to the east of the Indus, following a course which roughly coincided with that of the Eastern Nara Canal. Moreover, the country was blessed with a greater rainfall and consequently had better prospects of agriculture. For this, evidence is furnished by the large number of street-drains and the rainwater pipes discovered at Mohenzo-Daro, the universal use of burnt instead

London News, January 7 and 14, 1928; February 27 and March 7, 1926; also in Times of India Illustrated Weekly, 7th March 1926.

<sup>\*1</sup> Explorations in Sind, published by the Govt. of India, Delhi, 1934.

of sun-dried bricks in its buildings and the representation on the seals of the tiger, the rhinoceros and the elephant who favour a moist climate. 3 some significance should also be attached in this connection to the preponderance of vegetation motifs on the painted pottery of Mohenzo-Daro and other contemporary sites in the Indus valley. Though little has yet been discovered of the processes of cultivation and irrigation then in vogue it is worthy of note that the specimens of wheat found in Mohenzo-Daro resemble the common variety grown in the Punjab to-day.

Hunting and fishing continued to be the occupation of a large section of the people. In their houses bones of the Gharial, boar, sheep and the bovine species as well as the shells of tortoises and turtles have been found, sometimes in a half-burnt condition, so that the conclusion is irresistible that besides bread and milk, fish from the rivers and the flesh of these animals formed their food.

The principal domestic animals, besides the cow and the sheep, were the humped long-horned bull, the buffalo, the short-horned bull, pigs, horse, elephant and dogs. The breed of Brahmini bulls as depicted on the seals seems to be every whit as good five thousand years ago as it is to-day.

The Babylonian and Greek names for cotton—Sindh and Sindon respectively—have always pointed to Sind as the home of cotton-growing and it is interesting to note that numerous spindle whorls in the debris of houses have been found, thus proving the practice of spinning and weaving. That the weaving material was cotton from the cotton plants of the genus Gossypium and not cotton from the silk-cotton tree has been proved by the discovery at Mohenzo-Daro of cotton of the former kind, with the typical convoluted structure which is the peculiar characteristic of that fibre. Even scraps of a fine woven cotton material have been found.

The dress among the upper classes consisted of two garments: a skirt fastened round the waist like the primitive Sumerian skirt and a plain and patterned shawl which was drawn over the left and under the right shoulder, so as to leave the right arm free. Earrings, bangles, girdles and

<sup>\*\*</sup> The lion which prefers arid and sparsely covered country does not occur.

anklets were worn by women while necklaces and finger-rings were worn by men and women of all classes, rich or poor. The ornamets of the latter were mainly of shell and terracotta while those of the rich were of latter were mainly of shell and terracotta while those of the rich were of silver and gold or copper plated with gold, of blue faience, ivory, cornelian, jadeite and muti-coloured stones of various kinds. Beads and bangles made of bronze, bangles and other ornaments made of shell (sank) were also in common use. The seals were sometimes worn by a cord round the neck or waist or as amulets. The girdles of cornelian and gilded copper neck or waist or as amulets. The girdles of pure gold have so fine as some of the earrings and "netting" needles of pure gold have so fine a polish on their surface that it would do credit to a modern jeweller.

The Indus people were familiar not only with gold and silver as the various ornaments made from them show but also with copper, tin and lead. Copper which was obtained from Beluchisthan on the west and from Afganisthan on the north was mostly used for weapons and implements like daggers, hatchets and celts as well as for domestic utensils like vessels, like daggers, knives etc. Personal ornaments, amulets and statuettes chisels, sickles, knives etc. Personal ornaments, amulets and statuettes were also made of copper. Most of these objects were wrought by hammering though examples of cast copper are by no means uncommon. A unique object made of copper, found in a low stratum at Harappa is a model of a two-wheeled cart with a gabled roof and driver seated in front. This is the oldest known example of a wheeled vehicle older than the steel Tragment with the picture of a chariot recently found by Woolney at Ur in Sumer.

The finds of bronze objects as compared with copper are small, doubtless owing to the difficulty and cost of obtaining tin. Tin was probably imported from Khorasan or through Sumer from further west, to be alloyed imported from bronze as the remains of bronze vessels, statuettes, with copper to form bronze as the remains of bronze vessels, statuettes, bangles, beads and buttons show. Specially striking is the use of bronze in making tools like razors, chisels and celts which require a hard cutting edge.

Pottery was well-known and common domestic vessels were of earthenware. They have a great variety of shapes, though it is curious how few of the vases are provided with handles. Most of the pottery is of plain undecorated red colour, but painted pottery is not uncommon. As a rule the designs are painted in black, on a darkish red slip. This dark and red Indus were has been found in abundance by Sir Anrid Stein in N. Beluchisthan and along the Waziristhan borderland and more sparsely in Sistan. A few specimens of polychrome decoration in red, white and black have also been met with at Mohenzo-Daro. Blue encaustic faience of a kind similar to that found in Mesopotamia and Egypt also played an important part in the making of miniature vases, ornaments, amulets and the like while a finer and harder variety of this paste was used for finishing off the surface of seals.

The remains laid bare at Mohenzo-Daro belong to the three latest cities on the site, each erected successively on the ruins of their predecessors. The date of these remains can be determined within tolerably narrow limits by the discovery at Susa and several sites in Mesopotamia of typical Indian seals inscribed with Indian pictographic legends, in positions which leave no doubt that they belonged to the period before Sarpon I, that is, before about 2,700 B. C. On another seal of the same pattern recently unearthed at Ur in Sumer, the legend is in cuniform characters of about 2,700 B. C. It may be inferred, therefore, that this class of Indian seals is to be assigned to the first half of the third millenium B. C. or earlier; and in as much as seals of this class are associated with the three uppermost cities at Mahenzo-Daro we may confidently fix the date of these cities between 3,500 and 2,500 B. C.

A bird's eye of the uppermost city at Mohenzo-Daro would reveal that the streets and lanes were laid out regularly according to a plan. The roads were broad and alignment of houses very good. The roads were broad enough to admit of all kinds of traffic and their surface was sometimes hardened with solid materials. The buildings abutting on the streets and lanes were so built, the walls being broad at the base and narrowing towards the top, that as the level of the streets and lanes rose, their width increased. There were central drainage channels in every street fed by subsidiary drains in the lanes.

The dwelling-houses of Mohenzo-Daro, though bare of all ornament are made of well-burnt brick, usually laid in mud but occasionally in

gypsum (plaster of Paris) mortar with foundations and infillings of sundried brick. The laying of the bricks suggested the use of instruments of level. One interesting feature of the houses was that all of them opened in by-lanes. Further, there was no direct access from the doorway into the house, but one had to pass through a room into a courtyard and then to the rooms of the house. Storied houses were very common as the existence of stairways revealed. Roofs were supported by beams and cross beams and roofing was done by spreading reed matting daubed with mud. Another interesting point about the houses was that no two of them had a common wall though they were all built close together in blocks. A narrow space was allowed between the walks of neighbouring houses, the same being walled up at either end. Some of the houses were very spacious and consisted of several rooms besides large courtyards and halls, suited to the accommodation of large families -- an indication probably of the existence of joint family system among the Indus people. The houses are equally remarkable for the relatively high decree of comfort evidenced by the presence of brick-flooring bath rooms and wells. Near the wells were paved washing places and the used water was drained away by well-constructed drains which sometimes ran forty or fifty feet before connecting with the street-drain. There were cess pits and small jars used for collecting drainage water at houses.

Outstanding among the buildings at Mohenzo-Daro is a temple with a beautiful public bath. On the four sides of the bathing tank is a boldly fenestered corridor, with a platform in front and small chambers behind. The outer wall which is more than six feet in thickness with a pronounced batter on the outside was pierced by two large entrances on the south and smaller ones on the east and north. At either end of the bath is a descending flight of steps. Like the bath-room floors of the private houses, the floor is laid in finely joined brick-on-edge and remarkable care and ingenuity have been exercised in the construction of the surrounding walls. These walls which are nearly ten feet in thickness are made up of three sections; the inner and outer of burnt brick, the infilling between them of sun-dried brick; but in order to render them completely water-tight, the brick-work has been laid in gypsum mortar and the back

of the inner wall coated with an inch thick layer of bitumen. Bitumen was also used for bedding the wooden planks with which the steps were lined. A number of rooms on the story above, the wells close by to feed the bath with a regular supply of water, the covered drain over six feet in height, furnished with a corbelled vaulted roof by which water was conducted outside the city, and the care taken to secure privacy for each individual resorting to the bath all made the bath one of the finest discoveries in the city.

Though town-planning was not much in evidence in Harappa it was more extensive than Mohenzo-Daro. Its buildings were similar in character to those of Mohenzo-Daro but there is one tolerably well preserved building the like of which has not been found at Mohenzo-Daro. It comprises a number of narrow halls and corridors disposed in two parallel series with a broad aisle down the middle. The plan and the shape of the chambers recall to mind the store-rooms of the Cretan palaces. Small brick-structures somewhat like Hindu samādhis containing cinerary remains as well as a platform partially covered with ashes and half-charred bones which is thought to be a cremation platform have also been found at Harappa.

A new outpost of this Indus civilisation has been discovered in Kathiawar in the state of Limbi which is not far from the Gulf of Cambay; and it was at the ports of Cambay and Broach that the cornelian industry of India was concentrated. When therefore we find an extensive use of this material in the Indus sites, the conclusion may be safely drawn that it was imported from these parts. The Tinnevelley district along the coast of Tāmraparaī river was the most ancient seat of conch-shell industry and when we find this conch-shell as a typical and very extensively used material in the Indus sites, we may safely assume that it was imported as much from the sea-coast down the Indus as from the south-eastern coast of the Madras Presidency.

Trade was carried on not only with other parts of India but also with countries further west. The affinity between the purely geometric patterns of Amri pottery of W. Sind, of the Kulli and Mehi fabrics of S. Beluchisthan and the painted ceramic wares of Sahr-i-Sokhta and other sites in

Sistan, of Tepeh Musyan and Susa in W. Persia, of Al-Ubaid and Samarra in Mesopotamia together with the occurrance of a figure closely resembling the Sumerian hero-god Eabani depicted on some Mohenzo-Daro seals is clear evidence of a close contact between these contiguous areas. But notwithstanding these and other points of similarity 5 the art of the Indus valley is distinct from that of any neighbouring country. Some of the figures on the engraved seals-notably the humped Indian bulls and short-horned cattle-are distinguished by a breadth of treatment and a feeling for line and form unequalled in the contemporary glyptic art of Elam or Mesopotamia or Egypt. The modelling too in faience of the miniature rams, monkeys, dogs and squirrels is of a very high order, far in advance of what we can expect in the fourth or third millenium B. C. Similarly, the houses recently unearthed by Mr. Woolney in Ur no doubt suggest an interesting parallel to those of Mohenzo-Daro but they are by no means equal in point of construction to those of the latter nor are they provided with drains of finely chiselled brick, covered with limestone slabs and connected with the main drain in the street. The conclusion is, therefore, irresistible-and it is being daily strengthened by the progress of exploration in the Indus valleythat whatever similarity we find between this Indus culture and the Sumerian civilisation of Mesopotamia, it is due not necessarily to actual identity of culture but to intimate commercial and other intercourse between these countries. Tin, as we have seen, was probably imported from Khorasan or through Sumer from further west, and bitumen from Beluchisthan. Dr. Sayce in his Hibbert Lectures for 1887 on the Origin and Growth of Religion among the Babylonians has proved the existence of commerce between India and Babylon as early as 3000 B. C. The discovery by Rassam of Indian cedar in the palace of Nebuchadnezzer and of Indian teak in the temple of the moon-god at Ur refounded by Nebonidus, the use of the word "Sindh" for muslin in an old Babylonian list of clothes certainly point to commercial intercourse between India and Babylon. The bas-reliefs of the temple of Deir-el-Bahari at Thebes

<sup>\*\*</sup> Sumerian connections with Ancient India—by E. Mackey in J. R. H. S. 1925, pp. 697—701.

which represents the conquest of the land of Punt under Hatasu contain a picture in which is described the booty which the Pharoah is carrying to Egypt. And in this booty, according to Leormant "appear a great many Indian animals and products not indigenous to the soil of yemen—elephant's teeth, gold, precious stones, sandal-wood and monkeys." 34

We have already seen that the smaller earthen vessels found in the burial sites at Adichanallur in Tinnevelly closely resemble objects of pre-historic pottery found in Egypt. Some of the potteries discovered from the sepulchral remains in the Nizam's dominions bear marks which, according to Dr. Hunt, closely resemble early forms of the "Ka" mark of Egypt. We have also seen how from the nature of construction and the contents found in the tombs of Anantapur district the religious belief of the primitive peoples who constructed them seems to have been much the same as that held by the ancient Egyptians regarding man's life after death.) On one of the faience sealings discovered in Mohenzo-Daro is a row of four standards borne aloft by men, each of which supports a totem figure remarkably like the well-known totem standards of the Egyptian names. The resemblance is so striking that it might almost be supported that this particular sealing was an import from pre-dynastic Egypt, were it not that it is inscribed on the reverse with an Indian pictographic legend. Long ago there was a school of orientalists who believed in the colonisation of Ethiopia and Egypt from N. W. India and the Himalayan provinces. Indeed if the people to whom the Indus civilisation was attributed had occupied cities for at least 500 to 1000 years, it is quite possible that the natural growth of population must have made them seek fresh fields and pastures for their expansion. In Philostratus an Egyptian is made to remark that he had heard from his forefathers that the Indians were the wisest of men and that the Ethiopians, a Colony of the Indians, preserved the wisdom and usage of their forefathers and acknowledged their ancient origin. We find the same assertion made at a later period in the third century B. C. by Julius Africanus, from whom it has been preserved by Eusebius and

<sup>\*\*</sup> History of Ancient Del Orient Eng. ed. Vol. II. p. 299 Quoted in Indian Antiquary, Vol. XIII. p. 298.

Syncellus.35 Philostratus introduces the Brahmin Iarchus by stating to his auditor that the Ethiopians were originally an Indian race compelled to leave India for the impurity contracted by slaying a certain monarch to whom they owed allegience. 36 Cuvier, quoting Syncellus even assigns the reign of Amenophis as the epoch of the colonisation of Ethiopia from India.37 Eusibius states that Ethiopians emigrating from the river Indus settled in the vicinity of Egypt. 38 Again, we find great similarity in the names of rivers, towns and provinces of both India and Egypt. "For about ten miles below Attock" says a critic, "the Indus has a clean deep and rapid current; but for about a hundred miles further down to Kalabagh it becomes an enormous torrent. The water here has a dark lead colour and hence the name Nilab or Blue river given as well to the Indus as to a town on its bank about twelve miles below Attock." According to another writer "Aboasin (a classical name for the Indus) gave its name to Abyssinia in Africa"39 Indian "Suryarika (Sun-burnt land) is perhaps the Sahara desert of Africa. The names of towns at the estuaries of the Gambia and Senegal rivers, the Tamba Cunda and another Cundas are according to Col. Todd 60 Hindu names. A writer in in the Asiatic Journal 1 gives a curious list of the names of places in the interior of Africa, mentioned in Park's Second Journey, which are shown to be all Sanskrit, and most of them actually current in India at the present day. We also find striking similarity in the names of rulers and gods of both India and Egypt. King Rama of India is king Ramses of Egypt. The first Egyptian Solar king Manes sounds like Hindu Manu, the first solar king of India. The bull-bannered Egyptian Isis is Indian Isa. Further the religious systems of India and Egypt "both proceed from monotheistic principles and degenerate into a polytheistic heathenism though rather of a symbolic than of a positive character. The principle

<sup>\*5</sup> India in Greece by Pococke, p. 205.

<sup>56</sup> India in Greece by Posseke, p. 200.

p. 18 of his " Discourse."

<sup>16</sup> Lemp. Barker's edition, " Merce."

Heeren's Historical Researches, Vol. II. p. 310.

<sup>\*\*</sup> Todd's Rajasthan, Vol. II. p. 309 footnote.

<sup>41</sup> Vol. IV. p. 325.

of Trinity with that of the Unity, the pre-existence of the soul, its transmigration, the division of castes into priests, warriors, traders and agriculturists are the cardinal points of both systems. Even the symbols are the same on the shores of the Ganges and the Nile. Thus we find the Lingam of the Siva temples of India in the Phallus of the Ammon temple of Egypt-a symbol also met with on the headdress of the Egyption gods. We find the lotus flower as the symbol of the Sun both in India and in Egypt and we find symbols of the immortality of the soul in both countries. The power of rendering barren women fruitful ascribed to the temples of Siva in India, was also ascribed to the temples of Ammon in Egypt."49 Nor is this all. Mr. Pococke has found points of similarity not only in the objects of sculpture but also in the architectural skill and in the grand and gigantic character of the architecture of India and Egypt. Professor Heeren therefore concludes "whatever weight may be attached to Indian tradition and the express testimony of Eusubius confirming the report of the migrations from the banks of the Indus into Egypt, there is certainly nothing improbable in the event itself, as a desire of gain would have formed a sufficient inducement." But to sober minds it is reasonable only to assume that whatever similarity there might exist between the place-names, the names of gods and kings and the social and religious institutions of ancient India and Egypt, it was the result of early commercial intercourse between the two countries.

In the Book of Genesis\*5 we read that Joseph was sold by his brethern to the "Ishmaelites come from Gilead, with their camels, bearing spicery, balm and myrrh going to carry it down to Egypt." Here, Dr. Vincent observes, we find "a caravan of camels loaded with the spices of India." Some suppose that myrrh used to be imported into Egypt by the Abyssinians, in whose country it largely grows. But the proof of its importation from India may be found in the name which it took in Egypt. Dr. Royle44 observes that myrrh is called "bal" by the Egyptians, while its sanskrit name is "bota", bearing a resemblance which leaves

<sup>42</sup> Count Bjornstjirna's Theogony of the Hindus pp. 40-41.

<sup>48</sup> Chapter XXVII. v. 25.

<sup>44</sup> Aucient Hindu Medicine, "Myrrh" p. 119.

no doubt as to its Indian origin. According to Wilkinson 45 the presence of indigo, tamarind-wood and other Indian products found in the tombs of Egypt shows Indian trade relations with the land of the Pharoahs. The evidences of Comparative Philology corroborates this view. Ivory we know was largely used in India, Babylon, Egypt, Greece and Rome. Elephants are indigenous in India and Africa and the trade in ivory must be either of Indian origin or African. But the elephants were scarcely known to the ancient Egyptians 46 and Professor Lassen decides that they were neither used nor tamed in ancient Egypt. In ancient India, however, the elephant was an emblem of royalty and a sign of rank and power and no description of a king's procession or of a battle is to be met with where elephants are not mentioned. Even the god Indra has his "Airawat." Then the Sanskrit name for a domestic elephant is ibha and in ancient Egypt ivory was known by the name of ebu. Professor Lassen thinks "that the Sanskrit name ibha might easily have reached Egypt through Tyre and become Egyptian ebu."47 Similarly, Sanskrit kapi became Egyptian kafu and the Hebrew koph. This Indo-Egyptian trade is further supported by another crudite scholar the Rev. T. Foulkes48 who comes to the same conclusion and says "With a very high degree of probability some of the most esteemed of the spices which were carried by the Mediantish merchants of Genesis XXXVII. 25-28 and by the sons of the Pharoah Jacob (Genesis XLIII. 11) had been cultivated in the spice-gardens of the Deccan."

<sup>4.</sup> Ancient Egyptians II. p. 237.

<sup>40</sup> Mrs. Manning-Ancient and Mediaval India, Vol. II. p. 251.

<sup>47</sup> C. Lassen-Indische Alterthumskunde Vol. I. p. 354.

<sup>40</sup> Indian Antiquary, Vol. VIII.

## CHAPTER IV.

## The Rigvedic Age.

The Rigredic period was an age of migration and settlement. By this time the Aryan invaders had spread over the whole of the region, extending from the Kabul valley upto the Ganges and the Jumna. In the list of rivers in the Nadi-stuti hymn49, and elsewhere we find the names of the Gangā<sup>50</sup>, the Yamunī<sup>51</sup>, the Sarayu<sup>52</sup>, and the Saraswati<sup>53</sup> and this goes to show the eastern limit of Aryan advance in Rigvedic India. Of the western tributaries of the Indus we find the names of Kubhā 54 (modern Kabul river ) the Suvastus 5 (modern Swat river) the Krumus 6 (modern Kurrum river) and the Gomati<sup>57</sup> (modern Gomal) rivers. Though most familiar with the valleys of the Indus and its tributaries the Aryans gradually spread over the greater part of the Ganges valley as well. Thus the Rigveda mentions Kikata<sup>58</sup> which has been identified by some scholars with the country of Magadh.

Growth of agricultural life and landownership-The evidence of the science of Comparative Philology in relation to the Indo-European group of languages discloses the fact that the original Aryan stock, though preeminently a pastoral people were not unacquainted with agriculture. 59 It appears from the same evidence that during the Indo-Iranian period the Aryans were acquainted with agriculture 60 and we have even direct

<sup>40</sup> Rigveda X. 75;

<sup>\*\*</sup> Rigveda IV. 30, 18; V. 53. 9; X. 64. 9.

so Rigveda VI. 45. 31; X. 75. 5.

<sup>51</sup> Rigveda V. 52. 17; VII. 18. 19; VII. 33. 3; X, 75. 5.

<sup>\*\*</sup> Rigveda L 3, 12; II, 41, 16; III. 4.8; 1II, 23, 4; VI. 52, 6; VII. 2, 8; VII. 36.6; VII. 96; X. 64, 9; X. 75. 5.

sa Rigveda V. 53. 9; X. 75. 6.

Rigveds VIII. 24. 30; X. 75. 6.

<sup>68</sup> Rigveds VIII. 19. 37.

Rigveda III, 53, 14.

se Rigveds V. 53. 9; X. 75. 6.

Otto Schrader, Reallexikon der Indogermanischen Altertumskunde, s. v. Ackerbau, Familie, Stamm, Viehsucht; Hermann Hirt, Die Indegermanen, I. 251ff.

oo Keith and Macdonell- Vedic Index, I. p. 181 (kṛṣi)

reference to agriculture in the Vendidad.<sup>61</sup> When one branch of the Aryans ultimately migrated into the land of the five rivers, they found the country already in occupation of alien peoples, some of whom, as we have seen, judged by the wonderful remains of their civilisation in the Indus valley, attained a high level of material greatness; and even the confused and imperfect picture of the aborigines in the Rigveda furnishes some hints of their organisation in puras under the rule of Chiefs.<sup>62</sup> By the time even of the earliest hymns of the Rigveda the Indo-Aryans had settled down to a peaceful agricultural life and evolved the idea of landownership. The land was divided into Vāstu, Arableland, Pasture and Forests. The Vāstu was in individual ownership as was also the case with the Vāstu of the German Mark. But while the arable land in ancient India was in private ownership but ultimately in private ownership.

In one hymn of the Rigveda<sup>68</sup> we read of an impoverished gambler who is made to take shelter in another's house and the sight of another's prosperity torments him:

"The gambler's wife is left forlorn and wretched:
the mother mourns the son who wanders homeless
In constant fear, in debt and seeking riches,
he goes by night unto the home of others.
Sad is the gambler when he sees a matron,
another' wife, and his well-ordered dwelling."

This proves conclusively that houses were owned in severalty and that the owners had the right of transfer. In fact, we constantly read of prayers for the bestowal of houses on individuals:—

"Bestow a dwelling-house on the rich landlords and me and keep thy dart (O Indra) afar from these." \*\*

<sup>\*1</sup> III, 23 and 24; also XIV. 10,

<sup>\*\*</sup> Keith and Macdonell—Vedic Index, s. v. Däsa : for references. Compare Rapson—Cambridge History of India, Vol. I. p. 86.

<sup>\*\*</sup> Rigveda X. 34. 10-11.

<sup>\*\*</sup> Rigyeda VI. 46, 9.

"Give us, O Mitra-Varuṇa a dwelling safe from attack, which ye shall guard, Boon-givers."
"Give ample room and freedom for our dwelling, a home, ye Hemispheres, which none may rival."
"88

As regards the arable land we have a hymn of the Rigveda<sup>67</sup> which seems to make an indirect reference to the fact that the Aryans after conquering the land of the Dasyus used to share them apparently on a footing of equality. This sharing of the land by all the conquering persons during the Rigvedic age seems to be referred to in the Manu Samhita.<sup>68</sup> Even the priests who officiated at sacrifices for the victory of Aryan arms claimed a share in the war-booty.<sup>69</sup> In one hymn<sup>70</sup> Apātā, the daughter of Atri prays to Indra that something may grow on her father's (apparently bald) head and on his plough-land. Even measurement of fields with a rod is referred to:

"The Ribhus with a rod measured, as it were a field." According to Professor Scharder without private ownership we cannot expect fields to be measured in this way. We also meet with epithets like kshetrapati, kshetrasa, urbarapati and urbarasa, meaning lords or owners of fields, pointing to the existence of private ownership. 72

No royal ownership of land—The unit of Indo-Aryan society was the patriarchal family. The authority of the head of the family was very great and an instance of this may be found in the story of Rijrasva who was robbed of his eyesight by his father Vrishāgir for having slaughtered a hundred sheep for the she-wolf who was one of the asses of the Aswins in disguise.<sup>73</sup> Above the family stood the Viś in the sense of clan and a number of Viś groups formed the whole jana or people.<sup>74</sup> As regards the

<sup>\*\*</sup> Rigveds VI. 50, 3,

as Rigveds V1. 67. 2. Compare Rigveds L. 114. 5.

<sup>\*\*</sup> I. 100. 18-19. 70 Rigveds VIII. 91. 5-6.

<sup>\*\*</sup> VII. 97. \*\* Rigveds I. 110. 5.

<sup>\*\*</sup> Rigveda I. 180. 9.

<sup>\*\*</sup> Macdonell and Keith - Vedic Index, Vol. I. pp. 99, 210.

<sup>\*\*</sup> Rigveds I. 117, 16.

<sup>\*\*</sup> Macdonell and Keith - Vedic Index, s. v. Vis and Jans.

political organisation of this period monarchy as might be expected from their situation as settlers in the midst of a conquered population, was a well-established institution and the Rigveda gives as glympses of the king's functions in peace and war. 15 Originally, it seems, the authority of the king was largely limited by that of the heads of the family and the chiefs of the clans, though as guardian of his people he used to receive such voluntary contributions which are called by the generic name "bali" just to maintain his authority and dignity. There is nothing in the Rigveda to prove that he was ever regarded as the owner of the state-territory.

Corporate village-life-The grama or village consisted of a group of families united by ties of kindred but what place it held in the scheme of tribal divisions and in particular what relation it bore to the Vis with which it was immediately connected, it is impossible to state with any degree of certainty." Most of the villages were founded by settlers under some leader and apart from the question of consanguinity the people of a village regarded themselves as a united body. In times of war they fought under their leaders for the safety of their hearths and homes; and this is proved by the word samgrama which primarily meant an assembly of the villago-folk but later on came to mean a war-gathering. In times of peace they gathered in the village council (sava) which as Zimmer suggests "served like the Greek Leshke as a meeting place for social intercourse and general conversation about cows76 and so forth, possibly also for debates79 and verbal contests.80 The administrative machinery of the village also supports its corporate character. At the head of the village was the Gramania who according to Zimmera presided over the village

<sup>7\*</sup> Ibid., s. v. Råjan ; Rapson-Cambridge History of India, Vol. I. pp. 94-95, 98,

<sup>16</sup> Rigveds X. 173; Macdonell and Keith - Vedic Index, s. v. bali.

<sup>\*\*</sup> Macdonell and Keith — Vedic Index, s. v. Grams; Rapson—Cambridge History of India, Vol. I. p. 91, where reasons are shown for rejecting the older view of Zimmer (Altindisches Leben, pp. 159—60), namely that the Grams was a clan standing between the family and the tribe.

<sup>\*\*</sup> Rigveda VI. 28, 6, 7. Rigveda I. 91, 120,

<sup>\*\*</sup> Zimmer - Altindisches Leben, p. 172

<sup>\*\*</sup> Rigveda X. 62. 11; X. 107. 5.

<sup>\*\*</sup> Altindisches Leben, p. 172.

assembly though Macdonell<sup>63</sup> does not accept this view. Ludwig<sup>64</sup> infers judicial functions of the village assembly from the word kilvishasprit in the Rigveda<sup>85</sup> which can only mean "that which removes the stain attaching to a person by means of accusation."

The villages which thus became the basis of social life were connected by roads which were not free from dangers from wild beasts and robbers as is evident from the frequent prayers for protection on a journey offered to Pushan who was the deity presiding over roads and paths.<sup>86</sup>

Growth of towns-The existence of city-life in this period has been denied by Professors Keith, Kaegi and others. Pischel, Geldner and Wilson, however, think otherwise. According to the latter puras (cities) as distinct from gramas (villages) were well-known. "Indra broke through Ilibisa's strong puras."37 "Thou (O Indra) hero-hearted hast broken through Pinru's pūras."88 "Thou, O Indra, hast destroyed the hundred pūras of Vangrida."89 "Thou (O Indra) slayest the Vritras, breaker-down of puras," "Thou breakest down, Indra, autumnal püras."91 "Him (Agni), indestructible, dwelling at a distance in puras unwrought lies and ill-spirit reaches not." 91 "Maghavan with the thunderbolt demolished his (Sambara's) ninety-nine puras."95 "Agni, thou brokest down the puras."94 "Thou, (O Indra) hast wrecked seven autumnal puras."95 "Indra, thou humblest tribes that spake with insult by breaking down seven autumnal puras."96 "Thou hast smitten Sambara's pūras, O Indra."97 "(O Indra) dostroy the firm pūras built by man."98 "Indra overthrew the solid puras built by Pipru."99 "He (Agni) with the steed wins spoil even in the fenced pura."100 Indra is said to have

```
82 Vedic Index, Vol. I. p. 497.
```

<sup>94</sup> Der Rigveda, III. 254.

<sup>\*\*</sup> X. 71, 10,

<sup>\*\*</sup> Rigveda I. 42. 1; VI. 49. 8; V1. 51. 13; VI. 53. 1.

BY Rigveds I. 33. 12.

<sup>\*\*</sup> Ibid, I. 53, 8,

<sup>&</sup>quot;1 Ibid, I. 131. 4.

<sup>99</sup> Ibid, V. 29. 6.

<sup>\*\*</sup> Ibid, VI. 20, 10.

ит Thid, 1. 108. 8,

<sup>\*\*</sup> Ibid, X. 138, 3.

<sup>\*\*</sup> Ibid, L 51, 5.

a Ibid, I, 102. 7.

<sup>•</sup> Ibid, II. 35, 6.

<sup>\*\*</sup> Ibid, VI. 16. 39.

<sup>&</sup>quot;" Ibid, I. 174. 2.

<sup>10</sup> Ibid, Vl. 45. 9.

<sup>100</sup> Ibid, VIII. 92, 5.

"quickly demolished the strongholds and seven-walled puras of Srukta and other asuras."101 He is again said to have demolished one hundred pūras of stone for the pious Divodīsa. 102 Again he possessed all the pūras of the asuras as a husband his wife108 Saraswati is described "as firm as a pura made of ayas."104 Puras made of the metal ayas are also mentioned in several other places, 105 figuratively, no doubt, to express great strength. Professor Wilson remarks "cities are repeatedly mentioned, and although, as the object of Indra's hostility, they may be considered as cities in the clouds, the residences of the Asuras, yet the notion of such exaggerations of any class of beings could alone have been suggested by actual observations, and the idea of cities in heavenfcould have been derived only from familiarity with similar assemblages upon earth; but it is probable that by Asuras we are to understand, at least occasionally, the ante-vaidik people of India, and theirs were the cities destroyed. It is also to be observed, that the cities are destroyed on behalf of or in defence of mortal princes, who could scarcely have beleaguered celestial towns, even with Indra's assistance. Indeed, in one instance, it is said that, having destroyed ninety-nine out of hundred cities of the Asura Sambara, Indra left the hundredth habitable for his protégé Divodāsa, a terrestrial monarch, to whom a metropolis in the firmanent would have been of questionable advantage. That the cities of those days consisted, to a large extent, of mud and mat hovels is very possible : they do still ; Benares, Agra, Delhi, even Calcutta present numerous constructions of the very humblest class; but that they consisted of those exclusively, is contradicted in several places. In one passage the cities of Sambara that have been overturned are said to have consisted of stone; in another the same cities are indicated by the appellative dehyah, the plastered, intimating the use of lime, mortar or stucco; in another we have specified a structure with a thousand columns, which whether a palace or a temple, must have been something very different from a cottage; and again, supplication is put up for a large

<sup>101</sup> Wilson's Rigyeds IV. 59.

<sup>108</sup> Ibid, IV. 75.

<sup>104</sup> Ibid, IV. 12.

<sup>100</sup> Ibid, IV. 30, 20.

IV. 27. 1; VII. 3. 7; VII. 15. 14; VII. 95. 1; VIII. 89. 8; X. 101. 8.

habitation which could not be intended for a hut: cities with buildings of some pretence must obviously have been no rarities to the authors of the hymns of the Rigveda."108 According to Professor Keith, however, "the pura which is often referred to and which in later days denotes a town was probably no more than a mere earthwork fortification. In certain passages, these puras are called autumnal, and by far the most probable explanation of this epithet is, that it refers to the flooding of the plains by the rising of the rivers in the autumn when the cultivators and the herdsmen had to take refuge within the earthworks which at other times served as defences against human foes."107 But the actual remains of well-planned cities like those of Mohenzo Daro and Harappa of the Calcholithic Age seem, however, to confirm the imperfect picture of the pre-Aryan inhabitants of the Indus valley in the Rigveda, living in puras, some of which might, therefore, will have been cities and not mere earthwork fortifications.

Development of Agriculture-Agriculture was already a part of Vedic economy. The very name Arya by which the Aryan conquerors have distinguished themselves from the aborigines is said to have come from a root (krish) which means to cultivate. 108 Similarly the words kristayah 109 and carsanayah 110 are applied to the people in general. In other places we find Pancha kristyah 111 and Carsanayah 112 applied to the great tribes.

Fertile plots of land (urbara) were selected and divided into separate fields (kshetras) which were measured with a rod. 113 Forests were cleared up by fire as well for purposes of cultivation. 114 The Aswins taught the Great Manu the art of sowing seeds 118 and the Indo-Aryans the use of the plough. 116 The plough was known as Sira 117 and Langala. 116 The

<sup>100</sup> Wilson's Rigveds III. p. XIV.

<sup>107</sup> Rapson-Cambridge History of India, Vol. L.

<sup>100</sup> R. C. Dutt - Civilisation in Ancient India, p. 35.

<sup>100</sup> Rigveds I. 52, 11; L. 100, 10; L. 160, 5; L. 189, 3; III, 49, 1; IV. 21, 2

<sup>110</sup> Ibid, I. 86. 5; III. 43. 2; IV. 7. 4; V. 23. 1. 111 Ibid, II. 2, 10; III. 53, 16; IV. 38, 10; X. IO. 4. 119 Ibid, V. 86, 2;

<sup>113</sup> Ibid, I, 110. 5.

<sup>114</sup> Thid, I. 58. 4-5; I. 140. 4-8; II. 4. 4, 7; IV. 4.

<sup>110</sup> Rigveda I. 112, 16; Sāyana's Commentary.

<sup>117</sup> Ibid, IV. 57. 8; X. 101. 3, 4.

VII. 15. 2; IX. 101. 9.

<sup>110</sup> Ibid, L 117. 21. 110 Ibid, IV. 57. 4.

ploughshare was called phala119 and the yoke was called Yuga,120 The plough was driven by oxen 121 which were yoked and harnessed with traces (varatra)199 and urged with the goad193 with horny point194 by the ploughman (kinzsa), 125

For the improvement of agriculture cowdung was probably used as manure. Sakrt in the Rigveda 196 means according to Professors Macdonell and Keith dung and "it is clear that the value of manure was early appreciated."197 For irrigating the fields water-courses seem to have been dug out. The epithet khanitrima (produced by digging) of apah (water) in the Rigveda 198 "clearly refers to artificial water-channels used for irrigation, as practised in the times of the Rigveda."129 Muir 130 took the word kuly3 to mean artificial waterways which carried water to reservoirs. Wells for purposes of irrigation were also well-known. The word avata frequently occurs in the Rigveds 181 and denotes an artificial hollow in the earth containing water. Kūpa having the same meaning also occurs in the Rigveda. 132 Such wells are "described as unfailing (aksita) and full of water.133 The water was raised by a wheel of stone 134 to which was fastened a strap (varatra) with a pail (kośa) attached to it. When raised, it was poured into buckets (āhāva)185 of wood. Sometimes these wells appear to have been used for irrigation purposes, the water being led off into broad channels (sūrmi susirā). 188 In some cases they (the wells)

```
110 Ibid, IV. 57. 8; X. 117. 7.
```

117 Vedic Index, IL. p. 348.

1se Rigveds VII, 49, 2,

<sup>100</sup> Ibid, I. 115, 2; I. 184, 3; II. 39, 4; III. 53, 17.

<sup>191</sup> Thid, X. 106.

<sup>199</sup> Ibid, IV. 57. 4.

<sup>199</sup> Ibid, IV. 57. 4; X, 102. 8.

<sup>100</sup> Ibid, VL 53, 9.

<sup>100</sup> Ibid, IV. 57. 8.

<sup>100</sup> Ibid, I. 161. 10.

<sup>100</sup> Vedic Index, I. p. 214.

<sup>100</sup> Sanskrit Texts, Vol. V. pp. 465-66.

<sup>181</sup> I. 55. 8; I. 85. 10, 11; I. 116. 9, 22; IV. 17. 16; VIII. 49. 6; VIII. 62. 6; X. 25. 4,

<sup>100</sup> L 105, 17.

<sup>188</sup> Rigveda X. 101. 6.

<sup>184</sup> Asma-Cakra, Rigveda X. 93, 13; X. 101, 7.

<sup>100</sup> Rigveda X, 25, 4,

must have been deep, as Trita in the myth is said to have fallen into one, from which he could not escape unaided."137

For successful agriculture timely rain was a necessity. Hence the innumerable prayers for rain preserved in the hymns of the Rigveda, 130" Sacrifices were also offered for helping Indra to fight Vrtra or the Demon of Drought and bring down rain by rendering open his cloud-body with Indra's thunderbolt. Indra was assisted in his work by some other deities, notably Visnu the Sun-god who heated the sea-water, converted it into vapour and lifted them into the sky above, 189 the Maruts or Winds (Monsoons) who carried the watery vapour inland from the surrounding seas, Trita the third month of the rainy season when rainfall was incessant, Parjanya the ancient god of rain and Brhaspati of "loud speech"140 who helped the worshippers in properly chanting the mantras at the sacrifice, held for the propitiation of the gods. The Saraswati was called Vrtraghnl the killer of Vrtra, like Indra.141 That obtaining rains was the main object of holding the annual and special sessions of sacrifice in those days is evident from the following verse: "I offer to you (gods) for the sake of water, an all-bestowing sacrifice whereby the Navagvas have completed the ten month's rite."149

Before agricultural work was begun, certain verses were uttered to propitiate the Lord of the Field (Kshetrapati) and other deities, supposed to preside over agriculture, as will appear from the following verse of the Rigveda<sup>143</sup>:—

"We through the Master of the Field, even as through a friend obtain

Macdonell and Keith-Vedic Index, L. 40, 177; also Macdonell-Vedic Mythology, p. 67.

<sup>188</sup> V. 63, 2; V. 63, 6; V. 83, 6—7; VI. 70, 5; VII. 64, 2; VII. 65, 4; VII. 73, 3; VII. 102, 1; VIII. 7, 16; VIII. 25, 6; IX, 8, 8; IX, 39, 2; IX, 49, 1; IX, 65, 3, 24; IX, 96, 4; IX, 97, 17; IX, 106, 9; IX, 108, 10; X, 98, 5, 10,

<sup>100</sup> Rigveds VIII. 77. 10.

<sup>140</sup> Tbid, IV. 50, 5.

<sup>141</sup> Ibid, VL 61. 3, 7.

<sup>249</sup> Ibid, V. 45. 1.

<sup>148</sup> IV. 57.

What nourisheth our kine and steeds. In such way may he be good to us.

As the cow yieldeth milk, pour for us freely, Lord of the Field, the wave that beareth sweetness,

Distilling meath, well-purified like butter, and let the Lords of holy Law be gracious.

Sweet be the plants for us, the heavens, the waters, and full of sweets for us be air's mid-region.

May the Field's Lord for us be full of sweetness, and may we follow after him uninjured.

Happily work our steers and men, may the plough furrow happily,

Happily be the traces bound; happily may be ply the goad.

Suna and Sira, welcome ye this land, and with the milk which ye have made in heaven.

Bedew ye both this earth of ours.

Auspicious Sită, come thou near : we venerate and worship thee

That thou mayest bless and prosper us and bring us fruits abundantly.

May Indra press the furrow down, may Pūṣhan guide its course aright

May she, as rich in milk, be drained for us through each succeeding year.

Happily let the shares turn up the ploughland, happily go the ploughers with the oxen.

With meath and milk Parjanya make us happy; grant us prosperity, Suna and Sira."

In another hymn<sup>144</sup> sacrifice is figuratively spoken of as ploughing, sowing and reaping.<sup>145</sup> We also read of other agricultural operations like

<sup>144</sup> Rigveds X. 101, 3-12.

<sup>146</sup> Compare Satapatha Brahmana VII. 2. 2, 4.

cutting of corn by the sickle, 146 the laying of it in bundles, 147 on the threshing floor 146 and final shifting by winnowing. 149

Coming to the nature of the grain grown we find that Yava<sup>150</sup> and dhānāh<sup>151</sup> or dhānya<sup>155</sup> were cultivated.<sup>155</sup> According to Macdonell and Keith<sup>154</sup> Yava perhaphs meant any kind of grain and not merely barley. But we should bear in mind that Indian commentators have always taken Yava to mean barley only. Moreover, we should note in this connection that barley is one of the earliest grains to be cultivated by man. Again European scholars interpret dhāna and dhānya as grain in general and not as rice, though in later literature it always means rice. The absence of the name of vrihi (the boro rice of Lower Bengal which later became the general name of rice) in the Rigveda lend colour to the view that rice was unknown in this age.<sup>155</sup>

Food of the people—The food of this age consisted of barely flour and its various preparations, fruits, flesh of animals like goats, sheep, oxen, buffaloes, deer and sometimes horses as well as honey, clarified butter, curds and other preparations of milk. The drink consisted of milk, the Soma juice and wine.

Apūpa<sup>186</sup> was a kind of cake made of barley mixed with clarified butter. Pakti<sup>187</sup> was another kind of cake. Grain cooked with milk was called khīra-audana.<sup>188</sup> Karamba<sup>189</sup> was a kind of porridge made of fried barley-flour, mixed with curd or clarified butter.

<sup>140</sup> Srpl, Rigyada I. 58. 4; IV. 20. 5; X. 101. 3; datra, Rigyada VIII. 67. 10.

parsa, Rigveda X. 48. 7.

<sup>240</sup> Rigveda X. 27. 15; X. 68, 3; X. 71, 2,

<sup>230</sup> Rigveda I, 53, 2; IV. 24, 7; V. 85, 3; VII, 3, 4; VIII, 2, 3; VIII, 81, 4; X. 27, 8; X. 13L 2,

<sup>151</sup> Rigweds I, 16.2; III, 35.3; III, 52.7; VL 29, 4.

<sup>252</sup> Rigveds V. 53, 13; VI. 18, 4; X. 94, 13.

<sup>103</sup> Cucumber is also referred to, Rigveda VII. 59, 12. 154 Vedic Index, II. p. 187.

Culture, pp. 266-69, 281-83,

<sup>100</sup> Rigveds III. 52.7; X. 45.9. 107 Ibid, IV. 24.5; IV. 25.6; VI. 29. 4.

<sup>\*\*\*</sup> Ibid, VIII. 69. 14; VIII. 77. 10.

<sup>150</sup> Ibid, I. 187. 16; III. 52, 7; VI. 58. 1; VI. 57. 2; VIII. 102. 2.

Meat was a principal item of food. The sage Bharadwaja praved to Indra to grant him and his worshippers food with cow as the principal item. 160 Agni is called "eater of ox and cow." 161 Bulls were sacrificed to Indra as well. 162 There was even an appointed place for the slaughter of bulls and cows. 163 On rare occasions horse was sacrificed and its flesh was cooked and offered to the gods, 164 both roasted 165 and boiled 166; while the worshippers "craving meat, await the distribution."167 We also hear of buffaloes dressed for and eaten by Indra. 168 The cow, however, was gradually "acquiring a special sanctity, as is shown by the name aghnya (not to be slain) applied to it in several passages."169 The word occurs sixteen times in the Rigveda as opposed to three instances of aghnya (masculine). It would thus appear that there was a school of thinkers among the Risis who set their face against the custom of killing such useful animals as the cow and the bull. Relying on Sayana's interpretation we also find a reference to the fowler's wife cutting a bird, evidently for food, 170

Fish is mentioned in the Rigveda<sup>171</sup> but we are not sure whether or how far it was used as food by the people of this age.

Fruits were eaten<sup>172</sup> though we do not come across the names of any of them. Honey was also taken with food and drink.<sup>173</sup> It is curious that there is no mention of salt in the Rigveda. "It is, however, quite conceivable that a necessary commodity might happen to be passed over without

```
160 Ibid, VI. 39. 1.

161 Ibid, VIII. 43. 11.

163 Ibid, X. 89. 14.

164 Ibid, I. 162. 3, 10, 11.

165 Ibid, I. 162. 11.

166 Ibid, I. 162. 12.

167 Ibid, V. 29. 8; V1. 17. 11.

168 Mecdonell and Keith—Vedic Index, II. p. 146.

178 Rigyeda I. 92. 10.

171 Ibid, VII. 18. 6; X. 68. 8.

173 Ibid, III. 45. 4; X. 146. 5.

174 Ibid, III. 45. 4; X. 146. 5.

175 Ibid, I. 19. 9; I. 154. 4;

II. 19. 2; II. 37. 5; III. 8. 1;
```

VII. 24. 2.

III. 39, 6; III. 43, 3; IV. 38, 10;

literary mention in a region where it is very common, but to be referred to in a locality where it is not found and consequently becomes highly prized."<sup>174</sup> In the Chāndogya Upanisad<sup>175</sup> it seems to be placed above gold in value, probably because it had to be imported at a heavy cost into the region where the Upanisad was composed. From the absence of any mention of salt in the Rigveda some European scholars have come to the conclusion that the Indo-Aryans of this age did not use salt in the preparation of their food. But this, as Macdonell has observed "is a good illustration of the dangers of argumentum ex silencio." <sup>176</sup> The existence of seas near the Punjab and of the Salt Range in the heart of the country precludes a supposition like that from being at all probable.

Milk furnished a nourishing drink and was called payas. 177 Curd was called dadhi. 178 Butter was prepared by churning (mantha) 170 and ghrta was made from it by melting it on fire. 180 Another drink Soma was made 181 with the pressed juice of a creeper or plant, diluted with water and mixed with milk (gavāsir), curd (dadhyāsir) and grain (Yavāsir) 182 and sometimes with honey 188 The Soma plant grew on the mountains, that of Mujavant being specially renowned. 184 At first unmixed juice (sukra, suchi) was offered to Indra and Vāyn 185 but this usage was afterwards dropped by the kanvas 186 The whole of the Nineth Mandala of the Rigveda and

<sup>174</sup> Macdonell and Keith-Vedic Index, II. p. 230.

<sup>175</sup> IV. 17. 7.

<sup>176</sup> Macdonell-History of Sanskrit Literature, p. 105.

<sup>377</sup> Rigveda I. 164, 28; II. 14, 10; IV. 3, 9; V. 85, 2; X. 30, 13,

<sup>178</sup> Ibid, VIII. 2. 9; IX. 87. 1.

<sup>170</sup> Ibid, L. 28, 4,

<sup>100</sup> Ibid, I. 184, 6; II. 10, 4; IV. 10, 6; IV. 58, 5, 7, 9; V. 12, 1.

<sup>181</sup> Read Stevenson—Sāma Veda, p. 5; Hang—Aitareya Brāhmapa, I. p. 6; Manning—Ancient India, I. p. 86. For the mantrae used in the course of preparing the Soma beverage are Taittiriya Sambitā, Kāṇḍa I. Prapāṭakas II., III., IV., and kāṇḍa IV. Prapāṭakas I., II., III., and IV. The Kalpasūtras and Somaproyogas supply the details.

<sup>183</sup> Hillsbrandt-Vedische Mythologie, I. 219-22.

<sup>193</sup> Rigveda IX. 103, E.

<sup>104</sup> Tbid, I. 93, 6; III. 48, 2; V. 36, 2; V. 43, 4; V. 85, 2; IX. 1, 18 etc.

<sup>105</sup> Tbid, I. 137. 1; III. 32. 2; VIII. 2. 9. 10.

<sup>100</sup> Tbid, VIII. 2. 5, 9, 10, 28.

six hymns in other mandalas are most lavish in its praise. It enabled men to concentrate their mind, made them active, cured their diseases and preserved their characters. 187 It was also believed to prolong their lives. 188 But it also had an inebriating effect on its consumers, ultimately inducing sleep189 and was compared with mada.190 When singing the praise of Some some Risis made apparently incoherent prayers for winning beautiful damsels, doubtless the result of an overdose of the drink.191 On the eve of a battle the warriors used to divide the Soma among themselves and drink it, probably for excitement and exhibaration. 191 Sura was the name of an intoxicating spirituous liquor. 193 It has been generally condemned in the Rigveda as under its influence, men committed sins and crimes 194 and became devoid of sense.195 It has been classed with dicing as an evil.196 It was the drink of men in the Sava and gave rise to broils"197 Panta was the name of another drink in the Rigveda. 198 As it was offered to the gods, it has been identified by commentators with Soma. But it may have been a drink of a different kind.

Sheep and Cattle-rearing: the domesticated animals—The principal animals domesticated in this age are the cow, the buffalo, the horse, camel, ass, sheep and goat. Oxen and horses were indispensible for agriculturalwork and milk was required not only for daily consumption but also for offering libations to the Sacred Fire twice a day and for preparing butter and ghee to enable the people to perform the annual and periodic sessions of sacrifice so that they might be blessed with sufficient rainfall for the successful cultivation of their crops. Pūṣhan was the god of the shepherds to whom

<sup>147</sup> Ibid, VIII. 48. 5.

<sup>189</sup> Ibid, VIII. 48. 11.

<sup>100</sup> Ibid, IX. 69, 6.

<sup>100</sup> Ibid, IX 68. 3; X. 69. 3.

<sup>101</sup> Ibid, IX. 67, 10, 11, 12.

<sup>100</sup> Ibid, IX. 106. 2.

According to Taittiriya Brāhmaņa "it was, as opposed to Some, essentially a drink of ordinary life" (Macdonell and Keith—Vedic Index, I.L. p. 458.)

<sup>104</sup> Rigyeds V11, 86, 6,

<sup>105</sup> Ibid, VIII. 2, 12; VIII. 21, 14,

<sup>100</sup> Ibid, VII. 86, 6.

<sup>107</sup> Macdonell and Keith-Vedic Index, II. p. 458.

<sup>1 00</sup> L 122. 1; I, 155, 1; VIL 92, 1; X, 88, 1,

prayers were offered. 199 "Give us wide pastures" was the cry. 200 We read of cattle going to the pasture at daybreak for grazing, 201 of herdsmen driving them, 202 of herdsmen guarding them, 203 of herdsmen calling out to the cattle 204 and of herdsmen driving them home from the pasture. 205 The eager solicitude for the welfare of their kine will be evident from the following verses:—

"May Pūşhan follow near our kine; may Pūşhan keep our horses safe:

May Pūşhan gather gear for us.

Follow the kine of him who pours libations out and worship thee;

And ours who sing songs of praise.

Let none be lost, none injured, none sink in a pit and break a limb

Return with these safe and sound."206

"Yea, let the herdsman, too, return, who marketh well their driving forth;

Marketh their wandering away, their turning back and coming home

Home-leader, lead them home to us; Indra, restore to us our kine

We will rejoice in them alive."207

"May the wind blow upon our cows with healing; may they eat herbage full of vigorous juices.

May they drink waters rich in life and fatness: to food that moves on feet be gracious, Rudra."208

From the above quotations it is evident that the cattle were objects of great care with the Rigvedic Aryans. They were kept in the cowstall,\*\*\*

```
200 Rigveda I, 42; VI, 54; VI, 55; VI, 56; VI, 57.

200 Ibid, I. 42, 8.

201 Ibid, V. 31, 1.

202 Ibid, V. 31, 1.

203 Ibid, VI, 19, 3.

204 Ibid, III, 35, 9.

204 Ibid, VI, 54, 5—7.

205 Ibid, VI, 54, 5—6.

206 Ibid, X, 169, 1.

207 Rigveda V, 23, 10; V, 24, 5; V, 45, 6; V, 62, 2; VI, 10, 3; VI, 17, 2; VI, 28, 1; VI, 45, 24; VI, 62, 11; VI, 65, 5; X, 169, 3, 4,
```

fed on barley and corn, 2 10 and supplied with pure drinking water raised from the wells and poured into wooden cattle-troughs which were bound with straps for being conveniently carried from the side of the wells to the cowpens.\*11 Prayers were offered to Agni not to burn up the places where the cattle find refuge and food. 212 The milching of the cow was usually done by the daughter of the householder as the word duhitr proves. 213 We have already seen that besides milk and the preparations from milk, cow was also used for food and as a standard of value in purchasing goods. Oxen were used for ploughing 214 and for drawing cars and waggons. \$15 The skin served the purpose of a mattress, specially for the newly married wife who had to sit on a cowhide along with her husband. The hide was also used in covering chariot. 216 We also read of wine-bottles made of leather,217 of skins for carrying water,218 of a skin filled with meath kept in the chariot219 and of a skin containing curds. 220 No wonder, therefore, that Rigvedic princes vied with one another in making gifts of cows to the most deserving. 221 The name of the sacrificial fee daksina is explained as referring originally to a cow placed on the right hand of the singer of hymns for reward. The composer of the hymns of the Rigveda compares himself to the cow and his hymn to the milk. 322 The composers also delight to compare their songs to the lowing of cows to their calves. \*\*\*

Buffalo was well konwn.224 We have already seen that besides ita milk, its flesh was also eaten.225 That buffaloes were used in drawing cars is evident from a hymn of the Rigveda 228 where mention is made of a car

```
210 Ibid, X. 27. 8.
```

\*\*\* Ibid, X. 101. 5-7.

212 Ibid, IX, 97, 47,

910 Ibid, II, 2, 1.

127 Ibid, I. 191. 10.

<sup>312</sup> Ibid, L 47. 3.

<sup>314</sup> Ibid, IV. 57. 4; X. 106. 2.

<sup>910</sup> Ibid, VI. 47. 27.

<sup>\*10</sup> Ibid, I. 85, 5,

<sup>220</sup> Thid, IV, 45, 1. and Ibid, VI. 48, 18. Compare Krivi, Rigveda II. 17. 6; II. 22. 2.

Rigveda I, 126, 1-4; V. 30, 12-15; VIII, 1, 33; VIII, 4, 20-21; VIII, 5, 37; VIII. 5, 47; I. 122, 7; VII. 8, 22.

<sup>\*\*\*</sup> Ibid, I. 186. 4.

<sup>\*10</sup> Ibid, VI. 45, 25; VI. 45, 28; VIII, 77. 1.

<sup>224</sup> Ibid, IV. 21. 8; V. 29. 7, 8; VI. 5. 37; VIII. 6. 48; VIII. 35. 8; IX. 33. 1.

Ibid, V. 29.8; VI. 17. 11.

<sup>\*\*\*</sup> Ibid. X. 102.

which was drawn by a team, one of which was a bull and the other a buffaloes were also objects of gifts. 227

The horse has various names in the Rigveda. It was called atya (runner), arvant (the swift), vajen (the strong), sapti (runner) and haya (the speeding). Horses of various colours were known, dun (harita, hari), ruddy (aruna, arusa, piśanga, rohita) dark-brown (śyava), white (śveta) etc. The regions bordering upon the Sindhu<sup>228</sup> and the Saraswati<sup>229</sup> were famous as breeding places of horses. Horses were used to draw not only carts laiden with harvested corn 250 but also carriages or chariots containing passengers. It seems to have been considered undignified for a wealthy man to come to the sacrificial assembly in a one-horse car. 281 It is surprising to be told by some European scholars that though the horse was employed to draw carts and carriages or chariots, it was not used for riding. 239 Macdonell remarks "No mention is made of riding in battle." 238 Professor Keith observes "Though horse-riding was probably not unknown for other purposes, no mention is made of this use of the horse in war." \*\*\*\* But as a matter of fact, we find innumerable references to horse-riding\*\*\* and even of the use of horse in war. 286 Thus we read :-

"Where are your horses, where the reins? How came ye? how had ye the power?

Rein was on nose and seat on back

The whip is laid upon the flank. The heroes stretch their thighs apart,

Like women when the babe is born." 287

<sup>\*\*\*</sup> Ibid, VIII. 5. 37; VIII. 6. 48.

<sup>\*\*\*</sup> Ibid, X. 75. 8.

<sup>\*\*\*</sup> Tbid, I. 3. 10; IL 41. 48; VI. 61. 3, 4; VII. 90. 3.

<sup>200</sup> Rigveda X. 101. 7. Did, X. 131. 3.

Macdonell-History of Sanskrit Literature, p. 150. vedic Index, I. p. 42.

<sup>804</sup> Rapson-Cambridge History of India, Vol. 1. p. 98.

<sup>\*\*\*</sup> Rigveds I. 155. 1; I. 158. 3; I. 162. 17; II. 1. 6; II. 27. 22; V. 61. 2, 3; V. 61. 11; V. 53. 3; V. 34. 3; V. 64. 7; VIII. 5. 7, 8; VIII. 6, 36.

<sup>\*\*\*</sup> Rigveda II. 34. 3; IV. 42. 5; V. 61; VI. 93. 1; VI. 46. 13, 14; VI. 47. 81; IX. 37. 5; IX. 86. 3; IX. 108. 2; X. 6. 6; X. 96. 10.

<sup>237</sup> Ibid, V. 61. 2-3.

No better description can be given of riding a horse. In another hymn addressed to the horse we read:

"If one, when seated, with excessive urging hath with his heel or with his whip distressed thee,
All these thy woes, as with oblation's ladle at sacrifices, with my prayer I banish." 288

As regards the use of the horse in war by the cavalry we read :

"Our heroes, winged with horses, come together. Let our car-warriors, Indra be triumphant." 289

Here the poet evidently mentions two separate classes of warriors—"heroes winged with horses" (asvaparṇāh, meaning 'riding on fleet horses') and "carwarriors." In another hymn we read:

"Heroes with noble horses (svaśvāh) fain for battle, selected warriors call on me in combat.

I Indra Maghavan excite the conflict.

I stir the dust, Lord of surpassing vigour." \$40

Dadhikras is the name of the divine war-horse whose feats are described in the Rigveda.<sup>241</sup> The Rigvedic Aryans were also fond of horse-racing which supplied the people—with fun and excitement and the horses and their riders with exercise necessary to keep them fit. Thus we read:

"Indra hath helped Etaşa, Somapresser, contending in the race of steeds with Sürya." \*\* \*\*

"To him these ladles go, to him these racing mares." 348

"They have come nigh to you as treasure-lover, like mares, fleet-footed, eager for glory." 344

The race-course was called Kāṣṭhā<sup>945</sup> or āji<sup>346</sup> and the person who instituted a horse-race was called āji-kṛt.<sup>947</sup> The Rigvedic Aryans were also fond of the race of chariots drawn by horses, for, it was "the peaceful preparation for the decisive struggle on the battle-field." Thus we read:

<sup>980</sup> Ibid, I. 162. 17.

<sup>230</sup> Rigveda VI. 47. 31.

<sup>942</sup> Ibid, IV. 38; IV. 39; IV. 40.

<sup>240</sup> Ibid, J. 145. 3.

<sup>\*\*\*</sup> Ibid, VIII. 80. 8.

<sup>94</sup> Ibid, VIII. 53. 6.

<sup>940</sup> Ibid, IV. 42. 5.

<sup>249</sup> Ibid, I. 61. 15.

<sup>244</sup> Ibid, IV. 41.9; compare also IX. 97. 25.

<sup>24.8 ;</sup> X. 156. 1.

sas Kaegi's The Rigveds, p. 19.

"Ho there! why sittest thou (O Indra) at case? Make thou my chariot to be first:

And bring the fame of victory near."949

"As for a chariot-race, the skilful Speaker (Soma), Chief, Sage, Inventor, hath with song been started."250

"Thou conquerest thus with might when car meets car and when the prize is staked." \*\*51

The horse was occasionally used for sacrifice and its flesh was partaken of by the worshippers. 252 Horses like cows were also objects of gift. 253

Camels are frequently mentioned. 254 They were used for carrying loads 255 and as objects of gift. 256

Asses are also mentioned as drawing the car of the Aświns. They were also objects of gift. Wild ass is also referred to in the Rigveda according to Von Roth.

Sheep<sup>260</sup> was a very useful animal in this age, for, besides its milk and flesh, its wool was a material for clothing. Pushan is described in one verse<sup>261</sup> as "weaving the raiment of the sheep." The Indus region was wooly (suvasa urnavati)<sup>262</sup>; Parusni also was wooly<sup>263</sup>; and the softest wool was of the ewes of Gandharans.<sup>264</sup>

Goats are repeatedly mentioned in the Rigveda.<sup>265</sup> Pushan's chariot like Thorr's in the Edda is said to be drawn by a team of goats.<sup>266</sup> Besides

```
24 * Rigveda, VIII, 69. 5.
                                        aso Ibid, IX. 91. 1.
201 Ibid, IX, 53, 2,
                                        *** Ibid, I. 163, 10, 12, 13, 19.
252 Ibid, I. 123. 2; VII. 18, 23; VIII. 1. 32; VIII. 3. 21, 22; VIII. 4. 19; VIII. 6. 47;
      VIII. 46. 23.
244 Ibid, I. 138. 2; VII. 5. 57; VIII. 6. 48; VIII. 46. 22, 31.
258 Ibid, L. 138. 2.
                                        *** Ibid, VIII. 5; VIII. 46.
207 Ibid, I. 34.9; I. 116.2; I. 117. 16; I. 162. 21; IV. 36.1; VIII. 74.7.
200 Ibid, VIII. Balkhilya Hymn No. 8, line 3,
200 Thid, X. 86. 18.
                                        200 Ibid, I. 10. 2; I. 51, I; I. 52. 2; etc.
ses Ibid, X. 26. 6.
                                       262 Ibid, X. 75. 8.
see Ibid, IV. 22. 2; V. 52. 9. see Ibid, I. 126. 7.
ses I. 162, 2; I. 163, 12; II. 39, 2; VII. 18, 17.
244 Rigyeds 1. 138, 4; IX. 67. 10; X. 26. 8.
```

the milk of the she-goat, and the flesh of the goat, its wool was a material for clothing. In early times goat-skins were worn, ajin coming from aja, a goat.

Elephants, 367 deer, 368 spotted deer, 369 pigeons, 370 swans, 371 peafowls, 378 parrots, 278 quail, 274 chakwa (chakravaka), 275 cuckoo, 276 antelopes 277 and wild boars 378 are also mentioned.

Economic importance of Forests—The forests were of great economic value to the Indo-Aryans of this age. In the first place, they served as natural pastures. The forest secondly, they were utilised as burial places and probably also as cremation grounds. Thirdly, a hymn of the Rigveda makes it apparent that certain classes of people used to live in the forest tracts. Lastly, they provided the house-holder with the materials for the construction of houses, chariots, sacrificial implements and the like. Above all, they were a constant source of fuel to the community. It is no wonder, therefore, that the people regularly prayed that the trees and the plants would be endowed with sweetness so that they might conduce to the benefit of the people—

"To us Herbs and Forest trees be gracious."\*\*

Again "May herbs that grow on ground and Heaven

And Earth accordant with Forest-Sovrans, and both the

World-halves round about protect us."\*\*

```
307 Ibid, I. 64. 7; VI. 4, 5; VIII. 33. 8; VIII. 45. 5; IX. 57. 3; X. 106. 6.
```

<sup>200</sup> Ibid, I. 38, 5; I. 105, 7; I. 163, 1; VIII, 2, 6; IX. 32, 4,

<sup>200</sup> Ibid, I. 37. 2; VIII. 7. 28. 270 Ibid, I. 30. 4; X. 165. 1, 2.

<sup>\*\*1</sup> Ibid, I. 65. 5; I. 163. 10; VIII. 35. 8; VII. \$9. 7; IX. 32. 3.

<sup>\*\*\*</sup> Ibid, I. 191. 14; III. 45. 1. \*\*\* Ibid, I. 50. 12.

<sup>\*\*\*</sup> Ibid, I. 112. 8; I. 117. 14; I. 117. 16.

<sup>97</sup> Ibid, VII. 104. 22. 977 Ibid, I. 64. 8; VIII. 4. 10.

<sup>27.</sup> Ibid, I. 61. 7; I. 88. 5; I. 114. 5; VIII. 66. 10; VII. 55. 4; IX. 97. 7; X. 28. 4; X. 67. 7; X. 99. 6.

<sup>970</sup> Ibid, X. 146. 3; compare Ibid, IV. 1. 15.

<sup>\*\*\*</sup> Ibid, X. 18. 4, 10, 12.

<sup>\*\*\*</sup> Compare Ibid, X. 146. 4, 5. \*\*\* Rigveda VII. 35. 5.

<sup>904</sup> Ibid, VII, 34, 28,

Poid, I. 135. 8; X. 31, 10; X. 51. 2; X. 97. 5.

The various useful trees mentioned in the Rigveda are: -(1) Asvattha \*\* 5: from the wood of this tree and of Sami tree are made the arani, the two pieces of wood which are rubbed together to produce the sacred fire-the upper and the harder piece is the Sami and the lower and the softer is the Asvattha wood. The vessel for holding the Soma juice is made of the wood of this tree. 236 Other sacrificial vessels were also made of the wood of this tree and hence it is called "the home of plants used in religious ceremonies." 987 (2) Same (Acacia Suma)288: its wood formed the upper log of arani which when rubbed against the lower log of Asvattha wood produced the sacred fire. Its juice says Dhanwantari when applied on the body would deprive the skin of hair. (3) Parna or Palasa (Butea Frondosa)200: sacrificial vessels were made of the wood of this tree and hence it is called the "mansion" of the plants used in religious ceremonies. 200 (4) Khadira (Acacia Catechu): the pin of the axle of chariots was made of this hard wood. 291 (5) Haritala (haridrava) 292: according to Sayana it was a kind of tree. (6) Semala (Salmalia Malbarica)298: it is also known as the Simbala or Salmali tree. Its blossoms give silk-cotton, 294 while its wood, being hard was used in the construction of the wheels of chariots. 295 (7) Sinsipa, sisu tree 996 : cars were made of this timber 207 which is called the "sovran of the wood" \$98 (8) Kinsuka (Butea Frondosa) \$299 : wheels of chariots were made of this wood. 300 (9) Vibhidaka or Vibhitaka (Terminalia Bellerica)301: These trees were tall, of windygheights and their nuts were used as dice in early times. 809 (10) Kākambara 103 it is apparently the name of some umbrageous tree. 304

```
200 Ibid, I. 135, 8.
```

<sup>160</sup> Ibid, X. 97. 5; X. 51. 2.

<sup>200</sup> Tbid, X. 97. 5.

<sup>201</sup> Rigveds III. 53, 19.

<sup>\*\*\*</sup> Ibid, III. 53. 22; VII. 50. 3; X. 85. 20.

<sup>308</sup> Ibid, X. 85, 20.

<sup>307</sup> Ibid, III. 53. 19.

<sup>100</sup> Ibid, X. 85. 20.

ao1 Thid, X. 34, 1.

<sup>\*\*\*</sup> Ibid, VI 48. 7.

<sup>\*04</sup> Griffith-Rigveds, Vol. I. p. 614 fn.

per Thid, X. 97. 5.

ans Ibid, IV. 27. 4; X. 97. 5.

<sup>209</sup> Ibid, I. 50, 12.

<sup>\*\*\*</sup> Ibid, III. 53, 22.

<sup>900</sup> Ibid, III. 53, 19.

<sup>\*\*\*</sup> Ibid, III. 53. 20.

<sup>900</sup> Ibid, X. 85, 20,

<sup>100</sup> Ibid, X. 34 1

Various species of grass are also mentioned in the Rigveda:—
(1) Dūrvā<sup>\$0,5</sup> (Panicum Dactylon): it is a species of bent grass whose filaments stretch horizontally away from the stem. (2) Kuśa<sup>\$0,6</sup> (Poa Cynosuroides): this grass, after its roots are cut off, is spread on the sacrificial altar; and upon it the libation of Soma juice or oblation of clarified butter is poured out. It is also spread over the sacrificial ground or floor to serve as a seat for the gods and the sacrificers. The flame produced by the attrition of the two logs of wood which constituted the arani was caught by the tuft of Kuśa grass carefully kept between the two.<sup>\$0,7</sup> (3) Munja<sup>\$0,8</sup>: the strainer through which Soma juice was filtered was made also of this grass.<sup>\$0,9</sup> (4) Balbaja<sup>\$1,0</sup> (Eleusine Indica): it was a species of coarse grass used in religious ceremonies and for other puroposes when plaited.<sup>\$3,1,1</sup> Besides these, different varieties of grass like Sara, Darbha, Kuśara, Sairya and Virana are mentioned in which snakes and other venomous reptiles lurk.<sup>\$3,1,2</sup>

Among the plants Soma was undoubtedly the most important, for, as we have seen, its juice was used in sacrificial drink. It grew on the mountains, that of Mujavant being specially renowned. Medicinal herbs and plants are frequently mentioned in the Rigveda. In the tenth mandala of the Rigveda we find a hymn of twenty-three stanzas in praise of medicinal herbs and plants. To of these Pata is mentioned, probably indentical with Patha (Clypea Hernandifolia), a climbing plant, possessing various medicinal properties. To

Hunting and Fishing—Besides agriculture and cattle-rearing, hunting and fishing remained the occupation of a large section of the people,

<sup>805</sup> Rigveda X. 134, 5; X. 143, S. 806 Ibid, I. 4, 3; III. 29, 1.

Rigveda III. 29. 1. In the Satapati Brahmana V. 2, 1, 8 the wife of the sacrificer wears a garment of Kusa grass for some rites—a relic of primitive dress.

<sup>\*\*</sup> Rigveda I. 161. 8; I. 191. 3. \*\* Ibid, I. 161. 8.

<sup>\*10</sup> Ibid, VIII. Balkhilya 7. 3. \*11 Griffith's Rigveda Vol. II. p. 265 fn.

<sup>\*10</sup> Rigveda I. 191, 5.

<sup>\*1\*</sup> Ibid, I. 93. 6; III. 48. 2; V. 36. 2; V. 48. 4; V. 85. 2; IX. 1. 18. etc.

<sup>814</sup> Ibid, I. 43. 2; VII. 34, 23; VII. 35. 5.

<sup>\*1</sup> Ibid, X. 97. \*1 Ibid, X. 145. 1.

<sup>319</sup> Griffith's Rigveda, Vol. II. p. 589 fa.

specially the aborigines. The word śva-ghnin occurs in the Rigveda<sup>313</sup> in the sense of hunter as well as gambler. The arrow was employed in hunting down beasts<sup>319</sup> and the normal instruments of capture were nets and pitfalls. Nets were called pāśa<sup>320</sup> or nidhā,<sup>321</sup> the hunter being called pāśin. Pits were used for capturing antelopes (ṛṣya) and so were called ṛṣya-da, antelope-catching. Hunters chasing a deer<sup>322</sup> and wild elephants<sup>23</sup> are referred to. Lions were captured in pits covered with snares<sup>324</sup> or were surrounded by the hunters and slain.<sup>325</sup> In another passage<sup>326</sup> we read that "the Soma flows on in order to be taken up and used in libations as a lion goes to the place where men lie in wait to capture him or where a pitfall has been prepared to entrap him."<sup>337</sup> The capture of the wild steer is referred to thus:

"Even the wild steer in his thirst is captured: the leather strap still holds his foot entangled" 3 2 8

Wild bulls were sometimes hunted down with the arrow 'from the archer's bow-string'. The boar was captured in the chase with the help of hounds "who seize him and bite him in the ear." Birds were caught in nets, the bird-catcher being called nidhipati. Sometimes birds were shot down with the arrow. St

Fish is mentioned in the Rigveda<sup>332</sup> as well as pearls.<sup>333</sup>

The growth of arts and crafts—As regards the arts and crafts of this period scholars differ. According to Professor Kaegi "In arts the race still stood on the lowest stage" while Professor Ragozin and Macdonell hold the opposite view. According to Macdonell "already in this period

```
*1 I. 92. 10; IL 12. 4, 5; IV. 20. 3; VIII. 45, 38.
810 Rigveda, IV. 58. 6; X. 51. 6.
                                             820 Ibid, III. 45. 1; VI. 48. 17.
*** Ibid, IX. 83. 4; X. 73. 11.
                                             399 Ibid, VIII. 2, 6.
3 18 Ibid, X. 40, 4.
                                             594 Ibid, X. 58, 10.
ase Ibid, V. 15. 3.
                                             320 Ibid, V. 74, 4.
307 Griffith's Rigveda, Vol. L. p. 542 fn.
                                            *** Rigveda X. 25. 10.
                                            900 Ibid, X. 86. 4.
399 Ibid, X. 51. 6.
381 Ibid, II. 43. 2.
                                            *** Ibid, VII. 18.6; X. 68.8.
*** Ibid, I. 35. 4; I. 126. 4; VII. 18. 23; X. 68. 11.
*34 Introduction to the Rigveds, p. 40.
```

specialisation in industry had begun." The chief impulse for this specialisation had come from the ever-increasing agricultural and military needs of the community, settled in the midst of a hostile population. There was a well-marked tendency towards division of labour and the growth of various sub-crafts, leading ultimately to the organisation of craftsmen even into guilds. A further impetus towards the development of industry came from the fact that in this age some of the craftsmen like the Ratha-kāra and the Takṣan enjoyed a considerable social status. They stood in close relation to the king of whom they were regarded as sti or clients. \*\*35\*\*

From the researches of Professors Max Muller<sup>386</sup> and Schrader<sup>387</sup> regarding the Indo-European group of languages we find great similarity existing between the Sanskrit words Tan and Tanti (string) and Zend Tan and Greek Teinō and Latin Tendo, all meaning stretching. For weaving we have the Sanskrit root Ve, akin to Latin Vieo and Teutonic Weban. Similarly, Sanskrit Takṣan is akin to Zend Tashan and Greek Tektan, all meaning a carpenter. For plaiting we have the Sanskrit root Pre, akin to Greek Plekō and Latin Plico, all similar in sound and meaning. The conclusion may, therefore, be safely drawn that a common knowledge of some of these crafts (e.g., those of the weaver, the carpenter and the plaiter of grass and reeds) existed among the people speaking the Indo-European group of languages.

(1) Weaving industry—The Rigveda contains many passages which show that even then the people were perfectly familiar with the art of weaving. The passages, it must be confessed, are brief and casual, occuring mostly by way of similes and metaphors in hymns designed for the glorification of particular divinities; but they are none the less interesting and suggestive on that account. Thus the verse "Night and Morning like female weavers ........... interweave in concert the long-extended thread, the web of worship" 333 gives only a simile, yet that refers to a familiar fact whose existence cannot be questioned. Again we have a verse 330

<sup>\*\*\*</sup> Rigveds X. 97. 23; Macdonell and Keith-Vedic Index, Vol. I. p. 96.

<sup>386</sup> Biographies of Words.

<sup>\*\*\*</sup> Reallexikon der Indogermanischen Altertumskunds.

<sup>\*\*\*</sup> Rigveds IL 3. 6.

<sup>\*\*\*</sup> Ibid, II. 88. 6.

which Wilson following Sayana paraphrases thus: "She (Night) enwraps the extended (world) like (a woman) weaving (a garment)."340 Elsewhere we read "Mothers weave garments for him their offspring."341 The words tantum, otum and vayanti occur in the following versesas: "I know not either warp or woof, I know not web they weave when moving to the contest." Here the threads of the warp (tantum) are the metres of the Vedas, those of the woof (otum), the liturgic prayers and ceremonial, the combination of which two is the cloth or sacrifice. According to the Vedantists the threads of the warp are the subtle elements, those of the woof the gross and their combination the universe. Tantum and Otum are also referred to figuratively in the following verse: "For both the warp and the woof he understandeth and in due time shall speak what should be spoken,"345 Tantra meaning warp or loom344 and tasara meaning weaver's shuttle 845 are also mentioned. Vaya meaning a weaver occurs in the Rigveda<sup>3 46</sup> as also various uses of the root va. 347 The expression vaso-vaya shows that other "Vaya"s had already arisen who produced sundry piece-goods other than the standard vasas or wearing cloth; besides there were the female weavers called "Siri"s. \$48 Female weavers are often referred to in the Rigveda<sup>849</sup> and there is a fling at spinsters who spin out thread in ignorance. 3 50 Indeed we have a large number of words showing the extensive use of woven garments. Thus we have at least three words to denote the ordinary wearing cloth viz., Vasas, vastra and vasana. We read-

```
*** Wilson's Rigveds II. p. 307.

*** Ibid, V. 47. 6.

*** Rigveds V. 9. 3.

*** Ibid, X. 130. 2.

*** Macdonell and Keith—Vedic Index: 'Vaya' and 'oto.'

*** Rigveds X. 71. 9.

*** Ibid, II. 3. 6; II. 38. 4. cf. V. 47. 6.

*** Ibid, X. 71. 9.

*** Ibid, X. 71. 9.
```

"Loose in the wind the woman's vasas was streaming,"354

"O worthy of oblation, Lord of prospering powers, assume they vastra." 355

"For thee the radiant Dawns in the far distant sky broaden their lovely vastra forth in wondrous beams."\*\*\*\*

"Anspicious, clad in white and shining vastra." 557

"Loudly the folk cry after him in battles, as it were a thief who steals away a vastra." 358

"Like fair and well-made vastras, I seeking riches, as a deft craftsman makes a car, have wrought them." See "Yea from his Mother draws he forth a new vasana." 360

The vasas seem to have borders and fringes denoted by the word sic. Thus in one hymn of the Rigveda<sup>361</sup> the child is covered by its mother's sic and in another<sup>362</sup> the horizons at Sunrise and Sunset are said to be the two sican of the sky-cloth. In yet another hymn<sup>363</sup> we read "I grasp, mighty Indra, thy garment's hem as a child his father's." The upper part of the body was covered by another separate garment called adhivasa.<sup>364</sup> The forests are the adhivasa of mother earth licked by the fire-child.<sup>365</sup> The drapi<sup>366</sup> is not a coat of mail as the authors of the Vedic Index say, for, it was worn by women as well. In Atharvaveda<sup>367</sup> Arati is called hiranya-drapi and is likened to a courtesan for wearing it. Moreover, the use of vasanah<sup>368</sup> would rather show that it was made of vasas. Further in the Atharvaveda<sup>369</sup> the Sun wearing the three worlds

\*\*\* Ibid, I. 26. 1.

<sup>969</sup> Ibid, VIII. 3. 24,

<sup>304</sup> Ibid, X. 102. 2.

<sup>\*\*</sup> Ibid, I. 134. 4.

ast Ibid, III. 39. 2.

<sup>\*\*\*</sup> Ibid, IV. 33. 5. 240 Ibid, V. 29. 15.

No. 1. 15. 7. For other references to woven garments read Rigweds I, 140. 1; I. 152. 1; II. 14. 3; III. 1. 6; III. 8. 4; V. 42. 8; V. 57. 4-5; VI. 4. 3; VI. 11. 6; VI. 35. 1; VI. 47. 23; IX. 8. 6; IX. 96. 1; X. 71. 4.

<sup>561</sup> X. 18. 11. \*\*\* Rigveds, L. 95. 7.

<sup>348</sup> Ibid, III. 53, 2.

<sup>\*\*\*</sup> Rigveds I. 140. 9; X. 5. 4. \*\*\* Ibid, I. 140. 9.

<sup>\*\*\* 1</sup>bid, I. 116. 10; IV. 53. 2; IX. 100. 9. \*\*\* V. 7. 10.

<sup>\*\*\*</sup> Compare drāpim vasānah, Rigveda III. 86. 14. \*\*\* XIII. 9. 1.

is said to have made a drapi of them, so that drapi like a vest or waist-cost had three pieces—two side ones and one back. It was close-fitting \$70 and gold-embroidered.311 The atka372 was worn by men only and was a long373 and fully covering374 close-fitting375 cloak, bright376 and beautiful, 877 the stuff being bleached 578 cotton 579 interwoven 380 or embroidered 381 with gold threads. Pesas 382 is gold embroidered cloth, 880 the designs being artistic and intricate384 and the inlay of gold heavy and brilliant. 38 5

The material for clothing was probably wood (ūrnā). Puşan is described as vaso-vaya, weaving woolen cloth. 3 3 6 Indra is "wearing wool Parushne for adornment"587 while the Maruts are said to "tarry on the Parushne, putting on robes of wool."388 In another hymn we learn of "weaving the raiment of the sheep."359 In this age the wool of Gandhara, 590 of the Parushni country 391 and of Sind 399 was highly prized.

372 Ibid, I. 25, 13 (hiranyayam); IV. 53, 2 (pisangam).

379 Ibid, L. 95. 7; I. 123, 2; IV. 18. 5; VI. 29. 3; VIII. 41. 7 etc.

97 . Ibid, V. 74. 5 (vavrim atkam, likened to Cyavana's old age.:

ava Sarabhimatkam : Rigveda VI. 29. 3; X. 123. 7.

\*\*\* Like Sun : Rigveda VI. 29. 3; X. 129. 7.

377 Sudrái : Rigveda I, 122, 2.

ara Sukram : Rigveda I. 95. 7.

•7. As vyūtam (Rigveda I. 122. 2) and frequent use of vasanah shows.

\*\*\* Hiranyair vyūtam : Rigveda I. 122, 2.

\*\*\* Hiranyayan : Rigveda V. 56, 6.

see Rigveda I. 92, 4; IV. 36.7; IL 3.6; VII. 34, 11; X. 114, 3 etc.

\*\*\* Rigveda IV. 36, 7. VIII. 31, 11; VII. 42, 1.

304 Ibid, II. 3. 6.

see Ibid, VIL 34, 11 (the glittering surface of rivers - petas). Compare X, 114. where peter is called bright as ghee (i.e., golden.)

ses Rigweds X. 26. 6.

107 Ibid, IV. 22. 2.

ass Ibid, V. 59. 9.

101 Ibid, X. 26. 6.

\*\*\* Ibid, I. 126. 6-7.

are Rigveda I. 166. 10 (Cyavāna's old age like a drāpi); probably drāpi-a tight vest suitable for running about (dra).

ate Ibid, II. 35. 14 (food carried in one's own atka : i.e., in the long skrit made into an apron.

set Ibid, IV. 22. 2; V. 52. 9.

<sup>\*\*\*</sup> Ibid, X. 75. 8.

In the Rigveda there is no mention of cotton (kārpīs) though silk-cotton tree was known. When, however, we bear in mind that already in the Calcholithic age the people of the Punjab and Sind knew the use of cotton and cotton-weaving the following remarks of Professor Muir gain added strength: "It is difficult to conceive that cotton (which as we learn from Professor S. H. Balfour, is supposed to have been indigenous in India), though not mentioned in the hymns, should have been unknown when they were composed or not employed for weaving the light cloth which is necessary in so warm a climate." \*\* Long ago Professor Ragozin also wrote in the same strain "The Aryan settlers of Northern India had already begun at an amazingly early period to excel in the manufactures of the delicate tissue which has ever been and is today doubtless incomparably great in perfection, one of their industrial glories—a fact which implies cultivation of cotton-plant or tree." \*\* 394\*

Metal industry—The metal industry was also in a highly developed condition "but it is, however, still uncertain" says Mr. Macdonell "what that metal which was called ayas was." The evidence of some of the old texts is often misleading. Thus in the Satapatha Brāhmaņa \$95 ayas is any metal which is neither gold nor lead. In the Vājaseniya Saṃhitā \$06 ayas is separated from Loha and Syāmam. From the Atharvaveda \$07 and even the Rigveda \$38 the sense of iron for ayas is certain. Professor Schrader in his Prehistoric Antiquities well points out that Sanskrit ayas = Latin \$\sigma es = \text{Goth aiz} = \text{Zend ayarih}, meaning pure dark copper and it is, therefore, quite probable that ayas of the Rigveda was neither iron nor bronze but the pure dark copper, a knowledge of which was common to all the Indo-European peoples. He further points out that "a series of names of copper gradually assumes the name of iron." Thus Sanskrit Loha originally meant copper but later it was used to denote iron. \$98

<sup>503</sup> Muir's Sanskrit Texts, V. p. 462.

<sup>\*\*\*</sup> Ragozin-Vedic India, p. 306.

<sup>\*\*\*</sup> V, 1. 2, 14.

<sup>\*\*\*</sup> XVIIL 13,

<sup>\*\*\*</sup> X. 3. 17.

<sup>\*\*\*</sup> Schrader-Prehistoric Antiquities, p. 212; Max Muller-Biographics, of Words,
Appendix V.; Macdonell and Keith-Vedic Index, I. p. 32.

In the Rigveda we have distinct references to the smelting of metals and the business of the smith. 401 Vessels called mahāvira or gharmā made of ayas 402 and receptacles hammered or formed with a tool of ayas 403 are mentioned. We also read of chariots whose pillars or rather poles were made of ayas. 404 Knives made of ayas, 405 axes wrought of good metal, 406 arrows tipped with ayas 407 and the bits of the horse made of ayas 408 are also mentioned. Swords, 409 breast-plates, 410 lances, 411 spears, 412 daggers, 413 rings or quoits, 414 hatchets, 415 axes, 416 knives, 417 awls, 418 sickle, 419 hooks, 420 nails, 421 needles 422 and razors 423 are mentioned.

According to Professor Schrader gold was known to the Indo-Iranians as is proved by the similarity between Sanskrit hiranya and zend zaranya; and as a matter of fact we find innumerable references to gold and its use in the manufacture of weapons and ornaments as well as in exchange. Golden helmets for the head, 426 golden swords, 425 golden fellies, 426 cars

```
400 Rigveda IV. 2. 17; V. 9. 5; VI. 3. 4; VI. 12. 3; IX. 72. 2; X. 61, 3.
 4et Ibid., IX 72, 2; IX. 112, 2.
                                         409 Ibid., V. 30. 15.
 405 Ibid., IX. 1, 2; IX. 80, 2,
                                         404 Thid., V. 62, 7; V. 62, 8,
 408 Ibid., VIII. 29. 3.,
                                         404 Ibid, X. 53. 9.
 407 Ibid., VI. 75. 15.
                                         400 Ibid., IV. 37. 4.
 409 Ibid., I. 37. 2; I. 87. 6; I. 88, 3; V. 53. 4; X. 20. 6.
 410 Ibid., V. 53. 4.
 ATS Ibid., I. 64. 4; I. 88. 1; V. 54. 11; V. 55. 1; V. 60. 3; VIII. 20. 11.
412 Ibid., I. 31. 1; L. 37. 2; I. 85. 4; I. 87. 3; L. 167. 3; I. 169. 3; V. 57. 2;
       X. 78. 7.
410 Ibid., V. 57. 2.
414 Ibid., I. 64, 10; I. 87, 6; I. 166, 9; I. 168, 3; VIII, 85, 9; X, 38, 1; X, 73, 9.
*1 1 Ibid., III. 8, 11; VI. 3, 4.
41* Ibid., I, 162. 9; I. 162. 18; III, 2. 1; III. 2. 10; III. 52, 22; V. 43. 4;
       VII. 3; 9; VII. 83, 1; VII. 104, 21; VIII. 62, 17; IX. 96, 6; X. 53, 10,
417 Ibid., L. 130. 4; of. I. 166. 10.
                                                 418 Ibid., VI. 53. 6.
410 Ibid, I. 58, 4; IV. 20, 5; VIII, 67, 10; X. 101, 3,
490 Ibid., I. 162. 3; III. 45, 4,
482 Ibid., I, 162, 9.
                                         499 Ibid., II. 33, 4.
425 Ibid., VIII. 4. 16; X. 28. 9; cf. X. 142, 4,
434 Ibid., 1L 34. 3; VIII. 7, 25.
45 Ibid., 1. 42. 6; VII. 97. 7; VIII. 7. 32.
430 Ibid., L. 64. 11.
```

with golden seats,427 chariots decked with gold,428 golden mail,429 golden coloured mail,430 golden mantles,431 spears and weapons bright with gleaming gold432 and arrows decked with gold433 are mentioned.

Gold ornaments are frequently mentioned. 434 Gold chains worn on the breast,435 gold on the priest's finger,436 visors of gold for the head,457 gold trappings for horses, 458 golden ornaments for kine 439 and golden goad for horses440 are mentioned. Besides golden ornaments we find many references to glittering ornaments. 441 In the four Vedas, however, the word alamkara does not occur. 449 The words aramkrta and aramkrti, having the sense of ornament do occur. From the Rigveda we get the names of the following ornaments of this period: -(1) Anūka. Geldner takes it as an ornament, though Roth, Ludwig and Oldenburg take it as an adverb only. But as the Vedic commentators have taken it to be an ornament, we may accept it as such. (2) Opasa.443 It was used for adorning the head. Roth thinks that it was a corruption of aba + pasa and hence meant hair-tape or hair net.444 (3) Karna-sovana.445 It means an ornament for the ears, hence earring. (4) Kukira.446 According to

```
497 Ibid., IV. 46. 4.
```

<sup>430</sup> Ibid., V. 57. 1; VII. 69. 1; VIII. 5. 35; VIII. 46. 24.

<sup>400</sup> Ibid., I. 25. 13.

<sup>430</sup> Ibid. IV. 53, 2.

<sup>481</sup> Ibid., V. 55. 6.

<sup>489</sup> Ibid., V. 52, 6.

<sup>450</sup> Ibid., VIII. 66. 11.

<sup>484</sup> Ibid., I. 85. 3; V. 56. 1; VII. 57. 3; VIII. 20. 11; X, 46. 33.

<sup>400</sup> Ibid., I. 64, 4; I. 166, 10; V. 54, 11; X. 78, 2; of, VIII. 20, 22.

<sup>450</sup> Ibid., VIII. 29. 1; IX. 27. 4; IX. 55. 1; IX. 86, 43; IX. 97. 1.

<sup>487</sup> Ibid., V. 54, 11.

<sup>430</sup> Ibid., IV. 2. 8; IV. 37, 4.

<sup>400</sup> Ibid., VIII. 54. 10.

<sup>440</sup> Ibid., VIII, 55. 3.

<sup>\*\*1</sup> Ibid., I. 37. 2; I. 64. 4; I. 166. 10; V. 53. 4; VIII. 20. 7; VIII. 67. 2.

<sup>449</sup> The word alamkara occurs for the first time in the Satapatha Brahmana : Afijanavyafijane prayachchatieşah amanuşah alamkarah, XIII. 84. 7; also III. 5, 1, 36,

<sup>44.</sup> Rigveds, X. 85. 8.

<sup>866</sup> Bloomfield in his Hymns of the Atharvaveda, pp. 538-39 takes it meant coverlet for women (Orug). Prof. Sabimal Sarkar in his Some Aspects of the Earliest Social History of India, pp. 71-72 take it to mean a style of hair-dressing.

<sup>44.</sup> Rigveds, I. 112. 14; VIII. 67. 3.

<sup>446</sup> Ibid., X. 85. 8.

Zimmer it means peacock and therefore may well have been an arch-like ornament.447 (5) Krsan (6) Krsanin (7) Khādi. According to Roth it was of three kinds: (a) an ornament for the legs like anklets 448 (b) an ornament for the arms like modern armlets or for the wrists like modern bangles449 and (c) ring for the fingers.450 (8) Niska. It was a necklace consisting of niskas, a kind of coins, as the word niskagriva \* 51 would show. (9) Nyochani. (10) Pundarika (11) Puşkara (12) Pravüsana (13) Varhana (14) Vūsana) (15) Mani. 452 It was a jewel worn on the neck, as the word manigriva458 would prove, by means of a thread.454 According to the commentator Dürgācārya 455 maņi = āditya-mani, Süryakānta-mani, (16) Ratua (17) Rukma. 456 It was an ornament worn on the breast, 457 as the epithet rukma-vaksas 458 would prove. It appears to have been worn by the males as well, for, the Maruts or Wind-gods are described as decorated with it,459 (18) Rukmi (19) Lalami. It was a tiara worn on the forehead like a frontlet. (20) Varimat (21) Vyānjana. (22) Visana (23) Satapatra (24) Sivana. (25) Suniska. (26) Stūkā (27) Hiranyayī (28) Hiranyasipra (29) Hirimat.

Carpentry—The worker in wood constructed carts, 460 chariots 461 for war and race, ferry-boats 463 and ships. 463 Chariots were usually made of the wood of the Sinsipā tree; 464 the wheels of the chariots were made of

```
447 Mr. Subimal Sarkar in his Some Aspects of the Earliest Social History of India,
p. 72 takes it to be a kind of horn-shaped Coiffure.
```

\*\*\* Rigveda, V. 53, 4; V. 53, 11,

\*\*\* Ibid., I. 64, 10.

\*\*\* Ibid., I. 168. 3. \*\*\* Ibid., L. 83. 8.

413 Ibid., V. 19. 3. 458 Ibid., I. 122, 14.

\*\* Pañchaviméa Brāhmana XX. 16. 6.

\*\*\* VII. 23.

Ase Rigveda, I. 166. 10.

487 Cf. Rakmapasa in the Satapatha Brühmapa VI. 7. 1. 7.

400 Rigveds H. 34, 2; H. 34, 8; V. 55, 1; V. 57, 5 etc.

449 Ibid, V. 54. 11, and Rigveds, H. 2. 1.

401 Ibid., L. 61. 4; L. 94. 1; L. 130. 6; V. 2. 11 etc.

\*\*\* Tarah, Rigveda I. 190, 7,

\*\*\* Rigveda, I. 116. 4; I. 116. 5; I. 25. 7; I. 48. 3; I. 97. 7; I- 131. 2; V. 25. 9; V. 45. 10; V. 54. 4; V. 59. 2; VL 58. 3; VIII. 18. 17; VIII. 64. 9; VIII. 72. 3; IX. 73. 1.

<sup>\*\*\*</sup> Ibid., III. 53, 19.

the wood of the Semal tree 465 and of the Sinsipa tree; 466 and the pin of the axle of chariots was made of the wood of the Khadira tree.487 The fashioning of chariots was a frequent source of metaphor, the poet comparing his own skill of composing hymns to that of the wheel-wright.468 The carpenter's work (taksana) is also referred to in many passages. 489 One passage476 even describes "the carpenter who usually bends over his work till his back aches." Sacrificial vessels were made usually of Palasa wood. 471 Wooden buckets 472 wooden vessels, 473 large wooden sacrificial ladle, 474 small wooden ladle, specially for Soma libation, 475 wooden ladle, 476 wooden posts with carved images of girls on them 477 and wooden bedsteads are mentioned. Of the last there were three varieties: (1) the talpa478 (2) the prostha479 and (3) vahya.480 Talpa was apparently the nuptial bedstead as the special use of the word talpass in the sense of legitimate son, being born on the nuptial bed482 and its being made of sacred udambars wood would indicate. Prostha as the epithet prosthasaya would show was a furniture to recline on; while vahya was a couch as proved by the simile in the Atharvaveda483 like a tired bride ascending the vahya.

Pottery—The potter's art was also known. We read of Indra smashing the enemies like earthen vessels. 484 We also read of girls bearing water in their jars-485 evidently made of pottery.

```
*** Ibid., X. 85. 20 *** Ibid., III. 53. 19. *** Ibid., III. 53. 19. *** Ibid., I. 61. 4; I. 94. 1; I. 130. 6; III. 39. 1; V. 2, 11; V. 29. 15. *** Ibid., IV. 35. 6; IV. 36. 5; VI. 32. 1. *** Ibid., I. 105. 18. **** Ibid., X. 97. 5. *** Ibid., X. 101. 7. *** Cf. Hears, Rigueda, I. 180. 3. According to Ludwig it means neither a snake nor a thief but a tub or wooden vessel. The common name for a wooden vessel was drops, Rigueda, VI. 2. 8; VI. 37. 2; VI. 42. 10; IX. 65. 6; IX. 92. 6; IX. 93. 1.) **** Sruc, Rigueda, L. 84. 18; I. 110. 6; I. 144. 1.
```

<sup>478</sup> Srupa, Rigveda, I. 116. 24; I. 121, 6.

<sup>474</sup> Drawi, Rigveda, V. 6, 9; X. 105, 10.

<sup>477</sup> Rigvedn, IV. 32, 23. 418 Ibid., VII. 55. 8. 418 Ibid., VII. 55. 8.

<sup>\*\*\*</sup> Satapatha Brahmana XIII. 1, 6, 2,

Taittirlya Brāhmaņa. 400 IV. 20. 3.

<sup>\*\*\*</sup> Rigyeds, VII. 194. 21; X. 89. 7.

Leather work-The tanner (carmanna)488 and the leather-worker are also mentioned.487 We read of leather-receptacles for storing wine,488 meat,489 curds490 and water,491 leather-straps for chariots499 etc.

Manufacture of liquor - The principal liquors manufactured were the Soma and the Sura. The juice was extracted from the Soma plant by being pounded with stones, 493 held in the hands. 494 Then the juice was squeezed out with the fingers,405 and strained through a sieve made of wool496 or of munja grass. 497 Thus strained, the juice was blended with milk or curds.498 Another intoxicating liquor manufactured was the Sura. According to the Taittiriya Brahmana "it was, as opposed to Soma, essentially a drink of ordinary life."499 Panta was the name of another drink in this age. 500 As it was offered to the gods, commentators identified it with Soma. But it may well have been a drink of a different kind.

House-building-Though we have no extant remains of any building of this period, the great variety of words denoting a house to be found in the Rigveda shows that the people were long settled with a tradition of house-building. Agni raising his smoke to heaven has been compared to the builder of a house, rearing up a structure. 501 Measurement in connection with the building of a house or chamber is also referred to. 500 Gayasos is a common word for the house, inclusive of the inmates and their belongings; so are dama, 504 meaning house or home, implying an

```
400 Rigveds, VIII. 5, 38,
```

<sup>487</sup> Muir-Original Sanskrit Texts, pp. 462 ff.

<sup>488</sup> Rigveda, L 191. 10.

<sup>400</sup> Ibid., IV. 45, 1. 400 Ibid., VI. 48, 18, 401 Ibid., I, 65. 6 ; V. 83. 7.

<sup>\*\*\*</sup> Ibid., VI. 47. 27.

<sup>408</sup> Grana, Rigveda, I. 83, 6; I. 135, 7; adri, Rigveda, I. 130, 2; I. 135, 5,

<sup>494</sup> Rigveds, V. 45, 7; IX. 11, 5.

<sup>415</sup> Ibid., IX. 67, 8, 404 Ibid., I. 135. 6 ; IX. 103, 2, 3,

<sup>407</sup> Ibid., L. 161, 8, 414 Ibid., IX. 103, 2,

<sup>\*\*\*</sup> Macdonell and Keith-Vedic Index, II. p. 458.

<sup>&</sup>lt;sup>400</sup> Rigveds, I. I22. 1; I, 155. 1; VII, 92. 1; X, 88, 1,

<sup>601</sup> Ibid, 1V. 6. 2. 100 Ibid, II. 75. 3,

see Ibid, I. 74. 2; V. 10. 3; V. 44. 7; VI. 2. 8.

<sup>\*\*</sup> Ibid, I. 1. 8; I. 61. 9., I. 75. 5; II. 1. 2.

idea of control 508 and dhaman, 508 implying dwelling and signifying on the one hand the inmates of the house 507 and on the other law 508\_ showing the connection in the Vedic mind between the house and all conceptions of law and order. Similarly, sarma 500 is a house and pastya(f)510 and pastya(n)511 occuring singly or in the compounds pastyāvant<sup>512</sup> pastyavant<sup>513</sup> and pastya-sad<sup>514</sup> are other terms denoting a house. Dur, 515 the earlier and commoner word for door 516 has an implied sense of the whole house, 517 and dur-ya (door-posts), 518 duryona, 519 all signify the house itself. Sthanus 20 and sthunas 21 are early names for pillars while smaller timber-posts were svaru, 522 Yūpa 523 and drupad. 524 This great variety of names for posts and pillars shows that they were a marked feature of a particular type of house-building. We have also references to the use of metals in the construction of houses such as ayahsthuna (pillar made of ayas). 525 In the Rigveda a sage named Saptagu. prayed to Indra for "a spacious home unmatched among the people." \$28

```
*os Roth-St. Petersburg Dictionary, s. v. dama.
```

ses Rigveda, I. 144, 1; II. 3, 2; III. 55, 10; VIII. 61, 4; VIII. 87, 2; X. 31, 1,

sor Ibid., VIII. 101. 6; IX. 36, 14; X. 82. 3,

sas Ibid., IV. 55, 2; VI. 21. 3; VII. 63. 3; VIII. 41, 10; X. 48, 11.

sos Rigyeda VII. 82. 1; L 51. 15.

<sup>\*\*</sup> Ibid., I. 25. 10; I. 40. 7; I. 164, 30; IV. 1, 11; VI. 49. 9; VII. 97. 5; IX. 65. 23 ; X. 40. 6.

<sup>\*11</sup> Ibid., X. 96. 10, 11.

<sup>539</sup> Ibid., I. 151. 2; II. 11. 6; IV. 54. 5; IX. 97. 18.

<sup>810</sup> Ibid., IV. 55. 3; VIII. 27. 5.

<sup>\*14</sup> Ibid , VI. 51. 9. Roth-St. Petersburg Dictionary, s. v.; Pischel-Ved. Stud. Vol. II. p. 211.

<sup>815</sup> Rigveds, I. 68, 10; L. 113, 4; I. 121, 4; I. 188, 5.

<sup>116</sup> Dear in Rigveda, I. 13, 16.

say Thus Dur-ya (in masculine plural) = belonging to the door or to the house : Rigveds, I. 91. 19; X. 40. 12.

<sup>\*\*</sup> Ibid., IV. 1. 9, 18; IV. 2. 12; VII. 1. 11.

<sup>410</sup> Ibid., L. 174. 7; V. 29. 10; V. 32. 8.

<sup>200</sup> Ibid., X. 40, 13,

<sup>\*\*\*</sup> Ibid., I. 59. 1; V. 45. 2; V. 62. 7; VIII. 17. 14.

Ibid., I. 92, 5 ; L. 162, 9 ; III, 8, 6. 590 Ibid., I. 51. 14,

<sup>114</sup> Ibid., I. 24 13 ; IV. 32, 23, \*\*\* Ibid., V. 62. 7, 8.

<sup>\*\*\*</sup> X. 47, 8,

The word grad occurs in many passages of the Rigveda. 327 According to some it denotes the house of the Vedic Aryan; but as it is used of a special type of Smasina, it may well have been a mansoleum erected over or beside the grave as described in the Satapatha Brahmana. 528

The hormya<sup>523</sup> denoted the Vedic house including stables etc<sup>530</sup> and was adorned with pillars which supported the roof.<sup>551</sup> Mitra and Varuna had a palace with one thousand pillars.<sup>532</sup> The sage Bharadvāja prayed to Indra for a house which should be tri-dhātu and tri-varūtha.<sup>533</sup> According to some scholars the house prayed for was to be made of wood, brick and stone and hence called tri-dhātu. Sāyana explains tridhātu by the word tri-bhūmika, that is, three-storied or possessing three court-yards or separate apartments. The first that was in the front was probably constructed with stone to make it strong enough to stand the attacks of enemies or robbers and the second and third were made of mud and timber. The word tri-varūtha occurs again in another verse<sup>534</sup> where it probably means a house possessing three appartments. We also find references to ladies' apartments<sup>535</sup> halls of sacrifice with doors, <sup>536</sup> cow-pens<sup>557</sup> and stables for horses.<sup>538</sup>

<sup>\*\*\*</sup> IL. 42, 3; III. 53, 6; IV. 49, 6; V. 76, 4; VIII. 10, 1; X. 18, 12; X. 85, 26,

Satapatha Brihmana, XIII. 8. 1), 'enclosed by an indefinite number of Stones' (Ibid., XIII. 8. 2. 2). The Orthodox style is square or quadrilateral (Ibid., XIII. 8. 1. 1 ff), not separate from the earth, that is, not towering (Ibid., XIII. 8. 2. 1) and made of bricks one foot square (Ibid., XIII. 8. 4. 11). The unorthodox style was the prototype of Buddhistic Stupa architecture and the Orthodox style is represented in the temple architecture of Madura, Tanjore and other cities of Southern India.

<sup>\*\*\*</sup> Rigveds L 166. 4; IX. 71. 4; IX. 78. 3; X. 48. 3; X. 73. 10.

ass Ibid., VII. 56, 16; of. X. 106. 5. ast Ibid., IV. 5. 1.

<sup>\*\*\*</sup> Sahasra-sthuna, Ibid., IL 41. 5; V. 62. 6; VIL 88. 5.

<sup>\*\*\*</sup> Thid., VI. 46. 9.

<sup>\*\*\*</sup> Rigveds X. 66, 5. \*\*\* Ibid., I. 167, 3.

<sup>\*\*\*</sup> Tbid., L 13.6; I. 188. 5; IL 3. 5; III. 4. 5; III. 34. 7; III. 51. 3; V. 5. 5; V. 11. 4; V. 12. 3; VL 27. 2.

VI. 17. 2; VI. 28. 1; VI. 45. 24; VI. 62. 11; VI. 65. 5.

<sup>1</sup>bid., VII. 56. 16; cf. X. 106. 5,

Building activities must also have developed in these times through the needs of social and corporate life as in the case of the gosthi (clubs), the vidatha (royal audience-hall), the sachi and the like.

We have no direct allusion to the arts of painting and sculpture in the hymns of the Rigveds. According to Max Muller "the religion of the Veda knows of no idols"540 though Dr. Ballensen541 finds in the hymns clear references to the images of gods. Thus we read: "who for ten milch kine purchaseth from me this Indra who is mine? When he hath slain the Vrtras let the buyer give him back to me."569 Now what is signified by the purchase of Indra for ten milch kine? Was there any painted figure of Indra or carved out image of Indra on wood or stone that used to be temporarily parted with for a consideration and returned after worship? Or, is it merely a metaphorical way, as Griffith points out, of saying that the poet-priest who had obtained the favour of Indra for his patron by sacrifice demanded a fee of ten milch kine? We further read : "O Caster of Stone, I would not sell thee for a mighty price, not for a thousand, Thunderer! nor ten thousand, nor a hundred, Lord of countless wealth."545 The word used here for price is sulka. The reference must, therefore, have been to an image of Indra. The authors of the Vedic Index observe "Ten cows are regarded as a possible price for an (image of) Indra to be used as a fetish (Rigveds IV. 24. 10); elsewhere (VIII. 1. 5) not hundred, nor a thousand nor a myriad are considered as an adequate price (sulka) for the purchase of Indra" In this connection it is worthy of note that the description of gods in the Rigveda is mainly anthropomorphical and it is just possible that artists sometimes painted their figures in colour or carved out images on wood or stone to represent their functions. As a matter of fact, carved images on wooden posts are mentioned in a verse which reads: "Like two slight images of girls, unrobed upon a new-

\*\*\* Chips from a German Workshop I. p. 38.

as Mr. Subimal Sarkar-Some Aspects of the Earliest Social History of India, pp. 5-15.

<sup>\*\*\*</sup> Journal of the German Oriental Society, XXII. p. 587 ff.

Rigveda, IV. 24. 10. Griffith's Translation of the Rigveda, I. p. 427.

Rigveda, VIII. 1. 5. Griffith's Translation of the Rigveda, II. p. 108.

wrought post, so shine thy Bay Steeds in their course"544 Caste system in relation to mobility of labour-The question now presents itself as to the extent to which in the period of the kigveds the caste system had been developed and stood as a barrier against the mobility of labour. The orthodox Hindu holds that the caste system is of divine appointment and that it had existed for all time. But the sacred books themselves when they are studied historically, supply evidence both of its origin and of its growth. We are told in the Santi Parva of the Mahabharata that "at first there was no caste." The distinction between the colour (varna) of the Aryan conquerors and that of the coloured aboriginal tribes first formed the basis of easte. 545 The question is thus narrowed down to the consideration of the arguments for and against the view that among the Aryans themselves caste divisions were appearing. Messrs. Muir, \*4 \* Zimmer, \*47 and Webers 48 have denied the existence of caste in any form in this period. Professor Max Muller says "If then with all the documents before us. we ask the question, does caste as we find in Manu and at the present day form part of the most ancient religious teaching of the Vedas? we can answer with a decided 'no'."549 Weber in his History of Sanskrit Literature also hold the same view and says "there are no castes as yet, the people are still one united whole, and bear but one name that of Visas." 850 But Messrs. Geldner<sup>551</sup> and Oldenburg<sup>552</sup> hold the opposite view. It has been argued that the warriors of the community were the agricultural and industrial classes and the priesthood was not yet hereditary. Any person who distinguished himself for his genius or virtue or who for some reason was deemed specially receptive of divine inspiration could be a priest. Every Vedic householder was a priest unto himself so far at least as the

\*\* Rigvada, I. 100. 18.

<sup>846</sup> Rigveda, IV. 32. 33. Griffith's Translation of the Rigveda, L. p. 437.

<sup>\*\*\*</sup> Original Sanskrit Texts, Vol. L. pp. 239 ff.

<sup>\*\*\*</sup> Altindischen Leben, pp. 185-203.

<sup>\*\*\*</sup> Indische Studien, Vol. X. pp. 1 ff.

chips from a German Workshop, Vol. II. p. 307.

<sup>\*\*\*</sup> English Translation, p. 38.

<sup>181</sup> Vedische Studien, Vol. II. p. 146.

<sup>\*\*</sup> Z. D. M. G., Vol. LI. pp. 267 ff.

performance of ordinary daily religious duties was concerned viz., the lighting up of the sacred Household Fire and the pouring of libations of habis into it thrice a day. It was only on special occasions when any Sattra or big religious sacrifice had to be performed that the services of experts were requisitioned and paid for. These experts, did not, however, form a separate caste by themselves in the sense in which we understand it today, with its exclusiveness and strict elaborate rules as regards eating, drinking and association by marriage etc. For, "the word Brahmana, the regular name for a 'man of the first caste'" says Professor Macdonell "is still rare in the Rigveda, occurring only eight times, while Brahman, which simply means sage or officiating priest is found forty-six times"558 Indeed the growth of the caste system was the result of the complication of life due to the further penetration of the Aryans from the Punjab into the East. To resist the sudden incursion or to crush the attempts at rebellion of the aborigines, the petty tribal princes formed the nucleus of a standing armed force while the industrial and agricultural population relying on the protection of the warrior class abandoned the use of arms. Together with the growth in the size of kingdoms and the increasing complexity of civilisation, the simple ritual of an earlier period when the king himself can sacrifice for his people, grew to an extent which rendered this impracticable, while at the same time, the idea grew up that upon the faithful and exact performance of the rites depended the result of battle. The result was the growth of a priesthood, a warrior class and of a third the artisan and the cultivator sharply distinguished from one another and strictly hereditary. But the later origin of this development is proved by the fact that it took place not in the Punjab, the home of the Rigveda but in the Middle country whose geographical isolation favoured the evolution of this peculiar social system. A student of the Rigveda without knowledge of historical facts might reasonably presume that the Indus basin where the Aryans first settled in India would be the Holy land of Hinduism. The poets never tire of singing praises of the mighty Indus and its tributaries. 854 The combined testimony of the jatakas and the Greek

History of Sanskrit Literature, pp. 161-62.

<sup>044</sup> Cf. Nadl-stuti in Rigveda, X. 75.

authors proves that in the fourth century B. C. Taxila in the N. W. Punjab was still a centre of Vedic learning. But the strange fact is that orthodox Hindus regard the whole Punjab between the Indus and the Satlej as impure land unfit for the residence of strict votaries of Dharma. The reason apparently is that the N. W. territories continued to be overrun by successive swarms of foreigners from central Asia who disregarded the Brahmins with the result that the original inhabitants of the Punjab intermixed with these barbarian conquerors, imbibed their outlandish practices and did not follow the strict caste system.

While there is much truth in this view, it must be admitted that it exaggerated the freedom of the Rigveda from caste. For the term Brahmana 'son of a Brahma' which occurs no less than eight times in the Rigveda seems to show that the priesthood was normally hereditary. We are told that there is a case of a king exercising the functions of a domestic priest and sacrificing himself for his people but the alleged case, that of Devapi rests only on the assertion of a commentator of a hymn<sup>556</sup> in which Devapi appears that he was originally a king. Even, however, if this was the case, it must be remembered that even after the complete establishment of the caste system it was still the privilege of kings to exercise some priestly functions such as that of the study of the nature of the Absolute, a practice ascribed to them in the Upanisads. The arguments regarding the warrior class rest on a misunderstanding. Even in the latest Vedic epoch, we have no ground to suppose that there was a special class which reserved its energies for war alone and that the industrial population and the agriculturists allowed the fate of their tribe to be decided by contests between warrior-bands but the Rigveda certainly knows of a ruling class, and the Vedic Kingship was normally hereditary, so that we may well believe that even then there existed, though perhaps in embryo, a class of nobles who are aptly named in the term of the Purusasukta hymn, 556 Rajanyas, as being 'men of kingly family'.

But this Purusasukta hymn though commonly supposed to be "the only passage in the Rigveda which enumerates the four castes" has nothing to

<sup>\*\*\*</sup> Rigveda, X. 98.

ane Rigwede, X. 90.

do with caste. The hymn has for its subject a cosmogony, a theory of creation. It tells of the creation of all things from the sacrifice of a fabuluous monster-man or Purusa, his severed limbs giving birth to the world. As pointed out by Mr. Andrew Lang 5 57 the same primitive mode of accounting for creation is found in the Norse legend, where the earth, the seas, water, mountains, clouds and firmament are formed by dividing up the body of Giant Ymir. So also in the Chaldcen story, a monster-woman is divided in twain by Bel to form the heavens and earth. The same story runs through the myths of the Iroquois in North America as well as through those of Egypt and Greece. The Vedic story which runs close to those of other folk differs from them according to some scholars in this that it goes on to add that from Purusa also sprang the four classes of people. But Mr. V. A. Smith rightly observes "Both the Brahmin and fire come from Purusa's mouth, just as the servile man or Sudra and earth both proceed from his feet. No suggestion of the existence of caste-groups is made. Mankind is simply and roughly classified under four heads according to occupation, the more honourable profession being naturally assigned to the more honourable symbolical origin. It is absurd to treat the symbolical language of the poem as a narrative of supposed facts."558 "This is an attempt" says. Mr. R. W. Frazer, "to force an antiquity for a social system by connecting it with an undeniably ancient legend."509

Thus though there were kings and sacrificial priests though there were warriors and the great body of the people, cultivators, artisans and dealers in merchandise, the people were not tied down to the rigidity of a caste system whence hereditary occupation was alloted to the members. Viswāmitra who belonged to the rajanya class acted as a priest. Bell Poetpriests, on the other hand, prayed to the gods for the birth of sons who would be able to defeat their enemies in battles. Bell Indeed the poet-priest Mudgala did not hesitate to take up arms against robbers who had stolen

Myth, Ritual and Religion, Vol. I. p. 243.

<sup>\*\*\*</sup> Oxford History of India, p. 36.

<sup>140</sup> Literary History of India, p. 25.

<sup>\*\*\*</sup> Rigveda III. 53. 9.

<sup>\*\*\*</sup> Ibid., V. 28, 19; VL 81, 1.

his cows and his valiant wife drove the car for him and came to his rescue when the situation had become somewhat embarassing for him. The Rigveda also refers to Sadra kings. One poet-priest tells us that his father was a physician while his mother ground grain between mill-stones. The descendants of the poet-priest Bhrgu were experts in fashioning chariots. Gamblers are advised without any reference to their class to take to agriculture and pastoral pursuits, for proving thereby that in the economy of this period there was much mobility of labour. The existence of this freedom of movement from one occupation to another led to the dignity of labour. As Tvastr was the god who forged to the thunderbolt for Indra, no odium was attached to the work of the smith who manufactured weapons for men. The worker in wood had clearly the place of honour and we find the priets themselves preparing sacrificial posts and alters.

Labour and Occupations—We have just seen that the Rigveda shows germs of a social division arising out of the adoption of different occupations by different sections of the community. The following verse describes some of the professions very beautifully:—

"Men's tastes and trades are multifarious,
And so their ends and aims are various.
The smith seeks something cracked to mend,
The leech would fain have sick to tend.
The priest desires a devotee,
From whom he may extract his fee.
Each craftsman makes and vends his ware,
And hopes the rich man's gold to share." 565

Besides the priestly and ruling classes we find the following functional groups:—(1) Kināsa, 567 the ploughman (2) Dhanyakṛt, 568 the husker and

\*\*\* Ibid., IX. 112. 3.

<sup>\*\*\*</sup> Ibid., X. 102.

<sup>\*\*\*</sup> Ibid., X. 31. 14.

<sup>\*\*\*</sup> Ibid., X. 34, 13,

<sup>\*\*\*</sup> Rigveda IX. 112. 1-2.

<sup>\*\*\*</sup> Ibid., IV. 57. 8.

<sup>\*\*\*</sup> Thid., X. 94, 18.

winnower of corn (3) Gopa, 500 herdsman (4) Vaya, 570 the weaver of sundry piece goods corresponding to the modern Jola in Bengal producing napkins, covers etc. (5) Vāso-vāya, 571 the weaver of the standard vāsas or wearing cloth corresponding to the modern tanti in Bengal (6) Dhmatr, 579 one who smelts (dhma) the (metal) ore (with bellows of bird's feathers 578) (7) Karmara, 574 the smith (8) Taksan 575 or tvastr 576 the carpenter (9) Rathakara who made carts 377 and chariots (10) Carmamna<sup>578</sup> the tanner and leather-worker (11) potter who made earthen vessels of all sorts \$79 (12) vapta \$30 the barber who is clearly mentioned as shaving beards (13) Bhisak, 581 the physician who treated patients for a fee. A poet-priest says "I will give to thee, O physician, a horse, a cow, a garment, yea, even myself." 883 The healing properties of herbs and plants were known to them from which they prepared medicines as is apparent from a hymn<sup>583</sup> devoted wholly to the praise of medicinal plants and the physicians who deal with them. The physicians restored the aged and decrepit Cyavana to youth and rendered him desirable to his wife and made him the husband of maidens. 584 Rijrasva had his eyesight restored, 585 while Paravij was cured of blindness and hameness. 536 Ghosa was cured of her skin-disease 587 while Vispala whose-leg was cutt off in a

```
ace Ibid., I. 164 21; II. 23.6; III. 10.2; V. 12 4. etc.
```

are Macdonell and Keith-Vedic Index, s. v. Vaya.

<sup>871</sup> Rigveda, X. 26. 6.

<sup>479</sup> Ibid., V. 9. 5; VII. 2. 4.

<sup>510</sup> Ibid., IX. 112. 2.

<sup>174</sup> Ibid., IX. 112. 2; X. 72. 2.

<sup>\*\*\*</sup> Ibid., IX. 112. 1.

<sup>170</sup> Ibid., X. 119. 5.

<sup>19</sup> Ibid., X. 146. 3.

ave Ibid., VIII. 5. 38.

<sup>\*\*\*</sup> Ibid, VII. 104. 21; X. 89. 7.

<sup>\*\*\*</sup> Ibid., X. 142. 4.

<sup>\*\*\* 1</sup>bid., IX. 112. 1, 3.

<sup>\*\*\* 1</sup>bid., X. 97. 4.

<sup>\*\*\*</sup> Ibid., X. 97.

<sup>\*\*\*</sup> Ibid., I. 116. 10.

<sup>\*\*\*</sup> Ibid., I. 116. 16.

<sup>\*\*\*</sup> Ibid., I. 116. 8.

battle was given an iron one instead. (14) Vanij, 388 a merchant (15) Nrtu, a dancing girl. It has been contended that the word nrtu does not imply dancing girls as a professional class in the community; it might be that the unmarried girls or the ladies of the harem danced on special occasions as the Roman matrons danced and sang publicly on Floralia or Feast of Fool days and the females of the aristocratic families in Java and Vali still do. But the passage in question reads:

"Nrturivapornute bakşa usreva vajraham" 589

"Like a dancing girl she bares her bosom as a cow yields her udder (at the time of milching)"—such shameless dancing with bare breasts for attraction cannot be ascribed to decent and respectable women who always appeared before the public well—covered.<sup>5 9 0</sup>

Mr. Baden Powell in his Indian Village Community assumes that the Aryans had their lands cultivated by the conquered aborigenes; but the Rigveda unquestionably describes a society which is not dependent on such servile labour and in which cultivators, artisans and handicraftsmen are in no way regarded as inferior members of the community. We hear, no doubt, of slaves 191 and of gifts of slaves 192 but we have no evidence to show that they were largely employed or that slavery became the basis of husbandry. The ordinary tasks of life appears to have been carried out by the freemen of the tribe.

Domestic Labour—"Jāyedastam" \*\* \*\* \*\* (the wife is the home) exclaimed Viśwāmitra in his ecstatic vision of the true source of domestic felicity. Hence many of the household duties were entrusted to the ladies of the house. Philological evidence shows that it was the mātā (mother) who distributed the food, while the duhitā (daughter) used to milch the cow. We find women weaving, \*\*\* \*\* drawing water from wells in Kumbhas\*\* \*\* and preparing

<sup>\*\*\*</sup> Rigveds, L 112. 11; V. 45. 8.

<sup>\*\*\*</sup> Rigvada, I. 92, 4.

<sup>\*\*\*</sup> Ibid., VIII. 17. 7 ; VIII. 26, 13,

<sup>\*\*1</sup> Tbid., VII. 86, 7.

<sup>101</sup> lbid., VIII. 19. 13; VIII. Valkbilya Hymn No. 8. 3.

<sup>\*\*\*</sup> Bigveds III. 53. 4.

<sup>\*\*\*</sup> Ibid., K. 71. 9; af. IL 3. 6; IL 38, 4; V. 47. 6.

<sup>\*\*\*</sup> Ibid., I, 191. 14,

the Soma drink. \*\*\* We find them churning milk and curds and preparing butter out of them. \*\*\* Husking, winnowing and many other similar duties were entrusted to women \*\*\* though in the age of the Atharvaveda \*\*\* slave-girls were employed for the purpose in the comparatively well-to-do families. The tending of cattle while at home was part of the house-wife's duties as would appear from the marriage-hymn of the Rigveda \*\*\* where she is asked to be gentle to the cattle and to bring blessing to her husband's bipeds and quadrupeds.

Domestic and Foreign Trade-We have seen that Rigvedic society was sufficiently settled to admit of a prosperous agriculture and of a remarkable development in arts and crafts. "The Sindhu was rich in horses, rich in chariots, rich in clothes, rich in gold ornaments, well-made, rich in food, rich in wool, ever fresh, abounding in Silami plants (said to be used in cordage) and the auspicious river wears honey-growing flowers" 601 The trade in the products of agriculture and industry was carried on by the Vanij or Vanij denoting a merchant. In the Rigveda we find the use of the verb kri, to purchase on and of sulka, price. on We have also a passage 604 which suggests if not a contract for sale, at least haggling over prices: "A man has realised a small price for an article of great value, and again coming (to the buyer he says) this has not been sold; I require the full price; but he does not recover a small price by a large (equivalent): whether helpless or clever, they adhere to their bargain" According to this translation made by Wilson contracts seemed to have been made at the time of sale and purchase and the terms agreed upon could not be altered afterwards. Griffith translates the passage thus :

"He bid a small price for a thing of value : I was content, returning still purchased.

<sup>\*\*\*</sup> Ibid., I. 28. 3 ; IX. 67. 8.

<sup>\*\*\*</sup> Ibid., I. 28. 4.

<sup>\*\*\*</sup> Upalaprakçini in the Rigveds.

<sup>\*\*\*</sup> XII. 3. 13.

<sup>\*\*\*</sup> X. 85. 44.

<sup>\*\*\*</sup> Rigveds, X. 75. 8.

<sup>\*\*</sup> Ibid., IV. 24, 10.

<sup>\*\*</sup> Ibid., VIII. 1. 5.

## He heightened not his insufficient offer, Simple and clever both milk out the udder"

and remarks "both the simple or needy buyer and the shrewd seller make as much as they can out of the bargain." Thus prices seemed to have been settled finally only after much higgling and haggling.

For the conduct of this trade there were the roads and travellers' resthouses even in this age. The recent excavations in Sind and the Punjab prove the existence of S. W. ports in the pre-Aryan India of the third millenium B. C. and the cross-country roads feeding them may have been much older than the Aryan settlement. We have already referred to the prayers in the Rigveda for protection on a journey offered to Pusan who was the deity presiding over roads and paths. soc Agni and the sages like the Roman pontifices are called pathi-krt, the path-makers. 607 Travelling seems to have been quite common even in those early times for we read "Two with one Dame ride on with winged steeds and journey forth like travellers on their way."608 We also read of prapathas, rest-houses for travellers of and the epithet prapathinato given to a Yadava prince shows that princes of those times constructed rest-houses for the benefit of the travellers. The word setu occurs in the Rigveda 511 but its precise sense does not come out clearly. It has been held that a causeway of an ordinary type, merely a raised bank for crossing inundated land is meant, and that its use is probably metaphorical; but a metaphorical use of a term can hardly come into existence unless there has been previous simple use of it.

The articles of trade were carried from one part of the country to the other in waggons drawn by bullocks and horses, and probably also by

<sup>\*\*\*</sup> Griffith's Rigveds, Vol. I. p 426 fn.

<sup>\*\*\*</sup> Rigveda I. 42. 1; VI. 49 8; VI. 51, 12; VI. 53. 1.

<sup>\*\*\*</sup> Macdonell and Keith-Vedic Index, 1, pp. 48s-90.

<sup>\*\*\*</sup> Rigweda, VIII. 29. 8.

<sup>\*\*</sup> Ibid., X. 17. 4, 6; X. 63, 16.

<sup>\*10</sup> Ibid., VIII. 1, 13,

<sup>611</sup> X. 41, 2,

<sup>\*12</sup> Rigveda II. 2. 1,

<sup>\*18</sup> Ibid., X. 101. 7.

buffaloes 1.6 and asses. 615 Camels 616 and dogs 617 were also used an beasts of burden. A poet-priest prays for the gift of one hundred asses 618 which were required not certainly to draw his chariots, for, he could not have possessed many, but simply to carry his burden. It may seem strange that the dog was used as a beast of burden, but the reference in the Rigveda is quite clear. 610 The caravans consisting of the merchants, their retainers and waggons and the above-mentioned beasts of burden moved on from place to place, selling the commodities they carried and purchasing such articles as would be wanted elsewhere. They were thus the forerunners of the svartha-vahas of the early Buddhist literature and the Jatakas.

Scholars are, however, divided in their opinion as to whether this trade was carried on across the sens to foreign lands. Macdonell, Ragozin and Hopkins hold that the Aryans of this age were unacquainted with the sea. Mr. Keith observes "The Vedic Indian seems to have been very little of a navigator." Aryans ever knew the ocean. The seas of water they mention may have referred to the wide-stretching Indus." Mr. Macdonell also identifies the western Samudra with the Indus. But then what about the Purva or Eastern Samudra which also is mentioned. Further, the Rigveda speaks of the four Samudras. We shall now adduce evidences from the Rigveda which in Bühler's opinion prove the early existence of the complete navigation of the Indian Ocean and of trading voyages by Indians." One hymn prove the represents Varuna having a full knowledge of the ocean-routes along which vessels sail. Another hymn prove the merchants who

<sup>\*14</sup> Ibid., X. 102 7.

<sup>\*1\*</sup> Ibid., I. 34. 9; I. 116, 2; L. 162. 2; VIII. 74, 7; of. IV. 36. 1; L. 117. 16.

<sup>\*\*\*</sup> Ibid., I. 138. 2.

<sup>\*2\*</sup> Ibid., VIII. 46, 28,

<sup>\*\*\*</sup> Ibid, VIII. 56, 8,

<sup>\*1</sup> Sunesitam in Rigveda VIII. 46, 28.

<sup>\*\*\*</sup> Rapson-Cambridge History of India, Vol. I., p. 101.

<sup>\*91</sup> Literary History of India, p. 39.

<sup>\*\*\*</sup> Rigveds, IX, 33.6; X. 47.2.

<sup>\*\*\*</sup> Origin of the Brahmi Alphabet, p. 84.

<sup>\*\*\*</sup> Rigwoda, I. 25, 7.

frequent every part of the sea in pursuit of gain. Another hymness mentions merchants sending out ships to foreign countries under the influence of greed. Another hymness refers to a prayer to the sea by people desirous of wealth, before undertaking a voyage.

Mr. Keith observes "The use of boats or probably dug-outs for crossing rivers was known but the simplicity of their construction is adequately shown by the fact that the paddle alone was used for their propulsion. There is no mention of rudder or anchor, mast or sails, a fact which incidentally negatives the theory that the Vedic Aryans took part in ocean-shipping."638 But we can point out that the Rigveda has no prohibition against sea-voyages; on the contrary it has distinct allusions to them. All the Vedic ships were not simple in their construction as there is a reference to a ship with one hundred cars. 639 Some of them were furnished with "wings" i.r., sails. 800 Moreover, the people sailed on the seas, not only for trade but also for pleasure trips and warlike purposes. They must have resorted to coastal voyages only, though there is mention of a naval expedition 631 sent by Tugra under his son Bhujyu "in the ocean which giveth no support or hold or station."531 There is also mention of islands situated in the midst of the seass Vasistha thus describes his pleasure trip in Rigveda VII. 88. 3 :-

> "When Varuna and I embark together and urge our boat into the midst of ocean, We, when we ride o'er ridges of the 634,

waters, will swing within that swing and there be happy."

Referring to these passages oven Messrs. Macdonell and Keith<sup>638</sup> observe "It is not easy to refuse to recognise here the existence of longer vessels

<sup>\*\*\*</sup> Ibid., I. 48. 3.

<sup>\*\*\*</sup> Ibid., IV. 55. 6.

<sup>\*\*\*</sup> Rapson-Cambridge History of India, Vol. I. p. 101.

<sup>\*\*\*</sup> Rigyeda, L 116. 5.

<sup>\*\*\*</sup> Ibid., X. 143. 5.

<sup>\*\*\*</sup> Ibid., L. 116. 3-5.

Griffith's Rigveda L. p. 154.

<sup>\*\*\*</sup> Rigveds L 169, 3; X. 10. 1.

and Griffith's Bigweds II. p. 84.

with many oars and for sea-voyages." We further read "As merchants desirous of wealth surround the Sea, so do the priests surround Indra." \*\*\* Here the use of the theme by way of a simile seems to show that seavoyages by merchants were not a rare occurrence but fairly well-known to the public at large.

From the accounts of the earliest historiographers we learn that Navigation made its first efforts on the Mediterranean Sea and on the Perisan Gulf. These seas lay open the continents of Asia Europe and Africa and washing the shores of the most fertile and the most early civilised countries, seemed to have been destined by Nature to facilitate their communication with one another. We find accordingly that the first voyages of the Egyptians and the Phænicians were made in the Mediterranean and Red Seas. Their trade was however, not long confined to the countries bordering on these seas. By acquiring early possession of the ports of the Arabian Sea, they extended the sphere of their commerce and are represented to have opened up communications by sea with India. Dr. Day remarks in his History Commerce "The beginnings of these seavoyages are lost in the obscurity of the past. We know that they were highly developed by 1500 B. C., when Sidon was the leading city and that they did not cease to extend when the primacy of Phænician cities passed to Tyre."

It is a well-known fact that the Phoenician trade had three branches viz., Arabian-Indian, Egyptian and the Assyrio-Babylonian. We are here chiefly concerned with the first. According to some scholars the Pani of the Rigveda is Latin Poeni = Phoenicians, a trading people. They were a clan of Asuras whose chiefs Vitra and Vala were defeated in a fight with the Devas and were ousted from the north. They, therefore, finally settled in the Levant. Their new colony Pani-desa, Latin Finidis = Phoenicia. The Phoenicians are described by the Classical writers of Europe as faithless, treacherous and deceitful—a description quite in unision with the Vedic account. Thus they are described in the Rigveda as "riteless and godless" 657 "traffickers," 658 "extremely greedy like wolf, 639 foolish,

<sup>\*\*\*</sup> Rigveda, L. 56, 2.

<sup>\*\*\*</sup> Ibid., L. 33. 3.

<sup>\*\*\*</sup> Rigveda, L 33. 5.

<sup>\*\*\*</sup> Ibid., VI. 51. 14.

faithless, rude speaking niggards without belief, sacrifice or worship. 640 These Phoenician traders would come to India by the Red Sea route and also by the carevan route from the shores of the Persian Gulf to the Mediterranean coast of Syria. Several harbours of the Arabian Sea were seized by the Phœnic ans from the Idumeans. But the distance of Tyre from these ports being very great they afterwards occupied the nearest Mediterranean port called Rhinocolura. Tither were taken overland all the articles to be reshipped to Tyre. 641 Dr. Royle 642 says "Long before the Persians had made themselves masters of Babylon (531 B. C.) the Phœnicians had established themselves for pearl-fishery and the Indian trade on the isles of Tylos and Aradus, the modern Bahrein islands in the Persian Gulf." The 27th chapter of the Ezekiel gives a list of the articles of Phonician commerce brought from various countries. Among these "ivory and ebody could only have been procured in Dedan from India, for there were no elephants in Arabia." According to Classical writers India was throughout famous for ivory and ebony. \*\*\*

The fortunes of the Phænicians soon roused in the neighbouring Jews a spirit of emulation. Under David and Solomon they were great friends of the Phænicians under Hiram (980—917 B. C.) and this close friendship produced their combined commercial enterprise. This Jewish trade with India is proved by several allusions in the Bible itself. Thus we are told that Solomon founded a sea-port at Ezion-Geber in 992 B. C. \*\* From Ezion-Geber the ships of Solomon sailed under the guidance of the mariners of Hiram for distant lands. \*\* According to Professor Ball \*\* a some of the stones in the

oao Ibid., VII. 6. 3. Cf. niggards in Rigveda, X. 60. 6.

<sup>141</sup> Robertson-Disquisition on Anicent India, 1792. pp. 7-8.

<sup>\*\*\*</sup> Essay on the Anguity of Hindu Medicine, p. 122.

Historians' History of the World, Vol. IL pp. 336-37.

Strabo XV. 37; Theophrastus quoted by McCrinole in his India As Described By Classical Authors, p. 430. Virgil, Georgics I. 57; "India Sends ivory" II. 116—17. Horace. Odes, "India alone produces black about, I. 31. The author of the Periplus of the Erythræan Sea also mentions logs of about being exported from Berygasa (Schoff's translation, p. 36.)

<sup>\*\*\*</sup> Book of Kings, IX. 28.

<sup>&</sup>quot;A Geologist's Contribution to the History of Ancient India" in the Indian Anti-

breast-plate of the high-priest in the Mosaic period (1491 B. C.-1450 B. C.) may have come from the far East and India was famous for precious stones. In the days of Solomon (1015 B. C.) there could be supplied from India alone ivory, garments, armour, spices and peacocks. The evidence of Dravidian words os in the Hebrew text of the Book of the Kings and Chronicles of the Old Testa nent shows that Indians, specially those of the South carried on their commercial relations with the Hebrew people and the words concerned formed the chief articles of trade between them. Thus the Hebrew word for peacock in the Book of kings in Tuki and in Chronicles also is Tuki, while the old poetic Tamil Malayalam word for peacock is Tokei. 649 Again Hebrew abalim or apaloth which means fragrant wood and is otherwise known as aloes in the Proverbse 50 is derived from the Tamil Malayalam form of the word aghil. Similarly, almug = Tamil Valgu. 551 From these evidences we find that Rev. T. Foulkes is right when he says "The fact is now scarcely to be doubted that the rich oriental merchandise of the days of king Hiram and king Solomon had its starting place in the sea ports of the Deccan."852 Dr. Caldwell has come to the same conclusion and says "It seems probable that Aryan merchants from the mouth of the Indus must have accompanied the Phœnicians and Solomon's servants in their voyages down the Malabar coast towards Ophir (wherever Ophir may have been) or at least have taken part in the trade."653 The Jewish trade with India lasted a little over a century, for, when the fleet of Jehoshaphat, fifth in descent from Solomon which had started on a voyage to Tarshis, was destroyed, the Jewish commercial spirit cooled down.

We have seen how commerce between Egypt and India began from a very remote antiquity. "The labours of Von Bohl:n, \*5 confirming those of Heeren and in their turn confirmed by those of assen\*5 have estab-

<sup>\*\*\*</sup> Caldwell-A Comparative Grammar of the Dravidian Languages.

The Bayers Jataka also refers to peacocks as Indian exports to Babylon.

<sup>\*\*\*</sup> VII. 17.

<sup>\*\*\*</sup> Cf. Hebrew koph, meaning aps - Sanakrit kapi.

<sup>\*\*\*</sup> Indian Antiquary Vol. VIII.

<sup>\*\*\*</sup> Caldwell-A Comparative Grammar of the Dravidian Languages, p. 123.

<sup>\*\*\*</sup> Das Alte Indian Vol. I. p. 42. \*\*\* Ind. Alt., Vol. II, p. 580.

lished the existence of a maritime commerce between India and Arabia from the very earliest period of humanity." Professor Max Duncker says "Trade existed between the Indians and the Sabcens on the coast of South Arabia before the tenth century B. C." The bas-reliefs of the temple of Deir-el-Bahari at Thebes in Egypt which represents the conquest of the land of Pun under Hatasu contain a picture in which is described the booty which the Pharoah is carrying to Egypt. And in this booty, according to Leormant, "appear a great many Indian animals and products not indigenous to Yemen — elephant's teeth, gold, precious stones, sandal-wood and monkeys." \*\*658\*\*

But the question of the navigation of the Persian Gulf is still shrouded in mystery as well as that of the Alpha and Omega of all early communications between India and the land of Sumer and Akkad. It is inconceivable that the earliest civilisation of Chaldee had not engaged in navigation on the "sea of the East." Though no direct evidences regarding this is forthcoming, still we may point out that the great prosperity of Elam and its sturdy resistance first to Chaldee and then to Assyria may be partly explained by the wealth she acquired in trade with the countries on its eastern frontier; for, we know that she had a fleet manned with Phænician crew at the mouth of the Tigris and the Euphrates.

Dr. Sayce in his Hibbert Lectures for 1887 on the origin and growth of religion among the Babylonians have proved the existence of commerce between India and Babylon as early as 3000 B. C. Rassam has discovered Indian cedar in the palace of Nebuchadnezzer and Indian teak in the temple of the moon-god at Ur refounded by Nebonidus and he is supported by Hewitt who says that this wood must have been sent by sea from some port on the Malabar coast, for, it is only there that teak grew near enough to the sea, to be exported with profit in those early days or Dr. Sayce points to the use of the word Sindhu for muslin in an old Babylonian list

<sup>45\*</sup> Hist. Anc. del Orient, Eng. edition, II. pp. 299-301, Quoted in Indian Antiquary, Vol. XIII. p. 228.

<sup>\*\*\*</sup> History of Antiquity, Vol. IV. p. 156.

<sup>\*\*\*</sup> Hist. Anc. del Orient, Eng. edition, II. p. 299.

<sup>...</sup> L E. A. S., 1888, p. 837.

of clothes as the clearest proof "that there was trade between the Babylonians and the people who spoke an Aryan dialect and lived in the country watered by the Indus." And if in the Persian time in the fuller light of history the Aramic script wandered to India, such an event may equally have happened in an earlier millenia. The earliest Indian weights and measures 6 60 may be traced to Babylonian origin. Further, the division of the sky into twenty-four Naksatras and the naming of seven days in the week after the Sun, Moon and five other planets may be traced to Babylonian origin. But as these are mentioned in later astronomical works, they are thought to be borrowed directly from Alexandria. 661 Mr. S. Krisna Swami Iyenger, however, supports the Babylonian origin.669 The discovery of the records of the settlement of some branches of the Aryan race in Syria and Sumer worshipping some of the oldest gods of the Vedic pantheon,663 the recurrence of the Babylonian legend of the Flood among the Indians - all point to the existence of an intercourse between India and the land of Sumer and Akkad. 664

M. D.' Anville. The first climbs up the precipitous and zigzag passes of the Zagros range which the Greeks called the Ladders into the treeless regions of Persia. The second traverses the mountains of Armenia to the Caspian Sea and Oxus and descends into Indus by the passes of the Hindukush. Lastly, there is the sea. Of these, the overland routes were not impracticable; in fact, the desert steppes of Asia formed the merchantile ocean of the ancients — the companies of camels their fleet. But the commerce was from hand to hand, from tribe to tribe, fitful and uncertain and never possessed any importance. Similarly, the normal trade-route from the Persian Gulf to India could never have been along the inhospitable

<sup>\*\*\*</sup> Mănă biranya of Rigveda VIII. 72. 8.

<sup>\*\*\*</sup> Rawlinson-India and the Western World, p. 15.

<sup>\*\*\*</sup> Beginnigs of South Indian History, pp. 827, 329.

Vide the accounts of the Mitanni and of the Kassites in Hall's Ancient History of the Near East, pp. 201-30.

Recall in this connection the affinity between the Indus civilisation and the civilisation of the Valleys of the Tigris and the Euphrates brought to light by the recent excavations at Mohenso Darc and Harappa.

lished the existence of a maritime commerce between India and Arabia from the very earliest period of humanity." Professor Max Duncker says "Trade existed between the Indians and the Sabæns on the coast of South Arabia before the tenth century B. C." The bas-reliefs of the temple of Deir-el-Bahari at Thebes in Egypt which represents the conquest of the land of Pun under Hatasu contain a picture in which is described the booty which the Pharoah is carrying to Egypt. And in this booty, according to Leormant, "appear a great many Indian animals and products not indigenous to Yemen — elephant's teeth, gold, precious stones, sandal-wood and monkeys." \*\*658\*\*

But the question of the navigation of the Persian Gulf is still shrouded in mystery as well as that of the Alpha and Omega of all early communications between India and the land of Sumer and Akkad. It is inconceivable that the earliest civilisation of Chaldæ had not engaged in navigation on the "sea of the East." Though no direct evidences regarding this is forthcoming, still we may point out that the great prosperity of Elam and its sturdy resistance first to Chaldæ and then to Assyria may be partly explained by the wealth she acquired in trade with the countries on its eastern frontier; for, we know that she had a fleet manned with Phænician crew at the mouth of the Tigris and the Euphrates.

Dr. Sayce in his Hibbert Lectures for 1887 on the origin and growth of religion among the Babylonians have proved the existence of commerce between India and Babylon as early as 3000 B. C. Rassam has discovered Indian cedar in the palace of Nebuchadnezzer and Indian teak in the temple of the moon-god at Ur refounded by Nebonidus and he is supported by Hewitt who says that this wood must have been sent by sea from some port on the Malabar coast, for, it is only there that teak grew near enough to the sea, to be exported with profit in those early days of Dr. Sayce points to the use of the word Sindhu for muslin in an old Babylonian list

Hist. Anc. del Orient, Eng. edition, II. pp. 299-301, Quoted in Indian Antiquary, Vol. XIII. p. 228.

<sup>\*\*\*</sup> History of Antiquity, Vol. IV. p. 156.

<sup>...</sup> Hist, Anc. del Orient, Eng. edition, II. p. 299.

<sup>.</sup> F. L R. A. S., 1888, p. 837.

of clothes as the clearest proof "that there was trade between the Babylonians and the people who spoke an Aryan dialect and lived in the country watered by the Indus." And if in the Persian time in the fuller light of history the Aramic script wandered to India, such an event may equally have happened in an earlier millenia. The earliest Indian weights and measures 6 80 may be traced to Babylonian origin. Further, the division of the sky into twenty-four Naksatras and the naming of seven days in the week after the Sun, Moon and five other planets may be traced to Babylonian origin. But as these are mentioned in later astronomical works, they are thought to be borrowed directly from Alexandria.681 Mr. S. Krisna Swami Iyenger, however, supports the Babylonian origin.669 The discovery of the records of the settlement of some branches of the Aryan race in Syria and Sumer worshipping some of the oldest gods of the Vedic pantheon,663 the recurrence of the Babylonian legend of the Flood among the Indians - all point to the existence of an intercourse between India and the land of Sumer and Akkad. 664

This foreign trade could be carried along the three routes suggested by M. D.' Anville. The first climbs up the precipitous and zigzag passes of the Zagros range which the Greeks called the Ladders into the treeless regions of Persia. The second traverses the mountains of Armenia to the Caspian Sea and Oxus and descends into Indus by the passes of the Hindukush. Lastly, there is the sea. Of these, the overland routes were not impracticable; in fact, the desert steppes of Asia formed the merchantile ocean of the ancients — the companies of camels their fleet. But the commerce was from hand to hand, from tribe to tribe, fitful and uncertain and never possessed any importance. Similarly, the normal trade-route from the Persian Gulf to India could never have been along the inhospitable

Mant hiranys of Rigveds VIII. 72. 8.

<sup>\*\*1</sup> Rawlinson-India and the Western World, p. 15.

<sup>\*\*\*</sup> Beginnigs of South Indian History, pp. 327, 329.

Vide the accounts of the Mitanni and of the Kassites in Hall's Aucient History of the Near East, pp. 201-30.

Recall in this connection the affinity between the Indes civilisation and the civilisation of the Valleys of the Tigris and the Euphrates brought to light by the recent excavations at Mohenso Daro and Harappa.

deserts of Gedrosia. Doubtless then more than one adventurous vessel reached India by hugging the shores. But the exploring expeditions despatched in later times by Darius (512 B. C.) from the mouth of the Indus under Skylax of Karayandra and two centuries later by Alexander the Great under Nearchos show the difficulties and dangers of this route, the time it occupied and the ignorance of the pilots. The author of the Periplus, it is true, says that small ships made formerly voyages to India, coasting along the shores until Hippalus first ventured to cross the Ocean by observing the monsoon.668 But we know from other sources that the monsoon was known from the earliest times to all who sailed along the Arabian and African coasts; and direct sea-voyages were attempted only at the commencement of the monsoon. 666 The route for the direct sea-trade ran down the Persian and Arabian coasts to Aden, up the Red Sea to Suez, and from Suez to Egypt on the one hand and Tyre and Sidon on the other. Balkh, Aden and Palmyra were the chief halting stations and emporia of this trade.

Now was there any combination between merchants in this period? The Vedic expression panied? has been differently interpreted by different acholars. The St. Petersburg Dictionary derives it from pan, to barter and explains it as merchant. Zimmer and Ludwig and Ludwig also takes it in the sense of a merchant. Now the gods are asked to attack the panis who are referred to as being defeated with slaughter. Ludwig thinks that these references to fights with Panis are to be explained by their having been non-Aryan traders who went in caravans as in Arabia and North Africa, prepared to fight, if need be, to protect their goods against attacks which the Aryans would naturally deem quite justified. If we accept this

<sup>\*\*\*</sup> The Periplus of the Erythrean Ses ( Schoff's Eng. Trans. ) p. 45.

<sup>\*\*\*</sup> Monsoon - Arabie Mausim.

<sup>\*\*\*</sup> Rigveda L 32. 11; L 83. 4; L 93. 4; L 151. 9; H. 24. 6; IV. 58. 4; VI. 13. 3; VI. 20. 4; VI. 33. 2; VI. 39. 2; VI. 44. 22; VI. 45. 31; VI. 51. 14; VII. 9. 2; IX. 111. 2; X. 108. 2; X. 108. 4; X. 108. 6; X. 108. 10; X. 108. 11.

<sup>• • •</sup> Macdonell and Reith-Vedis Index, I. p. 471.

<sup>\*\*\*</sup> Der Rig Veda, III. 213-15.

<sup>\*\*\*</sup> Macdonell and Keith-Vedic Index, L. 471.

meaning, we presume a corporation of merchants strong enough to defy their opponents and carry on fight against them.

Again in the Rigveda<sup>672</sup> the army of the Maruts is said to be divided into Ganas and Vrātas, the two words always meaning guilds or corporate unions in later Sanskrit. Further, in connection with dice-play we hear of leaders of Ganas and Vrātas.<sup>673</sup> But our information about these corporate unions is so scanty that we know nothing about their nature, organisation and methods of work.

Methods and media of Exchange—The great volume of trade would necessarily presuppose the existence of an excellent system of exchange. But the general view held was that "in the Vedic Age all exchange was by barter."674 But we have seen that by the time of the Rigveda the cow formed a standard or unit of value. Thus there is a hymne? where Indra, that is, his image is offered as a fetish for ten cows and another 18 where Indra is considered to be so valuable that not a hundred, a thousand or even a myriad of cows is thought to be a proper price. Besides cattle as a standard of exchange we find references to Niska, a word which in later Sanskrit means a gold coin. In one hymners a poet-priest praises the munificence of his patron-king for giving him as reward for his priestly services a hundred steeds and a hundred niskas. Now what does the word niska mean here? No doubt we have passages in the Rigveda which certainly point to the use of niska as an ornament. Thus in one passage 678 we are told of sacrificers wearing niskas on their necks (niskagrivo). In another 679 the god Rūdra is described as wearing niskas. In another 680 goddess Usas is invoked to take away the evils of bad dreams from those who wear niskas. But in Rigveda I. 126. 2 where the poet-priest mentions a gift of 100 niskas, the meaning necklace would hardly be appropriate; for, a man cannot require a hundred necklaces to adorn himself. In regard

<sup>\*\*\*</sup> V. 53. 1.

<sup>\*\*\*</sup> Mrs. Rhys Davids in J. R. E. S., 1910.

<sup>• 7 8</sup> Rigveda IV. 24. 10.

<sup>• \*</sup> Tbid., I. 126. 2.

<sup>• \*</sup> Thid., II. 33, 10.

<sup>\*\*\*</sup> Rigveds, X. 34.

<sup>\*\*\*</sup> Ibid., VIII, 1, 5.

<sup>\*\*\*</sup> Ibid., V. 19. 5.

<sup>...</sup> Ibid, VIII. 47, 15.

to this passage the authors of the Vedic Index<sup>6 a 1</sup> rightly observes "As early as the Rigveda traces are to be seen of niskas as a sort of currency. For a singer celebrates the receipt of a hundred niskas and a hundred steeds. He could hardly require the niskas merely for personal adornment."

But was the nisks a coin? This may be solved, as has been pointed out by Professor D. R. Bhandarkar by reference to hymn No. 33 of the second Mandala of the Rigveda. Here the god Rudra is described as wearing "niskam viswarupam." Now what can viswarupa mean? Does it signify omniform? If so, what is meant by saying that Rūdra's necklace was omniform. Before we try to arrive at a natural and plausible meaning of the term we must consider how the word niska could come to signify both a currency and a necklace. A little reflection tells us that this is possible only if we suppose that niska means not simply a currency but a coin, that niska denoted necklace because it consisted of niskas, the coins. In many parts of India people even to-day wear necklaces of gold mohars. In Maharistra people even to-day get a goldsmith to cast gold coins in imitation of certain Byzantine originals which they call Putalya which are afterwards strung into a necklace called Putalya. This custom of making necklaces out of coins is not of modern origin but was also prevalent in Ancient India. Thus the Kalpasütra while describing the godess Sri whom Trisila, the mother of Mahavira saw in her dream, speaks of the former as bearing uratthedinara-mulya i.e., a string of dinaras (the Roman denarius) on her breast. Niska must, therefore, been taken in the sense of a coin and not merely a metallic currency. If this explanation is accepted, then a good sense of the term viswarupa is possible to fix upon. The rups in viswarups can at once be recognised to be a word technical to the old Indian Science of Numismatics and denoting the symbol or figure on a coin which for that reason is called rupa. Thus the necklace worn by Rudra was composed of niska coins; and just because these niska coins bore various rupas or figures on them, the necklace was naturally viswarupa. The earliest of coins found in India are the punch-marked

1728 . (- 1 +1)

coins and we know that no less than three hundred different devices or rupas have been marked on them.

Mana was the name of another metallic money. It occurs in the following verse<sup>682</sup> "O Indra, bring us jewels, cattle, horses and manas of gold." The word mana is derived from the root man, to measure or man, to prize or value and therefore may well have been a metallic money of some fixed and recognised weight or value. This probably reached the valley of the Euphrates through the Phoenician traders where it became the Akkadian mina.

Unstamped metallic money of another kind was also known in this period. In one hymn<sup>683</sup> we find mention of a gift of dasa hiranya-pinda. As these hiranya-pindas have been specifically mentioned as ten, it appears that each hiranya-pinda conformed to a definite recognised weight or value. We need not be surprised at the existence of both stamped and unstamped money circulating in one and the same period. Even to this day the Dhābuas which are unstamped copper money circulate freely in the Nepalese Terai along with stamped coins of various denominations.

The existence of a metallic medium of exchange in general acceptance may be proved by other evidences. Thus in one hymness we read of a gift of 10,000 pieces; another hymness mentions the gift of 100 pieces; another hymness refers to the gift of a hundred and a thousand pieces. These gifts of so many pieces do undoubtedly refer to some definite standard in general acceptance, since without such a standard in general acceptance, we can hardly expect the mention of mere numbers without any further specification. Professor Wilson, therefore, in his note on Rigveda V. 27. 2 rightly observes "It is not improbable, however, that pieces of money are intended; for, if we may trust Arrian, the Hindus had coined money before Alexander."

The general economic condition of the classes and the masses—In a system of private ownership of land and capital economic inequalities are

<sup>\*\*\*</sup> Rigveds, VIII. 78. 2.

<sup>\*\*\*</sup> Rigveda, VI. 47. 28.

<sup>\*\*\*</sup> Ibid., V. 27, 2.

<sup>\*\*\*</sup> Ibid., V. 27. 1.

<sup>\*\*\*</sup> Ibid., VIII. 8. 46-7.

bound to exist and Rigvedic society was no exception to this general rule. The tendency towards the accumulation of capital in a few hands was helped partly by the development of domestic and foreign trade and partly by the existence of freedom of disposal of property specially for satisfying debts to creditors as the evidence of Rigveda X. 34 shows. The Rigveda mentions the Mahakulases; and the Maghavanses who were distinguished for their wealth and liberality. The princes and kings who stood on a higher level than the Mahakulas and the Maghavans are represented as more wealthy and liberal. Thus Svanaya, son of Bhava gave Kaksivan a hundred niskas, one thousand cows, ten chariots, with mares to draw them and sixty thousand cattle. The Rusamas gave away four thousand cattle. 600 Prastoka (otherwise known as Divodāsa or Atithigva) gave away ten coffers, ten mettled horses, ten treasure-chests, ten garments, ten hiranyapindas, ten chariots with extra steed to each and one hundred cows. 691 Sudas, descendant of Pijavana gave away two hundred cows, two chariots with mares to draw them and four trained horses with pearl to deck them. 699 Asanga gave ten thousand pieces together with ten brighthued oxen. 698 Asanga's son Svanadratha gave away two brown steeds together with their cloths of gold. 694 Vibhindu gave Medhyatithi fortyeight thousand pieces. 6 . 5 Pākasthāman Kaurayān gave away a ruddy horse. \*\*\* Prince Kurunga gave away one hundred steeds and sixtythousand cows. 897 Kasu, son of Chedi gave away one hundred buffaloes and ten thousand cattle. 608 Tirindira, son of Parsu, gave away one lac cows. 599 The Yadavas gave to Pajra ten thousand cattle and steeds three times a hundred.700 Trasadasya made a gift of fifty female slaves.701

\*\*\* Rigveda, I. 31. 12; IL 6. 4; V. 39. 4.

<sup>\*\*\*</sup> Ibid., I. 55. 4; V. 79. 4; VIII. 7. 21; VIII. Valakhilya hymn No. 9. 3; X. 107. 4.

<sup>\*\*\*</sup> Ibid., I. 126. 2-3.

<sup>\*\*\*</sup> Rigveds, V. 30, 15.

<sup>\*\*\*</sup> Ibid. VII. 18, 22-3.

<sup>\*\*\*</sup> Ibid., VIII. 1. 32.

<sup>\*\*\*</sup> Thid., VIII. 3, 22-3,

<sup>\*\*\*</sup> Ibid , VIII. 5. 37.

<sup>700</sup> Ibid., VIII. 6, 47.

<sup>\*\*\* 1</sup>bid., VI. 47, 22.

<sup>\*\*\*</sup> Ibid., VIII. 1, 33.

<sup>\*\*\*</sup> Ibid., VIII. 2. 41.

<sup>\*\*\*</sup> Ibid., VIII. 4. 19-20.

<sup>\*\*\*</sup> Ibid., VIII. 6, 46.

<sup>\*\*\*</sup> Thid., VIII. 19. 35.

King Chitra "like Parjanya with his rain hath spread himself with thousand, yea, myriad gifts." Prithusravas, son of Kanita, gave away sixty thousand steeds, ten thousand cattle and two thousand camels" besides a chatiot wrought of gold." Even Brbu, the Pani chief is described as the giver of a thousand liberal gifts." The munificence of the rich patrons may be appreciated from the famous hymn on Daksina which praises in glowing terms the givers of horses, cattle, clothes and gold."

Side by side with these richer classes we find peoples in debt which was contracted for various purposes, gambling being one of them. 707 The Panis are described as "usurers who counted the days for calculating interest." 708 Debtors like other male factors were sometimes bound by their creditors to posts709 presumably as a means of putting pressure on them to pay up the debt. Everything was exacted, even the dwelling houses were sold and the debtors became homeless and destitute.7 10 Sometimes they were reduced to slavery and their relations renounced them. 7 t 1 The amount of interest payable is impossible to make out. In one passage718 an eighth (Sapha) and a sixteenth (Kala) are mentioned as paid, but it is quite uncertain whether interest or an instalment of the principal is meant, Some were born in debt and were under a moral and legal obligation to pay off the debt of their ancestors as the following passage715 will prove : "Discharge, O Varuna, the debts (contracted) by my progenitors and those now (contracted) by me; and may I not, royal Varuna be dependent (on the debts contracted) by another. Many are the mornings that have, as it there, not dawned; make us, Varuna, alive in them." Mr. Wilson observes "According to Sayana, this means that persons, involved in debt are so overcome with anxiety that they are not conscious of the dawn of the day; to them the morning has not dawned; they are dead to the light of day. The passage is deserving of notice, indicating an advanced as well

<sup>\*\*\*</sup> Ibid., VIII. 21. 18.

<sup>100</sup> Ibid., VIII. 46, 22.

<sup>&</sup>quot; Ibid., VI. 45, 33,

<sup>\*\*\*</sup> Ibid., X. 34, 10.

<sup>\*\*\*</sup> libid., X. 34. 4.

<sup>&</sup>quot;33 Ibid., X. 34, 4.

<sup>\*\*\*</sup> Ibid., II. 38. 0.

<sup>\*\*\*</sup> Ibid., VIII. 46, 24.

<sup>704</sup> Ibid., X. 107.

<sup>-</sup> Too Ibid., VIII. 66, 10,

<sup>\*\*\*</sup> Ibid., X. 34. 10.

<sup>\*\*\*</sup> Ibid., VIII. 47, 17.

as a corrupt state of society, the occurrence of debt, and severity of its pressure."

Economic pressure, however, became severest, when crops failed; and it is worthy of note that despite the care for irrigation, famines were not unknown. Sasarpari is said to have dispelled famine. Fervent prayers were offered to drive away famine from the country:—

"Drive far from us poverty and famine,

(O sacrificial post)"715

"Receive from us the arrow, keep famine,

O Adityas, far away"716

"O Much-invoked Indra, may we subdue all famine and evil want with store of grain and cattle."717

Indeed we read of "the needy who come in begging for bread to est"?18
"of the begger who comes in want of food"?19 and "of the friend and
comrade who comes imploring food."720 Hence great emphasis was laid
on the virtues of hospitality?21 and liberality,722 and the niggardly misers
were cried down.723 Society expected the rich man to alleviate the distress
of the needy as he himself may need the same assistance one day:

"Let the rich satisfy the poor implorer, and bend his eye upon a longer journey. Riches come now to one, now to another, and like the wheels of cars are ever rolling." 784

<sup>\*10</sup> Ibid., III. 53. 15.

<sup>\*10</sup> Ibid., VIII. 18. 11.

<sup>910</sup> Ibid., X. 117. 3.

<sup>\*\*\*</sup> Ibid., X. I17. 5.

<sup>100</sup> Ibid., X. 107.

<sup>106</sup> Ibid., X. 117. 5.

<sup>910</sup> Ibid., III. 8, 2.

<sup>\*1\*</sup> Ibid., X. 42. 10.

<sup>710</sup> Ibid., X. 117. 4.

<sup>191</sup> Ibid., X. 117.

<sup>723</sup> Ibid., IX. 63, 5.

## CHAPTER V.

## Brahmana Period.

(-600 B. C.)

Definitely later than that depicted in the Rigveda is the civilisation presented by the later Samhitis, the Brihmanas, the Aranyakas and the Upanisals. The story of the Rimiyana may have its origin in the later Brīhmaņa period 125 and the epic was composed according to Professor Macdonell796 before 500 B. C. In the period of the Rigveda, the centre of civilisation was tending to be localised in the land between the Saraswati and the Drsalbuti rivers; but in the Brilmana period, as the period under review may conviniently be called, the local sation of civilisation in the more eastern part of the country is achieved. In the Aitareya Brihmana a geographical passage ascribes the Middle Country to the later Madhya-desa, the Kurus and Pinchals with the Vasas and Usinaras, to the south the Satvats and to the north beyond the Hi nalayas, the Uttara-Kurus and the Uttara-Madras. On the other hand, while the west recedes in importance, the regions, east of the Kuru-Pinchal country come into prominence, specially Kośala, corresponding roughly to modern Outh, and Videha, the modern Tirhat or N. Bihar and Magalha, the modern South Bihar. In the south we hear of non-Aryan tribes like the Andhras, Pulindas, Pundras, Mutibas, Sabaras and the Naisadas.

The relation of two cities, namely, Asandhivat, 728 probably the capital

<sup>\*25</sup> Rapson-Cambridge History of India, Vol. L, p. 317.

<sup>\*\*\*</sup> History of Sanskrit Literature, p. 309.

<sup>\*\*\*</sup> XXIII. 18. \*\*\* S. B. E. Vol. XLIV. p. 836.

of King Janmejaya and Parivakra,723 the capital of the Panchala Kings. The word nagara meaning a town frequently occurs in Brahmana literature as also the epithet nagarin. The Taittiriya Brahmana describes Janasruteya as a nagarin. We also find epithets like Kausamveya, Kausalya and Vaidarva, derived from place-names which gradually grew into towns.

Land-system-The land was divided as in the previous period, into vāstu, arable land, pastures and forests. The vāstu as before was in private ownership. In the Chandogya Upanisad 780 houses are cited as instances of private wealth. The arable land was also in private ownership. In the Black Yajur Veda 231 we read "He should make an offering to Indra and Agni on eleven postherds who has a dispute about a field or with his neighbours." "It is" says from Prof. Keith "a clear evidence of separate ownership of land."733 In the Chindogya Upanisad733 we find fields along with houses cited as instances of private wealth. The pastures and the forests were enjoyed in common. Though this Right of Common or Estover was later on much circumscribed by the establishment of a highly centralised government, such as, under Chandragupta Maurya, the Brahmins or the learned nevertheless exercised the right of collecting fuel and other materials for religious purposes throughout ages. The Varana Jataka,734 for example, tells us that five hundred pupils of a teacher of Taksasila set out for the forest to gather firewood for their teacher and busied themselves in gathering sticks. The Agni Purana 785 lays down that a Brahmin exercises everywhere the right of collecting grass, fuel and flowers. Yājūabalkya736 is also of the view. It is well-known that the Āranyaka part of the Vedic literature was required to be read in the forests.

With the evidences at our disposal, it is difficult to decide whether the land belonged to the head of the family or to the members of joint families in common. The story told in the Aitareya Brāhmaņa of Viśwāmitra

va. Ibid., p. 397.

<sup>180</sup> VII. 24.9.

<sup>781</sup> IL 2. 1.

<sup>783</sup> Keith-Veda of Black Yajus School, p. 147. fo. 1. Compare Vedic Index, I. 210, 211.

<sup>- 750</sup> VII. 24. 2 (Kşetrăpi Ayatanâni).

THA No. 71.

<sup>\*\*\*</sup> Chapter CCLVii, 17.

<sup>780</sup> II, 169.

who outcasted and expelled his fifty sons as also of the sale of Sunahsepha by his father Ajigarta in lieu of one hundred cows prove the autocratic authority of the head of the family. It is, however, doubtful as to whether these are instances which give us the real state of affairs or were arbitrary exercises of authority. Indeed we have evidences to prove the joint ownership of property. Not only do we find repeated mention of Sajāta and Samīna, meaning clausmen or men of the same family but in one hymn<sup>137</sup> we find prayers to the gods for unity of the family:—

"Freedom from hate I bring to you, concord and unanimity.

Love one another as the cow loveth the calf that she hath borne.

One-minded with his mother let the son be loyal to his sire.

Let the wife, calm and gentle, speak words sweet as honey to her lord.

No brother hate his brother, no sister to sister be unkind.

Unanimous, with out intent, speak ye your speech in friendliness.

Let what you drink, your share of food be common: together with one common bond I bid you. Serve Agni, gathered round him like spokes about the chariot nave.

In the Black Yajur Veda<sup>738</sup> we read "The fore-sacrifices are the father, the after-sacrifices the son in that having offered the fore-sacrifices he sprinkles the oblations, the father makes common property with the son." Mr. Keith<sup>738</sup> observes "The commentator takes this as referring to the fact that the son's earnings are his own, the father shares them with the family,

Tat Atharva-veda, III. 30.

<sup>700</sup> II. 6, 1,

vas Veda of the Black Yajus School, p. 206, fn. 2.

and this seems correct. Sayana also notes that the son keeps his secretly i.e., perhaps his ownership was precurso, not of right; the parallel to Roman law is striking and justifies us in accepting the view of the commentator." Elsewhere in the Black Yajur Veda 740 we read "Manu divided his property among his sons. He deprived Nabhanedistha, who was a student, of any portion. He went to him, and said, 'How hast thou deprived me of a portion?' He replied, 'I have not deprived you of a portion; the Angirases here are performing a Sattra; they cannot discern the world of heaven; declare this Brihmana to them; when they go to the world of heaven they will give thee their cattle.' He told them it, and they when going to the world of heaven gave him their cattle. Rudra approached him as he went about with his cattle in the place of sacrifice, and said 'These are my cattle.' He replied 'They have given them to me.' 'They have not the power to do that' replied he, 'whatever is left on the place of sacrifice is mine.' Then one should not resort to a place of sacrifice. He said 'Give me a share in the sacrifice, and I will not have designs against your cattle.' He poured out for him the remnants of the mixed (Soma). Then indeed had Rudra no designs against his cattle."741 This story which also occurs in the Aitareya Brilmana74# shows undoubtedly that even during the life-time of the father, sons were regarded as having a vested interest in property, from which they could not be excluded at will. In the mythology of the Brihmana period we find that the children of the Father God viz., gods and devils fight for their respective shares and "enter into their inheritance" by dividing it. In another mythology we find a man who has no son, dividing his property between his two wives. We find the gift of a field; of whole villages; of all the king's lands to a priest; and when thus given, the land cannot be alienated. If the king should at another time, give all his land to another, that piece which he has formerly given to the first priest, is not included in the later donation.

<sup>741</sup> Compare MS. L 5. S, and for the substance see Vedic Index, I. 352. For Mann of. Levi, Ladoctrine du sacrifice, pp. 115 seq.; Macdonall, Vedic Mythology, p. 138. s and force of December away is a militial many the admit that

TAS V. 14.

But though the gift of lands specially to Brahmins who officiated in sacrifices<sup>743</sup> was quite common there was a decided feeling against land-transfer in the Satapatha Brahmana.<sup>744</sup> From another passage of the same book<sup>745</sup> we learn that Khatriya clansmen apportioned land given to them by a (Kshatriya) king with the mutual consent of all. Later on when we come to the Chandogya Upanisad<sup>746</sup> we find that houses and fields were regarded as objects of private ownership and easily transferable.

It is difficult to decide as to whether the king was regarded as the owner of the land in this period. We are told in the Aitareya Brahmana74? that a priest's function is to take gifts, while the Vai ya's peculiar function; is to be devoured by the priest and nobleman. From this it is apparent that the Vaisya cannot have any secure hold over his landed property. In one of the Upanisads it is said that the vital breath commands the other breaths just as a Samrīj commissions his officers saying, 'Be thou over these villages or those villages.' The statement of the Satapatha Brahmana,7 \*\* namely, that every one here is fit to be eaten up by the king except the Brahmin, is not of much significance, since it only embodies in a nutshell the view that the royal contributions from the subjects which were at first probably fitful in their character, had by this time become a general burden devolving upon nearly all classes of people. Of greater importance is the passage of the Aitaraya Brihma a, referred to above, declaring the Vai ya from the point of view of the katriya 'to be tributary to another, to be lived on by another, to be oppressed at will.' These striking phrases together with the epithet frequently applied in the Brihmanas to the king, namely that he is the devourer of his people doubtless signify that the king's claim of taxing his subjects was lim'ted only by his sweet free will, but there is nothing in them to indicate the king's ownership of the soil as distinct from his political superiority.749 Indeed it is clearly stated in

<sup>740</sup> Satapatha Brahmana XIII. 6. 2. 8; XIII. 7, 1, 13 and 15.

<sup>\*\*\*</sup> XIII. \*\*\* Ibid., VII 1 1 4. \*\*\* VII. 24. 2.

p. 128.

<sup>-- 1 540</sup> W. 3, 3, 12; Ibid , 4, 2, 3.

<sup>740</sup> Compare Vedic Index, S.V. Rajan, rejecting the view of Hopkins, Op. cit., p. 222.

the Satapatha Brahmana? 50 that to whomsoever the kshatriya with the approval of the people or clan (vis) grants a settlement, that is properly given. This evidently refers to the public land of the folk and it seems to mean that while the king's gift of such land with the consent of the people was in accordance with the tribal or customary law, it was sometimes arbitrarily disposed of by the sole authority of the ruler. It is possible that originally in the Rigvedic period the king could deal with the public land only with the sanction of the tribal assembly, but afterwards during the times of the later Samhitas and the Brahmanas the advance of the king's power had resulted in such land being looked upon as lying to some extent at the disposal of the Crown. The natural consequence of such development would be eventually to reduce the public lands to the condition of the king's private estates. But this step which seems to have been completed by the time of the Arthasastra was not reached in the period of the Brīhmanas.751 Indeed the prayer in the Atharvaveda753 for the grant of a share in villages to the king shows that the people granted him some land for the maintenance of his authority and dignity: there could have been hardly any room for this prayer if he was already the master of the soil. Professor Keith rightly observes "There can be no doubt that he (the king) controlled the land of the tribe. It is not, however, necessary to ascribe to this period the conception of the royal ownership of all the land, though it appears in the Greek source from the time of Megasthenes downwards and is evidenced later by law-books of the time. He had, it is true, the right to expel a Brahmin and a Vaisya at will, though we do not know expressly that he could do this in the case of a Kahatriya. But these considerations point to political superiority rather than to ownership proper and we may assume that when

<sup>\*\*\*</sup> VIII. 1.71, 4.

According to the Vedic In lex, s. v. Grima, the king's right to apportion the land with the consent of the clan (as mentioned e.g., in the text of the Satapatha Brahmana quoted above) contains the germ of the later State ownership of the coil. It is difficult to support this view, since the king's right of apportionment just mentioned is apparently concerned with the disposal of the public land as distinguished from the land held in private ownership by the freemen.

vas IV. 29. 2.

he gave grants of land to his retainers, he granted not ownership but privileges such as the right to receive dues and maintenance from the cultivators. There is a clear distinction between this action and the conferring of ownership, and it may be doubted if the actual gift of land was approved in this epoch. The only case of which we hear is one reported in the Satapatha and Aitareya Brīhmanas in which the King Viswakarman Bhauvana gave land to the priests who sacrificed for him but the earth itself rebuked his action. It is more probable that at this time, the allotment of land was determined by the king or by the noble to whom he had granted the rights of superiority according to customary law and that gifts not in accordance with this customary law were disapproved. It is hardly necessary to point out the close similarity between such a state of affairs and that existing at the present day in parts of West Africa, where kings have introduced for purposes of personal gain the practice of dealing as absolute owners with lands which according to the strict custom of tribal law they have no power to allocate save in accordance with the custom of the tribe. Nor is it inconsistent with the view that the king had an arbitrary power of removing a subject from his land. That power flowed from his sovereignty and though disapproved, was acquiesced in, we may presume, just as in West Africa; while the dealing of kings with lands by way of absolute ownership was regarded as a complete breach of the tribal law, the actual removal from his land, of any individual was recognised as a royal prerogative, even if the power was misused."753

As to the king's revenue we have the following passage in the Atharvaveda:

"Emam bhaja grāme asveṣu goṣu niṣṭhaṃ bhaja yo amitro asya." 756

"Give him a share in village, kine and horses and leave his enemy without a portion, (O Indra).

The king's share is called 'bali' in the Vedic Samhitas and the Brahmanas which is also used to denote the tribute paid by the conquered enemies and

<sup>750</sup> Rapson-Cambridge History of India, Vol. I. pp. 132-33.

<sup>144</sup> Atharvaveda IV. 22. 2.

offerings made to the gods. 785 Along with this is mentioned hiranya which as Professor U. N. Ghosal has suggested, means cash charge upon certain special classes of crops. 786 As to any fixed share of the produce being paid to the king, the evidence of the following passage of the Atharvaveda is significant:

"Yad rājīno bibhajanta iṣṭāpurttasya ṣoḍaśaṃ Yamasyīmi sabhāsadaḥ" "\*\*\*
"When yonder kings who sit beside Yama divide
among themselves the sixteenth part of hopes fulfilled."

This passage occurs in a hymn whose subject is immunity from taxation in the next world to be purchased by the performance of a certain sacrifice on earth and may, therefore, well point to the royal share being assessed to a sixteenth part of the produce in those days.

The rise of a landed aristocracy, of men who stood as intermediatories between the king and the common cult vator is hinted at in several passages of the Black Yajur Vela. There we are told in connection with the performance of certain sacrifices by a person desirous of winning a village (gramakima) how the gods concerned 'as ign him creatures led by the noses' 158 how they 'present his relatives to him and make the folk dependent on him' 159 and how they enable him to grasp the mind of his equals. These significant expressions can only refer to the lordships of single villages either obtained through royal favour or acceptance by villagers or acquired in the first instance by individual exertion, but afterwards receiving the seal of royal confirmation. According to the authors of the Vedic Index what the king granted was his right of levying contributions and probably nothing more. In the other case the man attained nothing more than social pre-eminence in as much as it required the sanction of sajītas and sanins, and this shows that no

was Macdonell and Kaith-Vedic Index, s. v. bali.

vas U. N. Ghosal - Contributions to the History of the Hindu Revenue System, pp. 59-62.

<sup>141</sup> Atharvayoda, III. 29. 1.

Tas Black Yajur Veda, II. 1. 1. 2.

tee Ibid., II. 1. 3. 2.

<sup>\*\*\*</sup> Ibid., IL 3. 9. 2.

real rights were parted with by the sajītas but were vested in him. When we come to later literature we find instances of gifts of villages by kings. The Chandogya Upanisad761 mentions the gift of a village by king Janaśruti to Raikka. In subsequent periods such gifts of villages were common and this contributed to the growth of the Mahasalas whom we find in the Upanisads and in early Buddhist literature. The evidence of Buddhist literature shows, as we shall see later on, that the Mahāsālas enjoyed the revenue of villages and may be regarded as occupying the position of land-lords.

As regards the law of inheritance we have a passage even in the Rigveda 762 which according to Sayana's interpretation appear to attribute, in a very obscure manner, to the customs or laws of succession to property among men. The passage reads thus:

> "Wise, teaching, following thought of Order, the sonless gained a grandson from his daughter. Fain, as a sire, to see his child prolific, he sped to meet her with an eager spirit. The son left not his portion to the brother ....."

The word vahnih, which usually means an oblation-bearer, a sacrificer, a priest or one who is borne along as a god in a celestial car, is taken by Sayana to mean sonless, the father of a daughter only. The sonless father, according to Sayana, "stipulates that his daughter's son, his grandson, shall be his son, a mode of affiliation recognised by law; and relying on an heir thus obtained, and one who can perform his funeral rites, he is satisfied." Sayana interprets "The son left not his portion to the brother" thus: "a son born of the body does not transfer (paternal) wealth to a sister."763 We have two mythological accounts of father Manu (not as Law-giver but as Adam of the race) and of the division of his inheritance. One of them

<sup>702</sup> IV. 2.4.

TOR 111. 31. 1-2.

<sup>768</sup> Professor Wilson remarks "These two verses, if rightly interpreted, are wholly unconnected with the subject of the Sukta, and come in without any apparent object : they are very obscure, and are only made somewhat intelligible by interpretations which seem to be arbitrary, and are very unusual, although not peculiar to Sayana, his explanation being based on those of Yaska.

says "Manu divided his property among his sons; one of them Navanedistha by name living elsewhere as a student he excluded from a share."764 The other account says "The brothers excluded from a share one of Manu's sons."765 In both the accounts the property is divided in the father's life-time and the division was equal. In due course Navanedistha demanded his share and his claim was accepted in principle, though many obstacles intervened in his regaining his lawful share. The story shows undoubtedly that even during the life-time of the father, son were regarded as having a vested interest in property, from which they could not be excluded at will. The Black Yajur Veda 766 speaks of a father making common property with a son. The commentator takes this as referring to the fact that the son's earnings are his own, the father shares them with the family and this seems correct. Sayana also notes that the son keeps his secretly, i.e., perhaps his ownership was precario, not of right; the parallel to Roman law is striking and justifies us in accepting the view of the commentator. In the mythology of the Brahmana period we find that the childern of the Father God viz., gods and devils fight for their respective shares and "enter into their inheritance" by dividing it. The division of property among the sons was not always equal, the eldest often getting a little more than the others, probably even a double share of the wealth as is evident from the following passage of the Atharvaveda. 767

> "Agni, the banqueter on flesh, not banished, for the eldest son Taketh a double share of wealth and spoileth it with poverty."

The meaning of the passage seems to be, that if the rites are not duly performed the eldest son of the departed, though he receives a double share of the property, will be eventually ruined.

Agriculture—Progress was doubtless made in agriculture. The plough was large and heavy; we hear of as many as six 768 or eight 769 or

<sup>104</sup> Black Yajar Veda, III. 1.9.

<sup>144</sup> Aitareya Brāhmaņa, V. 14.

Tas II. 6. 1.

<sup>\*\*\*</sup> XII. 2. 35

<sup>\*\*\*</sup> Atharvaveda, VI. 91. 1; Black Yajur Veda, V. 2. 5.

<sup>\*\*\*</sup> Atharvaveds, VI. 91, 1.

twelve<sup>770</sup> oxen being harnessed to the plough. The plough was "of keen share, with well-polished handle."<sup>771</sup> The seasons bearing on agriculture are mentioned in the Black Yajur Veda. Thus barley ripen in the hot season, rice in autumn, beans and sesamum in winter and the cool season."<sup>78</sup> Further we learn that "twice in the year does the corn ripen."<sup>718</sup> According to the Kausitaki Brāhmaṇa<sup>774</sup> the winter crop was ripe by the month of Chaitra. The mention of a double crop shows a distinct advance in agriculture, which may be attributed partly to the larger use of manure and irrigation and partly to the knowledge of the cultivation of a larger variety of grains and plants which grew in different parts of the year. Indeed the advantages of a rotation of crops were fully realised. Thus a season of barley (yava) would be succeeded by one of rice (vrihi)<sup>778</sup> bean (mudga or māsha) and sesamum (tila). Besides these, other varieties of crops mentioned in the White Yajur Veda<sup>778</sup> were probably sown on the principle of rotation.<sup>777</sup>

The adoption of a system of rotation of crops, combined with the undeveloped state of intensive cultivation, apparently gave rise to what is known as the Field-grass system or Pasture or Two-field and Three-field systems. We may call this system of 'Khila' system of agriculture, for the

<sup>\*\*\*</sup> Black Yajur Veda, V. 2. 5.

<sup>171</sup> Atharvaveda, III. 17, 3 = Black Yajur Veda, IV. 2. 5.

<sup>\*\*\*</sup> Black Yajur Veda, VII, 2. 10.

<sup>\*\*\*</sup> Ibid., V. 1, 7.

TTS Compare Gobbila, I. 4, 29 and Khādira, I. 5, 37: "From the rice barvest till the barley (harvest) or from the barley (harvest) till the rice (harvest) he should offer the sacrifices."

<sup>\*\*\*</sup> XVIII. 12.

As the seasons of the Velic Age did not exactly coincide with those of later times a short notice seems necessary here. In the Rigveds five seasons are mentioned vis., Vasanta (¡Spring), Grisma (Summer), Sarat (Autumn), Prāvṛṣa (Rainy season) and the Hemanta or Hima (Winter). The Brāhmaṇas also mention these seasons. The Sāṃkhāyana Grihya Sūtra (IV. 18.1) also mentions only five seasons of the year. A sixth season was recognised later on as the evidence of Kautilya's Atherthasistra (Book H. Chapter 20) shows. See Tilak Artic Home in the Vedas, p. 183; Macdonell and Keith—Vedic Index, I. pp. 110—11; Zimmer—Altindisches Leben, pp. 373—74.

reason that land in those days appears to have been alternately cultivated and laid fallow (khila) to recover its fertility.7 18 Under the Two-field system there were two plots of land, one remaining under cultivation in any particular year or season, and the other lying fallow after the last harvest. In alternate years or so the fallow lands, serving temporarily as pastures would be brought under cultivation. At a time when intensive cultivation was still in incipiency, this method would enable land to recover fertility easily. In very early times when the number of crops raised did not exceed one or two, the system was a simple one; one plot of land would in a particular season remain under cultivation, say, of barley (yava) only while the other would remain fallow say, after the rice-harvest. But when the number of crops raised increased and the cultivator sowed and reaped more than two varieties in rotation, 779 the system followed must have been a Threefold system, three or four varieties being raised in two of the fields every year and the third lying fallow once in every three years. The ideal system that would work, may be thus indicated : let A, B and C be the three fields; then, in the first year, A would produce in rotation, say, Yava and Vribi, B would similarly produce in retation tila, masha, godhuma or masura 780 and C would remain fallow; in the second year, A would be cultivated intensively for one or two crops, B would remain fallow and C would produce two crops in rotation; in the third year, A would lie fallow, B would produce one or two crops like A in the second year, and C would produce one or two crops like A in the first or the second year ..... if B produces one crop, C produces two and vice-versa.781

Some more details about agricultural operations are forthcoming. The Satapatha Brāhmaṇa<sup>789</sup> mentions the operations of ploughing, sowing, reaping and threshing. The Atharvaveda<sup>788</sup> mentions the use of manure

See Professor Kisheri Mehan Gupta's article on "The Land system and Agriculture of the Vedic Age" in Sir Asutosh Silver Jubilee Volume on Orientalia, Vol. III. Part II.

White Yajur Veda, XVIII. 12 seems to refer to this.

woo White Yajur Veda, XVIII. 12; Black Yajur Veda, VII. 2. 10. 2.

<sup>100</sup> A. D., pp. 197-99.

Tes L 6. 1. 3.

(karisa, cow-dung). One of its hymns<sup>784</sup> was composed on the occasion of cutting a channel for irrigation or to avert a flood. Here the newly cut canal is described as a calf to the river which is the cow.<sup>785</sup> Well irrigation is thus described in the Black Yajur Veda.<sup>786</sup>

"Make firm the straps,
Fasten the buckets;
We shall drain the well full of water,
That never is exhausted, never faileth."
The well with buckets fastened,
With strong straps, that yieldeth abundantly,
Full of water, unexhausted, I drain."

788

The Kausika Samhita<sup>789</sup> also refers to canal irrigation and gives us the practical part of the ceremony of letting in the water. At first some gold plate is deposited on the bed, a frog with a blue and red thread round it, is made to sit on the gold plate and after this the frog is covered with an aquatic plant called Sevala and water is then let in.

As to the crops, the Atharvaveda mentions besides yava, sesamum, 700 vrihi 701 (as also tandula 702). We also find the word śāriśākā 703 which Griffith has translated as cultivated rice. 704 The cultivation of sugarcane is also referred to in the Atharvaveda. 705 The White Yajur-veda mentions a large number of crops. Thus we read:

"Vrîhayascha me yavascha me masascha me tilascha me mudgāscha me khālvascha me priyangavascha me navascha me syamākāscha me nivārāscha me godhumāscha me masurascha me yajnena kalpyantām." 196

<sup>\*\*\*</sup> III. 13. \*\*\* IV. 2. 5.

<sup>787</sup> Of. Rigveda X. 101.5; Kathaka Samhita XXXVIII. 14.

<sup>\*\*\*</sup> Cf. Rigveds, X. 101.6.

<sup>790</sup> II. 8, 3; XVIII. 3, 69.

TO 1 VI. 140. 2; VIII. 7. 20; IX. 6. 14; XII. 4. 18, 30, 32; cf. IV. 35.

<sup>700</sup> X, 9, 26.

Tota Griffith's Atharvaveds, Vol. I. p. 101, 101 fn.

<sup>700</sup> L 34. 1, 5.

"May my rice-plants and my barley and my beans and my sesamum and my kidney-beans and my vetches and my millet and my Panicum Milliaceum and my Panicum Frumentaceum and my wild rice and my wheat and my lentils prosper by sacrifice." 797 Upavakas or Indra-vavas (seeds of the Wrightia Antidysenterica) are also mentioned in the White Yajurveda, 798 The Black Yajurveda mentions Yava, 799 rice, 800 beans 801 and sesamum, 809 The Black Yajurvedasos also distinguishes between the black swift-growing asu and the mahavrihi. In another place 804 we find reference to black rice and white rice. The Taittiriya Brahmana 505 speaks of two kinds of rice āśu and mahāvrihi. The Brhadāranyaka Upanisad mentions a large number of crops. Thus we are told "There are ten kinds of village (cultivated) seeds viz., rice and barley (vrihiyavas), sesamum and kidneybeans (tilamīsās), millet and panic seed (anupriyangavas), wheat (godhumā), lentils (masūrā), pulse (khalvī) and vetches (khalakula)."806 The Rāmīvana mentions sesamum, 807 mudga, 808 mustard, 809 masa, 810 śali rice 811 (as also tandula 12). The Ramayana refers to sugarcane, 13 sugarcandy 14 as well as molasses. 815 Royal grain-stores are also mentioned. 816

```
*** Griffith's White Yajurveds, p. 194.
```

<sup>700</sup> XIX. 22.

<sup>\*\*\*</sup> I. 3. 1, 2, 6; VII. 2. 10.

<sup>\*\*\*</sup> VII. 2. 10.

sos Ibid.

<sup>\*\*\*</sup> II. 3. 1. 3.

son Ibid.

<sup>\*\*\*</sup> I. 8. 10.

<sup>\*0 \*</sup> L 7, 3, 4,

<sup>6</sup>th adhyāya, 3rd Brāhmaņa, verse 13. Max Muller's Translation in S. B. E. Vol. XV., p. 214.

<sup>\*07</sup> Ajodhyakanda, 20th sarga; Uttarakanda, 104th sarga.

<sup>\*\*</sup> Ajodhyākānda, 20th sarga; Uttarakānda, 104th sarga.

<sup>•••</sup> Ajodhyākāņda, 25th sarga.

<sup>\*10</sup> Uttarakända, 104th sarga.

<sup>911</sup> Bālakānda, 5th sarga; Ajodhyākānda, 32nd sarga. Compare dhānya in Bālakānda, 6th sarga.

<sup>\*10</sup> Bālakāṇda, 5th sarga; Uttarakāṇda, 104th sarga.

<sup>\*18</sup> Ajodhyākānda, 91st sarga; Uttarakānda, 104th sarga.

<sup>\*14</sup> Ajodhyākāņda, 91st sarga.

<sup>\*18</sup> Uttarakāņda, 105th sarga.

<sup>•1</sup> Ajodhyakanda, 36th sarga.

From the Ramayana 817 we learn that agriculture was an important art, for, it was included in Vartta which along with Trayi and Dandaniti comprised the famous three branches of learning. In the Rāmāyana<sup>8 18</sup> we find that when Bharata came to the forest to take Rama back to Ajodhya, Rama enquired of Bharata whether agriculturists found favour with him, in fact whether all persons living by Vartta are prospering in his kingdom, for, it was the duty of the king to look after their interests and welfare. As a matter of fact, we find that in Rama's time the world was green with corn 819; every city, village and kingdom had plenty of corn. 820 Kośala mahajanapada abounded in corn.821 Ajodhya is described as abounding in corn. 622 Every house in the city of Ajodhyā was filled with śāli rice. 822 The Vatsakingdom had plenty of corn (Ajodhyākānda, 52nd sarga). The banks of the Magadhi river are described as very fertile and as producing corn. 824 The banks of the river Pampa flowing through the kingdom of Kiskindhya abound in corn. 615 Corn is also grown in Dravida, Sind, Soubīra, Sourāstra, Daksināpatha, Anga, Banga, Magadha, Matya and Kāśi. 826

The farmer had as now constant trouble to contend with: the fields were covered with weeds like salanjāla and nilagalasīlā<sup>8,27</sup>; moles destroyed the seeds; birds and other creatures destroyed the young shoots; both drought and excessive rain destroyed the crops; and lightning often injured crops and plants. The Atharvaveda provides us with a considerable number of spells to avoid these disasters and secure a good harvest. Thus we read:

<sup>\*17</sup> Ajodhyākāņda, sarga 100, verse 68.

<sup>\*1 \*</sup> Ibid., sarga 100, verse 47.

<sup>\*1</sup> Uttarakānda, sarga 70.

<sup>\*\*\*</sup> Bālakāņda, sarga 2.

<sup>811</sup> Bālakāpda, sarga 5; Ajodhyākāpda, sarga 50.

<sup>\*\*\*</sup> Ajodbyākānda, sarga 75 ; Ibid., sarga 82 ; Ibid., 34

<sup>\*\*</sup> Balakanda, sarga 5.

<sup>\*\*\*</sup> Bálakánda, sarga 32.

<sup>\*\*\*</sup> Kişkindhyākāņda, sarga 1.

<sup>\*\*\*</sup> Ajodhyākāņda, sarga 10.

<sup>\*\*\*</sup> Athervaveda, VI, 16, 4,

"Destroy the rat, the mole, boring beetle, cut off their heads and crush their ribs, O Aswins Bind fast their mouths; let them not eat our barley"s \*\* "Spring high, O Barley, and become much through thine own magnificence :

Burst all the vessels : let the bolt from heaven forbear to strike the down."829

"Strike not, O God, our growing corn with lightning, nor kill it with the burning rays of Surva."830

We have also charms for hastening the coming of periodical rains, es 1 for fair weather 832 and to avert inundation. 833 All these precautions generally resulted in agricultural prosperity which we find described in many hymns of the Atharvaveda and the other Samhitas. It is not necessary to quote at length the prayers for a bumper harvest, 334 increase of cattle 335 and accumulation of wealth 36; though these harvest songs throw much light on the requirements of the peasantry and their simple ideas of happiness.

Despite these precautions famines were not unknown. In the Chandogya Upanisad837 we are told of a famine caused by the destruction of crops by locusts (mataci) whose intensity was so great that a muni Cakrayana by name had to migrate to a neighbouring country along with his young wife and had to live on kulmīsa. In the Rāmāyana we find that in Rama's time the people were free from famine. 8 38 Nevertheless we find that after the destruction of Vrtrasura owing to drought many people died

<sup>\*\*\*</sup> Ibid., VI. 50. 1.

<sup>\*\*\*</sup> Ibid, VL 142, L 001 Ibid., IV. 15.

<sup>\*\*\*</sup> Ibid., VIL 11. 1.

<sup>\*\*\*</sup> Ibid., VI. 128.

sas Ibid., VII. 18. See Kausikasutra, CIII. 3. and Weber's Omens and Portents, p. 366.

<sup>\*\*\*</sup> Ibid., IV. 39. 2; VI. 142; XIX. 7. 4; XIX. 9. 1.

<sup>\*\*</sup> Ibid., L 3L 4; I. 15.2; VI. 16; VI, 59.; VII. 104.

<sup>130</sup> Ibid., I. 15; I. 26. 2; IV. 39; VI. 55. 2; VII. 16; VII. 17; VII. 20. 3; VII. 40; VII. 41; XIX. 3; XIX. 7. 5; XIX. 10. 2.

ast I. 10. 1-3.

<sup>\*\*\*</sup> Bālakāņda, sarga 1; Uttarakāņda, sarga 119.

of famine. 838 Again owing to the sin of king Lomapada, famine over took his kingdom of Anga, 840

Forests and their economic importance-Besides serving as natural pastures the forests supplied an essential part of the economic needs of the people of this age. They provided them with wild rice (nivara),8 41 fuel8 42 and with the materials for the construction of houses, 843 chariots, 844 sacrificial implements 445 and animals. 846 They were a perennial source of supply of medicinal herbs and plants 47 as well as of sacrificial grass. 848 They also supplied the people with aloe (aguru), \$40 bdellium (guggulu), \$50 spikenard (naladi), 851 resin (salanirjyasa), 833 musk, 853 sandalwood, 854 lac, 856 hides, 856 fruits 857 and honey. 858 Sandalwood was used not only for the cremation of kings859 but also for preparing a paste for personal

```
sse Uttarakanda, sarga 99.
```

\*\*\* Thid.

sas Bálakánda, sarga, 9.

<sup>642</sup> White Yajurvede, XVIII. 12.

<sup>\*\*\*</sup> Rāmāyaņa, Aranyakānda, 11th sarga.

Rāmāyaņa, Ajodhyākānda, 56th sarga; Ibid., Aranyakānda, 15th sarga.

<sup>\*\*\*</sup> Griffith's Atharvaveda, Vol. II. p. 440 fa.

<sup>\*\*\*</sup> Ramayana, Balakanda, 14th sarga.

White Yainrveds, XXIV. 1-40.

See below.

<sup>\*\*\*</sup> Ramayana, Ajodhyakanda, 70th, 86th and 91st sargas.

<sup>880</sup> Atharvaveda, H. 35. 7; IV. 37. 3; XIX. 38. 1, 2; Compare White Ysjarveda, V. 13,

esi Atharvaveda, IV. 37. 3.

<sup>889</sup> Ramayana, Ajodhyākanda, 76th sarga.

<sup>\*\*\*</sup> Ibid., Lankakanda, 75th sarga.

<sup>154</sup> Ibid., Aranyakanda, 15th, 35th and 60th sargas; Ibid., Kiskindhyakanda, Ist, 27th, and 41st sargas ;

sas Ibid., Ajodhyāzāņda, 75th sarga; Ibid., Kişkindhyākāpda, 23rd sarga.

uss [bid., Aranyakānda, 43rd sarga (deer-skin ) Ibid., Lankākānda, 75th sarga (tigerekin and the yak's tail ).

est See below.

<sup>\*\*</sup> Atharvaveda, I. 34. 1-4; III. 30. 2; IV. 36. 6; VII. 56. 2; IX. 1. 16-19, 22; Compare 1bid, XVIII. 2. 14; XVIII. 4. 3; White Yajurveda, I. 16; XVII. 2. 12; XVIII. 65; Black Yajarveda, V. 2. 6; V. 4. 2; Ramayana, Ajodhyākāpda, 75th sarga, etc.

<sup>\*\*</sup> Rāmāyaņa, Kiskindhyākāņda, 25th sarga.

adornment. 660 The milky juice of the Ficus Indica (Bata) leaves was used in preparing matted locks of hair. 661 No wonder, therefore that the poet-priests sang in the following strain:—

"May the plants be sweet for us." \*\*63
"May the tall trees be full of sweets for us." \*\*63

The various useful trees known to the people of this period are:—
(1) Vibhidaka or Vibhitaka (Terminalia Bellerica)<sup>864</sup> whose nuts were used as dice in very early times.<sup>865</sup> (2) Palāša or Parņa (Butea Frondosa)<sup>866</sup> from whose wood covers of some sacrificial vessels were made.<sup>667</sup> The great ladle called Juhū with which clarified butter was poured into the sacrificial fire<sup>868</sup> and other sacrificial vessels were made of this wood, to which in the shape of amulets, also great efficacy was ascribed.<sup>869</sup> (3) Udumbara (Ficus Glomerata)<sup>870</sup> from whose wood besides amulets, sacrificial posts and ladles were made.<sup>871</sup> In the Bṛhadīranyaka Upaniṣad<sup>872</sup> we are told: Four things are made of the wood of Udumbara tree, the sacrificial ladle (sruva), the cup (kamsa), the fuel and the two churning sticks." (4) Vaikankata

<sup>1000</sup> Ibid., Ajodhyākānda, 76th, 78th, 88th and 91st sargas.

set Ibid., 52nd sarga.

<sup>\*\*</sup> White Yajurveda, XIII. 27.

<sup>\*\*\*</sup> Ibid, XIII. 29.

<sup>\*\*</sup> Atharvaveds, VII. 109. 1.

<sup>068</sup> Rigveda, X 34. 1.

Atharvaveda, III. 5; V. 5. 6; XIV. 1. 61; XVIII. 4. 53; White Yajurveda, XI. 57. 50; XII. 86. 79; XXXV. 4; Black Yajurveda, IV. 2. 6; VII. 4. 12; Rāmāyana, Bālakānda, 14th sarga; Ajodhyākānda, 63rl sarga.

Atharvaveda, XVIII. 4. 53.

ass Black Yajurveda, III. 5. 7.

Atharvaveda, III. 5. Prof. Weber observes that Palida or Parna is etymologically identical with the German Farn, English Forn; Forn-seed was supposed to have the power of rendering one who carried it invisible, and the plant was said to be of celestial origin and able to secure the fulfilment of every wish (Simrock, Handbuch der Deutschen Mythologie, p. 498).

Atharvaveda, XIX. 31; White Yajurveda, V. 26. 26, 28; Black Yajurveda, III. 4.8; VII. 4, 12.

<sup>&</sup>quot;12 Griffith's Atharvaveda, Vol. II. p. 287 fn.

<sup>\*\* 6</sup>th Adhyaya, 3rd Brahmapa, 13.

(Flacourtia Sapida)373 whose wood was used as sacrificial fuel as well as for manufacturing vessels for spirituous liquors.874 (5) Madhuka or Mandhuka (Bassia Latifolia)875 whose wood was used as sacrificial fuel.876 (6) Aratu (calosan this Indica),877 a hard wooded tree from whose timber the axles of chariots and carts were made. 878 (7) Bilva 879 wbich grows wild and produces an edible fruit, the wood-apple It was used to curdle milk.880 (8) Chandana, sandal-wood.881 The Rāmāyana882 refers to three kinds of sandal wood viz., Gosira, Padmaka and Harisyama. (9) Syandana 888 (10) Raktachandana 886 (11) Nagakeśara 886 (12) Simha-(15) Sisunaga 489 (13) Naga 867 (14) Punnaga 888 kesara 886

878 White Yajarveda, X. 34. 32; XI. 75. 71; XVII. 74.

era White Yajarveda X. 34. 32. Compare Vikankata tree in Black Yajarveda, III. 5.7; V. 1.9; V. 4.7; VI. 4.10.

875 Black Yajurveda, III. 4.8; Rāmāyana, Ajodhyākānda, 94th sarga; Aranyakānda, 11th sarga; Lankākānda, 4th sarga; Uttarakānda, 52nd sarga,

870 Black Yajurveda, III. 4. 8.

477 Atharvaveda, XX. 131, 17, 18.

970 Griffith's Atharvaveda, Vol. II. p. 440 fn.

ere Atharvaveda, XX. 136. 3; White Yajurveda, XIX. 22; XIX. 89; XIX. 91; XXI. 29; Black Yajurveda, II. 5. 3; Rāmāyaņa, Aranyakānda, 13th sarga.

sso Black Yajurveda II. 5. 3. Sacrificial posts were made of Bilva wood (Rāmāyaṇa, Bālakānda, 14th sarga).

ees Rāmāyana, Aranyakānda, 15th, 25th and 60th sargas; Kişkindhyā-kānda, 1st, 27th and 41st sargas; Uttarakānda, 52nd sarga. The Malayachala hill (Kiskindhyā-kāṇda, 41st sarga), the islands or churs in the river Kāverī (Ibid) and the southern sea-coast of the Deccan (Aranyakanda, 35th sarga) were adorned with sandalwood forests.

\*\* Kiskindhyākāņda, 41st sarga.

\*\*\* Aranyakānda, 15th sarga; Kiskindhyākānda, 1st sarga.

ees Kişkindhyākānda, let sarga; Uttarakānda, 52nd sarga.

ses Kişkindhyākān iz, 73rd sarga; Uttarakānda, 52nd sarga.

\*\* Kiskindhyākānda, 1st sarga.

see Lankākānda, 4th sarga; Kiskindhyākānda, 1st sarga; Sundarakānda, 14th sarga.

\*\*\* Aranyakānda, 15th, 60th, 75th sargas; Kişkindhyākānda, 50th sarga; Sundarakāņda, loth sarga; Lankākāņda, 4th sarga; Uttarakānda, 31st and 52nd sargas.

... Kiskindyākāņda, let sarga.

\*\*\* Atharvaveda, IV. 27. 4; V. 5. 5; White Yajurveda, XXIII. 16. 13; Black Yajurveda, III. 4. 8; Rāmāyaņa, Arapyakānda, 73rd sarga.

\*\*\* Atharvaveda V. 5. 5; Rāmāyana, Aranyakānda, 73rd sarga; its wood was used as sacrificial fuel (Black Yajurveda, III. 4. 8).

\*\*\* Atharvayeda, VI. 11. 1; VI. 30. 3; Black Ysjurveda, V. 1. 9; V. 4. 7.

\*\*\* Atharvaveda, VI. 129. 1; XX. 129. 7, 8.

504 Athervaveda, VI. 15. 3.

\*\*\* Atharvaveda, V. 29. 15; Kansikasiitra, XXV. 27.

\*a? Atharvaveda, VI. 44. 3.

\*\*\* Atharvaveda, VIII. 2, 28; White Yajurveda, V. 18, 13; Rāmāyaņa, Kişkindhyākāṇda, 43rd sarga.

\*\*\* Rāmāyaņa, Bālakāņda, 14th sarga ; Uttarakāņda, 52nd sarga.

voo White Yajurveda, XII. 86. 79.

son White Yajarveds, XIII. 13.

was Griffith's White Yajurvada, p. 138 fn.

\*\*\* White Yajarveda, XI. 70; Compare Krumuka wood in Black Yajurveda, V. 1. 9.

\*\*\* Griffith's White Yajasveda, p. 117 fn.

sos White Yajarveda, XXIII. 16, 13; Rāmāyan, Kişkindbyākānda, Ist sarga.

\*\*\* Atharvaveda, XX. 131, 17, 18; Rāmāyaņa, Bālakāņda, 24th sarga; Ajodh-ākāņda, 94th sarga; Arapyakāņda, 15th and 73rd sargas; Kişkindhyākāņda, 1st and 50th sargas.

\*\*\* Atharvaveda, I. 22. 4= Rigveda I. 50. 1z.

... Rimayapa, Bilakanda, 14th sarga.

oos Thid.

<sup>\*\*\*</sup> Atharvaveda, III. 6; IV. 87. 4; V. 4. 3; V. 5. 5; VI. 11. 1; VI 95 1; VIII. 7. 20; VIII. 8. 3; XII. 3. 1; XX. 131. 17, 18; XX. 134. 3; Rāmāyapa, Arapvakāpda 13th and 72rd sargas.

(32) Kukuva 910 (33) Tinduka 911 (34) Patala 919 (35) Badari 915 (36) Sallakī<sup>914</sup> (37) Betasa<sup>915</sup> (38) Jambu<sup>916</sup> (39) Kimšuka<sup>917</sup> (40) Vallataka<sup>918</sup> (41) Bata (Ficus Indica) 919 (42) Sala 990 (43) Marichagulma 921 (44) Ingudi<sup>929</sup> (45) Kapittha<sup>993</sup> (46) Panasa<sup>924</sup> (47) Bijapūraka<sup>925</sup> (48) Asana<sup>986</sup> (49) Tamīla 927 (50) Vārunda 928 (51) Šiņsapī 929 (52) Nibāra 930

sao Bālakānda, 24th sarga; Aranyakānda 60th sarga; Kişkindhyākānda, 27th sarga.

- eas Bālakānda, 24th sarga; Aj dhyākānda, 94th sarga; Aranyakānda, 73rd sarga; Laukat anda, 4th sarga,
- ela Balakanda, 24th sarga; Aranyakanda, 15th sarga; Compare Patali tree in Kişkindhyākānda, lat sarga and Uttarakānda, 21st sarga.
- \*10 Balakanda, 24th sarga ; Ajodhyakanda, 55 h and 94th sargas.
- 11 Ajodhvákánda, 55th sarga.
- 215 Ajodhyākānda, 55th sarga, Aranyakānda, 61st sarga; Kişkindhykānda, 27th sarga.
- 916 Ajodhyākānda, 55th, 91st and 34th sargas ; Aranyakānda, 6.th and 73rd sargas ; Kişk'ndhyākānda, 28th sarga; Lunkākānda, 4th sarga; Uttarakānda, 52nd sarga.
- \*17 Ajodhyākānda, 55th, 56th and 63rd sargas; Aranyakānda, 15th sarga; Kişkindhyakāņda, let sarga ; Lankākāņda, 104th sarga.
- 110 Ajodbyākāņda, 56th sarga,
- \*1 Ajodhyākāpila, 15th, 53rd, 55th sargas ; Arapyakānda, 35th sarga ; Lankākānda, 4th sarga.
- ese Ajodhyākānda, 71st, 72nd, 96th and 99th sargas; Aranyakānda, 11th, 15th, 25th and 60th sargas; Kiskindhyākānda, 27th, 40th and 50th sargas; Sundarakānda, 14th sarga; Uttarakanda, 52nd sarga. There were beautiful avenues of Sala trees in the city of Ajodhya ( Ajodhyakanda, oth sarga ).
- ana Aranyakanda, 35th sarga.
- \*\*\* Arapyakanda, 50th and 88th sargas.
- Aranyakanda, 91st sarga.
- Aranyakanda, 11th, 15th, 60th, 73rd, 91st and 94th Sargas; Uttarakanda, 31st and 52nd sargas.
- ass Ajodhyākānda, 91st sarga.
- ... Ajodhväkända, 94th sarga.
- \*\*\* Ajodhyākāņda, 91st sarga; Araņyakāņda, 15th and 35th sargas; Kiskindbyākānda, 27th, 40th and 50th sargas ; Uttarakānda, 114th sarga,
- \*\*\* Ajodhyākānda, 71st sarya.
- as Ajodbyākāņda, Slat sarga; Kişkindbyākāņda, lat sarga; Sundarakāņda, 14th and 18th sargas ; Laukākāņda, 4th sarga.
- 130 Arapyakanda, 11th and 15th sargas,

- (53) Binduka 931 (54) Piyala 932 (55) Amkola 933 (56) Tinisa 934
- (57) Benu<sup>9 55</sup> (58) Chiribilwa<sup>9 56</sup> (59) Tilaka<sup>9 57</sup> (60) Nipa<sup>9 58</sup> (61) Bijaka<sup>9 59</sup>
- (62) Aśwakarna 40 (63) Lakucha 41 (64) Arjuna 42 (65) Kurara 45
- (66) Sindubāra 44 (67) Karnikāra 45 (68) Nīla 46 (69) Agnimukhya 47
- (70) Pāribhadraka 48 (71) Naktamāla 49 (72) Uddālaka 50 (73) Kuranta 51
- (74) Churnaka 959 (75) Kobidāra 953 (76) Muchukanda 954 (77) Karanja 955
- (78) Raktakuruvaka 958 (79) Ksiri tree 957 (80) Atimukta 958 (81) Pad-
  - 950 Arapyakanda, 11th sarga.
  - 252 Ajodhyākāņda, 94th sarga; Arapyakāņda, 73rd sarga; Uttarakāņda, 31st sarga.
  - \*\*\* Ajodhyākān la, 94th sarga | Kiškindhyākān la, 94th sarga ; Kiškindhyākānda, 1st sarga ; Lankākānda, 4th sarga.
  - \*\*\* Ajodhyākāpla, 91th sarga; Araņyakāņda, 11th and 15th sargas; Kişkindhyā-kāpda, 1st and 27th sargas; Lankākāpda, 4th sarga; Uttarakāpda, 52nd sarga.
  - \*\*\* Ajodhyākāpda, 94th sarga.
  - . . Lankákánda, 4th sarga.
  - \*\*\* Aj-dhyakanda, 94th sarga; Kiskindhyakanda, 27th sarga; Lankakanda, 4th sarga.
  - \*\*\* Ajodhyākāṇda, 94th sarga; Aranyakāṇda, 15th sarga; Kişkindhyākāṇda, 27th sarga; Lankākāṇda, 4th sarga,
  - ... Ajodhyākāņda, 94th sarga.
  - 640 Bālakāņda, 24th sarga; Aranyakānda, 15th sarga; Sundarakānda, 56th sarga.
  - \*\*\* Arapyakāņia, lötb sarga,
  - \*\*\* Aranyatānda, 60th sarga; Kişkindhyākānda, 1st, 27th and 28th sargas; Lankā-kānda, 4tb sarga; Uttarakānda, 31st and 52nd sargas.
  - osa Aranyakanda, 60th sarga.
  - p.4 Lankakanda, 4th sarga.
  - \*\*\* Arapyakāņda, 73rd sarga;; Kişkindhyākāṇda, 40th and 50th sarga; Uttarakāṇda, 31st sarga.
  - \*\* Kişkindbyākāņda, let earga.
  - \*\*\* Arapyakāņda, 73rd sarga.
  - \*\*\* Arapyakanda, 73rd sarga.
  - \*\* Arapyskānda, 73rd sarga; Kişkindhyākānda, 1st sarga.
  - \*\*\* Aranyakānda, 75th sargas; Kiskindhyākānda, 1st and 42nd sargas; Sundarakānda, 14th and 15th sargas.
  - esa Kişkindhyākāņda, let sarga,
  - \*\*\* Kiskindhyākānda, let sarga ; Lankākānda, 4th sarga.
  - \*\*\* Kişkindhyakanda, 1st sarga ; Lankakanda, 4th sarga ; Uttarakanda, 52nd sarga.
  - \*\* Kişkindhyākāņda, let sarga.
  - Dan Lankakanda, 4th sarga.

- \*\*\* Kişkindhyākāpda, 26th sarga.
- \*\*\* Kişkindhyakanda, let sarga. \*\*\* Kişkindhyakanda, 27th sarga.

- maka950 (82) Sarjja960 (83) Sarala, Indian pine tree961 (84) Bānīra968
- (85) Timida 963 (86) Kritamīla 964 (87) Saptaparņa 965 (88) Banjula 966
- (89) Vabya 967 (90) Ranjaka 968 (91) Muchulinda 969 (92) Patalika 970
- (93) Kutaja 971 (94) Hintala 978 (95) Lilasoka 973 (96) Priyangu 974
- (97) Tungaka<sup>978</sup> and (98) Khadira<sup>978</sup> (Acacia Catechu) from whose timber four-cornered sacrificial cups,<sup>978</sup> thrones,<sup>978</sup> sacrificial posts<sup>979</sup> and dipping spoons<sup>980</sup> were made.

From the Rāmāyana we learn that the art of gardening was known and practised in those days. The trees, flower-plants and fruit-trees were planted in the Aśoka forest, the royal pleasure-garden of Lankā by experts (in horticulture). The garden was furnished with tanks having rows of trees planted on their banks with pleasure-houses, beautiful groves and

- \*\* Kişkindhyabanla, 27th and 45rd sargas ; Lankikanda, 4th sarga.
- \*\*\* Kişkındhyākāpda, 26th sarga.
- 161 Kiskindhväkända, 27th sarga; Lankäkända, 4th sarga.
- · \*\* Kişkindhy ākāņda, 27th sarga,
- . 948 Kiskindhyākāpda, 27th sarga.
  - \*\*\* Kişkindhyakan Ja. 27th sarga.
- \*\*\* Kişkindbyākāņda, 30th sarga; Sandarakāpla, 15th sarga; Uttarakāpla, 52nd sarga.
- \*\*\* Kişkindhyakanda, 50th sarga.
- 94 Sandarskända, 14th sarga.
- \*\*\* Lankākānda, 4th sarga.
- Lanka anda, 4th sarga.
- 10 Lankākāņda, 4th sarga.
- " Lankakande, 4th sarga.
- \*\*\* Kişkindhyākānda, 1st and 27th sargas ; Lankākānda, 4th sarga.
- \*\*\* Lankākāņda, 41b sarga.
- \*\*\* Utterskända, 3let and 52nd sarga.
- \*\*\* Uttarakāņla 52nd sarga.
- \*\*\* Atharvaveda, III. 6. 1; V. 5. 5; VIII. 8. 3; X. 6. 7; XII. 3. 1; XX. 131. 17, 18; White Yujurveda, V. 42; VIII. 31; X. 26; Black Yajurveda, III. 5, 7, 1; Rāmāyan, Bālakānda, 14th sarga; Aranya-kānda, 15th sarga.
- \*\*\* White Yajurveda, VIII. 33,
- \*\* White Ynjurveda, X. 26.
- \* Rāmāyapa, Lālakāpda, 14th sarga.
- 860 Black Yajorveda, III. 5, 7, 1.
- \*\*\* Rāmāyaņa, Uttarakaņda, 52nd sarga.

raised seats here and there. The following flower plants and trees are mentioned in this period:—(1) Aśoka (2) Ketaka (3) Champaka (3) Champaka (4)

- (4) Bakula 88 (5) Raktotpala 987 (6) Kadamba 888 (7) Mālatī 989
- (8) Malliki 990 (9) Padma 691 (10) Karavira 992 (11) Sindabara 993
- (12) Bīsanti<sup>904</sup> (13) Matulinga<sup>905</sup> (14) Pūrņa<sup>908</sup> (15) Chirabilva<sup>907</sup>
- (16) Kunda<sup>998</sup> (17) Pirijita<sup>990</sup> (18) Aguru<sup>1000</sup> (19) Kaliguru<sup>1001</sup>
- (20) Tagara 1002 (21) Mandira 1008 (22) Madhavi 1004 (23) Bañjula 1008
- (24) Bakula 1006 (25) Gagapuspi 1007 (25) Sirisa 1008 (27) Nilajhipti 1009

\*\*\* Ajadhyākāṇda 10th sarga; Arapyakāṇda, 15th, 60th, 71st and 75th sargus; Kiskindhyākāṇda, 1st and 27th sargus; Sundarskāṇda, 14th sarga; etc.

coa Aranyatania, 15th and 60th sargas; Kiskindhya kanda, let and 27th sargas;

Lankākāpla, 4th sarga; Uttar kāp a, 31st sarga.

Ajodhyākāṇda, 10th sarga; Araṇyakāṇda, 15th sarga; Sundarakāṇda, 14th and 15th sargas; Kiṣkindbyākāṇda, 1st and 50th sargas; Lankākāṇda, 4th sarga; Uttarakāṇda, 31st sarga.

oco Aranyakania, 60th sarga.

oor Kişkindhyākāņda, let sarga.

- oss Aranyakānda, 60th and 73rd sargas; Kişkindhyākānda, 27th sarga; Uttarakānda, Sist and 52nd sargas.
- •s• Kişkindhyākāpda, 1st and 27th sargas, Fişkindhyākāpda, 1st sarga.
- White Yajurveda, II. 33; Compare Ibid., XI. 32; XXI. 31; Hāmāyaņa, Kişkin-dhyākāpda, 1st sarga.
- ••• Aranyakānda, 73rd sarga ; Kişkindhyākānda, 1st sarga ; Lankākānda, 4th sarga.
- \*\*\* Kişkindhyākāṇda, 1st and 27th sargas ; Lankākāṇda, 4th sarga.
- ••• Kişkindhyākāpda let sarga; Lankākāpda, 4th sarga.
- \*\*\* Kişkindhyakanda, 1st sarga.

one Itaid.

oor Ibid.

- ••• Kişkindhyākānda, 1st and 27th sargas ; Lankākānda, 4th sarga.
- ... Utiarakāp la, 52nd sarga.
- Uttarakānda, 52nd sarga. The southern Sea-coast of the Deccan was adorned with agurn forests (Aranyakānda, 35th sarga).
- 1001 Uttarakāņda, 5 ?nd sarga.

1005 Uttarakānda, 31st and 52nd sargas.

- 1000 Urturakāņda, Slat sarga. 1004 Lankākāņda, 4th sarga.
- 1000 Kiskindhväkända, let and 50th sargas ; Lankakanda, 4th sarga.
- 1000 Kiskindhyākāņda, 1st, 27th and 42ud sargas; Lankākāņla, 4th sarga; Uttarakāņda, 31st, 52nd and 114th sargas.
- 1001 Kişkindh; akanda, 12th and 14th sargas.
- 1008 Kişkindhyakanda, 1st and 27th sargas.
- 1000 Kişkindhyākānda, 30th sarga.

ses Ibid.

(28) Jivaka<sup>1010</sup> (29) Nilotpala<sup>1011</sup> (30) Lodhra<sup>1012</sup> (31) Amula (Menthonica Superba), <sup>1013</sup> a species of lily (32) Kandala, <sup>1014</sup>

The following fruit trees were known in this period:—(1) Mango<sup>1015</sup>
(2) Takkola<sup>1016</sup> (3) Dārimba,<sup>1017</sup> pomegranste (4) Cocoanut<sup>1018</sup> (5)
Date-palm (kharjura)<sup>1019</sup> (6) Āmalaki<sup>1020</sup> (7) Tāla<sup>1091</sup> (8) Kadalī plant (plantain tree) <sup>1022</sup> and Bilva (Bel tree) [ already referred to ].

Among the herbs and plants are mentioned (1) Abayu, 1023 a plant poisonous in its natural condition but medicinal when cooked and properly prepared. 1024 (2) Andikam, a plant with eggshaped fruits or

<sup>1010</sup> Ibid.

<sup>1011</sup> Kiskindbyākānda, let sarga.

<sup>1010</sup> Kiskindbyakanda, 1st and 43rd sargas; Uttarakanda, 31st and 52nd sargas.

<sup>1015</sup> Atharvaveda, V. 31, 4.

<sup>1014</sup> Ramayana, Kişkindhyakanda, 28th sarga.

Bihadāranyaka Upanisad, Adhyāya IV. Brāhman: III. verse 35; Rāmāyana, Ajodhyākānda, 63rd, 91st and 94th sargas; Arabyakānda, 15th and 73rd sargas; Kiskindhyākānda 1st sarga; Lankākānda, 4th sarga; Uttarakānda, 31st and 52nd sargas. The kingdom of Kosala was adorned with many mango-gardens (Ajodhyākānda, 50th sarga). The City of Ajodhyā also had many mango-gardens (Ajodhyākānda, 5th sarga).

<sup>1016</sup> Rāmāyana, Aranyakānda, 35th sarga.

<sup>1017</sup> Arapyakanda, 60th sarga | Uttarakanda, 52nd sarga.

zere Uttarakāṇda, 31st sarga; The southern sea-coast of the Deccau was adorned with groves of coccanut trees ( Arapyakāṇda, 35th sarga ).

<sup>1010</sup> Ibid., Arapyakānda, loth sarga.

<sup>1020</sup> Ibid., Ajodhyākānda, 91st sarga; Ibid., 94th sarga.

<sup>1011</sup> Ibid., Ajodhyākāņda, 91st sarga and 99th sarga; Aranyakāņda 15th sarga, 35th and 60th sargas; Kiṣkindhyākāṇda, 11th, 12th, 40th and 50th sargas; Uttarakāṇda 114th sarga. The poet Vālmiki compares the breasts of Sitā to the large tāla fruit (Araṇyakāṇda, 46th sarga).

Did., Kişkindhyakanda, 13th sarga. The hormitages of Agastya on the Godavari (Lankakanda, 125th sarga) and of Rama in the Panchbati forest (Aranyakanda, 35th and 42nd sargas) were adorned with groves of plantain tree; Maitrayana-Brahmans—Upanişad, 4th Pranataka, verse 2.

<sup>1023</sup> Atharvaveda, VI. 18. 1.

<sup>2014</sup> Griffith's Atharvaveds, Vol. I. p. 253 fn.

bulbs1095 (8) Apamarga1096 (from mrija, to cleanse or wipe, with apa+8) Achyranthes Aspera, a biennial plant frequently used in incantations, in medicine, in washing linen, and in sacrifices, and still believed to have the power of making men proof against the stings of scorpions. It is called also parakpuspi, pratyakpuspi and pratyakparni from the reverted direction of the growth of its leaves, flowers and fruits1027 (4) Aukshagandhi1028 (5) Guggulu1029 (Borassus Flabelliformis) from which a costly fragrant gum exudes. (6) Jaugida 1080 a plant frequently mentioned in the Atharvaveda as a charm against demons and a specific for various diseases. It appears to have been cultivated 1031 (7) Naladi 1032 8) N r chi 1033 (9) Pili 1034 (10) Pata, probably identical with Patha (Clypea Hernandifolia . 1038 Like the Scottish rowan or like St. John's wort it was potent against fiends. (11) Baja, 1036 apparently some strong-smelling herb (Atharvaveda, VIII. 6. 10) by whose scent the demon is chased away as was Asmodeus. by 'the fishy fume that drove him, though enamoured, from the spouse of Tobit's son' (Paradise Lost, IV. 168) (12) Pinga 1037 (13) Pramandini 1038 (14) Prisniparoi 1039 having variegated leaves) Hemionit's Cordifolia, a medicinal plant, a decoction of which is recommended by Susruta to be taken as a preventive against abortion. (15) Ajasringi, 1040 literally goat's horn, Odina Pinnata, a plant used in incantation. (16) Avakī, 10 41 Blyxa

1015 Atharvaveds, IV. 34 5; Compare Ibid., 17, 16.

1026 Atharvayeda, IV. 37, 3.

<sup>2016</sup> Ibid., IV. 17. 6; IV. 18. 7, 8; IV. 19. 1, 4; XIX. 20. 3; White Yajurveda, XXXV, 11; IX. 38.

<sup>30</sup> at See Atharvaveda IV. 19. 4, 7; VI. 129. 3 and VII. 65. 1.

<sup>.</sup> see Ibid., II. 36. 7; IV. 37. 3; XIX. 38. 1, 2; Compare White Yajarveda V. 13.

<sup>1000</sup> Atharvaveda II. 4. 2, 4, 5; XIX. 34; XIX. 35.

<sup>1001</sup> Ibid., II. 4. 5. ('Spring from the sape of husbandry').

<sup>1050</sup> Ibid., IV. 37. 3. " Smelling of spikenard."

<sup>1088</sup> Ibid., V. 31. 4. 1084 Ibid., IV. 37. 3.

<sup>1004</sup> Ibid., H. 27, 4; IV. 19. 4.

<sup>2010</sup> Atharvaveda, VIII. 6. 3; VIII. 6. 24.

<sup>1027</sup> Ibid., VIII. 6, 18; VIII. 6, 24. 1030 Ibid., IV. 37. 3.

<sup>1041</sup> Ibid., IV. 37. 8; VIII. 7. 9; cf. Ibid., III. 13. 7; VI 12. 3; White Yajarveda, XXV. 1; Compare Ibid., XIII. 30; XVII. 4; Kaušikasūtra, XL. 3—6.

Octandra, a water plant called Saivāla in later times (17) Sāluda 1042 (18) Sappaka, 1048 an aquaticplant (19) Mulilin, 1044 an aquaticplant (20) Sama1045 (21) Silachi 1046 more usually called Arundhati 1047; a medicinal climbing plant formerly applied in cases of severe contusion or fracture 1048 (22) Sipudru, 1049 an unknown plant or tree, a magic cure for consumption, 1050 (23) Vihalha, 1051 an unidentified plant (24) Madāvati, 1059 an unidentified plant (25) Tauvilika, 1033 some kind of plant or animal (26) Varana, 1054 Crataiva Roxburghii, a plant used in medicine and supposed to possess magical powers. It grew abundantly on the banks of the river Varanavati. This Varana healeth all diseases 1088 (27) Visha, 1086 some unknown herb (28) Vishātaki, 1037 some nnknown herb (29) Vishāņakā 1058 some unknown plant or tree (30) Kustha, 1059 Costus Speciosus or Arabicus, a medicinal plant, grown on the snowy mountains, a banisher of fever. 1060 (31) Jivala, Jivala, 1061 two species of plants (32) Nagnahu 1062 was a root used as yeast, for fermenting the sura1063 (33) Patika or Putika, 1086 a plant used to expedite the curdling of the sacrificial milk 1085 and as substitutes for Soma plant; a kind of grass according to Mahidhara

```
Atharvaveda, VIII. 6, 17,
1049
```

1049

Ibid., IV. 34. 5. 2045

<sup>1044</sup> Ibid.

Ibid, I. 24 4. Instead of Samā the Paippalada recension reads Syamā (the 1045 dusky ) with which compare Atharvaveda L 23 1; so also Sankara Pandit according to two Mss. Observe also Samaka - Syamaka in Kausikasutra VIII. 1. Syama is the name of various plants ( See St. Petersburg Dictionary, s. v. ).

Atharvaveda, V. 5. 1. 1048

Ibid., V. 5. 5; IV. 12. 1; VI. 59. 1; IX. 38. 1. 1047

Ibid., VI. 127. 2. Ibid., IV. 12, 1. 2048

Ibid., VI. 16. 2. 1061 Ibid., VI. 127, 2, 1050 Ibid., VI. 16. 3. 2005

Ibid., VI. 16. 2. Ibid., IV. 7. 1; VI. 85. 1; X. 3. 1044

Ibid., VII. 113. 2. 1055 Ibid . X. 3, 3, 2000

Ibid., VI. 44, 3. 1000 Ibid., VII, 113, 2. 1057

Atharvaveda, XIX. 39. 1; V. 4. 1; V. 22, 2; VI. 95; VI. 102, 3; XIX. 57, 2. 1019

<sup>1001</sup> Ibid., XIX. 39. 3. Ibid., V. 4, 1-2. 1000

White Yajarveda, XIX. 14; XX. 57; XXL 31. 5563

Atharvaveda, XIX. 83. 1065

White Yajurveda, XXXVII. 6. 1044

Black Yajurveda, II. 5. 3. 1044

(34) Sana (Cannabis Sativa 1066) or Bhanga = Bhang, 1067 a plant from which an intoxicating drug is prepared.

The following varieties of grass and reeds are mentioned:-(1) Darbha, 1088 a grass used for sacrificial purposes. It spreads rapidly and continually re-roots itself and hence described in the Atharvayeda as 'having a thousand joint.' 1069 The strainer of Soma juice was made of two or three blades of Darbha grass. 1079 Girdle or girth with which the sacrificial horse was to be girded was made of Darbha grass. 1071 (2) Durva (Panicum Daetylon), 1072 a creeping grass with flowering branches erect; by far the common and most useful grass in India. It grows everywhere abundantly, and flowers all the year. (3) Kuśa (Poa Cynosuroides, 1073 much used in sacrificial ceremonies and endowed with various sanctifying qualities. It is strewn on the place of sacrifice, specially on the altar, and forming a layer on which the oderings are placed, and a seat for the sacrificers and the gods who are present at the ceremony (4) Munja (Saccharum Munja), 1074 a sort of rush or grass which grows to the height of about ten feet. It is used in basket-work, and the mekhalā or girdle worn by the Brāhmanas is made from it. It appears from the Kausikasutra XXV. 6, and Dirila's Commentary thereon, that the head of a stalk of Munja grass, is to be tied with a cord, then, perhaps, to be suspended from the neck of the patient or to be otherwise attached to his body. Thus worn the grass will prevent diarrhee in an acute form. Small round mats were made of Muñja grass and used for ceremonial purposes. 1075 (5) Sara (Saccharum

<sup>1000</sup> Atharvaveda, II. 4. 5. 1007 Ibid., XI. 6. 15.

Atharvaveda, II. 73; VI 43. 1, 2; VIII. 7. 20; X. 4. 2; X. 4. 13; XI. 6. 15; XIX. 28; XIX. 32; XIX. 68; White Yajarveda, V. 6. 21, 25; XVIII. 75. 63; Black Yajarveda, V. 6. 4.

<sup>1000</sup> Atharvayeda, II. 7. 8.

<sup>1070</sup> White Yajuryada, I. 9. 3; X. 34, 31.

<sup>1071</sup> Ibid., XXII. 1-2.

<sup>1073</sup> Atharvaveda, VI. 106. 1; White Yajurveda, XIII. 24. 20.

<sup>1078</sup> Atharvaveda, IL 7. 1; XX. I31. 9; White Yajarveda, IV. 1; V. 42.

<sup>1076</sup> Atharvaveda I. 2. 4; Compare White Yajurveda, IV. 17. 10; XI. 68.

<sup>2018</sup> White Yajurveda, XII. 2.

Sara), 1076 a reed of which arrows were made. 1077 (6) Babbaja 1078 (7) Kāsa 1079 (8) Isīkā. 1080

Sheep and Cattle-rearing—Despite the great development of agriculture cattle remained the principal wealth of the people. In the Satapatha Brahmana in connection with the Royal Coronation the raid of cattle is mentioned, a relic no doubt of older days customs. In the Atharvaveda we find innumerable prayers for the increase of cattle. Thus, we have a benediction on homeward cattle, 1081 a charm against worms or bots in cows, 1082 a benediction on cattle-pen, 1083 glorification and benediction of cows, 1084 a charm for the increase of cattle, 1088 a charm to protect cattle, 1088 a benediction on cattle-calf, 1087 a charm to bring the cattle home, 1088 a blessing on cows, 1089 a glorification of the typical bull and cow, 1090 a glorification of the sacred cow, 1091 on the duty of giving cows to Brahmanas. 1093

The twenty-fourth book of the White Yajurveda contains an exact enumeration of the animals that are to be tied to the sacrificial stakes and in the intermediate spaces, with the names of the deities or deified entities to which they are severally dedicated. The principal stake, the eleventh and midmost of the twenty-one, called the Agnistha because it stands nearest to the sacrificial fire, is mentioned first. About fifteen victims are bound to each of these stakes, all demestic animals, the total number being 327. In the spaces between the stakes 2-2 wild animals are temporarily confined, to be freed when the ceremony is concluded, bringing the total number of assembled animals upto 609. "There is perhaps some exaggeration in the number" says Mr. Griffith, 1003

```
Atharvaveda, I. 2. 3; Rämäyana, Ajorbyākānda, 30th sarga.
1076
      Black Yajurveda, VI. 1. 3. (Uempare, Vedic Index, II. 357.)
LUTT
      Black Yajurveda, II. 2. 8.
      Ramayana, Ajodhyakanda, 30th sarga,
1019
                                                  Atharvayeda, II. 26.
                                           1081
      Ibid.
1080
                                           1098 Ibid., III. 14.
      Ibid., IL. 32.
1000
                                                 Ibid., V. 16.
                                           1055
      Ibid., IV. 21.
1084
                                                 Ibid., VI. 70.
                                           1051
      Ibid., VI. 59.
1086
                                                 Ibid. VII. 75.
                                          1000
1000 Ibid., VI. 77.
                                                Ibid., X. 10.
                                          1001
1000 Ibid., IX. 7.
                                          1099 White Yajurveda, p. 258 fa.
      Ibid., XII. 4.
3008
```

"and some almost impossible animals are mentioned, but it must be remembered that the Aswamedha was a most important tribal solemnity of rare occurrence and that no effort should be spared to assure its performance with all possible splendeur." The Taittiriya Brāhmaṇa 1094 in its account of the Aswamedha recommends 180 domestic animals to be sacrificed.

Among the domestic animals the following are the most important :-(1) con-The food-value of its milk was very great. The Satapatha Brahmana 1095 describes the various articles of food prepared from cow's milk. From the Panchavimsa Brāhmana 1096 we learn that bags were made from cow-hide for holding milk, wine and other liquids. The flesh was also used as food. In the Taittiriya Brahmana 1097 mention is made of scores of Kāmya Istis or minor sacrifices with prayers which required beef for their performance. In the larger ceremonies, such as the Rajasuva, the Vajapeva. and the Aswamedha, the slaughter of the cow was an invariable accompaniment. 1098 The Taittiriya Brahmana 1099 recommends the slaughter of cows, bulls, nilagaos etc. for the Aswamedha ceremony. It also recommends the slaughter of seventeen five-year old, humpless dwarf bulls and as many dwarf heifers under three years for the Panchasaradiya ceremony. 1100 The Tanda Brāhmana of the Sama Veda1101 recommends the slaughter of cattle of a different colour for each successive year. The Atharvaveda gives us a prayer accompanying animal sacrifice1102 and tells us that the dissectors of the sacrificial bull are to call out the names of the several parts of the carcase as they divide them, each portion being assigned to a separate divinity.1108 The Taittiriya Brahmana describes in detail the

-1

<sup>2004</sup> ašītyanhikašatasanskhyakāh pašava ālabadbyāh — Taittirlya Brābmaņa, II. p. 651.

<sup>1008 1</sup>H. 3. 3.

LOSS XIV. 11. 26; XVL 13. 13.

<sup>1007</sup> III. ch. VIII.

Taittiriya Brāhmapa, III. p. 658. Yathā goup arapye swachchandachāri, ebamayan brahmalokepi swatantro bhahati — Taittiriya Ārapyaka,

<sup>1012</sup> II. p. 651.

<sup>1100</sup> Taittiriya Brahmana, Book II.

<sup>1201</sup> Tanla Brāhmana, 643 :- şaştyāh faradi kārttike māsi Yajet. Saptamyāmaştamyām tāśwayojipakse tu batsatarīrevālaveran uksno bisigesyuh.

<sup>1105</sup> Atharvaveda, II. 34

<sup>1108</sup> Ibid., IX. 4. 11-14.

mode of cutting up the victim after immolation, evidently for distribution.\* The Gopatha Brihmana & of the Atharvaveda gives in detail the names of the different individuals like the Hota, the Udgata, the Adhvaryu, the Upagata, the householder who ordains the sacrifice, the wife of the latter etc.) who are to receive the thirty-six shares into which the carease is to be divided. Directions similar to these occur also in the Altareya Brahmana. The Satapatha Brahmana 1104 and the Taittiriya Brahmana 1105 describes Yajñavalkya and Agastya as taking beef. Yajñavalkya was "wont to eat the meat of milch-cows and bullocks, if only it was tender."1106 In the Aitareya Brahmana1107 we are told that when a king or a distinguished person comes as a guest one should kill a Vehat (old barren cow) for his entertainment. The great sage Yajhavalkya expresses a similar view.1108 At the same time we notice a growing feeling against beef-eating in this period. In the Satapatha Brihmana 1109 we have a long discourse on the non-advisibility of cow-slaughter and we find the injunction "Let him not eat the flesh of the cow or the ox for, the cow and the ox doubtless support everything on earth."

The cow was used as a standard of value in purchasing articles even in this period. 1110 Moreover, bullocks were used for ploughing, 1111 for drawing waggons 1112 and carriages 1113 and for carrying loads. 1114

(2) The buffalo—In addition to its milk, the flesh of the buffalo was probably eaten. The Taittiriya Brīhmaṇa<sup>1115</sup> recommends the slaughter of buffaloes for the Aswamedha sacrifice; so also the White Yajurveda.<sup>1116</sup>

1140 III. 1. 2. 3.

Daivyāh šamitārah uta manusyā āravadhwam. Upanayata medhyā durah.
 Ašāsānāmedhapativyām medham, etc.

<sup>1</sup> Gyathatah sabaniyasya pasorbibhagam byakhyasyan ah etc.

<sup>1104</sup> IIL 1, 2, 21,

<sup>1105</sup> II. 7, 11. 1.

<sup>1104</sup> III. 1, 2, 21 - Vedic Index, II. 145.

<sup>2107</sup> I. 3. 4. 2100 Vaj. I. 109.

<sup>1110</sup> Black Ysjurveda, VI. 1. 6.

<sup>1111</sup> Black Yajurveda, V. 2. 5. 2.

<sup>1119</sup> Ibid., V. S. 21.

<sup>1115</sup> Ibid., V. 6, 21.

<sup>11:</sup> White Yajurveda, XXIV. 13.

<sup>1118</sup> Books II and III.

<sup>1114</sup> Book XXIV. 28,

The dung of buffaloes was used as fuel for protection against cold.1117 (3) The hor.e-Horses were used in battle 1118 and in horse-racing. 1119 From the Ramayana 1190 we learn that Kamboja, Bahllika and Sind were famous for horses. Horses were sometimes given to priests as a sacrificial fee. 1121 (4) The donkey-In addition to the horse, the donkey was also used for drawing chariots and waggons and for carrying loads. The story of the race won by the Aswins with a chariot drawn by donkeys is found in the Aitareya Brahmana. 1192 (5) Mule - The hardiness of mules is praised and their sterility dwelt upon and explained in some of the Brahmanas. They were mainly used for drawing cars, 1128 and waggons and carrying loads. (6) The cane -Camels were objects of gift1124 and of sacrifice. 1195 In the Atharvaveda1196 we read of "camels that draw the car." (7) The goal-It was an object of sacrifice in the Aswamedha, 1197 to Indra 1128 to the Aswins, 1129 to Pusan, 1130 and to Vayu. 1131 Its flesh was used as food, 1132 milk as drink1133 and skin as clothing. 1134 (8) Sheep-The flesh of sheep was used as food, 1135 milk as drink and wool as a material for cloth. In the Atharvaveda kambalas1138 and Samulyas1137 are described as ordinary outfits of men and women and were probably made of

```
Rāmāyaņa, Ajodhyākāņda, 99th sarga,
1117
```

Bala-kanda, 6th sarga.

White Yajurveds, XXIX. 38-39. 1.114

<sup>111</sup> Atharvaveda, II. 14. 6.

<sup>1199</sup> IV. 9. 1101 White Yajarveda, VII. 47.

Atharvaveda, VIII. 8. 22. 1198

<sup>1194</sup> Ibid, XX. 127 1-2.

<sup>1105</sup> White Yajarveda, XXIV. 28 and 29; Black Yajarveda, V. 6, 21.

<sup>1110</sup> XX. 127. 2.

Mite Yajurveda, XXIV. 16, 32.

<sup>1190</sup> Ibid., XXVIII. 23.

<sup>1290</sup> Ibid., XXL 40, 41, 46, 47, 59.

<sup>1150</sup> Ibid., XXVIII. 23, 27.

<sup>1181</sup> Griffith's White Yajurveds, p. 281 fu.

Atharvaveda, IX. 5. 4. 1159

<sup>\*</sup>The milk of goat is the highest form of draught"-Black Yajarveda, V. 1. 7.

Satapatha Brahmana, III. 9. 1. 12; V. 2. 1. 21, 24; Panehawimia Brahmana, 1184 XVII. 14-16; of. Atharvaveda, IV. 7. 6.

<sup>2100</sup> Ramayana, Aranyakanda, 11th sarga.

<sup>1187</sup> XIV. 1. 25 = Rigveds, X. 85, 29, 1104 XIV. 2, 66, 67.

sheep's wool. Cloths made of avika, sheep's wool are clearly mentioned in the Ramayana. 1138 Acceptance of sheep has been described as having bad effects in the Black Yajurveda. 1139 The sheep seems to have been used in drawing the plough, though the commentator takes sheep to mean 'small | oxen like sheep.'1140 (9) The ass-The ass has been described as "the best burden-gatherer of animals."1141 They are also described as drawing the car of the Aswins. 1142 (10) Swine-The Satapatha Brahmana describes the origin of the boar and refers to its fat and the sandals made of its skin.1143 The Atharvaveda1144 refers to its extraordinary quickness at discovering and unearthing all sorts of edible roots. The boar was an object of sacrifice to Indra. 12 \* 5 (11) Elephants-Elephant-keepers are mentioned in the White Yajurveda.1146 There is a hymn in the Atharvaveda1147 whose subject is the taming of elephants and of training them up for the king to ride. From the Ramayana1148 we learn that the elephants of the Himalayan and Vindhyan regions were famous for their large size and great length. Hides of elephants are also mentioned. 1149

Hunting and Fishing-Hunting remained the occupation of a large section of the people. 1150 No doubt the forest tribes resorted to hunting mainly for obtaining food but the people in general as well would resort to hunting not only for the pleasure and excitement which it afforded but also on economic grounds, as the frequent slaughter of domestic animals would reduce the livestock before long. Hunting down wild beasts was also necessary for the protection of cattle. The wild dog was tamed mainly for the purpose of assisting the people in the hunt.

Rāmāyapa, Lankākāņda, 75th sarga. 1150

II. 2. 6. 3: "the nature of the sheep he accepts who accepts a sheep'. 1141 Ibid., V. 1. 5. 5.

<sup>1140</sup> Black Yajurveda, V. 6. 21.

<sup>1149</sup> White Ysjurveds, XI. 13; XXV. 44.

<sup>1145</sup> V. 4. 3. 19.

<sup>1144</sup> IL 27. 2; V. 14. 1; VIII. 7. 23.

<sup>2145</sup> White Yajurveda, XXIV. 40.

<sup>1146</sup> XXX. 11.

<sup>1144</sup> III. 22.

Balakanda, 6th sarga.

<sup>114.</sup> Atharvaveda, XX. 131, 23.

<sup>2160</sup> White Yajurveda, XVI. 27; XXX. 7.

The Atharvaveda<sup>1151</sup> refers to the hunting of boars with the help of hounds. The arrow was sometimes employed but the normal instruments of capture were nets and pitfalls. The word ākhaḥ occurs in the Black Yajurveda<sup>1152</sup> which is taken by Sāyana as a pit artificially made where the hunter could lie in wait at a convenient distance for shooting. <sup>1153</sup> The net called jāla<sup>1154</sup> which was fastened on pegs<sup>1155</sup> was used for capturing wild birds and heasts. The hunting of the deer<sup>1156</sup> and antelope<sup>1157</sup> with the help of the bow and the arrow is referred to in the Rāmāyaṇa.

Fishing became the main occupation of a section of the population. The fisherman fishing in rivers<sup>1158</sup> and in lakes<sup>1159</sup> and the fishvendor<sup>1160</sup> are mentioned. Of fish the Nirāla is mentioned in the Atharvaveda. <sup>1161</sup> Of aquatic animals crabs (kakkata) and tortoises (kurma)<sup>1162</sup> are mentioned. The Satapatha Brīhmaṇa<sup>1163</sup> describes the kaśyapa (which is identified with kurma), a sacred animal, a form of Prajāpati from which all beings sprang up, though we do not learn that the kaśyapa was worshipped or eaten sacramentally. <sup>1164</sup>

The word kṛśana, meaning a pearl occurs in the Atharvaveda. The belief mentioned by Dioscorides and Pliny — a belief also prevalent among the Persians — that pearls are formed by drops of rain falling into the oyster-shells when open is recorded in the Atharvaveda. Pearls seem to have been fished in large quantities for, we find that they were

11.51 XX. 126, 4.

<sup>1155</sup> The word is mentioned in Papini, III. 3, 125, Varte. 1, while Papini himself gives akhana

<sup>1184</sup> Atharvaveda, X. 1. 30. 1188 Ibid., VIII. 8. 5.

<sup>1156</sup> Rāmāyaņa, Araņyakāņda, 14th sarga.

<sup>1187</sup> Ibid., Ajodhya dada, 56th sarga.

<sup>1200</sup> White Yajurveda, XXX. S.

<sup>1189</sup> Ibid., XXX 16. 1180 Ibid.

<sup>1141</sup> VI. 16. 3.

<sup>1149</sup> Atharvayeds, IX. 4, 16; Black Yajurveda, V. 2, 8, 4-5.

<sup>1163</sup> VIII. 5. 1. 5.

<sup>1144</sup> Keith - Black Yajurveds, Introduction, C XXI.

<sup>1</sup>V. 10. 1, 3; XX, 16. 11.

used by men and women not only for the beautification of their persons but also for adorning their horses. 1167 Amulets of the shell of pearloyster were also worn by the people as a protection against disease and indigence. 1168

Progress in arts and crafts—In keeping with its wider geographical outlook and its growth of towns this period is marked by a striking development of industrial life and the subdivision of occupations caused by the ever-increasing needs of the townpeople and the agricultural and military requirements of a community settled in the midst of a hostile population. Among the more important industries of this period we may mention the following:—

(1) Weaving—Technical terms connected with weaving like otu (woof), 1169 tantu (yarn, threads), 1170 anuchāda 1171 or prācinātāna 1172 (forward stretched web) are frequently mentioned. The vemān (loom) 1173 and the mayūtha 1174 meaning wooden pegs to stretch the web on or shuttle are mentioned in simile:

"Like shuttle through the loom the steady ferment mixes The red juice with the foaming spirit." 1178

And in the Atharvaveda we read :

"Singly the two young maids of different colours

Approach the six-pegged warp in turns and weave it." 1176

Day and Night are compared here to two young maids, the six regions of the world to the six wooden pegs: Dawn weaves the luminous weft of

<sup>1107</sup> Atharvaveda, XX. 16. 11.

<sup>1100</sup> Ibid., IV. 10. 3.

<sup>2169</sup> Ibid., XIV. 2.51; White Yajurveda, VI. 1. 1. 4.

Atharvaveda, XIV. 2.51; cf. XV. 3.6; Kāthaka Sambitā, XXIII. 1.

<sup>2172</sup> Satapatha Brahmana, III. 1. 2. 13 ff.

<sup>1175</sup> Black Yajurveda, VI. 1. 1, 3 ff.

White Yajurveda, XIX. 83; Maitrāyani Samhitā, III. 11. 9; Kāthaka Samhitā, XL!II. 3; Taittirīya Brāhmaņa, II. 1. 4. 2.

<sup>2174</sup> White Ysjurveds, XIX. 80.

<sup>1175</sup> White Yajurveda, XIX. 83.

<sup>1170</sup> Atharvaveda, X. 7. 42.

Day and Night removes it from the loom. The use of a large number of words for cloth and for its different parts presupposes a fully developed and long established indigenous weaving industry. For cloth we have the words vastra, 1177 vasas 1178 and vasana. 1119 The sic meaning the border or fringe occurs in the Atharvaveda1180 where the child is covered by its mother's sic and in the Satapatha Brahmana 1181 where a deer horn is tied in the sacrificer's sic. Dasa meaning border or fringe occurs in the Brahmanas.1182 The wider border is specially designated wivi, 1182 the closely woven end of the cloth - from which depends the proghata1184 or the strikers, the loose long unwoven fringe with swaying tassels. The vasas has only one nivi usually, as now, the other end of the cloth being much plainer: to this plainer end would belong the fusa, 1183 (the chaffs), a shorter fringe corresponding to the modern chilka. The vataranal 186 descriptive of the vasas as part of it, obviously cannot mean 'a garment to protect against winds': it is rather that part of the cloth which protects it against winds, i. e., its lengthwise borders 1187 which keep the web together from becoming thread-bare by fluttering in the wind (specially during movements). The arokah1188 (or 'the brilliants') seem to have been

<sup>1277</sup> Ibid., V. 1. 3; IX. 5. 25; XII. 3, 21,

White Yajurveda, II. 32; XI. 40: Black Yajurveda, VI. 1. 9.7; VI. 1. 11. 2; Aitareya Brāhmaņa I. 3.

<sup>119</sup> Chandogya Upanişad VIII. 8, 5; Kanşitaki Upanişad, II. 15.

<sup>11\*0</sup> XVIII. 3. 50 - Rigveds, X. 18. 11.

Satapatha Erāhmaņa, III. 3. 2. 9; cf. IV. 2. 2. 11; I. 1. 2. 8; Aitareya Brāhmaṇa, VII. 32.

Atharvaveda, VIII. 2. 16; Biack Yajurveda, VI. 1. 1. 3 ff.; Kāthaka Samhitā, XIII. 1.; Satapatha Brāhmaņa, III. 1. 2. 13 ff.

Ibid. The antih of Atharvaveda, XIV. 2. 51, is clearly = proghata.

Black Yajurveda, I. S. 1. 1; II. 4. 9. 1; VI. 1. 1. 3; Kāthaka Samhitā, XIII. 1; Taittiriya Brāhmaņa, I. 6. 1. 8; Panchavimša Brāhmaņa, XVII. 1. That fūja = chan, like lashes is evident from its dedication to Agni.

<sup>1186</sup> Black Yajarveda, VI. 1. 1. 3 ff.; vātapā : Kāthaka Samhitā, XXIII. 1.

<sup>1147</sup> Probably preserved in the batas ( - border) of the Bengal weavers e.g., in goth-batan cloths; also in vernacular 'bata', split bamboo, used in strengthening borders of that close etc.

Satapatha Brāhmuņa, III. 1. 2. 13 ff; atirokāh: Kāthaka Samhitā, XXIII. 1; compare the classification of shawls as ek-rokhā and du-rokhā according to the nature of their embroidered patterns.

flowers, stars or other spotty patterns embroidered all over the cloth, 1189 corresponding to modern phul, buta etc.

The vasas was always tied or girt (nah)1100 which implies tucks and knots. The idiom nivimer 1191 shows that each individual wore the nivi in his or her own way. The nivi-knot was sometimes so fashioned as to form a pouch, wherein magic herbs could be borne. 1193 Sometimes also the nivi consisted of simply two tuckings up (udgūhana)1198 at the sides (as now, with men). Elsewhere women are said to tie their nivi on the right side of the hip; such nivi must have been an ampler gather of folds and fringe-tassels, for there a bundle of bahris represents the nivi.1194 It seems probable that no part of the broad border was left for covering the bosom and shoulders and the early sculptures, etc., do not show it. Apparently the upper part of the body was covered by another separate garment called adhivasa.1194 The adhivasa seems to have been an 'over-garment', worn by princes over their inner and upper garments.1195 We have already seen that in the Rigveda 1196 the forests are described as the adhivasa of mother-earth licked by the fire-child. It was thus more like a long loose-flowing dressing-gown, suiting both men and women 1107 and not a close-fitting garment as the authors of the Vedic Index have taken it to be. It may not, however, have been a tailor-made garment at all being called a vasas.1188 The drap;1199 seems to have

So also they are dedicated to the naksatras, stars. 1189

Atharvayeda, XIV. 2, 70. 1100

Ibid., VIII. 2. 16 (what nivi thou makest for thyself?); Atharvaveda, VIII. 6. 2. 20; XIV. 2. 49-50. It is possible, however, to see in 'yat te 1191 vässh paridhänam, yām nīvim kṛṇnṣe tvam, a reference to the ordinary wearing cloth and a separate woven strip to serve as waist-band and this separation of the nivi is also shown in quite early sculptures, etc. But even in that case nivi would be an outer adjunct and not an inner garment as taken by the authors of the Vedic Index.

Atharvaveda, VIII. 6, 20.

Satapatha Brahmana, III. 2. 1. 15.

Satapatha Brahmapa, V. 4, 4, 3.

<sup>1108</sup> 

<sup>1100</sup> I. 140, 9.

<sup>1100</sup> Rigveda, I. 162. 16. Rigveda, L. 140, 9 ( mātuh ) ; cf. Rigveda, X. 5. 4.

According to the authors of the Vedic Index drapi is a coat of mail.

been a gold-embroidered 1200 vest. 1201 Pesa: is gold-embroidered cloth generally 1202 with artistic designs. 1203 The pratiahi must from the context 1204 refer to a part of the bride's attire, apart from the newly woven, excellent garment. 1205 The usnisa, head-dress occurs for the first time in the Atharvaveda 1206 and often in the Yajurveda Samhitzs and Brāhmanas chiefly in connection with the Vrātyas 1207 and kings. 1206 The Vrātya usnisa was bright and white as day, 1200 so that it might well have been of some fine cotton-stuff. According to Kātyāyana Śrauta Sūtra 1210 the usnisa was tied with a tilt and cross windings (tiryan-naddham). At sacrificial ceremonies, however, the king's usnisa was tied in a special manner: the ends were gathered together and tucked away in front, so as to cover them up. 1211 Elsewhere in ritual the usnisa was a mere handkerchief 1212; so also Indrani wears an usnisa like a Zone, of variegated hue 1213—clearly a multi-coloured kerchief.

Among the materials used in the weaving of cloth wool was one. Uraā was the hairy covering of any animal while āvika in the sense of sheep's wool occurs in the Brhadāranyaka Upaniṣad. Threads of wool are mentioned in the white Yajurveda, 1915 Maitrāyani Samhitā 1916 and the

1800 Hiranya-drapi worn by Arati in Atharvaveda, V. 7. 10.

- Athervaveda, XIII. S. I where the Sun wearing the three worlds is described as making a drapi of them. Hence the drapi seems to have three pieces, two side ones and one back like a waist-coat. The fact that it was worn by women as well (Athervaveda, V. 7. 10) and the use of 'vasanah' (drapin rusanah in Rigveda, IX. 86. 14) would show that it was not a coat of mail but was made of vasas, cloth.
- white Yajurveda, XIX. 82, 83, 89,
- 1202 Ibid., XX. 41 where the design is compared to the poet's songs.
- 1904 Atharvaveda, XIV. 1. 8. 1905 Ibid., XIV. 1. 7. 45.
- 1804 XV. 2, 1 ff. 1807 Panchavingsa Brahmans, XVI. 8, 13.; XVII. 1.14.
- 1308 Satapatha Brāhmaņa, V. 3. 5. 23 (King at sacrifices); XIV. 2. 1. 18 (Indrāņī); III. 3. 2. 3. (King 'Soma'); Maitrāyani Sauphitā IV. 4. 3 (Kṣatra at sacrifices); Black Yajurveda, III. 4. 1. 4; Kāṭhaka Samhitā, XIII. 10.
- 1959 Atharvaveda, XV. 3. 1210 XXI. 4.
- 1921 Samhitya puraetid avaguhyati in Satapatha Brihmana, V. 3. 5. 20ff.
- 2512 Satapatha Brahmana, IV. 5. 2. 2. 7. Compare Satapatha Brahmana, III. 3. 2. 3.
- 1313 Satapatha Brihmapa, XIV. 2. 1. 8.
- 1914 II, 3, 6, 1914 XIX, 80, 1910 III, 11, 9.

Kāthaka Samhitā<sup>1217</sup>; while Kambala<sup>1218</sup> (blanket) and šāmulya (under-garment of wool?) are mentioned in the Atharvaveda. 1218

A more common material for weaving cloth for ritual use was linen or silk. The tarpya1920 with which the dead body is clothed in order that the dead may go about properly dressed in the realm of Yama1221 is a silken garment according to Goldstücker while others take it to mean linen. If the commentator has any basis for its explanation 'made from Trpa or Triparna leaves', these would refer to mulberry leaves or other leaves suitable for silk-cocoons. According to Professor Subimal Chandra Sarkar 1922 the 'uttuda' in Atharvaveda, III. 25.1. probably means 'sprung from 'tuda' or mulberry i.e., silken (coverlet). The Ksaums which according to Max Müller means a linen cloth occurs in the Maitrayani Samhita 1 \*\* 23 and in the Black Yajurveda. 1984 The Atharvaveda 1825 refers to Sana, hemp as growing in the forest but we do not know whether its fibre was used as a material for weaving cloth. Garments made of bark, so frequent in later literature are rarely mentioned in Vedic texts; probably the 'barāsi' of Kāthaka Samhitā1 9 98 was a barken stuff; and it is interesting to note in this connection that the Kathakas lived in the North-Western and sub-Himalayan regions where the Baras tree, a red-flowered rhododendron is still fabled to yield cloths.

No doubt, the word karpasa (meaning cotton from the cotton plants of the genus Gossipium with its typical convoluted structure) does not occur either in the Rigveda or in later Vedic literature proper; but we have already seen that the Babylonian and Greek names for cotton—

INT XXXVIII. 3.

In vernacular proverbs and folk-lore the kambala is made of lome, bair. Compare Tamil, 'Kam (p) ali = rough heir-cloth.

<sup>1310</sup> XIV. 2, 66, 67 (Kambala); XIV. 1. 25 (Samulya).

Black Tajurveda, H. 4. 11. 6; Maitrayani Samhiti, IV. 4. 3; Taittiriya Brahmana, I. 3. 7. 1.; I. 7. 6. 4; Satapatha Brahmana, V. 3 5. 20; Katyayana Srantasutra, XV. 5. 7.

<sup>1</sup> sas Atharvaveda, XVIII. 4. 31.

<sup>1993</sup> Some Aspects of the Earliest Social History of India, p. 63 fa

<sup>1916</sup> III. 6. 7. 1914 VI. 1. 1. 8. 1911 II. 4. 5.

xv. 4; also Panchavimsa Brihmana, XVIII. 9. 6; XXI. 3. 4.

Sind and Sindon respectively-have always pointed to Sind as the home of cotton-growing and that cotton as weaving material was known early in the Chalcolithic Age to the people of Sind as proved by the discovery at Mohenzo-daro of karpasa and of even scraps of a fine woven cotton material. The word kārpāsa does, however, occur in the Aśvalāyana Śrauta Sūtra which was composed not later than the eighth century B. C. towards the close of the Brahmana Period when the Aryans came to occupy the cotton-growing districts lying far into the interior of country.

From the Ramayana we find that the weaving industry was carried to its perfection. We hear of beddings decorated with gold, 1227 coverlets decked with gems and jewels,1333 coverlet decorated with gold1329 coverlet or carpet (astarana) decorated with gold and silver 1230 coverlet or carpet (astarana) dyed with the colour of lac (lakṣā-rāga-rañjita), 1831 gold-embroidered dress (worn by king Rāvaņa), 1959 cloth decorated with designs (citravastra) presented by Kekayaraja Yudhājit to king Rama of Ajodhyātass and blankets with variegated designs on them. 1284

Garments were a favourite article of gift to Brahmins and dependents. King Dasaratha is described as the giver of garments. 1235 As the funeral procession of Dasaratha proceeded to the cremation grounds, garments were freely distributed among the people.1936 At the śradha ceremony of Dasaratha Brahmins were lavishly presented with white cloths.1257 King Janaka's marriage-dowry to his daughters included among others blankets, silk or linen garments and ordinary cloth.1238 On the eve of her departure for the Dandaka forest Sita under the advice of her husband gave away all her best garments first to the Brahmins and then to her servants,1239

Ksauma is frequently mentioned in the Ramayana. We find Kausalya dressed in ksaums in puja time. 1240 The beauty of the hump-backed

1998

1180

1070

3334

Sundarakāpda, 10th sarga.

Ajodhyakanda, 88th sarga,

Sundarakāpda, 10th sarga.

1900 Ibid., 76th sarga.

Kişkindhyākānda, 50th sarga-

<sup>1997</sup> Kiskindhyākāņda, 50th sarga.

<sup>1999</sup> Lankikinda 11th sarga.

<sup>1981</sup> Kiskindhyākāpda 23rd sarga.

<sup>1000</sup> Uttarakinda, 113th sarga

Ajodbyškāpda, 77th sarga.

LEST Ibid., 77th mrga.

<sup>1920</sup> Bilakanda, 74th sarga : 'Kambalanincha muhayinam kecumyan ketyambarani cha'.

Ajodhyskanda, 30th sarga. 1579

<sup>1560</sup> Ibid., 4th sarga.

maid-servant Mantharā increased whenever she wore kṣauma. 1241 On the occasion of Rāma's proposed consecration as Yuvarāja his mother Kauśalyā wore kṣauma. 1242 On this occasion Rāma himself was dressed in kṣauma. 1243 On this occasion even the nurses of the royal palace of Ajodhyā were dressed in kṣauma. 1244 King Janaka's marriage-dowry to his daughters included a large quantity of kṣauma. 1245 Daśaratha's queens were clad in kṣauma when they welcomed their newly married daughters-in-law and led them to the temple. 1246 Leaving aside his usual dress and weapons Bharata before entering the hermitage of Varadwāja wore kṣauma as befitting such an occasion. 1248 It thus becomes apparent that in the age of Rāmāyana kṣauma was specially used on ceremonial occasions.

Blankets (made of wool) were also used. Blanket-makers (kambala-kāra) followed Bharata when he left Ajodhyā to bring Rāma back from the forest. 1249 Blankets formed part of the marriage-dowry given by king Janaka to his daughters. 1250 Bharata received as present from his maternal grandfather multi-coloured blankets. 1251 Kekayarāja Yudhājit sent presents of kambalas to king Rāma of Ajodhyā. 1252 In the palatial houses built by Maya in the Golden Forest Hanumāna saw innumerable blankets of variegated designs stored up. 1253 When Hanumāna set fire to the city of Lankā many blankets and cloth made of āvika, sheep's wool along with kṣauma were reduced to ashes. 1254

Silk cloths (kauseya) are also frequently mentioned. On the occasion of Rāma's proposed consecration as Yuvaraja the streets of Ajodhya were overspread with patta-vastra and kauseya. 1235 On the eve of his departure for the Dandaka forest Rāma gave away kauseya cloths to an Acarya. 1236

<sup>1841</sup> Ibid, 9th sarga.

<sup>1949</sup> Ibid., 20th sarga.

<sup>1940</sup> Ibid., 6th earga.

<sup>1944</sup> Ibid., 7th sarga.

sees Baiskands, 74th sarga.

<sup>1040</sup> Thid., 77th sarga.

<sup>1967</sup> Ajodhyākāpde, 90th sarge.

<sup>2240</sup> Lankakanda, 118th sarga.

<sup>234</sup> Ajodbyakanda, 83rd sarga.

<sup>19 &#</sup>x27; Balakanda, 74th sarga.

<sup>1901</sup> Ajodhyākānda, 70th sarga.

<sup>1909</sup> Utterakāņda, 118th earga.

<sup>2000</sup> Kiskindhyakanda, 50th sarga.

<sup>1 \*\*\*</sup> Lankākāņda, 75th sarga.

Ajodhyākāpia, 17th sarga,

<sup>1500</sup> Ibid., 32nd-sarga.

Sitä used to wear kauseya in the royal palace in Ajodhyā. 1287 On Daśaratha's death Vasistha sent messengers with presents of kauseya to Bharata to bring him back from his maternal grandfather's palace in the Kekaya kingdom. 1288 Bharata in the course of his search for Rīma found silken threads (kauseya-tantu) of Sitī's dress sticking to the grass over which she slept in the forest. 1289 Sitī used to wear yellow silken cloth (pita-kauseya) while at Pañchavati forest. 1280 While she was being carried away by Rāvana Sitī threw away her silken upper garment of golden hue (kanakadyuti-kauseya-uttariya) at the five monkeys so that they may give a clue to Rāma about her whereabouts. 1261 Even in the Asoka forest Hanumāna found Sitā wearing her self-same yellowish silk-dress. 1262

(2) Metal industry—The alvance of civilisation is also seen in the more extended knowledge and use of metals and in the large number of mining industries of the period. Besides gold 1263 and ayas 1264 known in the Rigvedic Age, the Atharvaveda mentions silver, 1265 tin (trapu), 1266 lead (sisa) 1267 and symma, occurring along with asi, meaning a sword. 1268 In a passage of the White Yajurveda we find a list of six metals then known.:

"Hiranyam chame ayaschame syamam chame loham chame sisam chame trapu chame." 1269

'May my gold, my ayas, my iron (syama), my copper (loha), my lead (sisa) and my tin (trapu) prosper by sacrifice. Elsewhere in the White Yajurveda

```
1987 Ibid., 37th sarga.
```

<sup>1990</sup> Ibid., 68th sarga.

<sup>1989</sup> Ibid., 88th sarga.

Aranyakanda, 47th, 52nd and 60th sargas.

<sup>1901</sup> Ibid., 54th sarga.

sees Sundarakāņda, 15th sarga.

V. 1. 3; V. 28. 1, 5; VI. 69. 1; VI. 124. 3; VII. 14. 2; IX. 5. 14, 25, 26, 29; XII. 1. 44; XIV. 1. 40; XVIII. 3. 18; XVIII. 4. 56; XIX. 26. 1; XIX. 27. 9, 10;

XIX. 57. 5; XX. 57. 16; XX. 131. 6, 8; XX. 127. 3; XX. 128 6.

<sup>1946</sup> Atharvaveda, V. 28. 1, 5; VI. 63.
2, 3; VI. 84. 3; VI. 141. 2; VII.
115 1; VIII. 2, 3; XIX. 58. 4;
XIX. 66; XX. 30. 3.

<sup>4.51,</sup> Atharvayeda, V. 28. 1, 5; XIII.

<sup>1</sup> see Atharvaveda, XL 3. S.

<sup>1947</sup> Atharvaveds, L 16. 2, 4; XII. 2. 1, 19, 30, 53,

Atharvaveda, IX. 5. 4.

<sup>· \* \*</sup> White Yajurveds, XVIII. 13.

The Balakanda of the Ramayana 1882 narrates the mythological origin of gold, silver, copper, iron, tin (ranga) and lead out of the womb of Ganga, the daughter of the Himalayas. The Himalayas are described as containing all kinds of metal. 1283 Mines of metals on hill-sides are referred to in the Ajodhyakanda. 1284 We find Rama showing to Sita the beauty of Chitrakuta hill, adorned with mines of metals of white, red and yellow

V. 15; VII. 45; X. 15; X. 25; XII. 1; XII. 3; XIII. 2, 4, 28, 39; XVII. 11, 71; XX. 1; XX. 2; XXIII. 37.

1911 Ibid., V. 8; XII. 63; XXVI. 26; XXIX. 20.

1978 Ibid, X. 14; XIX. 80; XXIII. 37.

1979 Ibid., V. 8; XXIII. 37; XX. 2; XXXVII. 11.

Rathaka Samhita, XVIII. 10;
Kapisthala Samhita, XXVIII. 10;
Maitrayani Samhita, II. 11. 5;
Satapatha Brahmana, XVIII.
13-15.

Lats Kathopanisad, I. 1. 23; Brhadarapys-

kepanişad I. 3. 26; VI. 2. 7; ef. I. 1. 2; III. 1. 1; IV. 4. 4; VI. 4. 25; Chandogyepanişad, IV. 17. 7; V. 10. 9; VII. 24. 2; VIII. 12. 5; Aitareya Ārapyaka, III. 2. 4. 17.

Chān logyopanisad, IV. 17. 7.

2077 Chandogyopanisad, IV 17. 7.

1970 Ibid.

AST | Ibid.

2250 Ibid.

p. 71 fs.

1151 37th sarga.

1008 Balakanda, S5th sarga.

1904 63rd sarga.

colour. 1988 Bharata while marching with his army by the side of Chitra-kūta in search of Rama, saw on the hill-slopes minerals of various kinds like gairika etc. 1286 Rāvaņa on reaching the mountaneous southern seacoast of the Deccan found the sea-shore strewn with dried up pearls and corals. 1287 On account of the coppery colour of his waist Hanumāna is described as a hill adorned with a newly worked up mine of gairika. 1288 Blood coming out of the wounded body of Bālī is compared to water oozing out of mines of copper and gairika on the body of the hill. 1289 There were mines of different kinds in Ajodhyā as well. 1290 On Sudarsans hill among the Himālayas there was a mine of gold 1291 The Ayomukha mountain otherwise known Malayāchal by whose side the river Kāverī flows is adorned with mines of different metals. 1292 Silver mines in which Sītā is to be searched for are also mentioned. 1293

In the Ramayana besides gold, silver, copper, iron, lead and tin we find mention of various other mineral products like gairika, 1294 sudhā, 1298 avra (mica), 1295 sphatika (crystal) 1297 and diamonds. 1298

In the literature of this period we find references not only to the goldsmith 1220 but also to his work: "As a goldsmith taking a piece of gold turns it into another, newer and more beautiful shape so does the Self, after having thrown off this body and dispelled ignorance, makes unto himself another, newer and more beautiful shape." The melting of gold in fire for purification 1201 and the softening of gold by means of

```
Ajodbyākāņda, 94th sarga.
```

<sup>122</sup> Ibid., 113th sarga.

<sup>1</sup> ser Arapyakānda, Söth sarga.

<sup>1980</sup> Sundarakāņda, let sarga,

<sup>199</sup> Kişkindhyakanda, 22rd sarga.

<sup>1800</sup> Ajodhyākanda, 100th sarga.

<sup>1991</sup> Kişkiodbyākāņda, 43rd sarga.

<sup>1909</sup> Ibid., 41st sarga.

<sup>1200</sup> Ihid., 39th sarga.

Ajodhyākāṇda, 113th sarga; Kiṣkindhyākāṇda, 23rd sarga; Sundarakāṇda, let sarga.

Ajodhyākānda, 80th sarga; Aranyakānda, :5th sarga; Sundarakānda, 7th sarga.

<sup>1910</sup> Ajodhyākāņda, 91st sarga.

Aranyakānda, 55th sarga; Sundarakānda, 9th and 10th sargas; Lankākānda, 11th sarga-

Aranyakania 55th sarga; Kiskindhyakanda, 10th sarga; Lankakanda, 7:th and 77th sargas.

White Yajurveda, XXX. 17; Rāmā-yaṇa, Ajodhyākāṇda, 83rd sarga; Kişkindhyākāṇda, 40th sarga.

<sup>1300</sup> Brhadáranyakopanisad, IV. 4 4.

asex Rāmāyapa, Kiskindhyākāpda, 24th

lavana (borax)<sup>1808</sup> are mentioned. The use of gold in exchange, in sacrifice as well as in the manufacture of ornaments and of sundry other articles for domestic use lends colour to the view that there must have been sources of local supply of gold. Professors Macdonell and Keith<sup>1303</sup> are of opinion that in those days gold was obtained from the bed of rivers, though the extraction of gold from earth was not unknown.<sup>1304</sup> In the Rāmāyaṇa <sup>1308</sup> we are told by Rāma that princes go to the forest on hunting excursions partly no doubt for the joys of the chase and partly for the flesh it will fetch but in that connection they search with great care for various metals, gems and precious stones and for gold. Washing for gold is recorded in the Black Yajurveda <sup>1308</sup> Kāthaka Saṃhitā, <sup>1307</sup> Kapisthala Saṃhitā, <sup>1308</sup> Maitrayanī Saṃhitā <sup>1309</sup> and in the Satapatha Brāhmana. <sup>1816</sup>

We frequently hear of various golden media of exchange like Hiranya-kṛṣṇala, 1511 Suvarṇa, 1512 gold pieces, 1513 Pādas of gold, 1514 Satamana 1515 and Niṣkas. 1516 Chips of gold used in sacrifica 1517 a circular gold disc or plate with 21 knobs used in sacrifice, 1518 golden needles with which are marked out the lines on the body of the sacrificial horse which the dissector's knife is to follow, 1519 golden figure of Prajāpati, Agni, the Sacrificer technically known as hiranyagarva, 1520 gold on the priest's finger, 1521 gold given as fee to the priest, 1222 sacrificial cauldron with gold-

```
1808 Chandogya Upanisad, IV. 17. 7.
```

<sup>1008</sup> Vedio Index, II. p. 504.

<sup>1804</sup> Atharvaveda, XII. 1. 6.

<sup>100</sup> Arapyakāņda, 43rd sarga.

<sup>1006</sup> VI. 1. 7. 1.

<sup>1207</sup> XXIV. S.

<sup>1900</sup> XXXVII. 4.

<sup>1848</sup> III. 7, 5, 6.

<sup>1010</sup> IL 1. 1. 5. ; III. 2. 4. 9-21.

Yajurveda, II. 3, 2, 1, Taittiriya Brahmana, I. 3, 6, 7; Maitrayani Samhita, II. 9, 2.

<sup>1919</sup> Satapatha Brähmana, XII. 7, 2, 13,

<sup>1315</sup> White Yajurvods, IV. 26.

<sup>2014</sup> Satapatha Brāhmaņa, Kāṇda XIV ; Brhadāraṇyakopaniṣad, I. 1. 1.

Satapatha Brāhmaņa, V. 4. 3, 24, 26;
 XII. 7. 2. 13; XIII. 2. 3, 2; V.
 5. 5. 16; Black Yajurveda, II. 3.
 11. 5; III. 2. 6. 3.

XX. 131. 8; Aitareya Brahmapa, VIII. 22.

<sup>1817</sup> Athervaveds, XVII. 11, 71

<sup>1810</sup> White Yajurveds, X. 25; XII, 1, 12.

White Yajurveda. XXIII. 35, 37.

veds, IV. 1. 8; IV. 2. 8; V, 2. 7.

Atharvaveda, XVIII. 3. 18; Satapatha Brahmapa III. 5, 2, 2.

abss Atharvaveds, IX. 5. 14.

en handles, 1323 golden vessel for Aswamedha called Mahiman, 1324 and a ladle of pure gold 1393 are mentioned. In the Ramayana we read of golden utensils, 3326 golden vase for containing water, 1327 golden pitchers, 1828 golden pots, 1319 golden water-pots used by ascetics, 1330 golden lamps, 1331 golden bedstead, golden bedstead decked with jewels, 1989 bedstead adorned with gold, 1394 seats made of gold, 1335 golden trappings for elephants, 1336 fly-flapper (chimara) with golden handles 2337 and decorated white gems, 1338 golden throne, 1239 seats bedecked gold with (Kīnchana-citrita),1340 altars made of gold,1341 gates mounted with gold, 1342 gold-mounted arch of a gateway, 1343 golden chariots 1344 chariots mounted with gold and decked with jewels, 1345 pillars (of chariots) made of gold, 1346 windows (of chariots) made of gold 1347 golden stair case, 1348 gold-mounted windows, 1349 finger-guard (angulitrana) overlaid with gold, 1350 golden hook or goad to drive an elephant, 1851

<sup>1340</sup> White Yajneveda, XXXIII. 19.

<sup>1824</sup> Brhadarapyokapanisad, I. 1. 2.

<sup>1921</sup> Ibid., VI. 4. 25.

Ajodhyākāṇda, 91st sarga; Kiṣkindhyākaṇda, 50th sarga; Sundarakāṇda, 1st and 11th sargas; Lankākaṇda, 75th sarga.

<sup>1887</sup> Suvarņa Vrngāra in Ajodhyāktņda, 14th sarga.

Ajodhyākāṇda, 15th sarga; Sundarakāṇda, 10th and 11th sargas; Kişkindhyākāṇda, 26th sarga-

Ghata in Ajodhyākāņda, 14th and 65th eargae.

<sup>1824</sup> Swarpakamandalu in Sundarakāņda, let sarga,

<sup>1981</sup> Sundarakāņda, 9th sarga.

Ajodbyākāņda, 16th and 19th sargas; Kiskindhyākāņda, 33rd sarga.

<sup>1880</sup> Sundarakanda, 11th sarga.

<sup>1904</sup> Ajodbyākāņdā, 72nd sarga.

Sundarakānda, 1st and 11th sargas.

<sup>1006</sup> Lankakanda, 129th sarga.

<sup>1537</sup> Kijkindhyākāņda, 26th sarga.

assa Ajodhyakanda, 15th and 16th sargas.

<sup>1229</sup> Kiekindhyākāņda, 26th sarga.

Ajodhyākāņda, 26th sarga; Uttarakāņda, 1st sarga.

Ajodhyākānda, 10th sarga.

<sup>1843</sup> Kişkind'nyakanda, 33rd sarga.

<sup>1546</sup> Sundarakānda, 6th sarga.

<sup>2646</sup> Bålakāņda, 53rd sarga.

<sup>1346</sup> Ajodhayākānda 16th sarga; Aranyakānda, 22nd sarga.

Sandarakāņda, 9th sarga.

<sup>1847</sup> Ibid., Sth sarga,

<sup>1840</sup> Ibid., 9th sarga.

<sup>1840</sup> Ibid.

<sup>1889</sup> Ajodhyākāņda, 99th sarga.

<sup>1841</sup> Bálakápda, 53rd sarga,

gold armour, 1858 weapons mounted with gold, 1858 sword decked with gold, 1854 sword with golden handles, 1855 bow decked with gold, 1856 shafts decked with gold, 1857 golden sheath for sword, 1858 golden image (of 8111), 1859 golden figures of fish, flowers, trees, birds, mountains and stars engraved on chariots, 1850 golden images engraved on chariots, 1851 and golden images placed in the bed-chamber of Ravana's palace. 1965

Golden ornaments are frequently mentioned. 1864 The word alamkāra does not occur in the four Vedas but the word aŭja or aŭji meaning ornaments does occur. 1865 The word alamkāra occurs for the first time in the Satapatha Brihmana 1866 and in the Chindogya Upanisad. 1887 In the Atharvaveda the following ornaments are mentioned:—(1) Tirita 1868—In Amarakosa it is explained as an ornament of the head (mukutamani or sirobhusana, a tiara-like ornament). (2) Parihasta 1869—It was probably a bracelet or two connected rings regarded as one amulet. 1870 (3) Pravarta 1871—It was an ornament, circular in shape, probably for the ears; (4) Ring 1872 (5) Golden amulets 1873 (6) Necklace of niskacoins as the term niskaguva 1874 shows; (7) Kurira 1875—According to Zimmer it means peacock. If this meaning is accepted, then kurīra is a tiara-like ornament for the head. 1876 (8) Kumba 1877—According to

1882 Lankakanda, 75th sarga.

1300 Ibid.

Ajodhyakanda, 31st sarga; Aranyakanda, 12th sarga.

darakānda, 1st sarga; Sun-

1000 Sundarakanda, 47th sarga.

Aranyakānda, 3rd and 20th eargas; Kişkindhyākānda, 16th sarga.

1000 Arapyakāņda, 12th sarga.

1800 Uttarakāņda, 112th sarga.

2000 Aranyakanda, 23nd sarga.

1883 Sundarskänds, 6th sarge.

1000 Ibid. 9th sargs.

and Ajodbyškanda, 15th sarga.

Yajarveda, XV, 50; XVII, 97; XXXIV, 52. 1868 Rigveds, I. 64. 4.

1044 III. 5. 1. 36; XIII. 8. 4. 7.

viii. 8, 5 : Protasya sariram vasanendlam drepa samekurvanti.

1 at Atharva veda, VIII. 6. 7.

1300 Ibid., VI. 81, 1, 2.

1070 See Kauşikasütra, XXXV. 11.

1991 Atharvaveda, XV. 2. 1.

1578 Ibid., XX. 128. 6, 7.

1210 Ibid., I. 35; V. 28; XIX. 26.

1274 Ibid., V. 14. 3.

1574 Ibid., VI. 133. 2; XIV. 1. 8.

\*\*Compare Apastamva Scautastira:

\*Kumba and Kurira on the patnile
head.\* Prof. Subimal Sackar in
his Some Aspects of the Earliest
Social History of India takes it to
be a kind of hore-chaped conflure
(p. 72).

Atharvayeda, VI. 138, 3.

Sayana it was used by women in hair-culture; probably it is comb. 1878 (9) Opasa 1379 - It was used for adorning the head. Roth thinks that it was a corruption of aba + pasa and hence meant hair-tape or hairnet. 1380 (10) Lalima - It was a tiara worn on the forehead like a frontlet. (11) Lalamya, frontlet (12) Lalamagu, frontlet (13) Surukma, an ornament for the chest (14) Rukmastarana, an ornament for the chest usually of crescent shape. (15) Ninaha, an ornament for the waist. (16) Devīnjana (17) Nalada (18) Madhūlaka (19) Siman (20) Susra (21) Swandzňji (22) Haritasraj or Hiranyasraj. The White Yajurveda refers to the gold-smith1381 and the jeweller1882 and to gold ornaments. 1383 It refers to a gold ornament, perhaps a chain, round the neck of the sacrificer, 1384 to Opasa, 1885 to gold worn as amulet1386 and to golden trappings for horses.1387 The Black Yajurveda, refers to Opasa, 1388 Sraj, Pundarisraj and Voga. In the Kathopanisad 1889 we find that Yams offered to Nachiketas an ornament called Srinka. The Tandamahabrahmana mentions the ornament called Sraj made of gold. The term niskagrya in the Aitareya Brīhmana undoubtedly refers to the practice of wearing necklaces of niska coins. The Panchavimsa Brahmana refers not only to Oposa 1890 but also to necklaces of silver niska coins worn by the Vratyas. 1391 We hear of Rukmapasa in the Satapatha Brahmana, 1392 a chain by means of which Rukma was worn on the breast. Karnasovana, mentioned in the Satapatha Brahmana, literally means an adornment for the ear, hence carring. In the Chindogya Upanisad1398 we read of a

Aspects of the Earliest Social History of India takes it to mean a style of hair-dressing (p. 73).

<sup>1570</sup> Atharvayeds, VI. 138. 1.

sand eyes spread over the roof of a house' in Attarvaveda, IX. S. S. See also ante, fn. No. 444.

<sup>1801</sup> White Ysjurveds, XXX. 17.

<sup>1888</sup> Ibid., XXX. 7.

white Yajurveda, XV. 50; XXXIV. 52.

<sup>1884</sup> Ibid., XXII. 1.

<sup>180</sup> Ibid., XI. 56.

<sup>1944</sup> Ibid., XXXIV, 50.

<sup>1887</sup> Ibid., XXV. 39.

asso Black Yajarveda, IV. 1, 5, 3,

<sup>13.6</sup> i. 'Tabaiba nāmnā vabitāyamagnih sţiñkānchemā manekarûpām gţhāņa,'

<sup>1800</sup> IV. 1. 1; cf. dvy-opasah in XIII. 4.3.

<sup>1091</sup> Ibid., XVII, 1, 14.

<sup>1518</sup> VI. 7. 1. 7.

<sup>1000</sup> IV. 2. 1-4.

necklace offered to Raikva which he politely refused to accept. Maitrāyanī Samhitā<sup>1304</sup> also refers to opaša.

In the Rāmīyaṇa we find mention of golden diadem (kirīta), 1898 golden diadem bedecked with gems and pearls; 1898 kuṇdala, earring worn by both men 1897 and women, 1898 golden kuṇdalas bedecked with diamond and vaidūryamaṇi, 1899 maṇikuṇdala worn by men as well, 1400 karṇāvaraṇa (earring or ornament for the ear) called trikarṇa; 1401 golden bracelets (kānchana keyūra worn on the upper arm by both men 1402 and women, 1403 karāvaraṇa (bangles) decked with corals, 1404 hastāvaraṇa worn by king Daśaratha, 1405 valaya, (armlet, bracelet) worn by men 1406 as well as women, 1407 kanaka añgada, golden bracelet worn by both men 1408 and women 1409; añguriyaka, ring for the fingers 1410; golden amulet (kavaca), 1411 golden amulet set with vaidūryamaṇi 1413; necklace made of gold 1413; kāñcana-mālā worn by king Bālī on the neck, 1414 pearl necklace, 1415 necklace of Indranīlamaṇi, 1416 necklace of precious stones strung together with a golden thread, 1417 necklace of vaidūryamaṇi, 1418 kaṇṭha-hāra, a kind of ornament for the neck, 1419 hemasūtra, a golden chain,

1594 H. 7. 5.

1818 Rāmāyaņa, Aranyakānda, 38th sarga.

1800 Kiskindhyākāņda, 10th surga.

Ayodhyākāṇda, 32nd and 43rd sargas; Sundarakāṇda, 8th and 10th sargas; Aranyakāṇda, 38th sarga; Lankākāṇda, 65th sarga.

sargas.

1500 Kiskindhyakanda, 10th sarga.

1400 Bālakānda, 14th sarga.

1401 Sundarakāņda, 15th sarga.

Bālakāņda, 15th sarga: Ayodhyākāṇda, 32nd sarga: Lankakāṇda, 65th and 130th sargas.

Ayodhyākāṇda, 32nd sarga; Sundarakāṇda 1st snd 11th sargas.

1404 Sundarskinda, loth sarga.

1408 Bālakāņda, láth sarga.

140 Ayodhyakanda, 32nd sargu.

1407 Sundarakānda, 9th sarga.

1408 Ayodhyakanda, 32nd sarga; Sundarakanda, 10th sarga.

1409 Ayodhyākāṇda, 32nd sarga; Sundarakānda, 10th sarga.

1410 Sundarakāņda, 10th sargu; Lankākāņda, 65th and 198th sargas.

1411 Lankākāņda, 65th sarga.

1419 Aranyakānda, 64th sarga.

1418 Balakanda, 53rd sarga.

1414 Kiskindhyākaņda, 11th sarga.

Ayodhyākāṇda, 9th sarga; Kiskindhyākāṇda, 40th sarga; Sundarakāṇda, 9th sarga; Lankākāṇda, 130th sarga.

1410 Sundarakāņda, 15th sarga.

1417 Ayodhyākāņla, 32nd sarga.

1416 Sundarakāņda, 9th sargu.

1410 Kişkindhyakanda, 9th sarga.

probably to be worn on the neck<sup>1420</sup> chandrahāra, a kind of necklace worn by both men<sup>1421</sup> and women,<sup>1422</sup> golden chain for sheep<sup>1423</sup>; kānchidīma, a girdle-like ornament for the waist<sup>1424</sup>; kinkiṇī-mīlī, a girdle of small bells,<sup>1425</sup> mekhalī, an ornament for the waist and loins<sup>1426</sup>; and nūpura, an ornament for the ankles and feet.<sup>1427</sup>

Among the articles made of silver, the Atharvaveda<sup>14\*8</sup> mentions silver amulets which are said to grant vigour to the wearer.<sup>14\*8</sup> The White Yajurveda<sup>14\*30</sup> mentions silver needles for marking out the lines on the body of the sacrificial horse which the dissector's knife is to follow. Silver plates used in sacrifice are mentioned in the Black Yajurveda and in the Satapatha Brähmana. The Brhadāranyakopaniṣad<sup>14\*31</sup> mentions the silver vessel called Mahiman used in the horse-sacrifice. The Paāchaviṃśa Brāhmana refers, as we have already seen, to necklaces made of silver niṣkas worn by the Vrītyas. In the Rāmāyana silver utensils,<sup>14\*35</sup> silver pitchers,<sup>14\*36</sup> seats made of silver,<sup>14\*35</sup> altars made of silver,<sup>14\*36</sup> bedsteads made of silver,<sup>14\*36</sup> pillars mounted with silver,<sup>14\*38</sup> silver-mounted arch of a galeway,<sup>14\*39</sup> windows made of silver,<sup>14\*40</sup> images of silver engraved on chariots,<sup>14\*1</sup> and images of silver placed in the bed-chamber of Rāvaṇa's palace<sup>14\*13</sup> are mentioned.

We have already seen that the third metal ayas is separated from loha and symmam 1443 and according to Schrader meant pure dark copper. 1444

cupper.

```
1410
      Sandaral loda, 9th sarga.
                                                         kāņda, 91st sarga; Kişkindhya-
                                                         kānda, 50th sarga.
1491
      Lankakanda, 6:th sarga.
                                                 1404
                                                        Ayodhyākāņda, 15th sarga.
1600
      Ayodh; Akanda, 32nd sarga.
                                                 1455
                                                        Ayodhyākānda, lūth sarga.
1432
      Ibid . 14th sarga.
                                                 3338
                                                        Ibid.
1454
      Sandarakāņda, 9th sarga.
                                                 1407
                                                        Kiskindhyākāņda, 33rd sarga
1415
      Ibid.
                                                 1403
                                                        Arapyakanda, 55th sarga.
1420
      Ayodhyakanda, 78th sarga.
                                                        Sundarakanda, 6th sarga.
                                                 310
      Aranyakinda, 52nd sarga; Sundara-
                                                 2140
                                                        Aranyakanda, 55th sarga.
      kānda, lat, 9th and 11th sargue.
                                                        Sundarakanda, 6th sarga-
                                                 1465
1400 V. 28. 1.
                                                 acce Ibid., 9th sarga.
1419
      Ibid., V. 28. 5.
                                                 正在在海
                                                        White Yajurveda, XVIII, 13;
Elack Yajurveda, IV. 7. 5.
生态器器
      XXIII, 35, 37,
1.40%
      I. 1, 2.
                                                 1144
                                                       Compare : Latin ass = Goth air =
2423
      XVIL 1, 14.
                                                        Zend ayarib, meaning pure dark
```

1400 Balakanda, 53rd sarga; Ayudhya-

Loba occurs in the Atharvaveda, 1445 the White Yajurveda, 1446 the Black Yajurveda 1447 and in the Chandogya Upanisad. 1448 The words Lohamaya and Lohayasa occur in the Satapatha Brahmana. 1449 According to Schrader 1450 loha originally meant copper but later it was used to denote iron. Syama is mentioned in the Atharvaveda, 1451 apparently meaning iron as the word occurs along with asi meaning a sword. It is also mentioned in the White Yajurveda, 1452 Black Yajurveda, 1453 Kathaka Samhita, 1454 Kapisthala Samhita 1456 and in the Maitrayani Samhita. 1456

We have distinct references to the iron-smelter and the black-smith. The Maitriyana-Brāhmana Upanişad thus describes the work of the blacksmith:—"Even as a ball of iron pervaded (overcome) by fire and hammered by smiths, becomes manifold (assumes different forms such as crooked, round, large, small) thus the Elemental Self pervaded (overcome) by the inner man and hammered by the qualities becomes manifold." The softening of silver by means of gold, of tin by means of silver, of lead by means of tin, of loha (iron) by means of lead was also known. Whatever be the real meaning of ayas, loha and syāmam these metals were extensively used in this period. Thus we read of receptacle that has been hammered or formed with a tool of ayas, the metal vessels, the metal jug, the pair of shears with sharp blades, the ardest soil cut the ripened grain, the knife, the spade to dig up the hardest soil

```
1448 XI. 3. 17.
```

<sup>1444</sup> XVIII. 13.

<sup>1447</sup> IV. 7. 5.

<sup>1440</sup> IV. 17. 7.

<sup>1440</sup> V. 4. 12; XIII. 2. 2. 8,

<sup>1450</sup> Prehistoric Antiquities, p. 212.

<sup>1401</sup> IX, 5. 4; XL, 3. 7.

<sup>1409</sup> XVIII. 13.

<sup>1435</sup> IV. 7. 5.

<sup>1454</sup> XVIII. 10.

<sup>1456</sup> XVIII. 10.

<sup>1455</sup> II. 11, 5.

<sup>1457</sup> White Yajurveds, XXX 14.

<sup>1488</sup> Ibid., XVI. 27.

<sup>1450</sup> HI. 3.

<sup>1440</sup> Chandogya Upanişad, IV. 17. 7.

<sup>1411</sup> White Yajurveda, XXVI. 26.

<sup>1444</sup> Bihadāraņyaka Upanişad, VI. 4. 13; Rāmāyaņa, Ajodhyākāņda, S2rd sarga; Sandarakāņda, 11th sarga.

<sup>1445</sup> Atharvaveda, XX. 127, 4.

<sup>1404</sup> White Yajarveds, XII. 68.

<sup>1465</sup> Ibid., IV. 1; VI. 11.

(evidently of metal, 1466 dātra, bill hook, 1467 hatchet, 1468 iron axe, 1469 iron hook, 1470 iron razor 1471 with razor-case, 1472 pair of nail scissors, 1472 iron nets, 1474 fetters wrought of iron, 1475 louha-maūjusī, iron box or trunk 1476 and collyrium-pots, probably made of metal. 1477 Among articles for use in sacrifice we read of the sacrificial hatchet, 1478 sickle to cut and trim the sacred grass, 1479 lead needles (according to the commentator Mahidhara copper or iron needles) to mark out the lines on the body of the sacrificial horse which the dissector's knife is to follow, 1460 bell, evidently made of metal 1461 and threads of iron for use in amulets. 1482 Among articles for purposes of war we read of phāla, blade of an arrow, 1483 sword, 1484 varman, armour, coat of mail, 1485 armour for elephants and horses, 1486. Iron forts 1487 and iron castles 1488 used in a

1. 4; khanitra, hoe, spade in Rāmāyaņa, Ayodhyākāṇda, 37th sarga; talīka, hoe, spade in Ibid., 80th sarga.

1407 Ayodhyākāņia, 80th sarga.

Chindogys Upanisad, VI. 16. 1.

Atharvaveda, VII. 115.1; VI. 141.
2: II. 12.3; White Yajurveda,
V. 42; VI. 15; Rāmāyapa, Eālakāṇda, 54th sarga; Ayodhyākāṇda,
S0th sarga.

1470 Atharvaveda, VII. 115. 1.

veda, III. 63; XV. 4; Brhadārabyaka Upanişad, III. 3. 2; Kanşîtakî Upanişad, IV. 20. Gompare "Just as the sharp edge of a razor is difficult to pass over, thus the wise say the path (to Self) is hard" — Kathopenişad, I. 3. 14.

1472 Kansitaki Upanisad, IV. 20.

1470 Karehanyasum in Chandogya Upanigad, VI. 1. 6.

1474 Atharvaveda, XIX, 66. 1.

1474 Ibid., VI, 63, 2; VI, 84, 3. White Yajarveda, XII, 63,

2676 Rāmāyaņa, Bālakāṇda, 67th sarga; cl. Petaka in Ajodhyākāṇda, 36th and 37th sargas.

1677 Ayodhyakanda, 91st sarga.

1470 Atharvaveda, VII. 28.

1470 Ibid., XII. ?. 31; cf. Black Yajurveda, I. 1. 2.

1486 White Yajurveda, XXIII. 37.

1481 Maitrayans-Brahmana Upanijad. VI. 22.

1482 Atharvaveda, V. 28, 1.

1406 Rāmāyana, Ayodhyākānda, 36th sarga.

1404 Kathopanişad, 11. 6. 4 ; Rāmāyaņa, Bālakanda, 54th sarga ; Ayodhyākānda, 23r l, 43rd and 52nd sargas.

1485 Atharvaveda, V.I. 118, 1; VIII.
5, 18; IX, 2, 16; XIX, 53, 4;
XX, 18, 6; White Yajurveda,
XIII. 35; XVII. 49; XXIX. 28,
45; Rāmāyaṇa, Ayodbyākāṇda,
40th and 91st sarga.

1400 Ramayana, Lankakanda, 75th sarga.

1487 Atharvaveda, XIX. 58. 4.

1400 White Ysjurveda, V. S.

figurative sense are also mentioned. Pillars made of iron, 1489 ornaments made of iron worn by king Triśańku in his chandala dress 1490 and images of tigers made of various metals 1491 are also mentioned.

We also read of the use of mixed metals (yougikadhātu) in this age. Bell-metal (kāṃsya) vessels, made of an alloy of copper and tin are mentioned in the Chāndogya Upaniṣad. In the Rāmīyaṇa 1493 we are told that after the marriage ceremony of his sons was over, king Daśaratha on reaching home presented four Brahmins with cows together with calves and bell-metal vessels for milching (kāṃsya-dohanabhāṇda). Vessels made of brass or pittala, an alloy of copper and zinc are mentioned in the Maitrāyaṇa-Brāhmaṇa Upaniṣad. In the Rīmīyaṇa 1495 we find a reference to brass when Khara angrily speaks to Rīma thus: "Just as the gold-like pittala (brass) is blackened when put to fire, so are you showing only your hollowness by self-laudation."

Whether alchemy was known in this period is not certain. Alchemy is the process by means of which an inferior metal is converted into a superior one. We find reference to this process in the 37th sarga of the Bālakāṇda of the Rāmāyaṇa where the origin of metals specially of gold (jātarūpa) is discussed. But some scholars look upon this passage as a later addition (prakṣipta).

The art of the jeweller — The manikara or jeweller is mentioned in the list of human victims of Purusamedha in the White Yajurveda. 1496 In the Taittiriya Brahmana 1497 the word used for jewellery is kacha which may mean glass or glass-beads; and it would be unreasonable to suppose that those who set glass on gold did not follow the same procedure with diamonds, and other precious stones for which they had names and which they knew and prized. 1498 When Bharata left Ayodhya to bring back

<sup>1489</sup> Atharvayeda, VI. 63, 3.

<sup>1400</sup> Rāmāyaņa, Bālakānda, 58th sarga.

<sup>1401</sup> Ibid., Ayodhyakanda, 15th sarga.

<sup>1499</sup> V. 2. 8.

<sup>1400</sup> Balakanda, 72nd sarga.

<sup>1404</sup> VI. 22.

<sup>1406</sup> Arapyakāņda, 29th sarga.

<sup>1496</sup> XXX. 7.

<sup>1407</sup> III. 665.

<sup>1498</sup> Manu ordains a fine for pieroing fine geme like diamonds and rubies and for boring pearls or inferior geme improperly.

Rama from the forest he was followed among others by the manikara. 1490 As a matter of fact, the Rīmīyana which treats of royal families generally as contrasted with the ritual literature mentions a large number of jewellery used in this period. Thus we read of golden diadem (kirita) set with jewels and pearls, 1500 golden kundalas (earrings) set with diamonds and vaidūryamaņi, 1501 maņikundala, 1502 pearl necklace, 1503 necklace of Indranilamani,1504 necklace of precious stones strung together with a golden thread, 1505 necklace of vaidūryamaņi 1508 golden amulet set with vaidūryamaņi, 1507 hastāvaraņa (bangles) set with corals, 1508 various images decked with gold, silver, diamonds, pearls and corals, 1500 images of birds decked wilh silver, coral and vaidaryamani,1510 images of serpents decked with gems, 1511 golden seats decked with gems, 1512 seats decked with gold and gems, 1513 bedstead decked with various gems, 1514 golden bedstead decked with gems, 1515 bed-sheet decked with gems and vaidaryamani, 1516 crystal altar decked with various gems 1517 altars decked with white gems like indranilamani and mahanilamani, 1518 fly-flapper (chamara) decked with white gems, 1519 chariot adorned with gems and corals, 1520 chariot mounted with gold and decked with jewels, 1531 and silver pillars decked with gold, gems and pearls. 1592

We may refer in this connection to prīkāśa which is frequently mentioned in the Taittiriya, Śatapatha and Paūchavimia Brāhmanas. It means

```
Rāmāyaņa, Ayodhyākāņda, 83rd
sarga.
1500 Ibid, Kişkindhyākāņda, 10th sarga.
1501 Ibid.
```

<sup>1002</sup> Bālakānda, 14th sarga.

Ayodhyākāṇda, 9th sarga; Kiṣkindhyākaṇda, 40th sarga; Sundarakāṇda, 9th sarga; Lankākāṇda, 130th sarga.

<sup>1</sup> se : Sundarakāpda, 15th sarga.

<sup>1005</sup> Ayodhyākāņdā, 32nd sarga.

<sup>1101</sup> Sandarakāņda, 9th sarga.

<sup>1007</sup> Arapyakünda, 64th sarga.

<sup>2000</sup> Sundarakanda, 15th sarga.

<sup>100%</sup> Ibid, 9th sarga.

<sup>1010</sup> Ibid., 7th sarga.

<sup>1511</sup> Ibid.

<sup>1018</sup> Ibid., 11th sarga.

<sup>1010</sup> Kişkindhyakanda, 50th sarga.

<sup>1812</sup> Ayodhyakanda, 76th sarga; Kişkindhyakanda, 50th sarga.

<sup>1818</sup> Sundarakāņia, 11th sarga.

<sup>1914</sup> Ibid., 10th sarga.

<sup>1817</sup> Ibid.

<sup>1013</sup> Ibid., 9th sarga.

<sup>1610</sup> Ayodhyākānda, 15th sarga.

<sup>1520</sup> Lankakanda, 11th sarga.

Ayodhyākāṇda, 16th sarga; Araṇyakāṇda, 53rd sarga.

<sup>1852</sup> Sundarakāņda, 9th sarga.

looking glass. Geldner thinks that pravepa in Maitrayani Samhita 1595 means the same thing. The Upanisads refer to polished mirrors 1624. The Ramayana also refers to polished mirrors (sumarjita darpana).1525 To people acquainted with crystals and metal foil the idea of setting small plates of crystal on foil for the manufacture of looking glasses would be easy enough. Polished metal plates seem, however, to be more frequently used and in the present day orthodox people prefer them to foiled glass in connection with marriage and other religious ceremonies. Such plates are usually made of silver. The mirror mentioned in the Svetasvatara Upanisad1526 was a metal disc.1527 The ancient Egyptians preferred copper or an alloy of copper and tin; but the Hindus hold that alloy as impure and unfit for religious purposes. The word kacha for glass occurs in the Taittiriya Brahmana 1 5 2 8 and seeing that the Ceylonese who borrowed all the arts of civilised life from the Hindus, make mention in the Dwipavamśa of a "glass pinnacle" placed on the top of the Ruanwelle dagoba by Suidaitissa, brother of Dutugaimuna, in the second century B.C. and of a "glass mirror" in the third century B.C. 1529 and Pliny describes the glass of India being superior to all others from the circumstance of its being made of pounded crystal 1530 it would not be presumptuous to believe that it was, in ancient times used in India in tha formation of looking glasses; but we have nothing as yet to show that mercury was used in fixing the foil on it. The looking glasses used in the decoration of the marble bath in the palace at Agra, were foiled with a film of lead and tin poured in a melted state in large glass globes which were afterwards broken to form small mirrors. This mode of foiling is still in common practice in many parts of India.

<sup>1848</sup> IV. 4. 8.

Upanisad, II. 6.5; Svetāšvatara Upanisad, II. I4; Aitareya Āranyaka Upanisad, III. 2. 4. 10.

<sup>1825</sup> Ayodhyākāņda 91st saega.

<sup>1890</sup> II. 14.

hy dust, sbines bright again after

it has been cleansed, so is the one incarnate person satisfied and free from grief, after he has seen the real nature of the self (Max Muller's Translation in the S. E. E. Vol. XV. p. 242).

<sup>11128</sup> III. 665.

<sup>1420</sup> Tennet's Ceylon, I. p. 454.

<sup>1</sup> ano Lib. XXXVI., C. 66,

(3) Working in wood-The ordinary carpenter made wooden vessels, implements and furniture for domestic as well as ritual use. Ladles of various kinds-the sruva1631 (small ladle used specially for Soma libation), the sruc1532 (large wooden ladle), dhruva1533 (having the largest bowl used in pouring libations of clarified butter into fire), the juhu1534 and the upablist1535 are frequently mentioned. Wooden mace used in sacrifice, 1535 wooden sacrificial spade 1537 with which earth is to be dug to form two square beds for the chief cauldron called mahīvīra aud gharma to rest on, large wooden soms reservoir called drona-kalasa, 1556 fourcornered sacrificial cups of khadira wood1529 mortar-shaped cup of palāša wood1340 cup made of udumvara wood, 1541 wooden soma cups, 1542 wooden covers for sacrificial vessels, 1545 wooden mortar 1544 and postle 1545 for extracting soma juice, wooden mortar and pestle for pounding out rice,1546 wooden pegs or wedges with which the pressing stones are beaten 1547 wooden pegs for stretching out skin or woven cloth 1548 wooden needles used in stitching together the folding doors of the cart-shed, 1549 fire-shovel or poker made of palasa wood, 1550 wooden instrument called sphya, shaped like a sword used in stirring up boiled rice, drawing lines on the ground and other sacrificial purposes, 1551 yupas or sacrificial

Nhite Yajarveda, I 29; II. 20; XVII, 77; Brhadaranyaka U pani-VI. 3. 13.

<sup>1403</sup> White Yajurveda, I. 29; II. 20; XVII. 79.

Yajurveda, XVIII. 5; Black Yajurveda, III, 5, 7.

Atharvaveda, V. 17. 5; XVIII. 5; Black Yajurveda, III. 5. 7.

<sup>1838</sup> Atharvaveda, XVIII. 5; Black yajurveda, III. 5, 7. 2.

<sup>1884</sup> Atharyaveda, VII. 28.

<sup>1837</sup> White Yajurveda, V. 22; XI. 10; XXXVII. 1; Altareya Āranyaka III. 1, 4.

Whitte Yajurveda, VII. 29; VIII. 42; XIX, 27; Black Yajurveda, III. 1, 6, 1.

<sup>1050</sup> White Yajurveda, VIII. 38.

<sup>1540</sup> Ibid., XIX. 33.

<sup>1141</sup> Bihadāraņyaka Upanisad, VI, 3, 1; VI, 3, 13,

<sup>1842</sup> White Yajarveda, XIX. 27.

<sup>1640</sup> Atharvaveda, XV111. 4. 53.

white Yajurveda, I. 14; XIII. 33.

<sup>1045</sup> Ibid., I. 15 ; XIII. 33.

<sup>1546</sup> Atharvaveda, XII. 15.

<sup>1547</sup> White Yajurveda, I. 16.

<sup>1646</sup> Ibid., V. 16.

<sup>1840</sup> Ibid, V. 21.

<sup>1880</sup> Ibid., I. 17.

<sup>1661</sup> Ibid., I. 24; Black Yajurveda, I. 1.9.

posts, 1559 timber posts called svaru, 1553 drupad 1554 and vanaspati 15 15 (evidently a dressed and entire sala trunk) are referred to.

Mention is also made of seats made of udumvara wood 1555 and of thrones of khadira wood. 1557 Among these the talpa is thus described in the Atharvayeda:

"Bhaga hath formed the four legs of the talpa, Wrought the four pieces that compose the frame-work. Tvastar (skilled carpenters) bath decked the straps that go across it.1558

Being the nuptial bed-stead1559 it was usually made of udumvara wood. 1568 The pitha (alluded to in the mention of pithasarpin 1561 cripple) was evidently a wooden seat. The epithet prostha-saya 1362 shows that prostha was something like a high and broad bench. 1563 In the Taittiriya Brāhmaņa 1564 prostha is, therefore, distinguished from talpa and vahya. As the name suggests vahya is a couch of light structure that could be carried about when necessary; it seems to have been an essential item of furniture for the bridal chamber, 1565 having an embroidered coverlet. 1566 Asandi which means either a shining seat or the occupier of a shining seat is referred to in the Atharvaveda in connection with not only the inauguration of the Vratya chief1567 but also a marriage-ceremony. 1588 In the White Yajurveda 1560 Isandi is specially associated with kingship, being

Atharvaveda, VII. 30; XIL 1, 38; XII. 3. 33; White Yajurveda, Bk. V. 41-43 and Bk. VL 1-6; Black Yajurveda, VI. 6. 4.; Rāmāyaņa, Bālakāņda, 14th sarga. Aitareya Brahmana II. 1; Kauşitakî Brahmana, X. 1.

Atharvaveda, IV. 24. 4; XII. 1. 13.

<sup>1884</sup> Ibid, VL 83. 3; VI. 115. 2; XIX. 47. 9 ; White Yajurveda, XX. 20.

<sup>1888</sup> Ibid., IX. 3. 11; Black Yajurveda, VI. 2. 8. 4.

Aitareya Āranyaka, I. 2. 4. 10. 1856

White Yajutveda, X. 26.

Atharvaveda, XIV. 1. 60.

Ibid., XIV. 1. 31. - 859

Taittiriya Brahmana, L 2. 6. 5. 1560

White Yajurwada, XXX. 21; | lack Yajurveda, III. 4. 17. 1.

Atharvaveda, IV. 5. 3=Rigveda, 1869 VII. 55. 8.

<sup>1255</sup> Compare vernacular paiths, a broad plank resting on two legs in the Gangetic river boats.

<sup>11. 7. 17. 1.</sup> 1504

Atharvaveda, IV. 20, 3. 1685

Ibid., XIV. 2, 30. 2.011.0

Ibid., XV. 3, 2, ff. 1567

Ibid., XIV. 2. 6 .. 1565

XIX. 86. 1569

regarded as the 'womb of rajanyas' 1570 and its use in ritual by a sacrificial priest ensures samrājya for his client1571; but the qualificatory term rajasandi 1572 shows that the humbler asandi's were also in use. The asandi is usually made of sacred udumvara wood, 1573 sometimes of khadirawood. 1574 It had four legs. 1575 It was sometimes square, 1576 and sometimes rectangular 1577 in shape. It was sometimes a span high, 1578 sometimes knee high 1579 or navel high. 1580 The Vratya chief's asandi described in the Atharvaveda 1581 had framework of wood and woven straps, two (fore) feet, two (back) feet; two lengthwise and two crosswise pieces; forward and cross tantus (wooven straps or cords), and upsraya, the support or back of the seat; its adjuncts were astarana, coverlet, asada, seat proper i.e., the cushion for sitting on, and upvarbana, cushion for leaning against. The paryanka is a later development being first mentioned in the later Vedic texts. 1889 It had four legs and was furnished with sirsanya, head-piece of the couch, upasri, the supporting back of the couch and ucchirsaka, cushion and pillow for the head.

In addition to the ordinary carpenter we find the Rathakara 1888 who besides making chariots for purposes of war 1884 and race made carts, 1885, waggons 1886 and carriages. 1887 References to boats 1888

1879 Cf. also White Yajurveda, XX. 1.

1871 Black Yajurveda VII. 5. 8. 5.

1972 White Yajarveda, XIX. 16.

Aitareya Brābmaņā, VIII. 5, 6, 12
 and 17, Satapatha Brāhmāņa III. 4.
 26 ff; V. 2. 1. 22; VI. 7. 1. 12ff;
 XIV. 1. 3. 8ff.

1874 Satapatha Brāhmaņa, V 4. 4. 1 ff.

Aitareya Brāhmaņa, VIII. 12 and 17; Kauşitaki Upanişad, I. 5; Sānkhyāyana Āranyaka, III.,

Aitareya Brahmana, VII. 5 and 6.

1877 Aitareya Brāhmaņa, VIII. 19.

1879 Satapatha Brahmana, VI. 7. 1. 1.ff.

1070 Ibid., XII. 8. 3, 4ff.

asso Ibid., III, 3, 4, 26ff.

1961 XV. 3. 2ff.

Aranyaka, III, Compare Jaim. Brāh, II. 24.

1888 Atharvaveda, III 5, 6.

1534 White Yajurveda, XXIX. 45.

1888 Ibid., L. 8; II. 19; IV. 33.

Black Yajurveda, I. S. 18; Brhadāraņayka Upanijad, IV. 4, 1, 35.

Atharvaveda, XX. 125.3; White Yajarveda, XII. 30; Brhadaranyaka Upaniyad, IV. 2, 1.

1000 Atharvaveda, II. 36, 5; III. 6, 7; IV. 33, 7, 8; V. 4, 4; V. 19, 18; XX, 46, 2; XX, 72, 1; Black Yajurveda, V. 3, 10, 1; Aitareya Aranyaka f. 2, 4, 6 etc.

presuppose the existence of boat builders. Boats of bigger size, having two rudders (nau-manda) 1589 came to be known in this period.

The Rīmīyana refers to specialised carpenters 1500 and to the manufacture of boxes (petaka) 1501 wooden sandals 1502 and artificial hills made of wood. 1503

(4) Leather-work-The hide-dresser is mentioned in the White Yajurveda 1594 and the Aitareya Brāhmana 1595 seems to refer to the stretching of hides with pegs, while the Svetasvatara Upanisad1528 refers to the rolling up of hides. The importance of the hidedresser is evident from the fact that skins of aja (goat) kṛṣṇasara (the black antelope), harina (deer) and the eta (spotted deer) were in common and ritual use. Thus the religious student (brahmacīrī) is clad in the black antelope skin. 1597 The gods dressd in doer skins 1598 used to alarm their enemies. 1593 The Kukundhas and the Kukurabhas used to dress themselves in hides and skins. 1509 Skins of deer were used as coverings 1600 and as seat-spreads. 1601 According to ritual custom the Brahmin priest goes clad in goat's skin. 1602 Goat skin was also used as coverlet for asandi's. 1603 A tradition of wearing cowhides in primitive times is hinted in a passage of the Satapatha Brahmana. 1604 Cowhide also served as a ritual seat for the newly married couple. The skin of the black antelope was used as coverlet for asandi's 1605 as well as for pressing soma and bruising and husking the rice used in oblations. 1606 The tiger-skin was used as

Satapatha Brahmana, II. 3. 3. 15.

<sup>1500</sup> Ayodhyakanda, 83rd sarga.

<sup>1501</sup> Ibid., 36th and 37th sargas.

<sup>1600</sup> Ibid., 91st sarga.

<sup>1003</sup> Sundarakāņda 6th sarga.

<sup>1884</sup> XXX, 15.

Yajarveda, p. 43 fn.

<sup>1896</sup> VI. 20.

<sup>1897</sup> Atharvaveda, XI. 5. 5.

<sup>1800</sup> Ibid., V. 21. 7.

<sup>1500</sup> Ibid., VIII. 6. 11.

<sup>1600</sup> Ibid., IV. 7. 6.

<sup>1801</sup> Rāmāyaņa, Araņyakāņda, 43rd sarga.

<sup>1003</sup> Satapatha Brahmana, III. 9. 1. 12.

<sup>1608</sup> Ibid. V. 2. 1. 22.

<sup>1004</sup> Ibid., III. 1. 2. 13ff.

<sup>2608</sup> Ibid , XII. 8. 3. 4-10.

Griffith's Atharvaveda, Vol. II. p. 52 fn.

coverlet for Tsandi's 1607 and for chariots. 1608 Lion skins were also used for covering chariots. 1609

Besides the hide-dresser, leather-worker (carmaśilpī)<sup>1610</sup> is also mentioned. Leather-bags were used for holding milk, wine and other liquids<sup>1611</sup> and dry skin-bags sometimes formed part of sacrificial fee. <sup>1613</sup> The ritual shoes mentioned in the Black Yajurveda<sup>1613</sup> were made of of black antelope skins while the ritual shoes mentioned in the Satapatha Brāhmaṇa<sup>1614</sup> and in the Kauṣitaki Brāhmaṇa<sup>1615</sup> were made of boar-skin.

- (5) Pottery—The potter is frequently mentioned 1616 Among the earthen pots made by him we find sthall, cooking pot which occurs in the Atharvaveda and the Brahmanas; asecana, vessel to hold liquids such as meat-juice (Yūṣan) 1617; and ukhā, a cooking pot which is described clearly as mṛṇmaya in the White Yajurveda. 1618 The Rāmāyana also mentions sthall, kumbhî and karambhi filled with curds. 1610 Broken liquor-pots are also referred to 1620
- (6) Ivory work—The Rāmāyana mentions altars 1621 and seats made of ivory, 1622 legs of bedsteads made of ivory and gold, 1623 pillars and windows (of Rāvaṇa's palace) made of ivory, 1624 and images of ivory placed in chariots. 1625

<sup>2007</sup> Satapatha Brāhmaņa, V. 4 4. 1 ff; Aitareya Brāhmaṇa, VIII. 5 and 6.

Ramayana, Ayodyakanda, 16th sarga; Sundarakanda, 6th sarga,

<sup>1000</sup> Ibid., Sandarakāņda, 6th sarga.

<sup>1610</sup> Ibid., Bälakünla, 13th sarga. See also carmachchhedaka in Ayodhyäkünda, 83th sarga

Pañchavinéa Brähmana, XIV. 11. 26; XVI. 13. 13.

<sup>1619</sup> Black Ysjurveds, I. S. 19.

<sup>1613</sup> V. 4. 4. 4 ; V. 6. 6. 1.

<sup>1414</sup> V. 4. 3. 19.

<sup>1618</sup> III. 3.

White Yajurveda, XVL 27; XXX. 7; Maitrāyani Samhitū, I. 8. 3.

<sup>1017</sup> Rigveda, I. 162. 13.

IV. 1. 5. 4; Atharvaveds, IX. 6 17.

<sup>1010</sup> Ayodhyākānda, 91st sarga.

<sup>1440</sup> Ibid., 114th sarga.

<sup>1421</sup> Ayodhyākāpda, 10th srrga.

<sup>1099</sup> Ibid.

<sup>1008</sup> Sundarakāņda, 10th sarga.

<sup>1000</sup> Arapykānda, 55th sarga.

<sup>1000</sup> Sundarakāņda, 6th and 9th sargas.

(7) Manufacture of liquor-The sacred sacrificial drink obtained from the Soma plant was highly prized in this period as none of the principal religious rites such as the Darsa, Pūrņamāsa,, Jyotistoma, Ukthya, Vājapeya, Atirātra, Āptaryāma etc., could be celebrated without it. It is no wonder, therefore that the Black Yajurveda 1826 furnishes innumerable mantras for repitition at every stage of its manufacture. It is not necessary to describe here in any detail 1772 the several steps in its manufacture; suffice it to say that it was made with the expressed juice of the Soma creeper, diluted with water, mixed with barley meal, clarified butter and the meal of wild paddy (nīvāra) and fermented in jar for nine days. 1628 It seems that the starch of the two kinds of meal (barley and wild paddy) supplied the material for the vinous fermentation and the Soma juice served to promote vinous fermentation, flavour the beverage and check acetous decomposition in the same way that hop does in beer. Its intoxicating effects as noticed in the Rigveda have already been described. In the Black Yajurveda we find a story in which a sage Visvarupa by name, son of Tvașțu while engaged at the Soma sacrifice is said to have indulged so inordinately in the exhilarating beverage as to have vomited on the animals brought before him for immolation.

In a distilled condition the Soma would be of no use and as it was not distilled it could not be kept for any great length of time. Accordingly no Soma juice was used when arrack was distilled from fermented meal. This fermented barley or wild paddy meal when distilled was called surā which was known, as we have already seen, early in the Rigvedic Age. It was used as an article of offering to the Gods in two important rites, namely, Sautrmānī and the Vājapeya. According to Baudhāyana and Kātyāyana three articles are used in its preparation viz. sprouting paddy, the sprout brought on by steeping paddy in water, slightly parched barley steeped in curds and diluted butter milk, and coarse powder of the same steeped in whey. After proper fermentation, this was distilled in the usual way. Unfortunately we do not get any description in contem-

<sup>1010</sup> I. 2-4; VI. 1-4.

The Kalpasütras and the Somaprayoga supply the details.

<sup>1688</sup> Stevenson's Samaveda, p. 5 ; Hang's Aitareya Brahmana I., p. 6.

porary literature, of the still in which the distillation was effected, the Taittiriya Brāhmaṇa suppling only a number of mantras for the preparation of the liquor. Another drink known as Kilāla was probably a variety of surā while Parisrut was a drink made from flowers. 1829

The Ramayana 1880 refers to sura which oozes spontaneously from trees (tadi?) and different varieties of madya prepared by the Saundika of which Varuni 1831 and Maireya 1832 were famous.

- (8) Painting—Frescoes (patibhīna or conversation-pictures i.e., love-scenes) are mentioned in the oldest Pali literature and the very fact that Buddha prohibited these paintings and permitted only the representation of wreaths and creepers shows the pre-Buddhistic origin of painting The Kathopanisad 1635 refers by way of simile to pictures (light and shade) and to the painter's brush 1634 while the Maitrāyaṇa-Brāhmaṇa Upanisad 1635 refers by way of simile to a painted wall. The Rāmāyaṇa refers not only to painters (citrasilpavid) 1636 but also to rooms (of Rāma's Mahal in Ayodhyā) adorned with pictures made by skilful artists. 1637 Picture-galleries 1638 are also mentioned.
- (9) Sculpture—Sculptured images on wooden posts are as old as the Rigveda. 1939 The Atharvaveda refers to decorated and inlaid (piś) bowls like the starry night 1949 and to carvings in relief of gods inside the bowl. 1841 The Rīmīyana refers to images of horses, birds, serpents and of Lakshmi with her elephants carved on the aerial chariot of Rīvaņa. 1842

6th and 12th sargus.

Citrugiha in Ayodhyākānda, 10th sarga; Citrašālā in Sundarakānda,

Pāraskara Gihyasūtra, III. 2 9; Pāraskara Gihyasūtra, III. 4. 4. See also Zimmer—Altindisches Leben, p. 281.

<sup>1100</sup> Sundarakāņda, 11th sarga.

<sup>1001</sup> Ayodhyakanda, 114th sarga.

<sup>1659</sup> Ibid, 91st sarga; Uttarakāņda, 52nd sarga.

<sup>1633</sup> II. 6. 5. 1034 II. 6. 17.

<sup>1000</sup> IV. 32, 23,

<sup>1640</sup> Atharvaveda, XIX, 49, 8.

<sup>1841</sup> Ibid., XII. 3, 33.

<sup>1649</sup> Sandarskänds, 7th sargs.

<sup>1055</sup> IV, 2.

<sup>1688</sup> Uttarakāņdu, 107th sarga.

Ayodhyākāṇda, 15th sarga.

(10) Architecture-The Atharvaveda 1648 gives us a graphic account of a style of architecture which evidently refers to the ordinary type of a dwelling house in this period. According to it four pillars (upamit) were set up on a good site and against them beams were leant at an angle as props (pratimit). The upright pillars were connected by cross-beams (parimit) resting upon them. The roof was formed of ribs of bamboo (va:nsa), a ridge called visuvant and aksu, either the wicker-work or split bamboo-lining, over which the thatch was laid and to which the description of thousand-eyed 1644 could aptly be applied or a net spread over the visuvant to keep the straw-bundles of the thatch in tact during stormy weather. The walls were filled up with straw or long reedy grass 1645 and the whole structure was held together with ties of various sorts. 1846 Besides the store-house of Soma, 1647 the agni-sala (the hall of the fire altar), 1648 patuinim sadana (ladies' apartments), 1649 sadas (a shed erected in the sacrificial enclosure to the east of the Pracinavamsa chamber, which had its supporting beam turned towards the east)1650 and covered verandahs (at least along the front and back as denoted by the term paksas) each house had a big store-room or sala full of clean corn 1651 and sheds for sheep and cattle.1652

In the Black Yajurveda we find frequent mention of bricks and of their use in the construction of fire-alters. Among the various forms of altar-bricks known to the people of this age, we may mention

<sup>1648</sup> Atharvaveda, IX 3; III. 12.

<sup>1444</sup> Atharvaveda, IX. 3. 8.

<sup>1048</sup> Palada, Atharvaveda, III. 12. 5;
IX. 3. 5; palāva, Atharvaveda,
XII. 3. 19; Jaiminīya Upanisad
Brāhmaņa, I. 54. 1; palāli Atharvaveda, II. S. 3; palāla, Kausitakī
Sūtra, LXXX. 27.

Sem lanisa, prāpāha, nahana, parisvalījalya—Atharvaveda, IX. 3. 4, 5.

<sup>1647</sup> Atharvaveda, IX. 3. 7.; IX. 6. 7.

<sup>1648</sup> Ibid., IX. 3, 7.

<sup>1040</sup> Ibid.

<sup>1000</sup> Ibid., IX. 6. 7.

<sup>1051</sup> Ibid., III, 12. 3.

<sup>1852</sup> As there is distinct mention of playful calves and children in the
house in the Atharvaveda III. 12.
3. Compare Rigveda, VII. 56.
16. Moreover, the house is described as rich in horses and in
kine (Atharvaveda, III. 12. 2) and
as giving rest to man and beast
(Atharvaveds, IX. 3. 17.)

<sup>\*</sup> The first explicit mention of burnt (pakva) bricks occurs in the Satapatha Brähmana late in the 7th century B. C. (VI. 1. 2. 23; VII. 2. 1. 7.)

mandalestakā (circular bricks) 1633 vikarņī, (cornerless bricks) 1634 codī (conical bricks) 1635 kumbhestakā (pot bricks) 1636 and other bricks with various linear markings. 1657 Mortar (purisa) was used in making bricks firm and has therefore been aptly compared to flesh adhering to bones. 1638 Such adhesive plasters must have been essential in the construction of the alternative forms of the alter 1639 like the 'bird' styles (representing the syena, kanka or alaja) or the 'bowl' or granary (drona), 'chariot-wheel,' 'circle' 'cementery' (smasāna) and 'triangle' models. It would be extraordinary if bricks were not used for the secular house-buildings as well, while alters (household or special) and cemeteries 1540 were brick-built.

The Satapatha Brāhmana describes at length the smasāna (funeral and memorial) structures and classifies them into vāstu, gṛhān and prajūānam. The vāstu reliquary of bones etc., was built in two styles. The Prīcya or unorthodox type was round and domeshaped (parimandalā), 1863 separate from the earth (i. e., towering), made of stone, instead of bricks 1863 and enclosed by an inlefinite number of enclosing stones. The orthodox style of vāstu was square or qualrilateral, 1665 not separate from the earth, 1665 and made of bricks one foot square. 1867 The gṛhān 1868 was either an actual house with many rooms, erected over or beside the grave in memory of the deseased or chambers and vaults of subterranean or rock-cut caves. 1869 The prajūānam means a pillar-like memorial monument. A pillar (sthūnī) is indeed set up on the

Black Yajurveda, IV. 4, 5; V. 3. 9; etc.

<sup>1054</sup> Thid., V. 3. 7.

<sup>1885</sup> Ibid., IV. 4. 3; V. 3. 7; etc.

<sup>1486</sup> Thid, V. G. 1; etc.

<sup>1027</sup> Ibid., V. 2. 3; V. 2. 10.

<sup>1000</sup> Thid., V. 2. 3.

<sup>2858</sup> Thid., V. 4. 11.

The direction that brick-altars could be erected after the model of (round or square) imaginas show that these latter were also brick-atructures by the time of the Black Yajarveda.

<sup>1001</sup> Satapatha Brahmana XIII. S. 1.

<sup>1002</sup> Ibid.

<sup>1008</sup> Thid., XIII. 8. 4. 11.

<sup>1664</sup> Ibid., XIII. S. 2. 2.

<sup>1065</sup> Satapatha Brahmana, XIII. S. 1, 1ff.

<sup>1000</sup> Ibid., XIII. S. 1. 1.

<sup>1007</sup> Ibid., XIIL 8, 4, 11,

X. 18. 13; Atharvaveda, XVIII. 3.51 - Rigveda
X. 18. 13; Atharvaveda, XVIII.

tian cave-graves offer instructive parallels.

Vedic grave 1670 and in the time of the Satapatha Brīhmaņa a stone 1671 pillar (śanku) was set up along with three timber ones at the four corners of the śmaśāna 1672

The great variety of names for doors <sup>1673</sup> and pillars <sup>1674</sup> shows that they were a marked feature of one other type of house-building, characterised by timber-work as opposed to bamboo, brick and stone work. This timber architecture seems to have been strengthened by the use of ayasthūṇa's <sup>1675</sup> (pillars made of the metal called ayas) and parigha's <sup>1676</sup> so that it constituted a necessary earlier stage of architecture to account for the elaborate gold-plated and inlaid timber-pillars of the Mauryan palace.

(11) Town planning—Town-planning seems to have been known in this period. Mr. E. B. Havell<sup>1677</sup> remarks "The close connection of the geometrical system (denoted by the mystic figures Paramašāyika, Swastika, Sarvatobhadra, etc.,) with the Vedic sacrificial lore, and the position of the master-builder as high priest or sacrificial expert are indirect proofs of the great antiquity of the Indian science of town-planning; for, geometry as a science was an Indo-Aryan invention and had its origin in the complicated system of Vedic sacrifices in which it became necessary to

veda, X. 18. 3. 52 = Rig-

According to the commentator made of witre - stone.

to stupes and later on to medieval

Dvār (White Yajurveda, XXX. 10;
Satapatha Brāhmaņa XI. 1, 1, 2);
dvāra (Atharvaveda, X. 8, 43);
durya (White Yajurveda, I. 11;
Black Yajurveda, I. 6, 3, 1);
duroņa, signifying house itself
(Atharvaveda, VI. 17, 3; White
Yajurveda, XXXII, 72.)

Satapatha Brāhmana XIV. 1. 63;

sthunā-rāja (Satapatha Brāhmaņa III. 1. 1. II; III. 5. 1. 1; avaru (Atharvaveda, IV. 24. 4; XII. 1. 13); methi, with variants 'medhi,' 'methi,' or 'methi' (Atharvaveda, VIII. 5. 20; XIV. 1. 40; Black Yajarvada, VI. 2. 9. 4; Kāthaka Samhitā XXXV. 8; Aitareya Brāhmaņa I. 29. 22; Satapatha Brāhmaņa, III. 5. 3. 21; Paūchaviņša Brāhmaņa XIII. 9. 17; Jaiminīya Brāhmaņa I. 19. 1).

1075 Rigweda, V. 63. 7, 8.

1014 Obbindogya Upanisad, II. 24, 6, 10, 15.

Rale in India, p. 25.

resolve geometrical problems such as constructing a circle equal in area to a square and vice-versa. The laying out of the Indo-Aryan village is treated in the Silpasastras as the preparation of sacrificial ground. I have, therefore, considered it justifiable to refer it historically to the Vedic period and to connect it with the camp or fortified settlement of the early Aryan invaders." In a later volume Mr. Havell writes that subsequent investigations confirm his foregoing observations. He says "If it be trueas the Russian scholar Sheftdovich, asserts-that the Kassites who took Babylon in 1766 B. C. and established a dynasty there which lasted for 600 years were Aryans speaking Vedic Sanskrit whose chief god was Süryya, Babylon must be regarded as a half-way house of the Aryan race in its march towards the Indus valley and some, at least of the early Aryan tribes must have acquired, before they entered India, not only the high spiritual culture which is reached in the Rigveds, but a prolonged experience of the civic arts, including architecture. Recent German exeavations on the site of Babylon show that the science of building in Vedic times had advanced much further than has hitherto been suspected." (E. B. Havell-Ancient and Medizeval Architecture, p. 3.)

Indeed the plan of the towns and their denominations were identical with those of the geometrical figures that had to be drawn on the sacrificial altars. These figures suggested the plans and the names. And the description of the cities of Ayodhyā and Laūkā as preserved in the Rāmāyaṇa seems to show that they were built according to a definite plan and are in wonderful agreement with the principles laid down in the later Silpaśāstras. Thus we are told that the city of Laūkā was situated on the top of a hill, 1878 surrounded on all sides by a wall 1878 and outside the wall was a ditch sorrounding the city. 1678 The ancient town-planners were not slow to seize the slighest opportunity to make the city as picturesque as they could. Accordingly, in the ditch were carefully nurtured lotus and lily plants 1878 The ditch was spanned by bridges in front of each of the many gates which pierced the wall surrounding the city. 1878 Inside the city were roads which were broad and well-divided. There were rows of beautiful houses plastered with lime, 1678

<sup>1470</sup> Ramayana, Sundarakanda Ind sarga.

The royal palace was sorrounded by a wall pierced by many beautiful gates. 1679 It contained latigrha, 1879 citrasala 1679 kridagrha, 1679 kamagrha, 1679 divavihara-grha 1679 and even artificial mountains made of wood 1679 besides many orchards 1879 and gardens. 1879 The famous Asoka forest with its rows of flower and fruit trees planted in their proper order by skilful sylviculturists, its well excavated tanks with their beautiful steps, its raised seats, rest-houses and latagrha's vied in beauty with the Nandanakānana of Indra, the Garden of Brahmā or the Chaitra-ratha of Kuvera. 1880 Near the royal palace were the houses of Prasasta, Mahaparsva, Kumbhakarna, Vibhisana and other notables of the kingdom. 1679 The city also contained savīgrha's, 1681 gosthasīlā's 1681 and yantrīgāra's, 1661 In fact, the buildings were so faultlessly constructed that they appeared to have been made by Mayadanava himself. 1889 The city has, therefore, been described as a mind-wrought city in the air, of Viśwakarman. 1879 It is likened to a woman with the walls and ramparts for her thighs, 1678 the wide expanse of water (in the ditch) and the surrounding jungles for her clothes, 1678 the sataghni (guns?) and salastra for her locks of hair, 1678 the palaces for her ornaments 1678 and the vantragara's for her breasts, 1681

Similarly, the city of Ayodhya is said to have been built by Manu. 1683 It was twelve yojanas in length and three yojanas in breadth. 1683 It was sorrounded by a deep most, which made it difficult of access. 1883 It was divided by one broad road which was met by other fine streets all regularly watered. 1683 The city was founded on a plain 1683 and had many stout arched gates with large door-panels.1888 In the middle of the city were rows of shops. 1683 In all quarters of the city were theatres, pleasuregardens, mango-groves and avenues of sala trees. 1683 Its innumerable palaces high like hills, 1683 sport-houses for ladies, 1683 tanks, 1683 chaityas, 1684 temples, 1684 yajnasalas 1684 and panasala's 1685 -all enhanced its beauty and magnificence. The buildings were not constructed in an irregular fashion, for, there was co-operation in alignment and structure (Sunivesitavesmantam).

<sup>1070</sup> 

Ibid., 6th sarga. Ibid., Uttarakāņda, 52nd sarga.

Ibid., Sundarakānda, 3rd sarga, Ibid., 7th sarga. 4000

<sup>1465</sup> Ibid., Halakanda, 5th earga.

Ibid., Ayodhyākānda. 71st surga.

Thid., 100th sarga.

In consonance with this great attention to town-planning the people developed a high tone of civic consciousness. In the Rāmāyana the city of Ayodhyā and everything in it fill the poet with delight. "He loses himself in the thought of its palaces, its arches and its towers. But it is when he comes to paint Lankā that we reap the finest fruit of that civic consciousness which Ayodhyā had developed in him. There is nothing in all Indian literature, of greater significance for the modern Indian mind than the scene in which Hanumāna contends in the darkness with the woman who guards the gates saying in muffled tones "I am the city of Lankā." \*\*1686\* Such a civic sense was quite probable because the cities in ancient times were more than centres of trade and corporate life; they were the ultimate resorts of the people against hostile invasion.

The occupations—We have already seen that the Rigveda shows germs of a social division, arising out of the adoption of different occupations by different sections of the community. An idea as to the enormous extent to which division of labour was carried out in this period will be evident from the following list of principal occupations most of which are described in the White Yajurveda<sup>1687</sup> in connection with the victims of the Purusamedha ceremony:—

- (a) Agricultural occupations—Besides the husbandman 1688 we hear of various agricultural labourers: (1) ploughman (kinasa, kṛṣivala), 1689 (2) sower (vīpa), 1890 (3) one employed in husking (dhānyakṛt) 1691 and (4) woman employed in grinding corn (upalaprakṣinī) 1693
- (6) Industrial occupations—Of those engaged in the various industrial arts the following are important: (5) smelter (dhmātṛ), 1693 (6) black-

Aham hi nagarī Lankā svayameva plavangama—Sundarakānda, Erd sarga.

Sister Nivedită-Civia and National Ideals, pp 6-7.

<sup>1467</sup> Chapters XVI and XXX.

<sup>1000</sup> Ath rvaveds, VI. 116. 1.

<sup>1889</sup> White Yajurveda, XXX. 11.

<sup>1400</sup> Ibid, 7.

<sup>1601</sup> Ibid., XVI. 33.

<sup>1002</sup> Rigveda, IX. 112. 3.

pare smelting of ores (asman) in Satapaths Brahmans, VI. 1. 3, 5.

smith (karmāra), 1694 (7) arrow-maker (işukāra), 1695 (8) female scabbardmaker, 1696 (9) goldsmith (hiranyakāra, suvarnakāra), 1697 (10) jeweller (manikāra), 1698 (11) carpenter (tastr, 1899 taksaka, 1700 sūtradhāra 1701), (12) carver (pesity), 1703 (13) chariotmaker (rathakara), 1703 (14) bowmaker (dhanuskāra), 1704 (15) bowstring maker (jyākāra), 1703 (16) ropemaker (rajjukāra),1706 (17) woman who splits cane, 1707 (18) basketmaker (vidalakāri), 1708 (19) woman who works in thorns, 1709 (20) weaver (vāya), 1710 (21) weaver of rugs (kambala-kāra), 1711 (22) female weaver (vāyitri), 1718 (23) woman who embroiders (pesaktri),1718 (24) female dyer (rajayitri),1714

(25) female ointment-maker, 1718 (26) scent-maker (gandbajīvî), 1716

(27) stone-carver (prakaritr), 1717 (28) leather-worker (carmanna, 1718 carma-

White Yajurveda, XVI. 27; Maitrayana Brahmana Upanisad, III. 3

White Yajarveda, XVI 46; XXX. 1098 17.

Ibid., XXX. 14. 1805

Ibid., 17; Ramāyaņa, Ayodbyākāņda, 1687 Sård sarga ; Brhadaranyaka Upanisad, IV. 4. 4.

White Yajurveda XXX. 7; Rāmāyana, Ayodhyakanda, 83rd sarga.

Atharvaveda, X 5.3; White Yajur-2659 veda, XVI 27 ; XXX. 6

Rāmāyana, Bālakānda, 18th sarga. 1700

Ibid., Ayodhyākānda, Soth and 83rd ITOI sargas.

White Yajurveda, XXX, 12, 1102

Ibid , XVI. 27 ; XXX. 6. 1795

Ibid , XVI. 46 ; XXX. 7. 1704

Ibid., XXX 7. 1703

Ibid.; Black Yajarveda, VII. 2. 4. 1708 2; compare Aitareya Aranyaka, I. 2. 3. 0-10.

White Yujurveda, XXX. 8. LTOT

Compare round mats of mania 1108 grass for ritual use in White Yajurveda, XII. 2.

White Yajurveda, XXX. 5.

See Vedic Index, sv. Vāya. 1710

83rd Ayodhyākānda, Rāmāyana, SETIES.

Panchavims, Brahmana, I. S. 9: 1713 compare Satapatha Brahmana, III. 1. 2. 13ff.

White Yajuryada, XXX. 9. 1718

Ibid., 12. 1714

Ibid., 14. 1718

Ramayana, Ayodhyakanda, 83rd 1710 surga.

A remarkable feature found in the 1717 smasana of the Satapatha Brahmann is the regulation : "Let there be citras on the back of the Smaśana' " "for 'citras' mean offepring" (The commentator takes it as natural scopery ; this is abourd, specially as natural scenery is suggested as an alternative in the following lines). In the case of the stone-built round reliquary the most suitable citras would be sculptured figures in relief. It is interesting to compare the account in the Epic of the representation of the fertility goddess Jara on the palace walls of the king of Girivraja, of a plump woman with children all around.

1716 White Yajurveda, XXX. 15.

- śilpi, 1719 carma-chchhedaka 1720) and (29) Potter (mṛtpaca, 1721 kumbhakāra 1722)
- (c) Priestly occupations—The priestly class who earned their livelihood by officiating in sacrifices, by teaching the sacred lore or in other ways ministering to the spiritual needs of the community came to be divided into the following classes:—(30) the riving or hot;—the leading priest who while the sacrifice was being performed recited hymns of praise in honour of the particular god he was worshipping; (31) the udgāt;—the priest who sang the sāmans or hymns in praise of the Soma plant hypostatised and regarded as god; (32) adhvaryu—the priest who was concerned with the manual acts of sacrificing (33) astrologer (gaṇaka, 1723 nakṣatradarśa 1734), (34) weather-prophet (sakadhūmam), 1723 one who foretells the weather by the way in which smoke rises from a fire of cowdung and (35) physician (bhiṣak 1726 vaidyaka), 1727
- (d) Domestic and Menial occupations—In addition to the above we find the (36) shepherd (avipala), 1728 (37) the cowherd (gopa), 1730 (38) goatherd (ajapīla), 1731 (39) elephant-keeper (hastipa), 1732 (40) horse-keeper (asvapa), 1733 (41) driver of horses, 1734 (42) charioteers, 1735 (43) cook, 1736 (44) servant, 1737 (45) houseguard, 1738 (46) washerman, 1739

```
1710 Rāmāyaņa, Bālakāņda, lāth sarga.
```

<sup>1710</sup> Ibid., Ayodhyākaņda, 83th sarga.

White Yajurveda, XVI. 27; XXX.
7; Maitrāyaņi Samhitā, I. 8. 3;
Maitrāyaņa Brāhmaņa Upanişad,
II. 6; III. 31.

<sup>1722</sup> Ramāyaņa, Ayodhyākānda, 83rd sarga.

<sup>1798</sup> Ibid. Balakanda, 13th sarga

White Yajueveda, XXX 10; XXX 20.

Atharvaveda, VI. 1, 4. Compare
Kauşika Sütra, XXX. 13. Bloomfield in American Journal of Philology, VII. pp. 484-88; WeberOmina et Portenta, p. 363; Zimmer
—Altindisches Leben, p. 353.

Yajurveda, V. 4, 9, 2,

<sup>1757</sup> Rāmāyaņa, Ayodhyākāņda, Sird

<sup>1720</sup> White Yajarveda, XXX. 11.

<sup>1789</sup> lbid.

<sup>1750</sup> Ibid., XVI. 7.

<sup>1781</sup> Ibid., XXX. 11.

<sup>1759</sup> Ibid.

<sup>1728</sup> Ibid.

<sup>1734</sup> Ibid., XVI. 26.

<sup>1785</sup> lbid.

<sup>2756</sup> Rāmāyaņs, Ayodhyākāņis, 80th sarga.

White Yajurveda, XXX. 13.

Grhapa, White Yajurveda, XXX.
11; dvārapa, Ibid., 13; pāyu,
purusa, Ibid., 20.

<sup>1700</sup> Ramāyaņa, Ayodhyākānda, 80th

- (47) washer-woman, 1740 (48) barber (vapt;), 1741 (49) waiter (parivest; paricara), 1742 (50) messenger (pīlāgala) 1745 and (51) bath-attendant (upsekt;) 1744
- (e) Recreationary occupations Besides these there were others who earned their living by amusing the public specially the richer sections of it. Such were the (52) drumbeater<sup>17,6,5</sup> (53) lute-player<sup>17,6,6</sup> (54) flute-blower<sup>17,6,7</sup> (55) musician<sup>17,6,8</sup> (56) public dancer<sup>17,6,9</sup> (57) ministrel (magadha)<sup>17,5,0</sup> (58) actor (nata)<sup>17,5,1</sup> (59) artist (silpi)<sup>17,5,9</sup> (60) painter (citrasilpavid)<sup>17,5,8</sup> (61) artificer<sup>17,5,4</sup> (62) magician<sup>17,5,5</sup> (63) question-solver<sup>17,5,6</sup> (64) jester<sup>17,5,7</sup> (65) keeper of gambling houses (sabhīvin)<sup>17,5,8</sup> (66) pole-dancer or acrobat (vaṃsanartaka)<sup>17,5,9</sup> (67) prize-fighter<sup>17,6,0</sup> and (68) woman who deals in love-charms.<sup>17,0,1</sup>
- (f) Other non-industrial occupations—No less important were the occupations of the following non-industrial groups: (69) hunter (govikartana), 1762 (70) fisherman, 1763 (71) fishvendor, 1764 (72) merchant, 1765

```
1740 White Yajurveda, XXX. 12.
```

<sup>1741</sup> Rigveda, X. 142. 4

<sup>1742</sup> White Yajarveda, XXX. 9.

<sup>1748</sup> Ibid., 13.

<sup>1744</sup> Ibid., 12.

<sup>1740</sup> Ibid., 19.

<sup>1740</sup> Ibid , 19, 20.

<sup>1747</sup> Ibid.

<sup>1745</sup> Ibid., XXX. 20; Rāmāyaņa, Uttarakāṇda, 107th sarga-

yana Brāhmana Upanisad, VII. 8; Rāmāyana, Bālakānda, 13th sarga; Uttarakānda, 107th sarga.

<sup>1750</sup> White Yajurveda, XXX. 5, 22.

Ayodhyākānda, S3rd sarga. Compare: changing dress in a moment like an actior in Maitrāyana Brāhmana Upanişad, IV. 2; VII. 8.

yana, Bālakāṇda, 13th sarga.

Ramayana, Ayodhyakanda, 15th sarga; Uttarakanda, 107th sarga; Kathopanind, II. 6. 5 and 17.

<sup>1754</sup> White Yajurveda, XXX. 7.

abhidhyātar vistritir iva in Maitrāyaņa Brāhmaņa Upanisad, VII. 1; VII. 8.

avac White Yajurveda, XXX. 10.

<sup>1787</sup> Ibid., 20.

<sup>1754</sup> Ibid., 18.

<sup>1750 1</sup>bid., 21.

vII. 8.

<sup>1701</sup> White Ynjurveda, XXX. 9.

<sup>1769</sup> Ibid., XVI. 28; XXX. 7.

<sup>1763</sup> Ibid., XVI. 27; XXX. 8, 16; Chhāndogya Upaniṣad, I. 4. 3.

<sup>1764</sup> White Yajarveda, XXX. 16 .

White Yajurveda, XVI. 19; XXX.
17; Rāmāyaṇa, Ayodhyākāṇda,
83rd sarga.

(73) banker (śresthin), <sup>1768</sup> (74) usurer (kusidia), <sup>1767</sup> (75) wood-ranger, <sup>1768</sup> (76) wood bringer, <sup>1769</sup> (77) forest fire-guard, <sup>1770</sup> (78) boatman (nāvāja), (79) mason, <sup>1771</sup> (80) sudhālepakāra, <sup>1772</sup> (81) bodhakāra, <sup>1778</sup> (82) vastrasīvanakāra, <sup>1774</sup> and (83) śastrajīvi, <sup>1775</sup>

Labour-(a) Free latourers: change in their social status-With the elevation of the princely and priestly classes, the agricultural and industrial population lost the social status they once enjoyed. We have seen that in early Vedic times the rathak Tras as the builders' of his war-chariots were on terms of friendly intimacy with the king. They were, moreover, regarded as the representatives of the Ribhus, those ancient artificers whose wondrous skill obtained for them a place among the gods. 1776 In the Taittiriya Brihmana, however, they appear as a special class along with the vaisyas and have through their devotion to a mechanical art, lost status as compared with ordinary freemen. Similarly, though the physician's skill was highly lauded in the Rigveda the germs of the later dislike for his profession are to be found in the Black Yajurveda. 1777 The position of the vaisyas, the mass of the industrial population also underwent a change, for, in the Aitareya Brahmana they came to be regarded as being tributary to another (anyasya valiket) and their function was to be devoured by the priest and the nobleman.1778 The industrial population, however, tried to improve their position towards the end of this period by organising themselves into guilds.

(b) Slave labour—In this period agricultural work was mostly done, as before, by the freemen of the tribe along with their sons and kinsmen. Gradually, however, there arose various labouring classes recruited from the landless poor or conquered enemies. We have already seen that the

```
1768
     Aitareya Brahmana, III. 30. 3;
                                               2771
                                                      Ramayana, Ayodhyakanda,
                                                                                    80th
       Kauşitaki Brāhmaņa, XXVIII. 6;
                                                      Barga.
       Taittirlya Brahmana, III. 1. 4. 10;
                                               1773
                                                     Ibid., 83rd sarga.
       Kausitaki Upanisad, IV. 20.
                                               1773
                                                     Ibid.
1767 Compare Atharvaveda, VI. 46.3-
                                               1774
                                                     Ibid.
      Rigveda, VIII. 47. 17.
                                               1775
                                                      Ibid.
LTSE
     White Yajarveda, XXX, 19.
                                               3774
                                                     Rigveda, I. 20,
STOD
     Ibid., 12.
                                               1 7 7 7
                                                     Black Yajurvada, VI. 4. 9. 1-2.
1770
     1bid., 19,
                                               STTS
                                                     Airtareya Brühmana, VII 29. 3.
```

Rigveda refers to dīsa's who could be gifted away, 1779 so that they must have been in some sort of bondage. In another hymn of the Rigveda 1780 we are told that King Trasadasya, son of Purukutsa gave its composer fifty vadhū's. As these young women were gifted away they must have been in some sort of bondage. In the Atharvaveda we read of dīsās's husking and pounding the rice 1761 or collecting the alkaline droppings of the cow. 1782 mean a slave; for all non-sacrificers were called dīsā's. 1782 It is also worthy of note that though we have mention of gifts of slaves we have none of slave-markets. This absence of slave-markets may be taken to mean that slaves were never largely employed and that the institution of slavory never attained that importance which it did in Greece or Rome or in the social system of the Semetic countries.

(c) Female Labour—In this period we find a large number of women earning their livelihood by husking and grinding corn<sup>1784</sup>, working as dīsi's, <sup>1785</sup> weaving, <sup>1786</sup> splitting cane, <sup>1787</sup> working in thorns, <sup>1788</sup> doing embroidery work, <sup>1789</sup> dealing in love-charms, <sup>1790</sup> washing <sup>1791</sup> and dying clothes <sup>1792</sup> and making scabbards <sup>1793</sup> and ointments. <sup>1794</sup> An interesting refrence to the position of women with regard to agriculture is to be found in the Taittiriya <sup>1795</sup> and and Satapatha Brah-

<sup>1710</sup> See ante, fn. No. 592.

<sup>1780</sup> VIII, 19, 36.

<sup>1781</sup> Atharvaveds, XII. 3, 13.

<sup>1789</sup> Ibid., XII. 4. 9.

Rigveda, V. 34. 6; X. 85. 19. The Yedns and Torvaias were Aryan tribes but as they second from the Vedic faith they had been described as Dasa kings (Rigveda, X. 62. 10) Brhadratha and Navavastva became favourities of Agni by their performance of sacrifices (Rigveda, I. 36. 8) but both were afterwards killed by Indre, probably because of their subsequent hetrodoxy and were called dasas (Rigveda, X. 49. 6).

<sup>1784</sup> Atharvaveds, XII. 3, 13,

<sup>1785</sup> Ibid., XII. 3. 13; XII. 4, 9; V, 22. 6,

Pafichavinsa Brāhmaņa, I. 8. 9. Compare Satapatha Brāhmaņa, III. 1. 2. 13ff.

<sup>1787</sup> White Yajurveda, XXX. S.

<sup>1785</sup> Ibid.

<sup>1750</sup> Ibid, 9.

<sup>1700</sup> Ibid. 1700 Ibid., 12.

<sup>1702</sup> Ibid.

<sup>1705</sup> Ibid., 14.

<sup>1794</sup> Ibid.

<sup>1706</sup> III. 3. 10. In the Päraskara Gthyasütra II. 17. 18 we are told that 'women should make accompanying oblations [in the sacrifice to the rustic deity of the furrow (sita)] because such is the custom.'

manas<sup>1798</sup> where we are told that in the harvest-offering ritual "as a rule the wife of the sacrificer was present, with hands joined to her husband." This participation of women can be explained by the fact that in primitive times the duties of agriculture lay, for the most part, in the hands of women. The fact tracing the historical development of this portion of the sacrifice. Jevons remarks: "It is, therefore, an easy guess that the cultivation of plants was one of women's contributions to civilisation and it is in harmony with this conjecture that the cereal duties are usually both in the Old World as in the New, female." Agriculture, however, when its benefits became thoroughly understood, was not allowed among civilised races to continue to be the exclusive prerogative of women and the Corn goddess, maiden or mother, had to admit within the circle of her worshippers, the men as well as the women of the tribe.

Caste system in relation to mobility of labour—In this period, the caste-system was getting stereotyped. Besides the priesthood and the nobility there comes into existence a new factor, the introduction of divisions among the ordinary freemen—the Vaisyas. In this development, there must have been two main influences—the force of occupation and the influence of the aborigines. We have already seen how in the Taittiriya Brahmana the charictmakers, the type of skilled workers in the Rigveds, have through their devotion to a mechanical art, lost status as compared with ordinary freemen. Similarly, in the Rigveda the healing art is highly lauded and the Aswins, the divine physicians are repeatedly invoked; but by the time of the Black Yajurveda, the physician lost his previous high position, for, we read "The gods said of these two (the Aswins): impure are they, wandering among men and physicians. Therefore a brahmana should not

were sacrificed, thence to the substitution of various animals as they became domesticated ending with the offering of fruits of the earth, when agriculture became widely known, is set forth as a recognised fact in the Aitarera Brühmaga,

<sup>1704</sup> IL 5, 2, 20.

Jevons—Introduction to the History of Religion, pp. 240—41.

<sup>2700</sup> The gradual transition from the early encrifice of human beings to the stage in which horses tended by man during the pasteral stage

practice medicine, for the physician is impure, unfit for the sacrifice". 1799 Moreover, contact with the aborigines 1800 must have raised questions of purity of blood very much like those which at present agitate the southern states of the U.S.A. or the White people in South Africa.

In deciding the question how far the caste system stood as a barrier against the mobility of labour and the people were tied down to the rigidity of a social system in which hereditary occupation was alloted to its members it is necessary that we should divest our mind of prejudices and guard ourselves against associating modern ideas with the old state of things. We are accustomed to say that the brihmanas alone could be priests, they alone could teach the Velas, whereas we have evidences which tend to prove that at least in the earliest times they alone were brihmanas who possessed a knowledge of the Vedas and could perform the function of a priest. Rules were indeed laid down that no body should serve as a priest who could not prove his descent from three (according to Kauşitaki Sütra) or ten (according to Latynyana Sütra) generations of rei's. But these very rules prove indirectly that the unbroken descent in a brāhmaṇa line was yet an ideal and not an actuality.

We have, however, not to depend upon negative proof alone to establish our thesis. Authentic ancient texts repeatedly declare that it is knowledge and not descent, that makes a brahmana. In the Black Yajurveda we read "Eṣa, vai brahmana ṛṣirārṣeyo yaḥ śusravan." (VI. 6.1.4) "He who has learning is the brahmana ṛṣi." Again, we have in the Kāṭhaka (XXX. I) and Maitrāyanī (XLVIII. 1; CVII. 9) Saṃhitās: "Kim brāhmanasya pitaram kiṃ tu pṛchchhasi mātaram." The Paūchaviṃśa Brāhmana 1801 speaks of certain persons as royal seers and the later tradition preserved in the Anukramani or Index to the composers of the Rigveda ascribes hymns to such royal seers. The hymns No. 30-34 of the tenth maṇḍala of the Rigveda were composed by Kavasha, son of Illusha, a low caste woman. In fact, the Aitareya Brāhmaṇa 1802 refers to his acceptance

<sup>1700</sup> Black Yajarveds, VI. 4. 9. 1-2.

<sup>1801</sup> XII. 12. 6.

<sup>1800</sup> Compare the case of Kavasha.

as a rsi for purity, learning and wisdom. The Satapatha Brahmana 1 a 0 3 refers to royal seers like Viśwamitra, Devapi and Janaka. Viśwamitra, the Purohita of King Sudas is described in the Panchavimsa and Aitareya Brāhmaņas as of royal descent, of the family of the Jahnus. Yāska 1804 represents a prince named Devapi sacrificing for his brother Santanu, the king. Similarly, king Viswantara sacrifices without the help of priests in the Aitareya Brāhmana. The Upanisads tell us of kings like Janaka of Videha, 1805 Aswapati, king of the Kekayas in the Punjab, 1806 Ajātasatru of Kāśi,1802 and Pravahana Jabāla of Panchāla1808 disputing with and instructing brahmins in the lore of the Brahma. The Chhandogya Upanisad 1809 tells us how a brahmin imparts knowledge to a sudra accepting presents and taking his daughter for his wife. The Jaiminiya Upanisal speaks of a king becoming a seer. Another case of interest is that of Satyakama Javala who was accepted as a pupil by a distinguished priest, because he showed promise, although he could not tell of his ancestry. 1810 Javala, it may be noted, became the founder of a school of the Yajurveda. In the Rāmāyana 1811 a brahmin is seen earning his livelihood by ploughing with no stigma attached to his action. Moreover, who was Vālmiki, the author of the Rāmāyana itself, but a sūdra?

Craft-guilds—The question now presents itself whether there existed in this period industrial combinations called craft-guilds. Geldner and Roth find references to them in the Brāhmaņas but there are other Vedic scholars who hold the opposite view. No doubt, considered by themselves merely as literary passages, these references seem to be doubtful indications of a formal and well-defined institution; but if we combine with the literary evidence, the evidence of history, the evidence furnished by the evolution of Aryan life, much of the uncertainty of the purely literary evidences will disappear. No doubt guild-life belongs to a consider-

<sup>200</sup> XI. 6, 2, 1,

<sup>1804</sup> II. 10.

<sup>1805</sup> Satapatha Brahmapa, XI. 6, 2, 1,

<sup>1000</sup> Ibid., X. 6. 11; Chhandogya Upaniand, V. 11.

<sup>1807</sup> Brhadaranyakopanisad, H. 1; Kaŭsitaki Upanisad, IV. 1.

V. 3. 1ff; Brhadarunyakopaniyad, VI. 2, 1ff.

<sup>1800</sup> IV. 2.

<sup>1010</sup> Chhandegya Upanisad, V. 4.

<sup>1911</sup> Ayodhyākānda, 32nd sarga.

ably advanced stage of economic progress in which individual mechanics, artisans and traders have sufficient business instinct developed in them and have achieved sufficient success in their respective businesses to appreciate the necessity of organising themselves into a community for the purpose of promoting their individual and collective interest. But we have already seen the enormous extent to which the differentiation of of economic occupations was carried on and the remarkable progress which the arts and crafts achieved in this period. And this will lead any sober and unbiassed historian to the conclusion that those scholars who choose to find in certain passages of the Brahmanas proofs of the existence of guilds cannot very well be considered as guilty of making any extravagant claim and taking up an untenable position.

Let us now proceed to the passages themselves. In the White Yajurveda1619 we have the word gana besides ganapati, which means the headman of a gana. Gana in later Sanskrit always means a guild or corporate union. In the Brhadaranyaka Upanisad 1813 we read "Sa naib vybhavata. Sa višamasrjata yanyetāni devajītāni ganašah ākhyāyante." Commentator Šankarācārya says: - "Kshātrasīstopi sa naiva vyābhavat karmane brahma tayā vyābhavat vittopārjjanyiturabhāvāt. Sa višamasrjata kārmasādhanavittopārijanāva. Kah punarasou bit? Yānyetāni devajātāni, nişthī ya ete devajātibhedā ityarthah gaņasa gaņam gaņam ākhyāyante kathyante ganaprāyā hi višah. Prāyena samhatya hi vittopārjjanasamarthāh naikaikasah" Thus the gods of the Vaisya class were called ganasah on the analogy of their human prototype because they could earn money evidently by industry and trade, not by their individual efforts but in a corporate body. We have also certain passages which contain the word śresthin,1814 meaning according to Hopkins a modern seth (banker) or more probably, according to Macdonell, the headman of a guild. 1815 Metaphorical and indirect allusions to gana and śresthi made in order to explain obstruse philosophical subjects show that they were already well-known existences within the

<sup>1519</sup> XXIII 19. 1.

<sup>\*\*\*\* 1, 4, 12,

\*\*\*\*\*</sup> Kauşitaki Brāhmaņa, XXVIII. 6;

Aitareya Brāhmaṇa, III. 39, 3;

Kauşitaki Upanişad, IV. 20.

<sup>(</sup>III. 1. 4. 10) Bhaga was the Sreyth
of the gods.

range of common observation and the allusions are warranted on the logical principle of arguing from the known to the unknown, of explaining the unfamiliar and the abstract from the familiar and the concrete. This is further corroborated by the Rīmāyāṇa 1816 where we are told that in the procession of citizens who accompanied Bharata in his quest of Rīma figured merchants, jewellers, potters carpenters, goldsmiths, physicians, wine-listillers, tailors etc., so that the Rīmīyaṇa recognises the position held by trades and crafts in society.

Domestic and Foreign trade-The striking development of industrial life and the consequent sub-division of occupations made self-supporting life an impossibility and gave greater scope to the interchange of the products of agriculture and industry. Unfortunately from the evidences at our disposal we can gather very meagre information about the interchange of commodities of various localities. The Atharvaveda describes the guggula (bdellium) as "produced from Sindhu" or coming from the sea; 1517 Varana, a plant used in medicine and supposed to possess magical powers is described as Varanavatyam, 1818 growing on the banks of Varanavati lake or river and bartered for coverings (pavasta), skins of goats ajina) and woven cloths (dūrša).1819 Horses are described in the Satapatha Brāhmana and the Brhadaranyaka Upanisad 1530 as "coming from the Indus regions" (Saindhava). Salt is similarly described as "coming from the Indus" in the Brhadaranyka Upanisad. 1821 From the Ramiyana we learn that Kamboja, Bahllika and Sind were famous for horses 1822 and that elephants of the Himalayan and Vindhyan regions were famous for their large size and great strength. 1828 The excess production as well as excellence of production of particular localities induced energetic men to carry them to other places where these could be disposed of with profit. Such men were called the Vanij1824 or merchant, who in a hymn of the Atharvaveda

<sup>1616</sup> Ayodhyākāpda, 53rd sarga.

<sup>1817</sup> Atharvayeda, XIX. 38, 2.

<sup>1010</sup> Ibid., IV. 7. 6.

<sup>1818</sup> XI. 5. 5. 12.

<sup>15 80</sup> VL 1. 13.

Upanisad, VI. 13. 1-2.

<sup>1002</sup> Balakanda, 6th sarga.

pean Ibid.

Taittiriya Brahmana, III. 4, 14, 1.

is made to speak of "the distant pathway which his feet have trodden" and to address the gods in the following strain :--

"I stir and animate the merchant Indra; may he approach and be our guide and leader Chasing ill-will, wild beast, and highway robber, may be who hath the power give me riches.

Propitious unto us be sale and bater, may
interchange of merchandise enrich me;
Accept ye twain (Agni and Indra) accordant, this
libation! Prosperous be our ventures and incomings.
The wealth wherewith I carry on my traffic, seeking,
ye gods! wealth with the wealth I offer,
May this grow more for me, not less: O Agni,
through sacrifice chase those who hinder profit."

For the conduct of this trade there were roads and travellers' resthouses. The Atharvaveda refers not only to the parirathyā<sup>18</sup> or road suitable for chariots but also to well-made cart-roads on a higher level than adjoining fields, forests and other village tracks with great trees planted beside, passing through villages or towns and with occasional pairs of pillars (i. e., gateways, evidently near the approaches of some town) through which bridal processions pass. <sup>1827</sup> Every tirtha along the bridal route is said to be well-provided with drink, so that it must have been a rest-house like the prapatha's of the Rigveda. <sup>1828</sup> Indeed travelling seems to have been quite common in those days. The Atharvaveda has charms to ensure a prosperous journey <sup>1829</sup> and gives us the parting traveller's address to the houses of his village. <sup>1830</sup> Villages are sometimes described as connected with mahāpathas or high roads <sup>1831</sup> and

<sup>1005</sup> III. 15.

<sup>1820</sup> Atharvayeda, VIII. 8, 22,

<sup>1027</sup> Ibid., XIV. 1. 63; XIV. 2. 6, 8, 8, 9,

<sup>1919</sup> I. 166, 9.

<sup>1890</sup> Atharvaveda, VII. 55.

<sup>1000</sup> Ibid., VIE. 60.

Chhandogya, Upaniyad, VIII. 6, 2.

causeways (badvan) firmer than an ordinary road are known. 1832 Setu meaning a raised bank for crossing inundated land frequently occurs in the literature of this period. 1832

Scholars are, however, divided in their opinion as whether this trade was carried on across the seas to foreign lands. Professor Keith observes "There is still no hint of sea-borne commerce or of more than river navigation, though we need not suppose that the sea was unknown, at least by hearsay, to the end of the period." But, as a matter of fact, we find distinct references to sea and to sea-voyages and at least indirect proof of sea-borne commerce in this perid. That the sea was widely known will be evident from the use of the sea by way of simile in the following:—

"Whatever I eat I swallow up, even as the sea that swallows all." 1835 "Raise thyself up like heaven on high and be exhaustless as the sea." 1836

That the sea is not the Indus in flood will be evident from the existence of three seas 1837 and from the fact that in a passage of the Atharvaveda Varuna's throat evidently means the sea into which the seven rivers flow:

"Thou, Varuna, to whom belong the Seven Streams, art a glorious god.

The waters flow into thy throat as 'twere a pipe with ample mouth' 1858

That the evaporation of sea-water went to form the clouds is clearly stated in the following verse: "Udirayata marutah samudra stveşo arko navah utpātayātha." "Up from the sea lift your dread might, ye Maruts as

Paŭchavinsa Brāhmapa, I. 1. 4.
Black Yajurveda, III. 2. 2. 1; VI. 1.
4. 9; VI. 5. 3. 3; VII. 5. 8. 5;
Kāthaka Samhitā, XXVII. 4;
Aitareya Brāhmapa, III. Ib; Satapatha Brāhmapa, XIII. 2. 10. 1;
Taittirlya Brāhmapa, II. 4. 2. 6;

Chhandogya Upanyad, VIII. 4, 1, 2; Bihadaranyaka Upanisad, IV. 4, 4.

Cambridge History of India, p. 136.

<sup>1808</sup> Ibid., VI. 135. 3. Compare VI. 135. 2.
1824 Ibid., VI. 143. 2.

<sup>1857</sup> Atharvayeda, XIX. 27. 4.

<sup>1838</sup> Ibid , XX. 92. 9.

light and splendeur, send the vapour upward !"1859 The White Yajurveda also refers to the sea: "Samudram gachehba svāhā, antarīkṣam gachchha svāhā, daivam savitaram gachchha svāhā."1840 "Go to the sea. Ail hail! Go to the air. All hail! Go to god Savitar. All hail!" In the Satapatha Brihmana we are told how Manu, the Indian Noah had directed to build a strong ship for carrying him safe from the floods which were prophesied by the Fish of the Fish-legend and how when the requisite ship was built, Manu was taken safe to the mountain. 1481 A string of words connected with navigation equally lends support to the view that extensive navigation existed in this period. Thus we have (1) aritram-This means an oar and we find ships propelled by one hundred oars: "Sunāvamāruheyamasravantīmanāgasam. Šatāritrāŭ svastaye". 1842 "May I ascend the goodly ship, free from defect, that leaketh not, moved by a hundred cars, for weal"; (2) arity-rower of a ship : "eyatirvacamariteva nāvam"; 1843 (3) nāvaprabhramśanam—the sliding down of the ship; 1844 (4) nau-manda-rudder of a ship. The Satapatha Brahmana refers to big ships having two rudders each; 1845 (5) nāvāja—pilot, boatman. 1848

There are also passages which indicate that sea-voyages were undertaken in this period. Thus in the Rāmāyaṇa, Sugrīva asks his followers to go the cities and mountains in the islands of the sea in search of Sītā. 1847 In another passage they are asked to go to the land of the koṣakāras 1848 (the land where grows the worm which yields the thread of silken cloth), generally

7. 16

<sup>1830</sup> Ibid., IV. 15. A.

<sup>1840</sup> White Yajarveds, VI. 21.

<sup>1842</sup> Satapatha Brabmana, I. S. 1. 1-10.

<sup>1849</sup> White Yajurveda. XXVII. 7.

<sup>1848</sup> Rigyeda, II. 42. 1.

Atharvaveds, XIX. 39. 8. This seems to be connected with manoravesarpanam in the Satapatha Brahmana, I. 8, 1, 6,

<sup>1845</sup> II. 3. 3, 15.

<sup>1844</sup> Ibid., II. 3. 3, 5.

<sup>1847</sup> Samudramavagādhāmicha parvatān pattanāni cha — Kişkindhyākānda, 40th sarga.

<sup>2849</sup> Bhūmišcha koşakārāņā o in Kişkindhyākānda, 40th sarga.

identified with China. In a third passage they are asked to go to Yava-dvipa<sup>1849</sup> and Suvarnadvipa: <sup>1850</sup> "Yatnavanto Yavadvipam saptarājyo-pasobhitam. Suvarnarupyakadvipam suvarnakarmanditam." <sup>1851</sup> In a fourth passage they are asked to go as far west as the Red sea: "Tato raktajalam bhīmam Lohitam nāma sāgaram". <sup>1852</sup> Lastly, we have a passage which hints at preparations for a naval fight thus indicating a through knowledge and a universal use of the waterway: "Nīvām śatānām panchānām Kaivartānām śatam satam. Sannaddhānām tathā yūnām tisthanttvitya bhyachodayat." <sup>1859</sup> "Let hundred of Kaivarta young men lie in wait in five hundred ships (to obstruct the enemy passages)".

The chief article of trade with China hinted in the Ramayana 1854 was silk. Mr. J. Yeats in his Growth and Vicissitudes of Commerce observes "The manufacture of silk among the Chinese claims a high antiquity, native authorities tracing it as a national industry for a period of 5000 years." This intercourse with China is corroborated by Professor La Couperie in his Western Origin of Chinese Civilisation which refers to the maritime intercourse of India with China as dating from about 680 B. C. when the sea-traders of the Indian Ocean founded a colony called Langga (after the Indian name Lanka or Ceylon) about the present Gulf of Kiao-tchoa.

According to Professor Keith "sea-borne commerce with Babylon cannot be proved for this epoch." The Baveru Jataka, however, relates the adventures of certain Indian merchants who took peacocks by sea to Babylon. No doubt the Jataka goes back only to 400 B. C. but the folk-tale on which it is based must be much earlier. Moreover, we

naud interprets Yavadvipa and Suvarpadvipa to mean the Islands of Java and Sumatra (vide Journal Asiatique, IV., p. 265).

Ptolemy has evidently adopted the name Jävä for the Sanskrit yavadvips, the former being a Greek equivalent of the Ister; while modern writers like Humboldt, call it the Barley Island.

Hindus call the Islands of the Malaya Archipelago by the general name of Savarya Island. M. Roi-

kiskindhyakanda, 40th sarga,

<sup>1884</sup> Appel

Ayodhyākānda, 84th sarga. Kişkindhyākānda, 40th sarga.

Cambridge History of India, p. 144,

have already seen that Mr. H. Rassam found a beam of Indian cedar in the palace of Nabuchadnezzar III. (580 B. C.) at Birs Nimrud; and of Indian teak in the temple of the moon-god at Ur refounded by Nebonidus. According to Mr. Hewitt this wood must have been sent by sea from some sea-port on the Malabar coast, for, it is only there that teak grew near enough to the sea, to be exported with profit in those early days. 1856 Further, Baudhāyana's condemnation of the Northern Aryans who took part in the sea-trade proves that they were not the chief agents though they had a considerable share in it. In the words of Mr. Kennedy "Maritime commerce between India and Babylon flourished in the 7th and 6th but more specially in the 6th century B. C. It was chiefly in the hands of the Dravidians, although Aryans had a share in it. And as Indian traders settled afterwards in Arabia and on the coast of Africa and as we find them settling at this very time on the coast of China, we cannot doubt that they had their settlements in Babylon also," 1837

Indeed there are circumstantial evidences which go to prove that there existed some sort of intercourse between India on the one hand and Babylon, Assyria, Judæa and Persia on the other. Mr. Keith observes "It is indeed probable enough that even before the time of Darius, Cyrus of Persia had relations with tribes on the right bank of the Indus and Arrian 1859 asserts that the Assakenoi and the Astakenoi were subject to Assyrian kings." 1859 Dr. Wincler has pointed out that Shalmanesar IV. of Assyria (727—722 B. C.) received presents from Bactria and India, specially Bactrian camels and Indian elephants. In the Historians' History of the World we are told "The pictures on the black obelisk of Shalmanesar shows us such beasts as apes and elephants being brought as tributes to the conquerers or confirming in the most unequivocal way the belief based on Ktesias and Strabo that the Assyrians had commercial relations with India......The first article which we may confidently assert the Babylonians to have obtained at least in part from these countries were precious stones,

Journal of the Royal Asiatic Society, 1888., p. 337.

Kennedy—Early commerce between India and Babylon in J. R. A. S. 1898.

p. 179).

<sup>1888</sup> Cambridge History of India.

the use of which in seal-rings was very general among them. Ktesias says expressly that these came from India and that onyxes, sardines and the other stones used for scals were obtained in the mountains bordering on the sandy desert ..... The passage of Ktesias to which we have just referred contains some indications which relatively to onyxes appear to refer to the Ghat moutains, since he speaks of a hot country, not far from the sea. The circumstance of large quantities of onyxes coming out of these mountains at the present day, viz., the mountains near Cambay and Broach (the ancient Barygaza) must render this opinion so much the more probable as it was this very part of the Indian coast with which the ancients were most acquainted ..... Also the Babylonians imported Indian dogs. The native country of these animals according to Ktesias was that whence the precious stones were obtained. And this account of the regions has been confirmed by Marco Polo who mentions that the large dogs of these regions were even able to overcome lions. A third and a no less certain class of productions which the Persians and the Babylomians obtained from this part of the world were dyes and amongst them the Cochineal or rather Indian laksa. The most ancient though not quite accurate description of this insect is also found in Ktesias."1860

Weights and Measures—The development of trade facilitated the growth of weights and measures. The tūlā or balance is mentioned in the White Yajurveda<sup>1861</sup> and in the Satapatha Brāhmaṇa. Wooden vessels of definite size<sup>1863</sup> called ūrdara were used in measuring grains. Standards of weight were also invented. Thus the kṛṣṇala (berry of abrus precatorius) and māsa and some other grains were used as standards of weight in measuring precious metals. <sup>1863</sup>

Methods and Media of Exchange—In this period there was not only simple barter, proved by the evidence of words like prapana (barter) and pratipana (exchange of merchandise) 1868 but the use of gold as well as silver money. We have already seen that the niska of the Rigveda was

Vol. 1., pp. 484-90.

<sup>1941</sup> XXX 17.

Vol. I., p. 185.

<sup>1000</sup> Atharvaveda, III. 15, 4; IV. 7, 6,

not a mere metallic standard but a coin. The use of these niskas was also known in this period. The word occurs in many passages of the Atharvaveda 1864 and the Aitareya Brahmana 1865 describes a man as niskakantha, wearing a necklace of niska coins. The Panchavinsa Brahmana 1866 refers to silver niska worn by a Vratya chief.

A different kind of currency called satamana was known in this period. Reference to it occurs not only in the Taittiriya1887 and Kathaka Samhitas1868 but also in the Taittiriya1869 and Satapatha Brahmanas; so that it seems to have been widely used as a metallic standard at least in those regions where the Taittiriya Samhitā and the Satapatha Brāhmana were composed. It is interesting to note that the passage in the Taittiriya Brāhmana I. 7. 6. 2 occurs also in the Taittiriya Samhita1870 thus proving that satamana was provalent not only when the Brahmagas were written but also in the early period when the Samhita was composed. In Kanda V of the Satapatha Brahmana 1871 dealing with the Rajasuya, we have a section which treats of the Ratha-vimochaniya oblations; and in connection therewith, we are told that behind the right hind-wheel of the cart-stand, the king fastens two round sataminas which he has afterwards to give to the brahmin priest as his fee for this ceremony. In another passage of the Satapatha Brihmana 1879 we read: "Three sataminas are the sacrificial fee for this (offering) which he presents to the brahmin; for, the brahmin neither performs (like the adhyarya) nor chants (like the udgate) nor recites (like the hot;) and yet he is an object of worship: therefore he presents to the brahmin three satamanas. Many other passages of the Satapatha Brahmana 1873 contain this reference to the satamana which was given as fee to the officiating priest in the sacrifice. No doubt Sayana takes satamana to denote a round plate but the case is not unlike that of Nagojibhatta who commenting on a celebrated passage in the Mahabhasya has explained the Mauryas as idol-manufacturers. But just as no scholar

<sup>1004</sup> V. 14, 3; V. 17, 14; XX, 131, 8.

<sup>1888</sup> VIII. 23.

<sup>1044</sup> XVII 1, 14.

<sup>1007</sup> II. 3. 11. 5; III. 2. 6. 3.

<sup>1808</sup> XL S.

<sup>1888</sup> I. 2. 7. 7; I. 7. 6. 2.

<sup>11. 3, 11. 5;</sup> III. 2. 6. 3.

<sup>1071</sup> V. 4, 8, 24, 25,

<sup>1 1679</sup> V. 5. 5. 16.

<sup>1878</sup> XII. 7, 2. 3; XIII. 2. 3. 2.

would now explain the Mauryas as idol-manufacturers but take them to denote Maurya princes only, so no one can explain the term Satamāna in the way in which Sāyana has done. Satamana may, however, have been 100 mānas or gunja-berries in weight as explained by Sāyana and accepted by Professor Eggeling and as it is spoken of as vṛtta<sup>1874</sup> it must have been round in shape.

Another class of matallic standard has been mentioned in the Satapatha Brīhmaņa side by side with the satamāna. Thus we read: "Suvarņam hiraņyam bhavati rūpasya eva ābbaruddhai satamānam bhavati satāyurbhai puruṣa." Hīraṇyam dakṣhinā, suvarṇam satamānam tasya oktam." In both the above passages suvarṇa is associated with satamīna and both are called hirnya or gold; so that suvarṇa like satamīna denotes a matallic standard, evidently of gold.

Another class of metallic standard called pada is mentioned in the concluding kanda of the Satapatha Brahmana where we are told that king Janaka of Videha celebrated a sacrifice in which he bestowed huge largesses upon brahmins of the Kuru-Pauchala country. A curiosity sprang up in his mind as to who was the best read of these brahmins. He collected a thousand kine and we are told that to every single horn of each cow were tied ten padas and it was proclaimed that they should be taken away by him alone who is best cognisant with Brahman. Now what were these padas? It has been suggested by Bohtlingh and Roth and accepted by Professor Rhys Davids 1877 that the word pada here denotes the fourth part of a certain gold weight and not a metallic standard. Are we then to suppose that as the cows were one thousand in number, as each cow had two horns and as each horn carried ten padas, king Janaka ordered twenty thousand pieces of gold to be hammered out, each again weighing just one-fourth of a certain weight -all this just on the spur of the moment, when the idea of testing the erudition of brahmins occurred to him? This idea, we are afraid, is too ridiculous for any scholar to entertain seriously in his mind. On the other hand, pada is known to be the name

<sup>1010</sup> Satapatha Brahmapa, V. 4. 3. 24.

<sup>1878</sup> Ibid., XII. 7. 2. 3.

<sup>1070</sup> Ibid., XIII. 2, 3, 2.

Ancient Coins and Measures of Ceylon, p. 3 n. 2.

of a metallic standard and has been referred to in Pāṇini's Sūtras<sup>1878</sup> and also in an inscription of the tenth century A. D.<sup>1879</sup> Only if pāda is taken to stand for a metallic standard, it is easy to understand that Janaka could at any moment get hold of twenty thousand such pādas from his treasury for being tied to the horns of the cows.<sup>1880</sup>

There is still another class of metallic standard referred to in the Taittiriya Brāhmaṇa<sup>183</sup> called kṛṣṇāla where we are told of a gift of kṛṣṇāla to each racer. Kṛṣṇāla denotes the well-known raktikā or gunjaberry and what kṛṣṇāla here means is a metallic standard possibly of gold weighing one gunjaberry. This receives confirmation from the fact that the Kāṭhaka Saṃhitā<sup>1832</sup> makes mention of hīraṇya kṛṣḥnāla or gold kṛṣṇāla. In fact kṛṣṇāla continued to serve as a metallic standard as late as the age of the Manusaṃhitā. <sup>1883</sup>

The general economic condition of the masses and classes—By the time the Brahmanas were composed the whole fertile plain of Northern India was appropriated and colonised by the Aryans. Agriculture became the principal occupation though cattle-rearing was not altogether neglected. Thrice a day the cows were driven out to graze 1884 and they were milched thrice 1885 as milk was required thrice daily for pouring libations into the sacred Household Fire. Villages were established in the midst of the conquered country—the conquered being pushed back to the hills or allowed to live on conditions of submission, service or tribute. These villages "were scattered over the country some close together, some far apart and were connected by roads." 1886

(1) The dwelling of the ordinary householder—Each village contained a number of families, each possessing its own separate dwelling. In the comparatively 1887 drier and hotter Upper Gangetic regions the entrance and

<sup>1010</sup> V. 1, 34.

<sup>1070</sup> Epigraphia Indica, I. 173. 23 and 178. 11.

The same story also occurs in the Brhadaranyakopanisad, III. 1. Iff.

<sup>1881</sup> L. 3. 6. 7.

<sup>1889</sup> XI. 4.

<sup>1000</sup> VIII. 215, 830; IX. 84; XI. 137.

<sup>1804</sup> Taittiriya Brahmapa, I. 4. 9. 2.

<sup>1005</sup> Black Yajurveda, VII. 5. 3, 1.

Vol. I, p. 211.

Compare the sense of enclosure in 'vraja' and 'vrjana.'

enclosure aspects of the dwelling house must naturally have been more prominent and the references to these features and their figurative use accordingly, occur in texts like the Rigveda which were mainly of Midlandie origin. With the march of Aryan arms into the rain-flooded Lower Gangetic valley the roof naturally had to be built carefully and we therefore find much care bestowed on the construction of the thatched roof in the house-construction outlined in the Atharvaveda 1868 which is preeminently a book of the Angirasas, who are definitely located in and associated with the very same Lower Gangetic provinces in Pauranic tradition. In every house guests were welcomed and attended to in the avasathateso which seems to be a structure of some sort for the reception of guests on the occasion of feasts and sacrifices and afterwards came to be used in in its literal sense of an abode for the first time in the Aitareya Upanisad. 1890 Every Vedic householder's house was supposed to have its own presiding Deity and his favour was constantly sought. The householder's warm attachment his sweet home will be evident from the parting traveller's address to the houses of his village :

"These houses we invoke, whereon the distant exile sets his thought Wherein dwells many a friendly heart: Let them be aware of our approach.

Full of refreshment, full of charms, of laughter and felicity
Be ever free from hunger, free from thirst! Ye houses fear us not
Try here and come not after me, prosper in every form and shape
With happy fortune will I come Grow more abundant still through me."1891

(2) Domestic furniture and utensils—The ordinary Vedic house-holder possessed wooden furniture like the pitha, talpa and prostha while the comparatively well-to-do people used the more comfortable bahya, asandi and the paryanka as well. 1892 Among the domestic utensils we find earthen

<sup>1688</sup> III. 12; IX. 3.

brahmins; Taittiriya Brahmana)

1. 1. 10. 6; HI, 7. 4. 6; Satapatha

Brāhmaņa, XII, 4, 4, 6; Chhāndogya? Upaniyad, IV. 1, 1.

<sup>1 190</sup> III 19

<sup>1892</sup> Atharvaveda, VII. 60. 3, 6 and 7

<sup>1892</sup> See ante, pages 137-38.

eooking pots (ukhā)<sup>1893</sup>, earthen pots like sthāli,<sup>1894</sup> kumbhi<sup>1895</sup> and karambhi,<sup>1896</sup> liquor-pots<sup>1897</sup> and āsecana [vessel to hold liquids such as meat-juice (yuṣān)]<sup>1898</sup>; skin bags for holding milk and other liquids;<sup>1899</sup> winnowing basket (sūrpa),<sup>1900</sup> wooden Soma tubs called drona-kalasa, <sup>1901</sup> wooden cups,<sup>1902</sup> wooden mortar and pestle for pounding rice<sup>1903</sup> and for extracting soma juice,<sup>1904</sup> fire-shovel or poker made of palāša wood<sup>1905</sup>, wooden stirring prong,<sup>1906</sup> fork,<sup>1907</sup> and ladles of various kinds—the Sruva, Sruc, Dhruva, Juhu and Upabhṛt—already described.<sup>1908</sup> The Rāmāyaṇa also refers to the use of boxes (peṭakas)<sup>1909</sup> and iron trunks (louha-mañjuṣā).<sup>1910</sup>

(3) The food of the people—The food consisted of various preparations of barley, wheat and rice and other food grains and cereals; flesh of of animals like goat, sheep, deer, buffaloe and ox, fruit, honey and various preparations of milk.

Barley, wheat and rice were often powdered or boiled and made into various kinds of bread or cakes along with milk and other ingredients. Of such the pists, purodāša, apūpa and pakti were important. Rice was often boiled in milk to form kṣiraudana which was highly valued as food. Brāhmaudana was offered in the sacrifices. 1911 Other kinds of mess called

Yajarveda, XI. 59; Black Yajarveda, IV. L. 5, 4.

Rāmāyana, Ayodhyākānda, 91st

1000 Ibid.

sees Thid.

1887 Ibid., Il4th sarga.

1000 Rigveds, I, 162. I3.

Panchavinsa Brahmana, XIV. 11. 26; XVI. 13. 13. Cf. Black Yajurveda, I. 8. 19.

1900 Athnevavada, IX. 6, 16.

White Yajurveda, VII. 19; VIII. 12; XIX. 27; Black Yajurveda, III. 1. 6. 1. White Yajurveda, VIII. 33; XIX. 27; XIX. 33; Brhadarapyaka Upanisad, VI. 3. 1; VI. 3. 13.

1008 Atharvaveda, XII. 15.

1004 White Yajurveda, L 14-15; XIII. 33.

1000 White Yajurveda, I. 17.

1 as Atharvaveda, IX. 6. 17.

1sor Ibid.

100 Soe ante, p. 136.

Rāmāyaņa, Ayodhyākāņda, 36th and 37th sargas.

1910 Ibid., Bālakāņda, 67th sarga.

Atharvaveda, IV. 35, 7; XI, 1, 1; Black Yajurveda, III. 4, 8, 7, dadhyaudana, ghṛtaudana, māṃsaudana, mudgaudana, tilaudana and Udaudana were also known and used as food. Of fried grains we find mention of saktu, praivāpa and lāja.

The people seem to have been fond of meat-eating. In the Aitareva Brahmana 1912 there is a passage which distinctly says that when the king or a respected person comes as a guest one should kill a bull or an old barren cow (vehat) for his entertainment. In the Satapatha Brihmana 1913 the slaving of a great ox (mahoksa) or a great goat (mahaja) for the entertainment of a distinguished guest has been enjoined. The great sage Yajnavalkya also expresses a similar view. 1914 He was "wont to eat the meat of milch cows and bullocks (dehnvanaduha) if only it was firm or tender (amsala)."1918 We have already seen 1916 that the flesh of the sacrificed bull and the buffaloes was taken besides the flesh of the goat 1917 and the sheep. 1918 The flesh of hunted animals like krenasara 1919 and varāha1920 and of birds was also taken. The Rāmāyana1921 besides referring to the use of dried meat as food, also gives us a graphic account of the dainty dishes prepared in Ravana's kitchen containing boar's flesh prepared with curds and salt, salyapakva flesh of the deer, flesh of buffalo, cock, peacock, hare, and various kinds of krkala.1922 Meat boiled with rice (māmsaudana) was also highly prized in those days.

Though we hear very little of fish-eating in the Rigveda, fish was in regular use as food in this period. This is evident not only from the frequent mention of fishermen but also from the large number of words denoting them that came into use e. g., Dāsa, Dhivara, Dhaivara, Kaivarta, Kevarta, Maināla, etc. That fish was caught and offered for sale as food is apparent from the existence of a separate class of men—the fish-vender mentioned in the White Yajurveda. 1923 The Maitrāyaņa Brāhmaṇa Upaniṣad 1924 employs the simile of a fisherman drawing out the denizens of the

<sup>2919</sup> I. 15.

<sup>1018</sup> III. 4, L. 2,

<sup>1914</sup> Vaj. I. 109.

<sup>1918</sup> Satapatha Brahmana, III. 1. 2, 2 .

<sup>1010</sup> See ante, pp. 110-13.

<sup>1917</sup> Ramayana, Ayodhyakanda 91st sarga.

<sup>1919</sup> Thid.

<sup>1018</sup> Thid., 56th sargs.

<sup>1020</sup> Ibid., 91st sarga.

<sup>1001 1</sup>bid., 84th sarga.

<sup>1922</sup> Ibid., Sandarakānda, 11th sarga.

<sup>1995</sup> XXX. 16.

<sup>1934</sup> VI. 26.

waters with a net and offering them up (as a sacrifice) into the fire of his stomach to explain higher philosophical truths. The Rāmāyaṇa 1928 refers to dishes of cooked fish in Rāvaṇa's kitchen. Fish was also offered to the guests and the manes.

We have already seen that the milk of the cow, the buffalo and the goat was used. 1926 The Satapatha Brahmana 1927 describes the various articles of food prepared from cow's milk—butter (navanita), creamy butter (phanta) clarified butter (ghṛta) and curd (dadhi). Mixed milk (payasyā) is also mentioned. The drink consisted of milk and wines of different kinds already described. The Ramāyaṇa 1928 also refers to another drink called āsava. It was prepared from honey, sugar, flowers and fruits flavoured with various powdered ingredients. 1929

age many of the household duties were entrusted to the women of the house. The grhapatni was an 'alter ego' of the husband and the Atharvaveda 1930 tells us how she joined her husband in ceremonials and sacrifices and how she had often to take care of the Household Fire. In the marriage hymns she has been described as the queen of the household. 1931 Cooking was left to the wife as is proved by many passages of the Atharvaveda 1933 and the Black Yajurveda 1933 and the cooked food was distributed by the mother (mītā) as philological evidence shows. That the wife had to partake of the husband's burdens and household duties, seems to be indicated by some passages in the marriage hymn of the Atharvaveda. "Blest be the gold to thee, blest the water, blest the yoke's opening and blest the pillar." 1934 Here the yoke's opening stand sym-

<sup>1000</sup> Sandarakanda, 11th carga.

<sup>1926</sup> See ante, pp. 110-13.

<sup>1017</sup> III. 3. 3.

<sup>1928</sup> Bālakāṇda 53rd sarga; Suudarakāṇda 11th sarga.

<sup>1010</sup> Sundarakāņda, 11th sarga.

<sup>1950</sup> XII. 3.

<sup>&</sup>quot;As vigorous Sindhu won himself imperial lordship of the streams

So be imperial queen when thou hast come in thy husband's home.

Over thy husband's father and his brothers be imperial queen.

Over thy husband's sister and his

Over thy husband's sister and his mother bear supreme control."

<sup>1939</sup> XII. 3. 4.

<sup>1035</sup> V. 1. 7. 1-2.

<sup>1004</sup> Atharvaveda, XIV. 1. 40.

bolical of agricultural operations, while the pillar in the middle of the threshing floor evidently refers to the wife's participation in the work of treading out corn. The tending of the cattle in her husband's house also formed part of her duties as would appear from a passage of the marriage hymn of the Atharvaveda in which Brhaspati is asked to make her gentle to the cattle. 1935 It seems to have been the custom in those days for the bride to weave the garment which the husband is to wear on the first day of his wedded life—das Brauthemde—the bride-shirt of the peasant of Saxony mentioned by Weber: "(May) the garment woven by the bride be soft and pleasant to our touch." 1936 The girls of the house continued to be the milk-maids of the family in this period as well:

"Quickly and willingly like kine forth come the singers and their hymns:

Their little maidens are at home, at home they wait upon the cows." 1937

To women of the house was entrusted the work of fetching water, 1938 preparing the Soma drink, churning curds and milk and preparing butter, creamy butter (phāṇṭa) and clarified butter (ghṛta) out of them. It is no wonder, therefore, that among the blessings which the king hopes the Horse-sacrifice will bring to him is the birth of industrious women in his kingdom... 1938

It is thus evident that the average Vedic householder lived a life of self-sufficiency, depending mainly on his own exertions. He tended his own cattle and his own fields with the help of his kinsmen and the products of his farm and dairy supplied almost all the needs of his family. There was at first very little of luxury as well as of scarcity.

(5) Development of copitalism and of a landed aristocracy—But this state of affairs did not last long. Conquest brought in wealth and with the growth of towns luxury invaded society. Gambling and want of thrift reduced families to want and and poverty and much of this wealth passed into other hands. The existence of little restrictions on transfers, whether of cattle or of real property together with the almost unfettered power

<sup>1000</sup> Ibid., 1, 62.

<sup>1050</sup> Tbid., 2, 51,

<sup>1037</sup> Ibid., XX. 127. 5.

<sup>1938</sup> White Yajurveda, XVI. 7.

<sup>2039</sup> Ibid., XXII. 22.

of the pater familias in the matter of disposal of property helped the growth of capitalism. Usury came to be the occupation of the rich, some of the merchants made huge profits and money came to be accumulated into the hands of the few. We have already seen 1940 that the Rigveda refers to the Maghavans who were famous for their wealth and liberality. An idea of the wealth of the princes of this period may be gathered from the account of gifts bestowed by them on brahmins, even though the accounts be a bit exaggerated and the figures conventional, as they come mostly from the recipients of these gifts. Thus besides ordinary gifts Janaka bestowed one thousand cows with twenty thousand padas of gold to the best read brahmin. 1961 Again, we hear of the liberality of a worshipper who gave eighty-five thousand white horses, ten thousand elephants and eighty thousand slave girls adorned with ornaments to the brahmin who performed the sacrifice. 1949 We also find the gift of a village by Janasruti to Raikka, when the latter agreed to teach him the Deity he worships. 1943 Kaurama, king of the Rusamas gave away twenty camels with females by their side. one hundred chains of gold, three hundred mettled steeds and ten thousand cows. 1944 We also notice, besides the Maghavans and the princes, the growth of a landed aristocracy 1945 due either to the acquisition of superior rights by men of merit over equals in the village or to the custom of granting villages to sacrificial priests and śrotriyas.

(6) Princely palaces—These princes and richer people lived in comparatively comfortable dwellings called harmya in the Rigveda. 1946 The harmya primarily denoting a unity including the stables etc, 1947 very soon added on the qualification of being protected by a wall of some sort. 1948 In the Rigveda we find a harmyesthal prince standing probably

Ve 40 See ante, p. 78.

story is repeated in the Brhadirapyaka Upanisad, III. 1. 1 ff.

See also Satapatha Brühmana, II. 6. 3. 9; IV. 1. 11; IV. 3. 4. 6; Taittiriya Brühmana, III. 2. 5. 11—12.

<sup>1948</sup> Chhandogya Upanisad, III. 2. 4.

<sup>1964</sup> Atharvayeds, XX. 127. 2-3.

<sup>1945</sup> See ante, pp. 88-89.

IX. 78. 3; X. 43. 3; X. 73. 10.

<sup>1047</sup> Rigveds, VII. 56, 16; cf. X. 106, 5.

<sup>1040</sup> Ibid., VII. 55. 6.

on the roof or rather the balcony of his palace 1949 just as any later Indian king would do to please his people. When the Atharvaveda thinks of a residence for Yama, it is a harmya. 1950 Some details regarding this harmya are to be found in the literature of this period dealing with Rajasuya. 1951 During this sacrifice the 'ratna-havis' rite was to be performed at the house of the king's ratnin's including the Chief Queen and the Household officers so that Ratnins' houses must have been round about or adjacent to the king's harmya, being in the same royal and sacrificial area; and the separate houses of the sacrificing king's mahisi, vavata and pariwrkti indicate the existence of a complex palace of the harem type. The royal officer called kşattr1952 does the work of the distributor of the king's gifts in the Rigveda and the Atharvaveda, that of the gate-keeper in the Yajurvedas and early Brahmanas and that of the harem superintendent (antah-puradhyaksa) in the Satapatha Brahmana. The princes and nobles also employed dasi's for doing all sorts of domestic drudgery like husking and winnowing grain 1953 and collecting the alkaline droppings of the cow. 1954 They usually maintained a large number of attendants, 1955 cooks, 1956 servants, 1957 messengers, 1958 waiters, 1959 door-keepers 1960 and bath-attendants, 1961

The description of Kaikeyi's Mahala with its separate krodhāgāra, citragrha (picture-gallery) latāgrha (grove) and many rooms furnished with altars and seats made of gold, silver and ivory; 1969 of Yuvarāja Rama's Mahala with its white gate decked with gems and pearls and crowned with a golden image, with images of tigers made of different metals here and there,

<sup>1040</sup> Ibid, VII. 56. 16. (Geldner—Vedische Studien, 2, 278, n. 2; Alt. Leb. 149).

<sup>1050</sup> Athervaveda, XVIII. 4. 55.

Black Yajurveds, I. 8, 9, 1 ff; Maitrāyani Samhitā, II. 6, 5; IV. 38; Kāthaka Samhitā, XV. 4; Taittiriya Brāhmana, I. 7, 31 ff; Satapatha Brāhmana, V. 3, 1, 1, ff.

Vol. I., p. 201.

<sup>2000</sup> Atharvayeda, XIL 3. 13.

<sup>1034</sup> Ibid., XII 4. 9.

<sup>1985</sup> Atharvayeda, IX. 6. 50-51.

Ramayana, Ayodhya-kanda, 80th

<sup>1887</sup> White Yajarveds, XXX. 13.

<sup>1002</sup> Ibid.

<sup>1988</sup> Ibid., XXX. 9.

<sup>1000</sup> Ibid., XXX. 13.

<sup>1941</sup> Ibid., XXX, 12,

<sup>1963</sup> Ramayana, Ayodhyakanda, 10th sarga.

with its rooms adorned with the paintings of skilful artists;1968 of Ravana's palace ornamented with plastered jewelled pavements, studded with gems, crystals and pearls, with elephants of burnished gold and speckless white silver, girt round by a mighty wall, furnished with golden doors with beautiful golden stairs embellished with ornaments of burnished gold, with lofty edifices having excellent windows made of ivory and silver, with golden nets, with its beautiful latagrha's (groves), citragrha (picture-gallery), krdagrha (play-room), kāmagrha, divā-vihāra-grha and artificial mountains made of wood 1964 show the improvement of art and the luxury of the age. Well might Hanumana exclaim at the sight of the bed-chamber of Ravana with its jewelled staircase illumined with heaps of gems, its terraces of crystal and statues of ivory, pearls, diamonds, corals, silver and gold, adorned with jewelled pillars, furnished with carpets, golden lamps, 1985 crystal altar, bed-stead with ivory legs decked with gold, artificial ladies with flyflappers in their hands moving by mechanism 1986 that this must be svarga 1

(7) Growth of luxury—The luxury of the age is equally evident as much from the use of the large number of gold and silver ornaments and jewellery already described as from the use of toilette of various kinds (snāna-dravya) kept in different pots, 1967 sandal powder (candanakalka), 1963 sandal paste, 1969 aguru paste, 1970 white paste, 1971 sticks to brush the teeth with 1972 and of hair-comb (kankatikā). 1973 Manahšilā, a red-coloured mineral product found in the mountains (girija-dhātu) 1974 was used by ladies to colour their cheek. In the Rāmāyaṇa Sitā asks Hanumāna to remind Rāma of the fact that one day he painted with his own hands the cheek of Sitā with tilakas of manaḥšīlā. 1975 It was usual for the comparatively well-to-do people to burn aguru and sandal wood, 1976 resin

```
1005 Ibid , 15th surga.
```

<sup>1964</sup> Ibid., Sundarakāņda, 6th sarga.

<sup>1906</sup> Ibid., 9th sarga.

<sup>1900</sup> Ibid., 10th sarga.

<sup>1907</sup> Ibid., Ayodhyakanda, 91st sarga.

<sup>1</sup> bid.

<sup>1900</sup> Ibid., Ayodhyākānda, 78th and 91st sargae; Sundarakānda, 10th sarga.

<sup>1970</sup> Ibid , Ayodhyakanda, 91st sarga.

<sup>1071</sup> Ibid. Kişkindbyākānda, 26th sarga.

<sup>1979</sup> Ibid., Ayodhyākāpda, 91st sarga.

<sup>1978</sup> Ibid.

<sup>2074</sup> Ibid., Kişkindhyākānda, 26th sarga; Sundarakānda, let sarga.

<sup>197:</sup> Ibid , Saudarakānda, 40th sarga.

<sup>1070</sup> Thid., Ayodhyakanda, 14th, 76th and 88th sargas.

(sala-niryyas)1977 and various other kinds of incense (gandhadravya).1978 Not only do we find mention of the gandhajivi1979 but also of perfumes 2930 and ointments 1931 made by them. In the White Yajurveda the ointment-maker (who is usually a female) is mentioned 1988 and we are told that in the Soma sacrifice the Adhvaryu priest annoints the eyes of the sacrificer with collyrium.1983 Collyrium-pots are mentioned in the Rumiyana 1984 and the annointing instrument in the Black Yajurveda, 1985 The annointing instrument was called isika, as opposed to salali which is used by men according to the Kathaka Samhita 1986 and Maitrayani Samhita 1987 According to Satapatha Brahmana 1988 the annointing instrument was a reed stalk (saresika) with a tuft. In the Black Yajurveda 1989 the mythological origin of collyrium is thus told : "Indra slew Vrtra; his eye-ball fell away; it became collyrium." We also hear of musk (kasturi), 1890 lac (laksa), 1991 of saffron (kumkum) 1999 for colouring food 1993 and of flavouring ingredients for food. 1994 The use of umbrella, 1995 chāmara (fly flapper), 1996 wooden sandals 1997 and leather-shoes 1998 was also known in this age.

1012 Ibid., 76th sarga.

1976 Ibid.; Ibid., Sundarakāņda 10th sarga.

1978 Ibid., Ayodhyākāņda, 83rd sarga.

VIII. 8. 5; Kauşitaki Upanişad,

1881 Black Ysjurveds, VI. 1. 1. 5—6;
Kāthaks Samhitā, XXIII. 1;
Kapistala Samhitā, XXXV. 7;
Maitrāyani, Samhitā, III. 6. 1—3;
Satapatha Brāhmana, III. 1. 3. 13.

1995 White Yajurveda, XXX. 14,

1983 Ibid., IV. 3.

1004 Ayodhyākāņda, 91st Sarga.

100s VI. 1. 1. 6.

1989 XXIII. 1.

1 100 III, 6. 1-3,

1988 III. 1. 3. 13.

1 #5 VI. 1. 1. 5.

1000 Ramayana, Lankakanda, 75th Sarga-

rapyaka Upanigad, H. 3, 6;

Rāmāyana, Ayodhyākānda, 75th sarga; Kişkindhyākānda, 23ed sarga.

2002 Ramayana, Kiskindhyakan la 26th

1993 Ibid, Sundarakanda, 11th sarga,

1906 Ibid.

1900 Ibid., Ayodhyākānda, 14th,
45th and 91st sargas; Aranyakānda, 35th and 51st sargas;
Kişkindhyākānda 10th and 26th
sargas; Sundarakānda, 10th sarga;
Laākākānda, 11th and 129th sargas.

Ibid., Ayodhyākānda, 14th, 15th, 16th and 91st sargas; Aranyakānda, 35th and 51st sargas; Kiskindhyākānda, 10th and 26th sargas; Lankākānda, 11th and 129th sargas.

1997 Ibid., Ayodhyākānda, 91st, 112th and 113th sargas; Kijkindhyākānda, 26th sarga.

1 \*\*\* See ante, p 140.

(8) Existence of social inequalities -Side by side with richer people enjoying these luxuries we find also peoples in debt. In the Aitareva Britmana VIII. 11 we read : "To overcome the foe thou movest like one taking payment for debt; hail !" Debts were contracted for various purposes, pambling being one of them. 1999 The amount of interest payable is impossible to make out. There is a passage in the Atharvavela 1000 where an eighth and sixteenth are mentioned as paid; but, it is quite uncertain whether interest or an instalment of the principal is meant. The Atharvayeda contains prayers to Agni for absolution from sin arising out of non-non-tof debt200t and for release from debts incurred without intention of payment. 2002 In another hymn of the Atharvaveda 2003 the reciter prays to the two Apsaras (Ugrajit and Ugrampasya) for forgiveness for incurring debt in dice-play. Such prayers are really significant in as much as they show not only an advanced state of society with frequent occurrence of debt but also a corrupt state of affairs where people contracted debt with the intention of non-payment, though at the same time nonpayment of debt was regarded as a sin which brought evil consequences in the next world.

The state in relation to economic life—Before we conclude this chapter something may be said about the part the head of the state was expected to play in moulding the economic life of the people. The Coronation ritual proves beyond doubt that not only was it the duty of the ruler to protect the life and property of his subjects but also to promote their material welfare. Thus the priest during the Coronation ceremony addresses the ruler as follows:

"This is thy Sovereignty. Thou art the ruler, thou art controller, thou art firm and steadfast.

with kakara and ending with hakara if uttered thirty thousand times would bring freedom from debt. Hig VIII. 30. 4 if uttered eight or twenty-eight times a day for six months would bring freedom from debt. The mantra (1st Astaka, 2nd Adhyāya, 13th Varga) beginning with "Kasya ndamm" if uttered with priyangu and honey will bring freedom from debt.

V. 6. 6. 1; Satapatha Brāhmaņa, V. 4. 3. 19; Kanşitakî Brāhmaņa, III. 3; Paūchaviņda, Brāhmaņa, XVII. 14. 16; Rāmāyaṇa, Ayodhyākāṇda, 91st sarga.

<sup>2000</sup> VI. 47, 32 = Rigveda, VIII. 47, 17,

<sup>2001</sup> Atharvayeds, VI. 117.

<sup>2002</sup> Ibid., VI. 119.

Saunaka the Rig mantras beginning

Thee for land culture, thee for peace and quiet, thee for wealth, thee for increase of our substance.2004

In the Ramayana we similarly find Rama asking Bharata whether the people are living happily in his kingdom; whether the agriculturist and the cowherd find; favour in his sight; whether every day in the morning he watches from the balcony of his palace the prosperity of his subjects passing through the high roads; whether royal forests and cattle are well-protected; whether the forts are always filled with wealth, grains, weapons, water-appliances (jala-yantra), artisans and skilled archers; whether his income is always greater than the expenditure; whether the physicians and other notables are always kept in good humour by sweet words, gifts and honours. The is thus evident that the economic side of national life was to receive its fullest attention from the head of the state. The ideal of happiness which the king prays to the gods for his country to attain will be evident from the following hymn in connection with the Horse-sacrifice:

"O Brahman, let there be born in the kingdom the Brahmin illustrious for religious knowledge; let there be born the Rajanya, a skilled archer, piercing with shafts, a mighty warrior; the cow giving abundant milk; the ox good at carrying; the swift courser; the industrious woman. May Parjanya send rain according to our desire; may our fruit-bearing plants ripen; may acquisition and preservation of property be secured to us."2006

We have evidence in the panygeries of rulers how the theoretical concept of royal duty was translated into practice. In the eulogy which a subject of Pariksit bestows, he makes particular mention of the fact that agriculture and cattle-rearing were in a prosperous condition, that the subjects of Pariksit not only thrived well but also lived in unbroken peace and happiness under his rule.<sup>2007</sup>

<sup>2004</sup> White Ysjurveds, IX. 22.

<sup>2005</sup> Rāmāyaṇa, Ayodhyākāṇda, 100th sarga.

White Yajarveda, XXII, 22.

## CHAPTER VI.

## The Age of Gautama Buddha.

(600 B.C.-321 B.C.)

The chief sources of our knowledge of the economic conditions prevailing in this period are the Jatakas or the Birth-stories of Buddha and to a more limited extent the Vinaya and the Suttapitakas. It is true that the Jātakas are mere stories; but it is fairly clear that the folk in those tales have given them a parochial setting and local colour. And this evidence from the Jatakas is frequently borne out by the coincident testimony of other books not dealing with folk-lore. Of such books which furnish corroborative evidence, the Sūtras (specially the Grhyasūtras, Śrautasūtras and the Sütras of Pāṇini) and the works of Greek writers like Herodotus are important. Whatever may be the age of their representative works in their present form, the Sütras undoubtedly had their roots in a period at least as early as the rise of Jainism and Buddhism. The purpose of the Sūtras, so called from the sūtra which means a thread, is to afford a clue through the mazes of Brahminical learning contained in the Brahmanas and the earliest of them represent a phase which is transitional between the language of the Brahmanas and Classical Sanskrit as fixed by the grammarians.

Towns—This period is marked by a remarkable growth of towns good and the development of town-life which is so closely associated with the growth of industry and commerce. According to the Mahaparinibbana Sutta good there were some "great cities (mahanagara) such as Champa, Rājagrha, Śravasti, Sāketa, Kauśāmvi and Benares" as against "this little wattel and daub

commission by Alexander to a region left desert by a shifting of the Indus to the east, saw the remains of over a thousand towns

and villages, once full of men (Aristobulus, Frag. 39 = Strabo XV. C. 693).

<sup>1000</sup> V. 4. - S. B. E., Vol. XI. p. 99.

town" of Kuśmagara." We get the following list of towns from the literature of this period:—(1)Ālavī²²¹¹ (= Sanskrit Ātavī). It was situated near the bank of the Ganges on the way from Śrāvastī to Rājagṛha and thirty-five yojanas away from Śrāvastī; (2) Andhapura on the bank of Telavāhanada;³²¹¹¹ (3) Anupiya in Malladeśa;²²¹² (4) Ariṣtapura in the Śivi country.²²¹³³ It had four gates;²³¹⁴ (5) Asitāñjana;²³¹⁵ (6) Assapura, a nigama in Anga;³¹¹⁵ (7) Ayojjhā=(Sans. Ayodhyā);²³¹¹ (8) Aṭṭaka in Anga;²¹¹³ (9) Vārāṇasī (= Benares).²³¹⁰ It was surrounded by a wall,²⁰²²⁰ pierced by gates ²⁰²¹ with watch-towers over them.²⁰²² It was served by a good system of drains²⁰²³ through one of which a prince fled from the hands of the invaders.¹⁰²⁴ It was famous for her scents²⁰²⁵ and textile fabrics;²⁰²⁵ (10) Bhadravātikā;²⁰²ⁿ (11) Bhṛgukachchha;²⁰²⁵ (12) Brahmottara;²⁰²² (13) Champā, ancient capital of Anga,²⁰³⁰ It was surrounded by a wall, pierced by gates with watch-towers over them;²⁰⁵¹ (14) Danta-

```
2010
     Uvāsagadasao (Eng. Trans. by
      A. F. R. Hoernle) p. 52; Tri-
      paryasta Jātaka (No. 16); Mani-
      kaptha (No. 253).
3011
     Serivānij Jataka (No. 3).
     Sakhavihāri Jātaka (No. 10).
9019
8018
     Sivi Jātaka (No. 499);
8014
     Unmadayanti Jataka (No. 527); Sivi
      Jatska (No. 499).
2010
     Ghata Jataka (No. 454).
2018
     Majjhima Nikāya.
3017
     Vimanavatthu Commentary, p. 82.
8028
     Majjhima Nikāya.
     Uvasagadasao (Eng. Trans. by
      Hoernle), p. 52; Digha Nikaya,
      XIX. 86; Vimanavatthu Com-
      mentary, p. 82; Apappaka Jätaka
      (No. 1); Vannupatha (No. 2);
```

Tandulanāli (No. 5); Devadharma

(No. 6); Tailapatra (No. 96) etc.

Grdhra Janaka (No. 164); Samgra-

Khadirangara Jataka (No. 40);

māvacara Jātaka (No. 182).

3030

2001

Samgrāmāvacara Jātaka (No. 182)

soss Sīgāla Jātaka (Nos. 113 and 142). soss Aśātarēpaka Jātaka (No. 100).

2028 Bhimasena Jataka (No. 80).

Bhimsena (No. 80); Kāmavilāpa (No. 297); Mahāśvāreha (No. 302). Madīyaka (No. 390); Viša (No. 488); Mahāvāņij (No. 493); Soņananda (No. 532); Mahāhaṃsa (No. 534); Khandahāla (No. 542); Mahāunmārgs (No. 546); Viśwantara (No. 547);

souv Sarapina Jataka (No. 81).

Sušropi Jataka (No. 360); Supāraga Jātaka (No. 463).

2020 Divyāvadāna (Maitrakanyakāvadāna)

Hoerale), p. 52; Digha Nikāya, XIX 86;

2031 Mahajanaka Jataka (No. 539).

Mahāsilavaja (No. 51); Chullapadma (No. 193); Bhimasens (No. 80); also Nos. 156 and 34).

pura on the coast of Kalinga; 2032 (15) Desaka in Sumbha kingdom; (16) Gambhirapattana, a port; 2038 (17) Halidda-vamsa, a nigama in the Koliya country; 2034 (18) Indapattha; 2035 (19) Jetuttara in the Sivi country. 2036 It was surrounded by a wall pierced by gates; 2037 (20) Kāmpilya, the capital of N. Panchāla; 2038 (21) Kosamyi (Kauśamvi), 2039 the capital of Vatsarīja Udayana. According to Cunningham it is modern Kosam on the bank of the Jumna, thirty miles N. W. of Allahabad. It was an important halting place both for goods and passengers coming to Magadha; (22) Kapilavastu2040 on the bank of the river Rohini 100 miles north of Benares, birth-place of Gautama Buddha; (23) Kitagiri<sup>2041</sup> a nigama in the Kīśi kingdom; (24) Kusinārā<sup>2042</sup> (= Kusanagara). It is modern Kāśiā, 35 miles East of Gorakhpur. It was surrounded by a wall ;2048 (25) Kaveripattana in the Dravida country ;2044 (26) Kajangala, It was the name of a city according to the commentator of Visa Jataka where there was a vihāra at the time of Kāśyapa Buddha; (27) Kundiya; 2045 Koli on the bank of the river Rohini, just opposite to Kapilavastu. Devadatta and Yasodhara belonged to the ruling family of this city; (29) Madhurā (Mathurā), capital 2048 of the Surasenas; (30) Māhissatī; 2047

dharma Jataka (No. 276); Kurukalinga (No. 301); Kumbhakara (No. 408); Kalingavodhi (No. 479).

1000 Lodaka Jātaka (No. 41).

Majjhima Nikāya.

Hoernie), p. 52; Kurndharma (No. 276); Mahāsntasoma (No. 537).

1050 Viśwantara Jataka (No. 547).

soor Ibid.

vatthu Commentary, p. 82. Kumbhkāra Jātaka (No. 408),

Hoernie), p. 52; Vimanavatthu Commentary, p. 52. Its drainage system is referred to in Kranadvaipäyana Jataka (No. 444). Compare the epithet Kansanveys in Satapatha Brāhmaņa, XII. 2. 2. 18 and in Gopatha Brāhmaņa I. 4. 24. According to the Rāmāyaņa, (I. 32. 6) and Kāsikā commentary ca (Papial's Sūtra, IV. 2, 68): tena nirvrittam, Kansāmvī was founded by prince Kušāmva.

Uvāsagadasao (Eng. Trans. by Hoerule) p. 52.

2041 Majjhima Nikaya.

O 12 Uväsugadasao (Eng. Trans. by Hoerole), p. 52; Mahäsudaršuna Jätaka (No. 95).

seas Ibid.

2044 Akīrti Jātaka (No. 480).

204 \* Adatarupaka Jataka (No. 100).

2046 Vimanavatthu Commentary, p. 82, 2047 Digha Nikaya, XIX. 86. (31) Mithilā; 2048 (32) Nandana; 2049 (33) Polāsapura; 2050 (34) Potana; 2051 (35) Patiṭṭḥāṇa (= Paithan); (36) Pātaliputtaka; 2052 (37) Potali in the Kāśi kingdom; 2053 (38) Potali in Aśvaka kingdom; 2054 Its gates are also referred to; 2055 (39) Roruka, 2056 capital of Sovira. It was an important centre of coasting trade; (40) Ramaṇaka; 2057 (41) Rājagaha (= Rājagiha = 2058 Rājagṛha; (42) Sāgala; 2050 (43) Śrāvastī, 2060 capital of Uttara Kośala. It is modern Seth Maheṭha in the Gonda district of U. P., ten miles north of Valarīmapura, on the bank of the river Aciravatī (modern Rāptī). It gates are also referred to; 2061 (44) Sāṃkāśyā (= Pāli Samkissa). 2062 It is modern Saṃkiśa on the Kālī river in the Farakkabad district; (45) Sarundhana in the Kīśī kingdom; 2063 (46) Sadāmatta; 2064 (47) Šākala 2066 (otherwise known as Ayodhyā or Visīkhī) on the bank of the river Saraju in the Faizabad district; (49) Sālātura; 2067 (50) Šarkarā, a nīgama near Rājagṛha; 2066 (51) Setavya; 2069 (52) Sagula; 2070 (53) Sum-

Uvāsagadasao (Eng. Trans. by Hoerole), p. 52; Vimānavatthu Commentary, p. 82; Digha Nikāya, XIX. 86; Makhādeva Jātaka (No. 9); Gāndhāra (No. 406); Kumbhakāra (No. 408); Mahājanaka (No. 538).

Divyāvadāna (Maitrakanyakāvadāna)

2050 Uyasagadasao, Lacture X.

Assakānāna Potanam—Digha Nikāya, XIX, 86,

Uyāsagadasao (Eng. Trans. by Hosrule), p. 52.

aoss Aśvaka Jūtaka (No. 207).

2054 Khullakalinga Jataka (No. 301).

soss Thid.

Jūtaka (No. 424),

Divyavadāna (Maitrakanyakāvadāna).

Nos. 4, 11, 14, 37 etc. It was the capital of Magadha.

- Vimānavatthu Commentary, p. 82.
- Jataka Nos. 1, 2, 3, 5, 27, 37, 41, 44, 54, 75, 103 etc.
- aces Avikşņa Jātaka (No. 27).
- Hoernle), p. 52; Jääska Nos. 29, 134, 135 etc.
- 2012 Udaya Jataka (No. 456).
- Divyāvadāna (Maitrakanyakāvadāna).
- Kasa (No. 531).
- Buddhist Suttas—Rhys Davids, p. 99; Uväsagadasac (Eng. Trans. by Hoernle), p. 52; Vimänavatthu Commentary, p. 82; Säketa Jätaka (Nos. 68 and 237).
- soor Papint.
- anna Illisa Jätaka (No. 78).
- 2010 Uväsagadasao, Lecture X.
- Tvasagadasao (Eng. Trans. by Hoarale), p. 52.

sumāra<sup>2071</sup>; (54) Suppāraka; <sup>2072</sup> (55) Svātivatī in Chedi kingdom; <sup>2073</sup> (56) Takkhaśilā (Taxila). <sup>2074</sup> Its gates are referred to; <sup>2075</sup> (57) Ujjain in Avantī; <sup>2076</sup> (58) Ukkaṭṭha; <sup>2077</sup> (59) Uttara Mathurā; <sup>2078</sup> (60) Vai-śāli <sup>2079</sup> (= Pāli Vesālī). According to Cunningham it is modern Beśāra, <sup>20 miles</sup> north of Hājipur. It was surounded by three walls each at a distance of one gabyūti (=two miles) pierced by three gates with watchtowers over them. <sup>2080</sup> With its suburbs of Kulluga and Kundagāma Vaiśāli was called Vaniyagāma according to Jaina tradition. <sup>2081</sup>

(a) Origin of towns:—Some of these were in their beginnings mere villages and gradually developed into towns. In the Jayaddvisa Jūtaka<sup>2082</sup> we are told that a certain king made settlement on a certain mountain, brought virgin soil under cultivation by clearing off the jungles and bringing a thousand families with much treasure founded a big village. This village, we are told, grew into a town (Khullakalmāṣa by name). The town of Kammasadamma also grew out of a village<sup>2083</sup> The growth of villages into towns is further shown by the fact that some terms while generally meaning towns also mean villages e. g., kheṭa, pattana, kārvaṭa etc.<sup>2084</sup> In fact, one of the most potent factors which influenced the amalgamation of several villages into a city or a capital was the political condition of ancient India. Mr. Havell<sup>2083</sup> well remarks "A natural consequence of the consolidation of Aryan tribal system into these larger states and kingdoms was the gradual development of the village settlements into larger towns and cities planned on the same prin-

Sec. 81

sort Ibid.

<sup>2079</sup> Buddhist India-Rhys Davids, p. 31.

<sup>2028</sup> Chedi Jataka (No. 422).

Uväsagadasao — Hoernle's trans. p. 52; Pāṇinī; Jātaka Nos. 61, 71, 96, 408.

pots Paläyi Jātaka (No. 229).

<sup>2075</sup> Chitrasambhūta Jātaka (No. 498),

<sup>50?7</sup> Uvāsagadasao—Hoernle's trans. p. 52; Rhys Davids—Dialogues of the Buddba.

Ghata Jataka (No. 454).

<sup>52;</sup> Vimanavattu Commentary, p. 82; Tittira (No. 37); Ekaparpa No. 149).

saso Ekaparpa Jataka (No. 149).

<sup>9981</sup> Uväsagadasao-Hoernle, p. 4.

soss No. 513,

<sup>2088</sup> Mahāsutasoma Jātaka (No. 537)

p. 38.

Vaijayanti by Yādavaprakāša, p.159, LL. 1-6 p. 232, L. 2; Mayamatam, Ch. IX.

ciples in which wards or village units, were grouped round the royal palace and the citadel."

Some of the towns were fortresses in the midst of a collection of villages and these fortresses grew into towns. According to the Mahaparinibbana Sutta 2080 Ajātašatru of Magadha built a fortress at Pātaligrāma to check the advance of the Vajjis. This village and the fortress grew up into the town of Pātaliputra in the course of two generations. 2087 The hill-fortress of Girivraja four miles and a half in circumference which was said to have been built by Mahagovinda, the architect also grew into a town.

The necessity of a trading post led to the growth of many commercial towns in India also as in other countries. A centre of trade is very likely to be posted on or near by the well-known trade-routes of the Ancient World and Taxila is a case in point. "The valley in which the remains of Taxila lie is a singularly pleasant one, well-watered by the Haro river and its tributaries, and protected by a girdle of hills;—on the north and east by the snow-mountains of Hazra and the Murree ridge, on the south and west by the well-known Margalla spur and other lower eminences. This position on the great trade-routes which used to connect Hindusthan with Central and Western Asia, coupled with the strength of its natural defences, fertility of the soil, and a constant supply of good water readily accounts for the importance of the city in early times." 2088

(b) Town-planning:—Though we have no detailed description of the town-plan in early literature the fragmentary evidences concur in describing an Indian city as surrounded by walls pierced by lofty gates and defended by a most or even three mosts; and as divided into different wards or quarters which were allotted to men of different castes and trades excepting the Chandalas who lived outside the city. In the Pandara Jataka<sup>2089</sup> we are told that one should

sons L 26 - S. B. E., Vol. XL p. 18.

<sup>1001</sup> V. A. Smith-Early History of India, 4th edition, p. 39.

<sup>2008</sup> Sir J. Marshall-Guide to Tazila, pp. 1-2

<sup>1000</sup> No. 518.

keep a secret carefully guarded in his mind just as a city is strongly guarded by being girt round by deep moats. In the Mahajanaka Jataka 1000 are told that expert sthapati's have built the walls, wards and places of the city of Mithila after proper calculation and measurement, have beautified it with gates (torana), watch-towers (attalakas) and well laid out (suvinyasta) roads and kūtīgāra's made according to proper measurements (yathīmāna). From the Mahaunmarga Jataka 2091 we learn that the king dug three moats round Mithila-a water-moat, a mud-moat and a dry moat. The city of Kusavati was surrounded by seven ramparts (vapra) with four gates.2092 The story of how king Pasenadi of Kosala was kept out of his capital by the stratagem of Digha Kārāyana2093 and how this made him lose his kingdom also proves the existence of completely walled up cities and of the stringent rules for closing the city-gates. 2094 From the Uvzsagadasao we find that the ksatriya quarter of Vesali was different from that of the brahmins. From that Jatakas we learn of the ivory-workers' bazaar (danta-vithi),2095 weavers' place (palli)2096 and vaisya quarter (vithi)2097 in Benares, florists' quarter (utpalavithi)2098 and cooks' quarter2099 in Srivasti. The evil consequence upon the corporate life of the city of segregating people into detached wards where they could be liable to develop different habits and customs was provided against by the composite wards or simple residential blocks, by the establishment of temples in the centre with magnificient debating halls and rest-houses where all sorts of people congregated together irrespective of their caste. Moreover, caste-distinction prevented one thing; it did not make poverty a crime and did not divide the city into two parts like the East End and the West End of London.

(c) Corporate life in the towns:—As a matter of fact, we find a sturdy spirit of corporate life in these cities. In the Kandukapūpa Jataka<sup>2100</sup> we find that by raising subscriptions (chhandaka), the

```
moso No. 538.
```

<sup>2001</sup> No. 546.

<sup>\*\*\*</sup> Mahasudassana Sotta, I. 3-6 (-S. B E., Vol. XI. pp. 449-51,

as Diegha Carayana,

<sup>900 \*</sup> Bhadrafála Játaka (No. 495).

vannāga (72).

soss Bhimasens Jataka (No. 80).

<sup>2007</sup> Vidwantara Jataka (No. 547).

sous Padma Jataka (No. 261).

sove Marosa Jataka (No. 315).

<sup>9109</sup> No. 109.

citizens of Sravasti used to supply food on certain occasions to the monks of the Buddhist sampha in the city. Another example of such a corporate gift (gana-dana) by the citizens of Sravasti is given in the Susima Jataka<sup>2101</sup> where the question as to whether the gift is to be made to the Tirthikas or the Buddhists was decided by majority vote (samvahula). Such corporate gifts were also made by the citizens of Benares<sup>2102</sup> and Rājagṛha.<sup>2103</sup>

Rural Economy—Despite this remarkable growth of towns and the development of town-life the economy of India in this period, as in other periods, was mainly rural, based on a system of village-communities. Like the Jatakas the Dharmasūtras also depict the life of the country as mainly rural. Cities are not ignored but despised. Apastamva<sup>2102</sup> says "Let him avoid going into towns." Baudhāyana<sup>2105</sup> goes further and says "It is impossible for one to obtain salvation who lives in a town covered with dust." Moreover, the Sūtras do not prescribe any ceremony for urban life though there are many for agricultural life in the villages. The constant injunctions to sacrifice at a place where the four roads meet or near a hill etc., therefore, imply life in the villages rather than life in the towns. <sup>2106</sup>

(a) Origin and classification of villages: From the evidences at our disposal we are able to distinguish three main types of villages in this period: (1) the ordinary agricultural village or mixed type (2) the special and suburban village or industrial type and (3) the border village or frontier type. The first type consisted of those villages which were occupied by men of all castes and occupations and some of which were destined, in course of time, to grow into towns. The special and suburban type was occupied solely by particular communities, and some of them specialised in a particular branch of industry. We thus read of villages inhabited solely by hunters, 2 107 Chandala villages, 2 108

<sup>9101</sup> No. 163.

<sup>9109</sup> Durdada Jataka (No. 180).

<sup>2102</sup> Kaşaya Jataka (No. 221).

<sup>1104 1, 32, 21,</sup> 

<sup>2206</sup> II, 3, 6, 33,

<sup>2108</sup> Govila Grhyasutras, III. 5. 32-35.

<sup>\*107</sup> Mayura (No. 159); Rohantamiga (No. 501); Khullahamsa (No. 533).

<sup>\*10°</sup> Chittasambhūta (No. 495); Āmra (No. 474); Mātanga (No. 497).

Brahmin villages, 2109 a village of 500 robbers, 2110 a village of carpenters 2111 and a village of 100 families of smiths. 2112 The rise of these industrial villages in the suburban areas was partly due to the policy of segregation adopted by the higher castes or the king with regard to the people of the lower castes who were thus not allowed to live within the walls of the city. We find a Chandala village lying just outside the city of Ujjain. 2118 Chandala villages outside the city are also referred to in Amra 2114 and Matanga 2115 Jatakas. A nisada village outside Benares is referred to in Rohantamrga 2116 and Syama 2117 Jatakas. A nisīda village near Šakula is mentioned in Khullahamsa Jātaka. 2113 The village containing 500 families of carpenters mentioned in the Alinachitta Jataka 119 was situated near Benares. According to the Uvasagadasao 120 there were 500 potter-shops outside the town of Polisapura. Apparently these formed a suburban village of potters. Indeed the very nature of these industrial villages made it essential that they should be near a town which alone can afford to give their inhabitants a good market for their labour or for the products of their labour. The third or border type of villages are frequently 1111 referred to in the Jatakas. Thus the Sakuna and Kharamvara 192 Jatakas refer to border villages in Kosala while the Masaka 113 and the Mahasvaroha 134 Jatakas refer to border villages in Kasi. The Mahavamia also refers to such frontier villages founded by king Simhavahu of the Vanga country over which he placed a son of the princess's uncle, commander in the army of the Vanga king. \$125

Suvarnakakkata Jataka (No. 389); Kurudharma (No. 276).

1110 Saktigulma Jataka (No. 503).

Phandana (No. 475).

sus Süchî Jätaka (No. 387).

<sup>2212</sup> Chittasambbüta (No. 498).

<sup>1114</sup> No. 474.

<sup>1110</sup> No. 497.

<sup>2110</sup> No. 501.

ass: No. 540.

<sup>2110</sup> No. 533.

No. 156.

<sup>9140</sup> VII, 181, 184.

<sup>3131</sup> No. 36.

sizs No. 79.

<sup>1115</sup> No. 44.

<sup>2124</sup> No. 332.

<sup>&</sup>quot;Niväsetväna säkham te paohchantagamam ägamum. Tathäsi räja-dhi täya mätulassa suto tadä. Senäpati Vangaraüño thito pachchantasädhane nisinno vatamule so kammantam samvidhäpayam—Mahavamia, Oh. VI. 15-16.

It seems that villages were sometimes founded for military purposes. In the Mahāunmīrga Jātaka<sup>2126</sup> we find that the king, previous to his starting on a military expedition gave orders to his minister to build villages on the line of march. The minister, after accomplishing his task and completing the arrangements informed the king: "Great king, wait not a moment on the road, but advance immediately. I have already built villages for you at intervals of seven yojanas, establishing halting places, and filled the hundreds of villages that are on the way with cloths and ornaments, food and drink. I have kept elephants, horses and vehicles ready for you in those villages." These villages, were evidently utilised, subsequently to expedition, as resting places for caravans.

(6) Corporate village-lite-Over each village was the gama-bhojaka who was paid according to the Kulayaka Jataka 2107 a tax on wine levied on each tub of wine (hence called chāti-kahāpana) and fines. According to Professor Rhys Davids 2128 from the fact that the appointment of this officer is not claimed by the king until the later law-books it is almost certain that in earlier times the appointment was either hereditary or was conferred by the village council itself. The villages of the industrial type appears to have had an Alderman (Jettaka) as the head. Thus, for instance, the Suchi Jataka2190 tells us that there was a Jettaka at the head of the village of 1000 blacksmiths. The headman appears also to have been sometimes appointed by the king as the Kharamvara Jataka 1150 shows. Though we hear of the misas in the Kharamyara 2130 some of the headmen conduct of Jatakas 2131 the villagers were not altogether powerless. From the Pāniya Jātaka<sup>2152</sup> we find that the headman who prohibited the slaughter of animals and the sale of wine in the village had ultimitely to rescind his orders on account of the protest of the villagers. Even when the headman was a nominee of the king the villagers

<sup>\*118</sup> Ne. 546.

mist No. 31.

sano Buddhist India, p. 48.

<sup>212</sup>º No. 387.

<sup>1110</sup> No. 79.

s151 No. 199.

<sup>9150</sup> No. 459,

had a voice in the management of their affairs. 2133 In fact they met to confer with the gamabhojaka and carried the upshot of their counsels into effect. The Mahāsvāroha Jātaka2134 tells us that the thirty villagers of a border village met togther to transact the business of the place. The Kulayaka Jātaka2135 tells us that the members of the thirty-five families of a village met in the middle of the village to transact the affairs of the village. 2136 We are further told that they went about the village with axes and clubs. With the clubs, they would roll out of the way stones that lay on the four highways and other roads of the village. The trees that would strike against the axle of chariots, they cut down; rough places they smoothed down; cause-ways they built; dug water tanks and built a hall but they wanted to put a pinnacle on it. They found it in the possession of a lady from whom they could not buy for want of money. But the lady gave it to them when they agreed to make her a partner in their work. The Losaka2137 and Takka2138 Jatakas give us the story of the establishment of a village-school and the construction of a hut for the teacher at the instance of the villagers. In the Grahapati Jataka 2139 we are told that the villagers contracted a loan (of an old ox) from the gamabhojaka. In the Mahāunmārga Jataka 2140 a krdāsālā, a pānthasālā and a vicārasālā) were constructed by raising public subscriptions from the villagers. 2141 Such co-operative undertakings by villagers are confirmed by the later evidence of Kautilya's Arthsastra.

Being thus placed between two
masters the headman's lot was
not an enviable one as is apparent
from the Visa Jataka (No. 488)
where among the misfortunes or
rather curses that might befall
a man is mantioned village headmanship.

sannipatitvā gāmakishcham karonti."

<sup>\$100</sup> No. 31: "gāmamajjha thatvā gāmakammam karonti."

size In case of division of opinion the decision of the majority prevailed [Sunil

<sup>(</sup>No 163) and Kaşaya (No. 221) Jātakas].

<sup>9187</sup> No. 41,

<sup>9120</sup> No. 63.

<sup>\*1\*\*</sup> No. 199.

<sup>2140</sup> No. 546.

gers were sometimes put to forced labour and therefore the villagers would in a body sometimes beat the forest and collect the game in an enclosed place where the king could hunt [Nyagrodha-miga (No. 12) and Nandika-miga (No. 885) Jätakas].

The corporate character of villages is equally evident as much from the fact that the village elders administered justice in petty cases as from the fact that fines were sometimes imposed on the village as a corporate whole. 2142

Land System-The village arrangements remained practically the same as at the end of the previous period. In the centre was the inhabited portion containing the homestead of the villagers. Around this inhabited portion was the arable ground (khetta) the limits of which might be extended by fresh clearing of forest land. 2242 The majority of the holdings were were probably small, though estates of 1000 karisas 2144 also occur in the Jatakas 1245 and in the Vinaya, 2146 According to Baudhayana an ideal economic holding seems to have been a portion of land measuring six nivartanas which should be kept free from taxes on the ground that this much is necessary to support a family. Nivartana was used in the sense of vitti or allowance or livelihood; so an area of land sufficient to support one man from its produce was called nivartana. Around the village lay its grazing pastures of herds of cattle. In the earlier periods the pasture does not appear to have been organised in any particular way. In the Jatakas, however, we come across an indirect reference to an enclosed pasture. In the Dhūmkāri Jātaka, 2147 for instance, we read: 'A Brahmin goatherd took a flock of goats and making a pen in the forest, kept them there.' According to Gautama 2148 unenclosed land was used by all for grazing cattle, obtaining firewood, gathering flowers and getting fruits.

(a) Was there state-landlordism?—We have seen that in the previous periods while the king had absolute right of disposal of his own lands, he had, if any at all, at that remote age, very limited rights over the land of his subjects or clansmen. The Jatakas also very clearly distinguish private land from royal domain. Thus we were told in the Salikedara Jataka: Once upon a time, a king named Magadha reigned

<sup>2142</sup> Vasistha's Dharmasitra, III. 4.

<sup>2143</sup> Kāma Jātaka (No. 466).

<sup>1144</sup> Karisa = 4 amnapa = 8 ocres.

<sup>\*145</sup> Suvarvakakkata (No. 389); Sülikedara [No. 484.]

<sup>4144</sup> L. 287; H. 186.

<sup>\$147</sup> No. 413.

<sup>2140</sup> XII, 28.

<sup>214</sup> No. 484,

in Rājagīha. At that time there stood a Brahmin village named Sālindiya, towards the north-east as you go out of the city. In this north-eastern district was property (cultivable fields) belonging to Magadha (Magadha-khettam) A Brahmin named Kosiyagotta belonging to this village appears to have taken lease of one thousand karīṣas out of that royal domain and sowed paddy in it.'1150 The Jayaddiṣa Jātaka<sup>2151</sup> shows us one of the ways in which royal domain increased by way of colonisation. The Kurudharma Jātaka<sup>1152</sup> draws a distinction between the land of the king (rañño santakam) and the land of the ordinary land-holders (kutumbassa santakam). The Dharmasūtras also distinguish royal domain from private land. Thus says Vasiṣṭha''<sup>2153</sup> "A pledge, a boundary and the property of minors, an open deposit, a sealed deposit, women, the property of a king and the wealth of a śrotriya are not lost by being enjoyed by others."

(b) Private ownership of land—As to vastu and the arable land private ownership was fully established. Gautama<sup>216+</sup> recognises this private property in land when he says "Animals, land and females are not lost by possession of another." The Jatakas abound in references to the kutimvaka or kutamvika. They seem to be private landowners.<sup>2185</sup>

As regards the mode of acquisition of property the Gautama Dharmasūtra<sup>2156</sup> lays down that 'a man becomes owner by inheritance, purchase, partition, seizure or finding.' Acceptance is an additional mode of acquisition for a brahmin, conquest for a kṣatriya and gain by labour for a vaisya or sūdra. It is true that many of these ways of acquiring wealth

kāreti. Tadā nagarato puvvattarāya disāya sālindiyo nāma
brāhmaņa-gāmo ahosi. Tassa
puvvattara disāya magadhakhettam. Tattha Kosiyagotta
nāma sālindiyavāsi brāhmaņo
sahassa kārisamattam khettam
gahetvā sālimv apāpesi—Sālikedāra
Jātaka (No. 454).

<sup>1111</sup> No. 513.

<sup>\*\*\*\*</sup> No. 276.

p. 81). XVI. 18 (⇒S. B. E., Vol. XIV.

<sup>9184</sup> XII, 30 (-S. B. E., Vol. II. p. 243).

Mateyadāna (No. 289); Sujāta (No. 352) etc. See Childers— Pāli Dictionary and Rhys Davids— Pāli Dictionary.

X. 39-42. Cf. Vasistha, XVI. 16 S. B. E., Vol. II. 231 and Vol. XIV. 81.)

relate to moveable property, but it is also clear that immovable property like land may be acquired by inheritance and succession, which involve acquisition by partition and acceptance of dowry; by purchase, which implies commerce; by conquest and occupation or valour; and by acceptance of gifts in return for instructing a pupil. Land thus acquired might, at least in the kingdom of Magadha, be given away and in that of Kośala be sold. In the former case a Brahmin landowner (Kosiyagotta by name) offers 1000 karisas of land as a gift to the Buddha who, however, accepted only eight karisas; 2157 we also hear of the donations of pleasure-gardens to the Buddhist Order by the physician Jivaka at Rājagṛha, by the courtesan Amvapāli in Vaišāli and above all by the merchant Anāthapindada at Śrāvasti. 2158 As regards the sale of land we are told in the Chullavagga 2159 that the merchant Anāthapindada entangles an unwilling noble (prince Jeta) in the sale of a park. And in the law books we read that land might be let against a certain share of the produce. 2160

In proving property, documents, witnesses and possession are admitted as proof of title by Vasistha<sup>2181</sup> and if the documents conflict, the statements made by old men, by guilds and corporations are to be relied upon.<sup>9169</sup> Vasistha gives some good provisions on the right of way and evidence in disputes regarding immovable property.<sup>2168</sup> Gautama<sup>2164</sup> and Vasistha<sup>2165</sup> give the law of acquiring property by usage. The following eight things used by another for ten years continuously, are lost to the owner: ancestral property, a purchased article, a pledged property given to a wife by her husband's family, a gift property received for performing a sacrifice, the property of reunited co-partners and wages. A pledge, a boundary, property of minors, an open deposit, a sealed deposit, female slaves, the property of a king and the wealth of a śrotriya are not lost by

aust Salikedara Jataka (No. 484).

History of the Spread of Budddhism and the Buddhist Schools, pp. 103, 143—44, 153, 161.

<sup>\*\*\*\*</sup> VI. 4. 9. (= S. B E., XX. p. 187); Kern—Manual of Indian Buddhism, p. 28.

<sup>21</sup> co Apastamya, II. 11, 28 (1); I. 6, 18 (20.)

<sup>\$141</sup> XVI, 19.

<sup>21</sup>da Vasistha, XVI. 15.

<sup>\*\*\*</sup> XVI. 10-15.

<sup>\*\*\*</sup> XII 27-39.

<sup>\*105</sup> XVII. 16-18.

being enjoyed by others. Animals, land and females are not lost by possession of another. According to Vasistha 1166 property entirely given up by its owner goes to the king who is enjoined to administer the property of widows and minors.

(c) Law of Inheritance -- From the very modes of acquisition it follows that the land under private owners could pass from generation to generation under the customary rules of inheritance and succession. The rules of inheritance supplied by the Sūtras make sapindas the heirs after or in default of sons. The sapinda here is one within six degrees and is a male only. The widow is excluded and the daughter according to Apastamva, inherits only in default of sons, teacher or pupil. 167 The nuptial presents and ornaments of a wife were inherited by the daughters. 9168 Probably the general rule anticipates not the death of the owner but a division of property among the sons during his lifetime. The king inherits in default of the others named and some say that among the sons only the eldest inherits. These rules are sufficiently vague but local laws are also provided for in the additional rules: "In some countries gold or black cattle or black produce of the earth (grain or iron ?) is the share of the eldest." \$169 Then in regard to what the wife receives, the Sutra leaves it doubtful whether the rule "the share of the wife consists of her ornaments and wealth received from her relations according to some (authorities)" is to be interpretted in such a manner that 'according to some' refers only to the last clause or to the whole. "What is obvious" says Mrs. Rhys Davids 2170 "is that the whole matter of inheritance was not yet regulated by any general state-law. Different districts of India have different laws of inheritance. Baudhayana treats the subject of inheritance first under the head of impurity where he says that sapindas inherit in default of nearer relations and sakulyas (remoter relations) in default of sapindas; but afterwards he adds that the eldest son in accordance with the quotations cited by Apastamva may receive the best chattel or the father may divide equally between the

<sup>2100</sup> XIV. 8-9.

<sup>9107</sup> II. S. 14, 4.

Bandhāyana, II. 2. 3. 4; Vadistha, XVII. 46.

<sup>2100</sup> Apastamya, II. 14. 7.

in Rapson's Cambridge History of India, Vol. I.

sons. Here also the fact that the same subject is treated in different sections shows that as yet the matter of civil law was not treated systematically but incidentally." Nevertheless we can partially reconstruct the law of inheritance as it prevailed in those days. According to Baudhayana, of the fourteen kinds of sons, aurasa (legitimate), putrik Tputra (son of an appointed daughter), ksetraja (bastard) datta (adopted), krtrima (made) gūdhaja (secretly born) and the apaviddha (abandoned by the parents) were entitled to inheritance. The next six, kinina (son of an unmarried daughter), punarbhava (son of a remarried female), swaya ndatta (self-given son) and nisada (son of a twice-born father in a sudra mother) were regarded as members of the family. The last Parisara was not even regarded as a member of the family. Gautama names twelve kinds of sons of whom aurasa, the ksetraja, datta, kstima, gudhaja and apaviddha can inherit while kānina, sahoda (son of a pregnant bride), punarbhaya, putrikāputra, swayamdatta and krita (purchased) cannot inherit thoug's they are maintained as members of the family. Vasistha regards aurasa, ksetraja, putrikaputra, punarbhava, kanina and gudhaja as heirs while sahoda, datta, krita, swayamdatta, apaviddha and nisada cannot inherit except when there are no legitimate heirs of the first six classes above mentioned. 2171 Apastamya who flourished a few centuries later recognised the aurasa sons alone as the legitimate heir, for, the recognition of other sons as heirs could not be allowed among sinful men of his age. 2172 Yet the ancient customs did not die out soon.

Gautama, the earliest law-giver of this age seems to have favoured partition of an estate, for, "in partition there is an increase of spiritual merit." According to him, the eldest son should get, as an additional share, a twentieth part of the estate, some animals and a carriage, the middle-most son shall get sheep, grain, utensils, a house, a cart and some animals and then the remaining property is equally divided. Or, Gautama would allow the eldest son two shares and the remaining sons one share each. Or, they may take one kind of property by choice according to seniority; or the special shares may be adjusted according to their mothers. 2175 Vasistha

STIL XVII.

<sup>9278</sup> XXVIII. 4.

<sup>9179 11. 6, 13 ; 11. 10. 27.</sup> 

<sup>9174</sup> XXVIII, 5-17.

allows the eldest son to have a double share and a little kine and horses; the middle-most gets utensils and furniture, the youngest takes the goats, sheep and house.<sup>2175</sup> Baudhāyana allows all the children to take equal shares or the eldest son to take one-third in excess.<sup>2176</sup>

The property of unreunited brothers, dying without issue goes to the eldest brother; the property of a reunited co-parcener goes to the co-parcener; what a learned co-parcener has acquired by his own labour may be withheld from his unlearned co-parceners and unlearned co-parceners should divide their acquisitions equally.<sup>2177</sup>

A brahmin's son by a ksatriya wife, if the eldest, shares equally with a younger brother by a brahmin wife. The sons of a ksatriya by a vaisya wife share equally. The son by a sadra wife, if virtuous, is maintained, while even the son of a wife of equal caste does not inherit, if he be living unrighteously. According to Baudhayana the sons of wives of different castes will take four, three, two and one shares according to the order of castes. According to Vasistha 180 if a brahmin has sons by brahmin, ksatriya and vaisya wife, the first gets three shares, the second two and the third one share. Apastamva, however, protests against such unequal division of property and declares that all the virtuous sons should inherit but he who spends money unrighteously shall be disinherited, though he be the eldest son.

Ordinarily the heirs should pay the debts of a deceased person. But the money due to the parents of a bride, immoral debts and fine shall not devolve upon the sons of a debtor. 2182

(d) Land revenue: (i) the amount of the royal share—The Jatakas make it clear that in the monarchies the king had a right to a portion of the produce of the soil. In the Kurudharma Jataka<sup>2183</sup> a person having

<sup>9170</sup> XVIII. 42 f.

<sup>1176</sup> II. 2. 3. 2 f.

<sup>21.77</sup> Gautama, XXVIII. 27. 31.

<sup>2178</sup> Ibid., XXVIII. 35-40.

<sup>9170</sup> II, 2, 3, 2-10.

<sup>9190</sup> XVIII. 42-50.

<sup>2141</sup> П. 6. 14. 1—15.

<sup>2199</sup> Gantama, XII. 40-41.

No. 276: Imamba kedārā mayā rañāo bhāgo databbo, adianabhāgato yeva cha me kedārato śālisisamutthi gāhāpita.

carelessly plucked a handful of corn from his own field regrets: "From this field I have yet to give the king his due, and I have taken a handful of corn from an untithed field." The exact share of the king is not known. Baudhīyana<sup>184</sup> prescribes one-sixth of the income of the subjects as the pay of the king. According to Vašiṣtha<sup>2185</sup> the the royal share is a sixth part of the wealth of the subjects. According to Gautama<sup>2186</sup> cultivators must pay to the king a tax amounting to one-tenth, one-eighth or one-sixth of the produce. This difference in the royal share was due probably to the differences in the nature of the soil. A great deal also depended on the whim of the king, for, he seems to have exercised the right of increasing the taxes at will<sup>2187</sup> or of remitting them.<sup>2188</sup> Again according to Vašiṣtha<sup>2189</sup> no taxes are to be paid on the usufruct of river, dry grass, forest, (places of) combustion and mountains.

- (ii) Land survey—For the purpose of an accurate realisation of revenue land surveys were also made. In the Kama Jataka 190 we find the royal officers taking a survey of the fields. In the Kurudharma Jātaka 100 we read that one day the Rajjugāhakamachcha (literally the rope-holding minister) was measuring a field by tying a rope to a stick and giving one end of the rope to the owner of the field to hold, while himself keeping the stick into his own hand. The rope-holding minister (or surveyor) happened to put the stick in a crab's hole with the crab inside, whereupon he thought: 'If I put the stick into the hole, the crab in the hole will be hurt; if I put it on the other side the king's property will lose; and if I put it on this side, the farmer will lose.'
- (iii) Land revenue administration The local officials who carried on the civil, judicial and military administration appear also to have carried on the work of collecting the revenue. The Central Government, however,

<sup>1104</sup> I. 18 1 (= S. B. E., Vol. XIV. p. 199)

<sup>1. 42 (=</sup> S. B. E., Vol. XIV. p. 8)

<sup>229-30).</sup> E. Vol. II. pp.

sutasoma Jātaka (No. 155); Mahā-

<sup>1100</sup> Káma Játaka (No. 467).

<sup>2149</sup> XIX. 26 (=S. B. E), Vol. XIV. p. 99.

No. 467 : Rājakammikā khettappamānā-gabanatthāya tam gamam agamimau.

<sup>\*1\*1</sup> No. 276.

maintained a body of officials who co-operated with the local bodies in this respect. In the Jataka period Northern India was divided into sixteen independent states (solasamahājanapadāni). 1128 Some of these states were organised into provinces under viceroys and the province into districts (janapada) and villages. Thus the Kama Jataka 193 tells us that a prince, having at first no desire to rule his kingdom, left it but later on became greedy and won over a village. Then he wanted to have the janapada and the viceroyalty (uparājjam) as well. The Mahāswapna Jātaka2124 also refers to kingdom (ratta), district (janapada) and village (gīma) in successive order. From the Kharamvara Jātaka 195 we find that the revenue specially from the distant border villages was collected by an amachcha. According to Apastamva2196 the king should appoint men of the first three castes who are pure and truthful over villages and towns ..... (and) shall make them collect the lawful taxes. The royal share known as vali was collected generally in kind. The produce of the field was taken to the public granary for the excision of the royal tithe before being taken to the barns of the respective owners. Such public granaries were in charge of officers who are aptly called Drona-mapaka mahamatto. In the Kurudharma Jataka 197 we art told that sitting at the door of the granary he caused to be measured the king's share of the produce. The tax was collected by officials called Valisadhaka and Rījakammika. 2198 Though the vali was usually paid in kind, cash payment was not altogether unknown. Thus the Vardhaki-sukara Jataka 199 records the gift of the satasahassutthāyikam Kāsigāmam [a village of Kāsī yeilding 100,000 (kahāpanas) as revenue]. The Avarya Jataka 2 200 also refers to a village yielding the same amount.

Agriculture-Most of the arable land was cultivated by peasantproprietors (khettapati, vatthupati) and cultivation of lands by peasants

<sup>2125</sup> Rhye Davids-Buddhist India, p. 23.

<sup>1100</sup> No. 467.

<sup>2106</sup> No. 77.

<sup>2110</sup> No. 79.

<sup>11. 26, 4, 9 (-</sup>S, B, B, Vol. II. pp. 163-64).

No. 276 : Kotthägåradväre nislditvä räjabhäge vihim minäpento.

Jātaka (No. 467); Gaṇdatindu Jātaka (No. 520).

<sup>100</sup> No. 283.

<sup>2200</sup> No. 376.

for princes was regarded as a mark of social decay.<sup>2101</sup> From the Mahā vagga<sup>2202</sup> we learn that Buddhist saṃghas sometimes cultivated lands belonging to private persons and used to get half of the produce as their share or sometimes let out their own lands in lieu of half of the produce. "Of the seedlings belonging to the Saṃgha, grown upon private ground, half the produce, O Bhikkhus, you may have, when you have given a part to the private owner. Of seedlings belonging to private persons grown up on the ground, the property of the Saṃgha, you may have the use, when you have given a part to the owner."

(a) Agricultural operations: In the Suttanipata we have the story of Kāsī Bharadwāja where we find mention of the plough (nangala), the oxen-team, the yoke (yuga) and the goad (pacana). The Sakuna Jataka 2203 describes the successive stages of agriculture. In it we are told that when a Buddhist monk asked the villagers to build a house for him the latter agreed to do so after the rains have come and watered their fields ; when the rains came and watered their fields they agreed to build the house for the monk after sowing the seeds; when seeds were sown they agreed to do the monk's work after enclosing their fields; when their fields were fenced, they agreed to do the monk's work after clearing up the weeds in their fields; when the weeds were cleared up they agreed to do the monk's work after reaping the harvest; when the harvest was reaped, they agreed to do the monk's work after the corn had been threshed on the threshing floor; in this way the work of building a house for the monk was indefinitely put off. In the Chullavagga2104 Mahānāma the Sakyan thus describes the farming operations: "First you have to get your fields ploughed. When that is done, you have to get the water let down over them. When that is done, you have to get the water let off again. When that is done, you have to get the weeds pulled up. When that is done, you have to get crops reaped. When that is done, you have to get the crops carried away. When that is done, you have to get it arranged in bundles. When that is done, you have to get it trodden out.

<sup>1901</sup> Janka I. 339.

<sup>9303</sup> VI. 39, i (=S. B. E., Vol. XVII.

VI. 39, i (= S. B. E., Vol. XVII p. 143)

No. 36.

<sup>9904</sup> VII. 1, 2.

When that is done you have to get the straw picked out. When that is done, you have to get all the chaff removed. When that is done, you have to get the harvest garnered. When that is done, you have to get the harvest year and the same all over again the year after". The Uraga Jātaka (No. 354) refers to the custom of maid-servants bringing food to the cultivators working in the field.

- (b) Protection of the crops: In the Rigvedic period the cultivators kept away birds from the corn fields by making din and noise. 2205 But in this period as the Śīlikedīra Jītaka 2206 shows, nets made of the hair of horse's tail were used for catching birds that used to eat up the crops. The Mahāvagga (I. 50) even refers to the use of scare-crows. In the Lakṣaṇa Jātaka 2207 we find that to kill the deer which used to eat up the harvest, the cultivators used to dig up pits, place snares, fix stakes and pāsāṇa yanta (stone-made instruments to catch beasts).
- (c) Ceremonies connected with agriculture:—For success in agriculture the Grhyasūtras prescribe a number of ceremonies. Thus there is a rite for ploughing when sacrifice is made to aśani (thunderbolt) and to Sitz (furrow) as well as to Aradā, Anghā, Parjanya, Indra and Bhaga with similar offerings on the occasion of the threshing floor sacrifice, when one reaps the harvest or sows the seeds, all portraying the life of the agriculturist who also offers a sacrifice at mole-heaps to Akhurāja, the king of moles. 220 s
- (d) Rainfall: -The North-western part of the country seems to have enjoyed sufficient rainfall. Aristobulus 100 recorded that rains began when the European army reached Taxila in the spring of 326 B. C. and became continuous with the prevalence of the monsoon, all the time they were marching eastward along the foothills of the Himalayas. When the Greeks looked round upon the features of the country India seemed, before anything

<sup>1900</sup> Rig Veds, X. 68. 1

<sup>9505</sup> No. 484.

<sup>9907</sup> No. 11.

osos Govila Grhyactira, IV. 4. 281; Ibid., 301.

ef. C. 697.

else to be the land of rivers. 2210 Megasthenes mentions 58 rivers of which thirty-five names are preserved and are still recognisable to-day. 2211

- (e) Irrigation :- Despite this natural supply of water various methods of irrigation were also known. From the Dharmapada 2212 it appears that the boundaries of each house-holder's plot of arable land were made by channels dug for co-operative irrigation. These dividing ditches, rectangular and curvilinear, were likened to a patch-work robe, prescribed by the Buddha as a pattern for the uniform of his order.2218 The Kama Jataka2214 speaks of a brahmin making little embanked squares for water. We also hear of the rivers being dammed for the purpose of irrigation. We thus read in the Kunzla Jataka: 2215 "The Sakyas and the Koliyans had the river Rohini which flows between the cities of Kapilavastu and Kolia, confined by a single dam and by means of it cultivated their crops. In the month of Jettamula when crops began to flag and droop, the labourers from both the cities assembled together. Then the Koliyans said Should this water be drawn off on both sides it will not prove sufficient for both us and you. But our crops will thrive with a single watering, give us then the water."
  - (f) Cultivated plants:—The Grhyasutras prove that there were two harvests a year and that the people long realised the advantages of a rotation crops in that a season of barley was succeeded by one of rice. 2216 As to the cultivated plants we find the names of (1) vrihi (rice) 2217 (2) gandha-

<sup>5920</sup> Strabo XV. C. 689.

Pliny-Natural History, VI. Art. 641.

Dhp., verse 80 - 145 - Therag. 19.

Vinaya Texts, II. 207-09; Mah., VIII. 12; cf. Psalms of the Brethern, p. 152.

<sup>2214</sup> No. 466.

<sup>2218</sup> No. 536,

wate Vrihiprabhitya a yavebhyo yave-

bhyo vi vrihibhya swayam haret svayam haret—Khadira Grhyasütra, I. 5. 37 (—S. B. E., Vol. XXIX. p. 388); also Govila Grhyasütra, I. 4. 29.

<sup>\*\*\*\*\*</sup> Mahäsvapna Jätaka (No. 77);
Sudhäbhojana (No. 535); Aśvalayana Grhyasūtra, I. 11, 2; I. 9. 6;
I. 17, 12; Sankhyāyana Grhyasūtra,
I. 17, 7; I. 22, 5; I. 24, 3; I, 29, 6;
III. 1, 3.

śali<sup>2918</sup> (3) chinaka<sup>2219</sup> (4) tandula<sup>2220</sup> (5) śyamaka<sup>2221</sup> (6) yava<sup>2222</sup> (7) godhuma<sup>2223</sup> (8) mudga<sup>2224</sup> (9) masa<sup>2225</sup> and (10) sugarcane.<sup>2226</sup>

The Jātakas<sup>2 2 2 7</sup> refer to the parnikas who used to earn their living by growing green vegetables on their fields. Among the green vegetables we find the mention of (1) gourd (alāvu)<sup>2 2 2 8</sup> (2) pumpkin (kuṣmānda, <sup>2 2 2 8</sup> valiva)<sup>2 2 3 0</sup> (3) eucumber<sup>2 2 3 1</sup> (4) ervāruka (a kind of cucumber) <sup>2 3 3 2</sup> (5) yagdummura (a kind of fig)<sup>2 3 3 3</sup> (6) garlic<sup>2 3 3 4</sup> (7) radish (mūlā)<sup>2 2 3 5</sup> (8) a kind of sweet potatoes (mīluvā)<sup>2 3 5 6</sup> and (9) pot-herbs or esculent vegetables (šāka).<sup>2 2 3 7</sup> The Viśwantara Jātaka<sup>2 2 3 8</sup> refers to karoti (=rājamāsa=Bengali varbati) and to kalamvī. The leaves of a shrub (gulma) called kāra<sup>2 2 3 9</sup> and of Indravaruņī tree<sup>3 2 4 0</sup> were taken by the people after boiling them. Among different varieties of kanda (bulbous or tuberous

9918 — Scented rice (Keśava Jātaka No. 346).

• = Sanskrit vrihibheda (Sudhābhojana Jātaka No. 535).

Nikkunduka thusā swayamjūta tandulasisāni—rice that comes from the plant, having no husk etc. (Sudhābhojana Jātaka No. 535).

\*\*\*\* The seeds of a kind of grass called syama which were eaten by the poor (Sudhabhojana Jataka No. 535).

Mahāswapna Jātaka (No. 77);

Aśvālāyana Gṛḥyasūtra, I. 11. 2;

I. 9. 6; I. 17. 2; Sāūkhyāyana
Gṛḥyasūtra, I. 24. 3; I. 28. 6;

III. 1. 3; IV. 4. 9.

2225 Mahaswapna Jataka (No. 77).

Mahāswapna Jātaka (No 77); Sāākhyāyana Gṛhyasūtra I, 22. 5; Pāraskara Gṛhyasūtra, I. 15. 4.

auss Mahāswapna Jātaka (No. 77).

in the Sudhabhojana Jataka
(No. 77). In Pali it is the collective name for mudga, masa, tila,

alavu and kuşmanda. In Sanskrit it means a kind of beans.

4227 Kuddāla Jātaka (No. 70); Parņika Jātaka (No. 103).

2228 Knddāla (No. 70); Mahāswapna (No. 77); Parņika (No. 102); ṣaḍadanta (No. 514); Soumanasya (No. 505).

\*\*\*\* Kuddāla Jātaka (No. 70); Parņika (No. 102); Soumanasya (No. 505); şadadanta (No. 514).

2230 Viśwantara Jātaka (No. 547).

saat Kuddāla Jātaka (No. 70).

9932 - Pāli Elāluka (şadadanta No. 514).

2225 Udamyara Jataka (No. 298).

Viśwantara (No. 547); Savarnabamsa (No. 136).

Pañchāyudha Jātaka (No. 55).

Sudhābhojaņa (No. 535); Kunāla (No. 536); Viśwantara (No. 547).

asav Kuddāla Jātaka (No. 70); Parņika (No. 102).

assa No. 547.

ansa Akirti Jataka (No. 480).

suso Ibid.; Krana Jataka (No. 440).

roots) the Takkala<sup>9241</sup> and Viśwantara Jatakas<sup>2342</sup> mention (1) takkala (2) ālupa (3) virālikā and (4) kalamva which according to the commentator are (1) piņdālu (2) ālukanda (3) virālavalli kanda and (4) tālakanda respectively.

Of oil-bearing plants sesamum<sup>9948</sup> and mustard <sup>2944</sup> are frequently mentioned. Among spices the Jātakas refer to (1) ādraka (ginger)<sup>9245</sup> (2) jiraka (cumin-seed)<sup>2946</sup> (3) marica<sup>2247</sup> and (4) pippali (pepper).<sup>2948</sup>

Of colour-bearing plants indigo 9 3 4 9 was the most important.

As to fibrous plants kārpāsa is mentioned for the first time in the Āśvālāyana Śrautasūtra. 2250 Herodotus also speaks of the cotton plant as yielding vegetable wool "surpassing in beauty and quality the wool of sheep and the Indians wear clothing from these trees." From the Mahāvagga we learn that šimula or cotton silk mentioned in the Jātakas 2250 was used in the preparation of quilts (tulika) stuffed with cotton-wool. Sana (Crotalaria Junica) is mentioned in the Sāhkhyāyana Grhyasūtra 2853 and in the sūtras of Pāṇini. Linen flax (Linum Usitatissimum) was also known. 2354 Makaci, a kind of fibre with which strainers were made is mentioned in the Vālodaka Jātaka. 2250

Forests and their economic importance—The forests continued as in the earlier periods to serve the purpose of natural pastures. "The

# 68

<sup>1242</sup> No. 446.

<sup>2240</sup> No. 547.

<sup>\*\*\*\*</sup> Aśvālāyana Gṛhyasūtra, I. 9. 6;
I. 17.2; II. 4. 4; IV. 4.13; IV. 7.
11; Khadira Gṛhyasūtra, IL 2. 26;
I. 3. 18; IV. 1. 16; Pāraskara
Gṛhyasūtra, I. 15. 4; II. 6. 17;
Sānkhyāyana Gṛhyasūtra, I. 28. 6;
III. 1, 3; IV. 1. 3; IV. 3. 4.

Viśwantara Jātaka (No. 547); Pāraskara Grhyasūtra, I. 17. 23; Sānkhyāyana Grhyasūtra, III. 1. 3.

Jātaka (No. 125). Godhā

<sup>234:</sup> Romaka (No. 277); Godhā (No. 325).

sats Godha Jataka (No. 325).

Sääkhyäyana Grhyasütra, 1. 23. 1; compare Nili of Viśwantara Jütaka (No. 547).

<sup>2250</sup> V. 4. 17.

<sup>9251</sup> McCrindle's Ancient India, III. 105.

apas Khullanarada Jataka (No. 477).

пави Т. 24, 11,

<sup>2004</sup> Chullaśresthi Jataka (No. 4).

<sup>9955</sup> No. 183.

Bodhisattva had a herdsman who when the corn was growing thick. drove his cows to the forest and kept them there at a shieling,"2250 Secondly, they supplied the people with wild rice2257 and esculent vegetables,2958 In the third place, the forests were a perennial source of supply of fuel and timber. 2959 In the fourth place, the forests supplied the people with aloe (aguru), 2260 bdellium (guggulu), 2261 spikenard (naladī),2962 camphor (karpūra),2263 liquorice (yastimadhu),2364 costus (kustha), \$365 lac (laksa), 2366 tail of a yak, 2367 ivory 2268 and sandalwood. 2209 Sandalwood-powder used by ladies as a toillete for the breasts, 9270 essence of sandalwood (candanasara) 9371 and sandalwood oil3272 were highly prized. In the fifth place, the forest-tracts served as habitations for certain classes of people. According to the Pancha-upsattha Jataka 2273 people who had curbed their worldly desires inhabited these regions. The Sūtras 2874 also describe different classes of hermits living in these forests. The forests were also the habitations of the Ataviyas who appeared to have been fully acquainted with the forest-paths and used to hire themselves out as guides to cara-

Viśwasabhanjana Jataka (No. 93); Sandhibheda Jataka (No. 349).

Vālāhāśva (No. 196); Palāša (No. 368); Višwantara (No. 547). In the Višwantara Jātaka wild rice of two different kinds is mentioned (1) Swayam Sātikā = Pāli Samsādiyā.

According to commentator it is otherwise known as Sakarašāli (2) Prasātikā = Pāli Pasādiyā.

Parpika Jataka (No. 102).

<sup>2200</sup> Alinacitta Jataka (No. 156).

Bhailatika (No. 504); Khandahala (No. 542); Viśwantara (No. 547).

Mātanga Jātaka (No. 497); Viśwantara Jātaka (No. 547).

<sup>2442</sup> Viswantara Jataka (No. 547).

Viśwantara Jūtaka (No. 547);
Andhabhūta Jūtaka (No. 62).

<sup>9204</sup> Viśwantara Jataka (No. 547).

sees Ibid.

Nyagrodhamiga Jātaka (No. 12); Kāhāntivādi (No. 313); Suvarņamiga (No. 359); Vidurapaņdita (No. 545).

<sup>1367</sup> Nyagrodhamiga Jataka (No. 12).

<sup>\*\*\*</sup> Kājāya Jātaka (No. 221).

<sup>3350</sup> Kunāla Jātaku (No. 536); Viśwantara Jātaka (No. 547).

<sup>3070</sup> Kuśa Jataka (No. 537).

<sup>3171</sup> Kurudharma Jataka (No. 276).

<sup>1979</sup> Kaśa Jātaka (No. 537).

<sup>1113</sup> No. 490.

Apastamva, H.9. 13 (= S. B. E., Vol. II. p. 123.; Bandhayana, III. 3 (= S. B. E., Vol. XIV. p. 291 ff.; Gautama, III. 2 (= S. B. E., Vol. II. p. 192).

vans. 3275 Lastly, some of the forest-tracts were extremely valuable for their supply of elephants. The earliest reference to elephant-forests (mātangāranya) is probably in the Mahāvagga. 2276 The Majjhima Nikāya also refers to elephant-preserves (nāgavana). 2277

The various useful trees known to the people of this period are:—(1) Tirîti<sup>2278</sup> = Tirita of Amara (2) Śallakī.<sup>2279</sup> According to the commentator it is Indraśāla tree (= Boswellia Thurifera). From its extract (niryyāsa) a scent called lavān or kundurā was prepared (3) Karpūra (camphor)<sup>2250</sup> (4) Khadira<sup>2251</sup> from which we get catechu

- (5) Bhanga<sup>2282</sup> from which a narcotic (hemp) is obtained (6) Aśvakarna<sup>2283</sup>
- (7) Aśvattha 2384 (8) Palaśa 2285 (9) Tvaksāra (bamboo) 2286 (10) Kūtaja 2287
- (11) Visa<sup>2288</sup> (12) Šimula (silk-cotton tree)<sup>2289</sup> (13) Šīla<sup>2290</sup> (14) Tilaka<sup>2291</sup> (15) Soubhañjana (=Sajinā)<sup>2292</sup> (16) Varuņa<sup>2293</sup> (17) Vūrjja (Birch)<sup>2294</sup>
- (18) Vediša<sup>2295</sup> (19) Venu<sup>2296</sup> (20) Muchakunda<sup>2297</sup> (21) Picu-
- <sup>227.0</sup> K<sup>§</sup>hurapra Jātaka (No. 265); Jayaddvisa (No. 513).
- 2276 X. 3, 1,
- See Epigraphica Indies, Vol. II. p. 265).
- 2279 Kunāla Jātaka (No. 535).
- Viśwantara Jātaka (No. 547); Mātrpoşaka Jātaka (No. 455).
- \* Andbabhûti Jâtaka (No. 62); Viswantara (No. 547).
- 2201 Kandagalaka Jataka (No. 210); Vis. wantara (No. 547).
- 8200 Sadhabhojana Jataka (No. 535).
- 8200 Kakkara Jätaka (No. 209); Viswantars (No. 547).
- Samkalpa Jātaka (No. 210); Palāša (No. 305); Sadhābbojana (No. 535); Višwantara (No. 547).
- Palāša Jātaka (No. 305); Palāša (No. 368); Višwantara (No. 547).
- was Tvaksara Jataka (No. 368).
- Matrpojaka Jataka (No. 455); Kunala (No. 536); Vidwantara Jataka (No. 547).

- 220 Māirposaka Jātaka (No. 455).
- 3950 Khullanarada Jataka (No. 477).
- (No. 506); Nalinika (No. 526); Sudhābhojana (No. 535); Kunāla (No. 536); Višwantara (No. 547).
- Nalinikā (No. 526); Sudhābhojana (No. 535); Kunāla (No. 536); Vidurapaņdīta (No. 545).
- Sudhābhojans (No. 535); of Akṣiva

   Sajinā in Viśwantara Jātaka
  (No. 547); Sovāñjana Sajinā in
  Viśwantara Jātaka (No. 547).
- Varuns in Viswantara (No. 547).
- Sudhabhojana (No 535); Kunala (No. 536); Nalinikā (No. 526).
- Sodhābhojana Jātaka (No. 535).
- Buos Ibid.
- Sudhābhojana Jātaka (No. 535); Vidurapandita (No. 545); Muchilinda – Muchakunda in Kunāla Jātaka (No. 536).

manda (=Necm)<sup>2298</sup> (22) Kuravaka<sup>2399</sup> (23) Chetasa<sup>2300</sup> (24) Bajuḍa<sup>2301</sup> (=sanskrit Vaŭjula) (25) Punnāga<sup>2303</sup> (26) Priyaka<sup>2203</sup> (=Piyāśāla) (27) Āsana<sup>2304</sup> (28) Sarala<sup>2303</sup> (Pine) (29) Kāṇāgula (=Kālāguru)<sup>2306</sup> (30) Padmaka<sup>2307</sup> (31) Devadāru<sup>2308</sup> (32) Kakudha (=
Kakubha = Arjuna)<sup>2309</sup> (33) Kachchikāra<sup>2310</sup> (34) Tūṇa (=Toon)<sup>2311</sup>
(35) Kaṇavera (=Karavira)<sup>2312</sup> (36) Karaṇdaka<sup>2313</sup> (37) Kovidāra<sup>2314</sup>
(38) Anangana<sup>2315</sup> (39) Anavajja<sup>2316</sup> (40) Suruchira<sup>2317</sup> (41) Bhagini<sup>2318</sup>
(42) Dhanukārika <sup>2319</sup> (43) Tālisa (=Tāli = Paniyalā)<sup>2320</sup> (44) Koṭṭa<sup>2311</sup>
(45) Saptaparṇi<sup>2322</sup> (46) Uparibhadra<sup>2323</sup> (47) Karajña (=Karañjaka = Dalbergea Arborea)<sup>2324</sup> (48) Dhava.<sup>2325</sup> It is called Dhao tree in Orissa and in
the Santhal Pargannas (49) Dhātri<sup>2326</sup> (50) Vallika<sup>2327</sup> (51) Putrañjīva<sup>2328</sup>
(52) Kosamva<sup>2329</sup> (53) Somavṛkṣa<sup>2330</sup> (54) Pañgura<sup>2331</sup> (55) Mahā-

Päli Puchimanda (Pichumanda Jätaka (No. 310).

Kunāla Jātaka (No. 536); Švetapuspā Jhinti - Kuravaka while pītapuspā Jhinti - Kuraņţaka.

2500 Ibid.

saos Ibid.

seos Ibid. ; Viśwantara Jataka (No. 547).

Piyāšāla in Viswantara (No. 547); cf. Ajurkarņa — Piyāšāla in Viswantara (No. 547). Piyāšāla — Pentaptera tomentosa.

saos Kunāla Jātaka (No. 536).

1804 Ibid.; Viśwantara Jataka (No. 547).

\$308 Kunāla Jātaka (No. 536).

1807 Ibid., Viśwantara Jataka (No. 547).

asoe Kunāla Jātaka (No. 536).

2800 Ibid.; Viśwantara (No. 547); of. Kakuda in Viśwantara (No. 547).

2310 Ibid.

\*\* Kunāla Jātaka (No. 536).

2819 Ibid.

2515 Viśwantara (No. 547). It may be Kurupţaka of Amara; cf. Koranda of Kunāla Jātaka (No. 536). 9014 Viśwantara (No. 547); Kunāla Jātaka (No. 536).

\*215 Kunala Jataka (No. 536).

and Ibid.

2517 Ibid.

pandita Jataka (No. 545).

to the commentator it is the same

as Dhanupātali.

2890 Kunila Jätaka (No. 536); Vlśwantara Jätaka (No. 547).

ssei Kunāla Jātaka (No. 536).

Vidurapandita Jataka (No. 545); Vidwantara Jataka (No. 547).

Vidurapaņdita Jātaka (No. 545). Uparibhadra — Bhadraka — either Devādara or Kadamva

9594 Viśwantara Jataka (No. 547).

Spandana Jūtaka (No. 475); Višwantara Jūtaka (No. 547).

2886 Viśwantara Jataka (No. 547).

2527 Ibid. Vallika - Vallațaka (P).

1820 Viśwantara Jūtaka (No. 547).

2320 Ibid.

asso Ibid. Somavikas = Soma plant (?).

nāma 333 (56) Švetaparņi 2333 (57) Švetāguru 2334 (58) Jatāmāmsi 2356 (59) Nīlapuṣpi 2356 (60) Švetavārī 2337 (61) Kateruha 2338 (62) Tulasī plant 3836 (63) Asītaru 2340 (64) Katamāla (Viswantara Jātaka) = Kṛtamāla of Amara = Sonāli) (65) Coeha (Kunāla Jātaka). According to Amara it belongs to the 'guratvak' species (66) Phaṇijjaka (Viswantara Jātaka) = Phaṇijjhaka of Amara. According to Amara it belongs to the 'Jamvīra' species and (67) Kakkola from which a gandhadravya was prepared.

Among the flower plants and trees the following are mentioned in the literature of this period:—(1) Kusumbha (safflower)?341 (2) Karnikāra = Uddālaka = Sonāli = Casia fistula 2349 (3) Kantakuraņda 2348 (4) Kim-śūka 2344 (5) Kadamya 2345 (6) Añkola = 2346 Añkolaka = Añkolla = Añkolā = Añkotha (?) of Amara. According to the author of Flora Indica it is Bengali Ákārakantha. (7) Sattali (Pāli) = Sans. Saptali = Bengali Navamālikā 2347 (8) Mādhavi 2348 (9) Yūthikā 2340 (10) Lodhra 2350 (11) Sthalapadma (plant) 2351 (12) Ketakī 2352 (13) Vakula 2353 (14) Cham-

```
....
      Viswantara Jütaka (No. 547).
2359
      Ibid.
2243
      Ibid.
sees Ibid.
9055
      Toid.
5556
      Ibid.
#887
      Ibid.
8658
      Ibid.
BBB 9
      Thid.
             The commentator adds the
2540
      Toid.
                 Siniddhaya
                             bhūmiyam
       thita talaviya rokkha.
      Puspabhakta Jātaka (No. 147).
8041
      Dardara (No. 172); Bhallatika (No.
       504); Chāmpeya (No. 506); Nali-
       nikā (No. 526); Sudhābhojans
       (No. 535); Kunāla (536); Khanda-
```

bala (No. 542); Vidurapandita

(No. 545); Viswantara (No. 547).

Dardara (No. 172); cf. Karandaka

Kimsakopama Jātaka (No. 246); Kunāla (No. 536); Višwantara

in Viswantara Jataka (No. 547).

2042

2566

(No. 547). The Viswantera Jätaka (No. 547) refers to a plant called Kimsukalatikā.

Mahotkrośa (No. 486); Nipa-Kadamya in Kimehhando (No. 511) and Viśwantara (No. 547).

Nata Vallāţika Jātaka (No. 504); Kunāla (No. 536); Viśwantara (No. 547).

sear Vallätika Jätaka (No. 504)

Vallāţika Jātaka (No. 504); Atimuktaka — Atimukta — Mādhavilatā in Kunāla Jātaka (No. 536).

vallāţika Jātaka (No. 504); Yodhi
— Yodhikā — Yūthikā in Kunāla
(No. 536) and Viśwantara (No. 547).

8050 Sudhabhojana Jataka (No. 535).

ansı Ibid.; Viśwantara (No. 547).

Sudhābhojana (No. 535); Kunāla (No. 536); Vidurapaņdita (No. 545); Višwantara (No. 547).

80 Kunāla Jātaka (No. 536); Viéwantara Jātaka (No. 547). naka 4554 (15) Asoka 2858 (16) Nagakesara 4858 (17) Vanamallika 2857 (18) Tagara<sup>2353</sup> (19) Nāgamālikā<sup>2359</sup> (20) Nāgavalli<sup>2560</sup> (21) Madhuka<sup>2361</sup> (22) Nyagrodha<sup>2562</sup> (23) Kuravaka<sup>2863</sup> (24) Patali<sup>2564</sup> (25) Sindhuyāra = Nisinda 2365 (26) Bhandi = Bhandila = Sirisa or Ghentu flower 2366 (27) Jātī 3867 (28) Sumana 3868 = Davala Yūthikā or Mallikā (29) Madhugandhika2369 (30) Śwetachchha9370 (31) Raktamāla = Naktamāla2371 (32) Šimšapā 4379 (33) Asphotaka 4378 (34) Sūryyavallī 2374 (35) Anoja 4375 (36) Vāsanti 3376 (37) Kimsukalatikā 3377 (38) Padmottara 3378 (39) Elamvara, 2379 a plant of the draksa species the scent of whose flowers last for a week. 9380

Among the fruit trees of this period the following are the most important :- (1) Mango 2 3 8 1 (2) Dhruvaphalo Amyo (mango tree which yeilded

---Kunāla Jātaka (No. 536); Vidurapandita Jataka (No. 545).

2585 Kunāla (No. 536); Khapdahāla (No. 542); Viśwantara (No. 547).

Viswantara (No. 547); cf. Nagarukkba (Pali) = Nagaviksa - Nagakesara (?) in Kunāla (No. 536).

自然在中 Kunāla Jātaka (No. 536).

1056 Ibid. ; Viswantara (No. 547).

国用茅草 Vidurapandita (No. 545). In the Dravida land a kind of Yathika flower is called Nagamalli.

Viśwantara Jātaka (No. 547).

\$8 # E This tree yields Mahul flower. Mabāsyapna (No. 77); Samkalpa (No. 251); Saktigulma (No. 503); Sudhābhojana (No. 535).

2562 Samkalpa Jätaka (No. 251); Sudhābhojana (No. 535),

Vallāţika Jātaka (No. 504).

Vallāţika (No. 504) ; Chāmpeya (No. 506); Nalinikā (No. 526); Sudbā bhojana (No. 535); Khapdahāla (No. 542); Viswantara (No. 547).

Vallatika (No. 504); Sudhabhojana (No. 535); Viderapandita (No. 545). Compare Nirgund! - Nisinda in Viśwantara Jātaka (No. 547).

Kunāla (No. 536); Viswantara (No. 547); Sirişa is mentioned in Viswantara Jataka (No. 547).

Kunāla Jātaka (No. 536); Viśwantara Jātaka (No. 547).

2524 Kunāla Jātaka (No. 536).

-Viswantara Jataka (No. 547).

SETS Ibid.

BOTL Thid.

2375 Ibid.

STRE Ibid. Is it Asphota of Amara? Asphota is another name of Apardjita,

BETA Ibid.

**E378** Ibid.

STER Ibid.

1577 Thid.

SSTR Toid.

Ibid. 1980 Ibid.

....

2592 Dašabrāhmaņa Jātaka (No. 495); Champeys (No. 506); Nalinika (No. 526); Khandahala (No. 542); Vidurapandita (No. 545); Viśwantars (No. 547).

mangoes throughout the year)<sup>2582</sup> (3) Jamvu (black-berry tree)<sup>2383</sup> (4) Vilva<sup>2584</sup> (5) Vadari<sup>2585</sup> (6) Kapittha<sup>2386</sup> (7) Kharjjura<sup>2387</sup> (8) Tāla<sup>2388</sup> (9) Cocoanut<sup>2389</sup> (10) Haritaki<sup>2390</sup> (11) Āmalaki<sup>2391</sup> (12) Vibhītaka (Vahedā) <sup>2892</sup> (13) Tinduka (Gāva or Ebony)<sup>2593</sup> (14) Udamvara<sup>2394</sup> (15) Kuruvinda = Mūthā or Vādāma (Terminalia catappa)<sup>2395</sup> (16) Panasa<sup>2396</sup> (17) Piyāla<sup>2397</sup> (18) Lakucha<sup>2398</sup>(19) Lavuja <sup>2399</sup> (20) Kāra, a shrub<sup>2400</sup> (21) Kadalī (plantain)<sup>2404</sup> (22) Mocha (Pāli).<sup>2404</sup> According to the commentator it is aṣtikadalī (= Bengali Vichekalā) (23) Timvaru<sup>2403</sup> which yields a kind of Gāva fruit (Diospyros glutinosa) (24) Drākṣā (vine)<sup>2404</sup> (25) Saha<sup>2405</sup> (= Sahakāra, according to the commentator). The tree which yields scented mangoes is called Sahakāra (Sahakārah atisourabhah). In Sanskrit, however, Saha means other kinds of trees like Rāsuā.

Among shrubs, plants and trees yielding scents we find (1) Haridra 406 (turmeric, curcuma, haldi) (2) Kustha (costus) 2407 (3) Agurū (aloe) 2408 (4) Narada (= nalada, naladi, spikenard) 2409 (5) Guggulu (bdellium) 2410

```
Savaka Játaka (No. 309).

Dašabrāhmaņa Játaka (No. 495).

Chāmpaya (No. 506); Nalinikā (No. 526); Sudhābbojana (No. 535);

Vidurapandita (No. 545); Višwantara (No. 547).
```

pasa Dašabrāhmaņa Jātaka (No. 495).

sass Ibid.; Viswantara (No. 547).

<sup>2000</sup> Viśwantara Jataka (No. 547).

in Sudhābhojana Jātaka (No. 535).

vinilaka Jātaka (No. 160); Marksta (No. 173); Suvarņakarkata (No. 389); Višwantara (No. 547); cf. Vibhedaka = Tāla tree in Višwantara Jātaka (No. 547)

<sup>2000</sup> Viśwantera Jataka (No. 547).

Daśabrahmana Jataka (No. 495); Viśwantara (No. 547).

<sup>2501</sup> Dafabrāhmaņa Jātaka (No.495).

<sup>2512</sup> Karkara (No. 209); Dašabrāmaņa (No. 495); Višwantara (No. 547).

<sup>(</sup>No. 305); Saktigulma (No. 535); Sudhābhojana Jātaka(No. 535).

<sup>2014</sup> Samkalpa Jataka (No. 251).

Matrposaka Jataka (No. 455).

<sup>2300</sup> Viśwantara Jataka (No. 547).

Dašabrāhmaņa Jātaka (No. 495); Saktīgulma (No. 503).

nasa Dasabrāhmaņa Jātaka (No. 495).

<sup>2300</sup> Viśwantara Jūtaka (No. 547).

<sup>1400</sup> Saktigulma Jataka (No. 503).

padadanta Jātaka (No. 514); Sudhābhojana (No. 535).

<sup>2402</sup> Sudhabhojana Jataka (No. 535).

<sup>2452</sup> Viśwantara Jataka (No. 547).

Bags Ibid.

<sup>3405</sup> Vidurapandita Jataka (No. 545).

<sup>2400</sup> Viswantara Jataka (No. 547).

<sup>9401</sup> Ibid.

sage Ibid.

ason Ibid.

<sup>2410</sup> Ibid.

(6) Yaştimadhu<sup>9</sup><sup>411</sup> (liquorice) (7) Sandalwood<sup>2</sup><sup>412</sup> (8) Priyañga<sup>8</sup><sup>412</sup> (9) Gandhaśila<sup>9</sup><sup>414</sup> (10) Bhadramustā<sup>9</sup><sup>415</sup> (11) Šatapuṣpa<sup>2</sup><sup>416</sup> (12) Jhāmaka<sup>2</sup><sup>417</sup> (13) Tungavṛnta<sup>2</sup><sup>418</sup> (14) Hrivera<sup>9</sup><sup>410</sup> (15) Choraka<sup>2</sup><sup>420</sup> (16) Kalinga<sup>2</sup><sup>421</sup> (11) Unnaka<sup>2</sup><sup>422</sup> (18) Lolupa<sup>2</sup><sup>429</sup> (19) and Karpūra (camphor) already mentioned.

The following varieties of grass and reeds were also known in this period:—(1) Kāśa \*\*\*\* (2) Kuśa\*\*\*\* (3) Potakila (Pīli) = Potagala (Sans).\*\*\*\* It is a grass of the Sara species. (4) Pavvaja = Valvaja\*\*\*\* (5) Muñja\*\*\*\* and (6) Uśira (= Khaskhas).\*\*\*\*\*

Mines—As to minerals we find mention of (1) iron \*\*4\*\* (2) copper \*\*\*\* (3) lead \*\*4\*\* (4) tin (ranga) \*\*4\*\* (5) silver \*\*4\*\* (6) gold \*\*4\*\* (7) yellow orpiment (haritīla) \*\*4\*\* (8) manah ilā \*\*4\*\* and (9) hingulaka. \*\*4\*\* Precious stones like Vailurya \*\*4\*\* and diamond \*\*4\*\* were also known. The production of gold must have been considerable in North-western India, for, according to Herodotus, \*\*4\*\* the Indian satraphy of Darius paid a tribute exceeding that of every other people, to wit, three hundred and sixty talents of gold dust. The fact of India paying her tribute in gold naturally leads to the question—Where was the source of all this gold ? According to Hero-

```
9497
                                                        Ibid.
9411
      Thid.
      Kunsia (No. 526); Viswantara
                                                 8425
                                                        Ibid.
8819
                                                        Ibid.; Kunāla Jātaka (No. 536);
       (No. 547).
                                                 3499
viswantara (No. 547); ef, Piyangu
                                                         Sudhābhojana Jātaka (585).
       in Kunāla Jātaka (No. 536).
                                                 2400
                                                        Jarudapāna Jātaka (No. 256).
BASA
      Viswantara Jataka (No. 547).
                                                 2432
                                                        Ibid.
9415
      Ibid.
                                                 1489
                                                        Ibid.
2514
      Ibid.
                                                 9455
                                                        Ibid.
2427
      Thid.
                                                        Ibid. : Kunāla Jātaka (No. 536).
9616
      Ibid.
                                                 9455
                                                       Ibid.
3474
      Ibid.
                                                 3601
                                                       Kunāla Jātaka (No. 536).
34 80
      Ibid.
                                                 948T
                                                       Ibid.
5491
      1bid.
                                                 9450
                                                       Ibid.
5499
      Ibid.
                                                 2450
                                                        Jarudapāna Jātaka (No. 256).
9498 Ibid.
                                                 0.640
                                                        Supāraga Jātaka (No. 463).
3616
      Ibid.
                                                 9461
                                                        Rawlinson - Herodotas, Vol. II.
      Ibid.; Sudhābhojana (No. 535).
                                                         p. 487.
```

Viswantara Jataka (No. 547).

2425

dotus "there is abundance of gold in India partly brought down by the rivers and partly seized in the manner I have described." \$448 The last words refer to his famous story of the gold-digging ants which is repeated by subsequent writers like Pliny, Ælian, Chrysostom and even by more trustworthy writers like Magasthenes and Nearchos. The real origin of the theory of ant-gold was first explained by Dr. Wilson who pointed out that the Sanskrit name for small fragments of alluvial gold (gold dust) was paippalaka ( = ant-gold) in reference to their resemblance to ants in size and form. The Greeks accepted a too literal meaning of the word and supposed that gold was dug out by ants. When Herodotus says that the ants were of the size of dogs and fiercely attacked anyone carrying off the gold, it has been plausively suggested that the account was derived from people who had been chased by the formidable dogs kept by the native miners. 2448 The further addition of the myth referred to by Pliny who says that "the horns of the gold-digging ants were preserved in the temple of Hercules at Ervthral" has been explained by Professor V. Ball, Sir H. Rawlinson and Dr. Schiern. The explanation may be thus given in Professor Ball's words : "The so-called myth was not cleared up till by chance, information was received as to the customs and habits of the Tibetan gold-miners of the present day. The myrmeces of Herodotus and Megasthenes were Tibetan miners and their dogs. The horns mentioned by Pliny were the goldminer's pick-axes. I have been informed by an eye-witness, Mr. R. Lydekker that the picks in use in Ladak consist of horns of wild sheep mounted on handles."2444 Megasthenes has added the useful information that the country from which gold came was the country of the Derdae (in Sanskrit Darada or Darad = modern Dardisthan in Kashmere). 2445

It is interesting to note in this connection that from very early times mines appear to have been regarded as state property. According to Gautama all treasure-trove belongs to the king, but an exception in case of the

McCrindle's Classical Literature,

McCrincle's Ancient India, p. 44,

west Prof. V. Ball-A geologist's con-

tribution to the history of Ancient India in the Indian Antiquery, 1884.

<sup>2145</sup> Megasthenes, Fragment 29 – Strabo XV. C. 706,

treasure-trove is made when a preist is the finder and some say that anybody who finds it gets one-sixth. 2446

Cattle-rearing, pig-culture and poultry-farming:—Cattle formed an important item of wealth of the ordinary householder even in this period. Oxen were indispensible for agricultural work and apart from sacrificial use milk formed the principal drink of the people besides being the source of supply for curds, whey, butter and ghee. From the Suttanipata we learn that a Brahmin cultivator Kāsī Bharadwāja by name had five ploughs and the requisite number of oxen in addition to a large herd of cows. In the Dhaniyasutta a cultivator speaks of his wealth in cattle and is proud of his milch cows. The herds of cattle<sup>2+4-7</sup> and goats<sup>2+4-8</sup> were customarily entrusted to a communal neatherd who would bring them back every evening and count them out to the several owners.<sup>2+4-9</sup>

From the Munika<sup>2 4 5 0</sup> and Śalūka<sup>2 4 5 1</sup> Jātīkas we find that pigs were domesticated and fattened before being eaten up.

The Vartaka Jātaka<sup>2452</sup> refers to a hunter who earned his livelihood by catching quails, fattening them in his house for some time and then selling them to his customers.

Hunting and fishing—A large number of people earned their living by hunting birds and beasts. We read of hunters going to the market with eart-loads of fiesh to sell.<sup>2453</sup> For capturing deer people used to dig up pits, place snares, fix up stakes and pisāna-yanta.<sup>2454</sup> After the beaters had done their work deer were hunted either from a māchan on a tree<sup>2455</sup> or from a thatch constructed for the purpose.<sup>2456</sup> We

<sup>2440</sup> Gautam , X. 25 f.

<sup>\*\*\*\*</sup> Jätska III. 149.

<sup>2448</sup> lbid., III. 409.

<sup>2440</sup> A. I. 205 ; M. Dhp. comm. I. 157.

<sup>0410</sup> No. 30.

<sup>2011</sup> No. 286.

<sup>2443</sup> No. 118.

<sup>2405</sup> Māmsa Jūtaka (No. 315).

sasa Lakyana Jataka (No. 11.).

<sup>1455</sup> Kurangamiga Jātaka (No. 21)

deer net of leather-made straps made bright with lac were used [Nyagrodhamiga (No. 12) and Suvarpamiga Jätaka (No. 359)].

read of birds<sup>2457</sup> and peacocks<sup>2458</sup> being caught in traps made of wool<sup>2459</sup> or of the hair of horse's tail<sup>2450</sup> with the help of decoy birds.<sup>2461</sup> Lions were hunted from an 'aṭṭaka' (tower or māchan) specially constructed for the purpose.<sup>2452</sup> The method of capturing elephants described in the sadadanta Jātaka<sup>2453</sup> is substantially the same described by Megasthenes,<sup>2454</sup> the precursor of the modern 'Khedā' system.

Fishing became the main occupation of a section of the population. We read of fish being caught from rivers and tanks in nets<sup>2465</sup> or in a cage-like structure of cane or bamboo-splints called kumina. Of fish a large variety was known. We find mention of:—(1) Robita (= Bengali Rui<sup>2467</sup> (2) Pāgusa (= Sanskrit Vāgusa = Bengali Vāyuṣa i.e, Kālavāyuṣa)<sup>2468</sup> (3) Pāṭhīna (= Bengali Voyāla)<sup>2469</sup> (4) Šakulā (= Bengali Sol)<sup>2470</sup> (5) Sringī (= Bengali singi)<sup>2471</sup> (6) Vāluka (= Bengali Vele ?)<sup>2472</sup> (7) Pāvusa (= Bengali Kālavāyuṣa ?)<sup>2473</sup> (8) Muñja (= Bengali Miragela ?)<sup>2474</sup> (9) Kākiṇṇa (= Bengali Kānkley ?)<sup>2475</sup> (10) Kṣhuramāla (= a seafish with razor-like nose = sword-fish ?)<sup>2476</sup> (11) Aligargara<sup>2477</sup> (12) Savakra<sup>2478</sup> (13) Kākamatsya<sup>2479</sup> and (14) Satavakra,<sup>2480</sup> Tortoises<sup>2481</sup> corals<sup>2482</sup> and pearls<sup>2483</sup> are also mentioned.

```
sast Kakkara Jataka (No. 209).
```

sees Maytire Jataka (No. 159).

<sup>2400</sup> Kakkara Jataka (No. 209).

<sup>9100</sup> Salikedara Jataka (No. 484).

<sup>2461</sup> Kakkkara (No. 209); Mayūra (No. 159); Tittira (No. 317).

Manoja Jataka (No. 397).

<sup>3405</sup> No. 514.

Prag. 36 = Strabo, XV. 1. 41-43, pp. 704-05; Frag. 37 = Arrian-Indica, XIII—XIV.

<sup>2445</sup> Matsya Jātaka (No. 34).

<sup>\*\*\*\* =</sup> Bengali ghonā or ghūņi—Haritamāta ( = Haritamaņdaka ) Jātaka No. 239.

Chakravāka (No. 451); Sudhābhojana (No. 535); Vidurapaņdita (No. 545); Viśwantara (No. 547).

<sup>2455</sup> Vidurapandita Jataka (No 545).

Chakravāka Jātaka (No 451); Sudhābhojana (No. 535); Vidurapaņētta (No. 545); Mahānnmārga (No. 546).

stre Sudhabhojuna Jataka (No. 535).

sees Ibid.

<sup>3478</sup> Chakravāka Jātaka (No. 451).

mare Ibid.

atta Ibid.

sats Sadhabhojana Jataka (No. 535).

<sup>3476</sup> Supāraga Jātaka (No. 463).

<sup>2477</sup> Sadhabhojana Jataka (No. 535).

save Ibid.

BATS Ibid.

wase Ibid.

Mahotkrośa (No. 486); Pāraskara Gṛhyasūtra, I. 14, 5,

<sup>\*452</sup> Supāraga Jātaka (No. 463).

Anavirati Jātaka (No. 185); Jarudapāna Jātaka (No. 256).

Arboriculture:—It seems that when a cluster of villages was turned into a city, the intervening space between any two villages was trimmed with spacious parks. We find frequent mention of such parks in the Jatakas. In the Jetavana of Śrāvastī we find arbours (mālaka) of Nāga (= Nāgakeśara), Śāla, and other trees specially planted for the purpose. A gardener (udyānapāla) was appointed to see that the trees are properly watered with the help of buckets made of leather or wood. As 5 The Sānkhyāna Grhyasūtra 486 also lays down rules for the consecration ceremony of a garden.

Progress in arts and crafts : - In early times mechanics and craftsmen carned their living by serving the villagers. The Sutra "Gramah Silpini" in Panini2487 clearly points to such craftsmen attached to the village. Another sutra mentions such a village carpenter: "Gramakautabhyam ca taksana."2488 But dependence on the village compelled the craftsmen to subsist on the occasional doles and remunerations granted by the villagers according to their whims. To remedy this state of affairs, they had begun in the previous periods to organise themselves into guilds which gave them protection against oppression and helped them in making their economic condition better. When the growth of towns and town-life coupled with the development of domestic and foreign trade led to a greater demand for their products the craftsmen began to free themselves from the tutelage of the agricultural interest by withdrawing to those places where they had better opportunities of pursuing their own occupations, thus leading to the establishment of suburban industrial villages. This separation of the industrial element of the population is a notable feature of the economic life of this period, for, it is at once the effect and the cause of the remarkable growth of industry.

It is curious that the Greek observers should call the Indians backward in the scientific development of the resources of their country. They had, for instance, good mines of gold and silver, yet "The Indians

vates Varaņa Jātaka (No. 71).

Aramadusaka Jataka (No. 46).

<sup>\$480</sup> V. S. 1-5.

sens AI 5' 95'

<sup>1488</sup> V. 4. 95.

inexperienced in the arts of mining and smelting do not even know their own resources but set about the business in too primitive a way."3480 They did not pursue accurate knowledge in any line except Medicine; in the case of some arts it was even accounted vicious to carry their study far, the art of war, for instance.2490 But the construction and contents of the Piprawa Stupa belonging to 450 B. C., discovered on the Nepal frontier prove that among Indian craftsmen of 450 B. C. there were skilled masons, accomplished stone-cutters and dainty jewellers. masonry of the stupa is excellent of its kind, well and truly laid; the great sand-stone coffer could not be better made; and the ornaments of gold, silver, coral, crystal and precious stones which were deposited in honour of the holy relics display a high degree of skill in the arts of the lapidary and goldsmith." An examination of the crystal bowl and the steatite vases accompanying it shows that they are all turned on the lathe and we thus learn that the Indian lapidaries were familiar with the use of the lathe 2401 in or about 450 B. C." Equally evident is the skill of the ancient Indian craftsmen in "shaping, polishing and piercing gems of extreme hardness as well as the extensive use of jewellery of an elaborate kind."

(1) Metal industry: In fact, the metal industry was highly specialised. The word 'kammāra' mentioned in the earliest Buddhist literature is as comprehensive as our 'smith.' We find mention of weapons, tools and implements, household utensils and ornaments of various kinds. The manufacture of arrows is described in the Mahājanaka Jātaka<sup>2492</sup> and Herodotus<sup>2493</sup> describes the Indian army in the service of the Persian King Xerxes as armed with iron-headed arrows. Sword, <sup>2494</sup> adjustible sword, <sup>2495</sup> spear, <sup>2496</sup> armour, <sup>2497</sup> and iron helmet <sup>2498</sup> are also mentioned.

2000 Strabo XV. C. 700.

<sup>9400</sup> Strabo XV. C. 701.

<sup>2401</sup> Imperial Gazeteer, Vol. II.

<sup>2499</sup> No. 539,

VII. 65 (= Herodotus translated by Cary. London, 1848, p. 434.

Bhojājāneya Jūtaka (No. 23): Mahāślavaja (No. 51); Khapdahāla (No. 542); Sāākhyāyana Gṛbyaaūtra, J. 13. 1.

sans Asadréa Jataka (No. 181).

Süchi Jataka (No. 387); Paraskara Gibyasütra, H. 6, 16.

Bhojājāneya Jātaka (No. 23); Sarabhanga (No. 522); Mahāunmārga (No. 546); Āśwālāyana Grhyasūtra III, 12, 1, 3,

Mahanmarga Jataka (No. 546).

A small sword called illi<sup>2499</sup> and a sword of high quality called sikāyasamayī<sup>2500</sup> were also known. Dašīrnaka was famous for the high quality of her swords.<sup>2501</sup>

Among tools and implements we find (1) paraśu (axe), 2502 (2) vāsi (adze), 2503 (3) vāsīparaśu, a combination of the carpenter's adze and axe, 2504 (4) keen-edged saw (Pāli Krakacha), 2505 (5) bill-hook, 2506 (6) hammer, 2507 (7) fishing hook made of iron, 2508 (8) iron goad (Pāli pāchana = Sans. prājana), 2509 (9) crowbar (tomara, khanitra), 2510 (10) spade, 2511 (11) grasscutter's knife, 2512 (12) auger (nīkhādana), 2513 and (13) singhātaka (an instrument having three pointed corners like a singārā, an acquatic nut) 2514

Among domestic utensils we find (1) iron vessels, <sup>2515</sup> (2) iron jar (kumbhī), <sup>2516</sup> (3) bucket (Pāli udaāchani = Sans. udaāchana), <sup>2517</sup> (4) colander, a vessel with many holes (Pāli parisāvana karoţi), <sup>2518</sup> (5) fork (sandaṃśa) <sup>2519</sup> and (6) iron rods used in roasting meat. <sup>2520</sup> Razor made of metal, <sup>2521</sup> fine needles with case, <sup>2522</sup> key (Pāli avāpuraņa =

```
2400 Sopa (No. 529); Mahājanaka(No. 539).
```

wano Mahanmarga Jataka (No. 546).

<sup>2501</sup> Dažārņaka Jātaka (No. 401).

Tailapätra Jätaka (No. 96); Dadhivähana (No. 186); Süchi (No. 387);
Päraskara Gihyasütra, I. 16, 18;
III, 15, 21; Äśwaläyana Gihyasütra,
I. 15, 3; Sänkhyäyana Gihyasütra,
I. 28, 14.

<sup>2600</sup> Süchi Jätaka (No. 387); sadadanta Jätaka (No. 514).

<sup>2504</sup> Dadbivāhana Jātaka (No. 186).

Asitābhu (No. 234); Kṛṣṇadva; pāyana (No. 444).

<sup>2504</sup> Vaka Jataka (No. 38).

<sup>(</sup>No. 240); yadadanta (No. 514),

<sup>2608</sup> Süchl Jätaka (No. 387).

<sup>2401</sup> Süchl Jataka (No. 387).

padadanta (No. 514).

Vannupatha (No. 2); Nanda (No. 39); Midulaksana (No. 66); Kuddala (No. 70); sadadanta (No. 514).

danta (No. 514),

<sup>2512</sup> sadadanta Jātaka (No. 514).

<sup>1614</sup> Ibid.

<sup>2515</sup> Udaya Jataka (No. 458).

asaa Louhakumvi Jātaka (No. 314).

usia Udanehani Jataka (No. 106).

zote Kapota Jātaka (No. 42).

<sup>2010</sup> Karkata Jataka (No. 267).

<sup>2220</sup> Saśn Jataka (No. 316).

<sup>2821</sup> Khadira Grhyasūtra, II. 3. 27.

<sup>2131</sup> Süchi Jätaka (No. 387).

Sans. avāvaraņa)<sup>5523</sup> and seal (lānchchhana-mudrā)<sup>3524</sup> are also mentioned. Iron nets<sup>2525</sup> iron fetters<sup>2526</sup> (andu) and iron chains for prisoners<sup>2527</sup> were also in use.

Copper implements \*598 are frequently mentioned. Copper razor\*599 and copper vessels\*550 including tata used in religious worship being the most important.

Among silver wares we find (1) silver vessels<sup>2532</sup> (2) silver pot for milching cows<sup>2532</sup> (3) hare made of silver<sup>2533</sup> and (4) silver boxes for keeping ornaments.<sup>2534</sup>

Of alloys kamsa (bell-metal) is mentioned in Pāṇini. 2535 The Jātakas refer to (1) bell-metal vessels 2586 including (2) kāṃsya sthālī 2537; and kānsara, (a plate of bell-metal struck with a stick serving the purpose of a bell). 2538 Among articles made of brass (pittala) we find (1) brazen vessels, 2539 (2) bowls 2540 and (3) hare made of brass. 2541

The goldsmith is frequently mentioned and among articles of gold we find (1) gold vessels<sup>2542</sup> (2) gold pitcher<sup>2543</sup> (3) gold sthīli<sup>2544</sup> (4) gold drinking pot<sup>2545</sup> (5) gold vase (bhṛāgara)<sup>2546</sup> (6) gold plate

```
2507 Khulladhanurgraha Jataka (No.
      Srgāla Jātaka (No. 148).
#B34
                                                      374); Süchi Jataka (No. 387).
      Kalingavodki Jātaka (No. 479),
                                               8656
                                                     Losaka Jātaka (No. 41).
aras Abhyantara Jataka (No. 281);
                                               2520 Khadirangara Jataka (No. 40);
      Bhadrasala Jataka (No. 464).
                                                      Khadira Grbyasūtra, II. 5. 33;
2:20 Vaudhanāgāra Jātaka (No. 201).
1537 Thid.
                                                      III. 4. 18; III. 4, 20; III. 4, 23;
2020 Aswalayana Gthyasutra, IV. 3. 19;
                                                     III. 5. 12; Pāraskara, III. 4. 9.
      Sankhyayana Grhyasutra, I. 28.7;
                                               2250
                                                     Khadira Grhyasūtra, I. 5. 11,
       I. 28, 14; Paraskara Grhyamtra,
                                               -
                                                     Ghata Jätaka (No. 454),
                                              2002 Kāka (No. 140); Dyūta (No. 240);
       II. 1. 11, 19, 21; Aswalayana
       Grhyasutea, I. 17. 9, 10, 16.
                                                      Udays (No.
                                                                     458):
                                                                             Matanga
      Kousey! Jaka (No. 130).
                                                     (No. 497); Mahaiwaroha (No. 302);
金布田田
      Udaya Jaraka (No. 458).
                                                      Aswaldyana Grhyasutra, I. 15. 1.
      Viswantara Jataka (No. 547).
                                                     Sankhyayana Grhyasutra, I. 24. 3.
      Ghata Jātaka (No. 454),
                                               2543
                                                     Mātsuga Jātaka (No. 497).
      Vātamīga Jātaka (No. 14).
                                                     Kundaka-Kuksi-saindbava (No. 254).
-
      IV. 3. 168; IV. 5. 183.
                                               ....
                                                     Mahāśilavaja Jātaka (No. 51).
```

2246

Ibid.; Mahāsyāroha (No. 302).

Mahāsvapna Jātaku (No. 77).

(suvanna tattaka)<sup>2,5,4,7</sup> (7) gold plate worth one lac pieces<sup>2,5,4,5</sup> (8) golden basket (changotaka)<sup>2,5,4,9</sup> (9) gold spoon<sup>2,5,5,0</sup> (10) an instrument of gold used in giving honey and clarified butter to the new-born child in the Medhījanana (production of intelligence) ceremony<sup>2,5,1</sup> (11) a small pair of pincers made of gold<sup>2,5,5,2</sup> (12) golden stick<sup>3,5,3,3</sup> (13) golden dice-board<sup>2,5,5,4</sup> (14) golden dice<sup>2,5,5,5</sup> (15) golden sandals<sup>2,5,5,6</sup> (16) golden trappings for horses<sup>2,5,5,7</sup> (17) golden cage<sup>2,5,5,8</sup> (18) golden cup for a bird<sup>2,5,5,9</sup> (19) golden bedstead<sup>2,5,6,0</sup> (20) golden seat (Pāli kochchha)<sup>2,5,6,1</sup> (21) golden image of a girl<sup>2,5,6,1</sup> (22) hare made of gold<sup>2,5,6,3</sup> (23) elephant made of gold<sup>2,5,6,4</sup> and (24) gold box for keeping scents.<sup>2,5,6,5</sup>

The jeweller (manikara)\*\*\*66 and ornaments\*\*67 specially those made of gold\*\*68 are frequently mentioned. Among the ornaments of this period we find (1) kirita, tiars for the head.\*\*569 A seth's daughter Višākhā by name obtained from her father as part of her marriage-dowry a peacock-shaped tiars for her head. It was so nicely set up with pearls and gems of different colours that it looked as a real peacock and used to emit a cackling noise with the movement of wind; (2) mukhaphulla.\*\*570 According to the commentator it is "nalāṭante tilakamālābharaṇam"

ssar Sujata Jataka (No. 304).

seas Serivaņij Jātaks (No. 3); Bhojājāneya (No. 23); Mahāsvapus (No. 77); Asadrés (No. 181); Kāmanīta (No. 225); Manoja (No. 397); Tūsa (No. 338).

<sup>2540</sup> Ruru Jätaka (No. 483).

Sankhyāyana Grhyasūtra, I. 15. 1; Sankhyāyana Grhyasūtra, I. 21, 3.

Paraskara Grhyasütra, I. 5. 4.

sass Makhādeva Jātaka (No. 9).

sess Matenga Jataka (No. 497).

sees Andhabbūta Jātaka (No. 62).

sees Ibid.

<sup>1514</sup> Manoja (No. 297); Mitanga (No. 497).

seer Khandahala Jataka (No. 542).

<sup>9888</sup> Satyamkila (No. 73); Kalavahu (No. 329); Bāveru (No. 339).

assa Kalayahu Jataka (No. 329).

ssee Deuta Jataka (No. 260).

assı Mabahamsa Jataka (No. 534).

Kuśa (No. 531),

sees Ghata Jataka (No. 454).

<sup>2344</sup> Mükspangs Jätaka (No. 538).

<sup>1848</sup> Mahasilavaj Jataka (No. 51).

pandita (No. 545). Vidara-

I. S. 10; Päraskara Gihyasütra, I. S. 10; Päraskara Gihyasütra, I. S. 9; Khadira Gihyasütra, II. 4.7; II. 5.9; III. 1. 24.

Sankhyāyana Grhyasūtra, II. 2. 33; Sankhyāyana Grhyasūtra, I. 22. 17; III. 1. 7.

Kimehhande Jataka (No. 511).

<sup>1010</sup> Viswantara Jataka (No 547).

(something like our sinthi); (3) kundala, earring; 2571 (4) carring set with stones; 2572 (5) earring set with jewels; 2573 (6) necklace; 2574 (7) necklace of nisks coins; 2575 (8) golden necklace worth 1000 pieces; 2576 (9) ratnadāma, a necklace of gems; 2577 (10) ratnamaya graiveya, an ornament for the neck set with jewels; 2578 (11) kshauma. 2579 According to the commentator it is an ornament for the neck; (12) wreath of gold; 2589 (13) unnata, nose-ring (?); 2581 (14) ring for the finger of the hand; 2583 (15) keyūra, 2583 bracelet on the upper arm; (16) angada, 2584 bracelet on the upper arm; (17) golden comb; 2585 (18) valaya, 2586 bracelet on the lower arm; (19) golden bangles set with pearls and precious stones; 2587 (20) mekhalī, 2586 an ornament for the loins; (21) gingamaka, 2589 an ornament for the waist; (22) pālipāda, 2590 an ornament for the legs and (24) udghaṭṭana, 2592 an ornament for the legs.

(2) Weaving—In the Mükapanga Jātaka<sup>2598</sup> there is a nice simile from weaving. Life has been compared to a piece of cloth, Death to the weaver and Night to the woof. The weaver will place the warp first and as he places the woof, there will be less of the cloth to be woven; so also

- Bhūridatis (No. 543); Āśvālāyana Gihyasūtra, III. S. 1; Pāraskara Gihyasūtra, II. 6. 26; Sānkhyāyana Gihyasūtra, III. 1. 18.
- Rohantamiga (No. 501).
- Chāmpeya (No. 506); Nalinikā (No. 526); Unmādayantī (No. 527).
- sava Nalinikā Jātaka (No. 526).
- 3678 Kusa Jūtaka (No. 571).
- assa Kurudharma Jataka (No. 276).
- 9897 Apanpaka Jataka (No. 1).
- acra Viśwantara Jataka (No. 547).
- save Thid.
- sees Khadira Crhyasutra, III. 1. 43.
- 2002 Viswantara Jatala (No 517).

- No. 53); Parantapa No. 416).
- Champeya (No 506); Kingahhando (No. 511); Khandahāla (No. 542); Viśwantara (No. 547).
- Nied Kipehhando Jātaka (No. 511); Viśwantara (No. 547).
- 9283 Alamvuşā Jūtaka (No. 529).
- 2006 Mahājanaka Jātaka (No. 539).
- 9 . 67 Khapdahāla Jātaka (No. 542).
- Nalinikā (No. 526); Kuša (No. 531); Višwantara (No. 547); cf. mekhala in Višwantara (No. 547).
- 3600 Viśwantara Jataka (No. 547).
- 2800 Ibid.
- 2001 Robantamiga Jataka (No. 501).
- 2602 Viswantara Jainka (No. 547).
- 9893 No. 538.

with the passing of successive nights there will be less number of years for a man to live. Besides the wool of sheep and goat silk, linen and cotton formed the materials for weaving.

(a) Cotton: From the Chullavagga we learn that the Buddha allowed the bhikkhus "to comb out the cotton, and make the cotton up into pillows if it be of any of these three kinds-cotton produced on trees, cotton produced on creepers and cotton produced from potaki-grass."2504 In the Patimokkha we find weavers being employed to weave cloth for monks. The Jatakas also refer to chivara (dress of the Buddhist monks) being made by the monks themselves. 2595 The chivers consisted of (1) antaravāsaka, a small piece of cloth like a 'lungi'2596 (2) uttarāsanga which covers up the whole body from the shoulders 2507 and (3) sanghati, an upper garment which covers up the whole body from the shoulders and used only when stirring out of the monastery. 2598 A kāyavandhana, belt made of cloth, was also used by all the monks. 2599 The ordinary lay householder used to wear (1) nivisana, undergarment 2600 or sataka 2601 and (2) pravarana, upper garment. 2502 Usnisa, headdress 2503 and kañchuka, an overcoat resembling very much a dressing gown 9604 were worn by the nobility. We also find mention of (1) coverlet 2605 (2) coverlet for elephant inlaid with gold 2606 (3) coverlet for royal chariot with designs on it 3607 (4) multi-coloured coverlet for beddings 3608 (5) bathing cloth 2600 (6) cloth embroidered with gold 2610 (7) costly gandha-kāṣāya

Kuśa Jātaka (No. 531).

9410

Chullavagga, VI. 2. 6; See also IV.

44 and VIII. 1. 3.

Chullakařesthi Jataka (No. 4);

Vaka (No. 38); Varuna (No. 71);

Khullavodhi (No. 443).

Samrddhi Jataka (No. 167).

Ibid.

See Asadria Jataka (No. 181).

Chullakařesthi (No. 4); Matsya (No. 75).

Guna Jataka (No. 197).

<sup>2402</sup> Midulaksana (No. 66); Mangala (No. 87); Alinachitta (No. 156);

Kundaka-kuksi-saindhava (No. 254).

<sup>2602</sup> Gupa Jätaka (No. 197).

<sup>1604</sup> Sopananda (No. 532); Bhūridatta (No. 543).

acca Asadiśa (No. 181); Sarabhanga (No. 522).

<sup>100</sup> Apaņņaka Jātaka (No. 1).

<sup>2000</sup> Sivi (No. 499); Sops (No. 529).

Chitrasambhüta Jātaka (No. 498).

<sup>2000</sup> Tailapätra Jätaka (No. 96).

Mateya Jataka (No. 75).

sītaka, cloth dyed red and probably perfumed with aguru or musk\*611 (8) puspapata, cloth with flowers embroidered on it\*2612 (9) handkerchief (cholaka)\*2613 (10) canopy decorated with golden stars\*614 (11) screen\*615 (12) purse (sthavikā)\*2616 (13) kanthā\*617 (14) seats made of cloth\*2618 (15) pādapuāchhanam\*\*61\* (16) and pillows.\*2620 The Chuliavagga\*621 refers to bolsters which were made for the use of high officials and were of five kinds according as they were stuffed with wool, cotton-cloth, bark, grass or leaves. The floor-cloth, mosquito-curtain and sundry other articles are also mentioned.\*\*

We read of an extensive field near Benares where cotton was cultivated 2625 and of a weavers' ward in the city itself. 2624. The Therigatha and the Jatakas 2625 frequently refer to the cotton-cloth of Benares some of which were so fine in texture that they fetched a thousand pieces 2625 or even a lac. 2677 The Mahavagga 2628 and the Sivi Jatakas 2629 refer to the high quality of the cloth of the Sivi country.

(b) Linen: Cloth woven with the thread of sans was called sani. Screens were usually made of such linen cloth and were also called sani. 2630

```
usau Kātāya Jātaka (No. 221).
```

<sup>2011</sup> Chandeskinnara (No. 485).

Dana Challavagga, VI. 19; V. 9. 4.

Bhojājāneya Jātaka (No. 23); Tailapātra (No. 96); Kupdakakukṣi-saindhava (No. 254).

<sup>\*\*</sup> Kundaka-kukşi-saindhava (No. 254),

Susima Jataka (No. 163); Kuṇdakakukṣi-saindhava (No. 254); Triśakuna (No. 521).

<sup>2417</sup> Panini, IL 4. 20; IV. 2. 142-43.

<sup>9418</sup> Gupa Jātaka (No. 157).

sess Ibid.

<sup>3630</sup> Mahāsilavaj Jātaka (No. 5).

<sup>9491</sup> VI. 27, 1.

VI. 19; Mahávagga (V. 10. 3)
refers to cotton coverlets dyed with
figures of animals (compare in
No. 2607). The Bhuridatta Jitaka

<sup>(</sup>No. 543) refurs to masuraka, a sest covered with 'gadi',

sees Tundila Jataka (No. 388).

Bhlmasena Jataka (No. 83).

Mahāśwāroh (No. 302); Madiyaka (No. 390); Viśa (No. 488); Mahā-vāṇij (No. 493); Soṇananda (No. 532); Mahāhaṇaa (No. 534); Khaṇdahāla (No. 542); Mahāhaṇa (No. 547).

Gopa Jātaka (No. 157); Therigāthā Ch. XIV.

Mahanmarga (No. 546),

<sup>2558</sup> VIII. 1.

<sup>1431</sup> No. 499.

Asadria Jātaka (No. 181); Kupdakakukņi-saindhava (No. 254),

We also read of (1) cloth-made bags for storing up grains (bhastā)<sup>2631</sup> (2) cloth-made bags for keeping shoes<sup>2633</sup> (3) tents (mandapa)<sup>2633</sup> and (4) kṣauma, linen cloth.<sup>2634</sup> Kautumvara was famous for her cloth.<sup>2635</sup> specially linen (kṣauma).<sup>2636</sup> The Sudhābhojana Jātaka<sup>2637</sup> refers to coarse cloth made from the threads spun out of the roots of trees.

- (c) Silk: Silk-fabrics are mentioned in the Majjhimasila and in the Bhikkhu-Pātimokkha (on Eḍakalomavagga). The word kosiyamissakam (meaning mixed with silk) shows that mixed silk was also known. Kauşeya cloths are also referred to in Pāṇini. 2633 The Dadhivāhana Jātaka 2639 refers to screens made of silk cloth; while from the Therigāthā we learn that the sick fabrics of Benares were highly prized in those days.
- (d) Woolens: The Mahāvagga<sup>2640</sup> refers to coverlets with long fleece, counterpanes of many colours, woolen rugs with long hair on one or both sides, carpet inwrought with gold or with silk, large woolen carpets, rich elephant housings, horse-rugs or carriage rugs, large cushions and crimson cushions. In the Jātakas we read not only of blankets<sup>2641</sup> but also of carpets, <sup>2642</sup> traps made of wool for catching birds, <sup>2643</sup> screen made of raktakamvala<sup>2644</sup> and shoes made of cloth woven with threads of different colours and decorated with gold. <sup>2645</sup>

In the Mahāvānij Jātaka<sup>2646</sup> we have "kuṭṭiyo paṭiyāni cha." The commentator says "kuṭṭiyo hatthattharādayo paṭiyāni uṇṇāmaya pachchattharaṇāni setakamvalāni pi vadanti"; so that woolen shawl or some such

sasa Illisa Jataka (No. 78).

<sup>1432</sup> Mitrāmitra Jūtaka (No. 197).

Devadharma (No. 6); Kuläyaka (No. 31); Mašaka (No. 44); Šaša (No. 316); Uddšlaka (No. 487).

<sup>1444</sup> Aliosobitta Jataka (No. 156).

Mahājanaka Jātaka (No. 569); Viśwantara (No. 547).

sese Viswantara Jataka (No. 547).

<sup>\*\*\*\*</sup> No. 535.

<sup>1050</sup> IV. 3, 32.

seep No. 186.

<sup>2449</sup> V. 10. 3.

Mahawaniga Jataka (No. 72); Mahawanij (No. 493).

Pāṇinī (IV. 2, 12) also refers to carpets.

<sup>2548</sup> Kakkara Játaka (No. 209).

Bhojājāneya Jātaka (No. 23).

Bhūridatta Jātaka (No. 543).

<sup>1040</sup> No. 498.

costly woolen is meant. In the same Jātaka we also have "Uddiyāne cha kamvala." The commentator says "Uddiyā nama kamvalā atthi." If uddiya be taken as derived from Sanskrit udra then uddiya will mean made from the fine hair of udbirāla. Blankets made of goat's hair called gonako are mentioned not only in the Majjhimašīla but also in the Jātakas. 2647 The Sālikedāra Jātaka 2648 refers to net made of the hair of horse's tail for catching birds. Gāndhāra was famous for her blankets 2649 and some of them were so fine as to fetch a lac pieces. 2650

(3) Carpentry: In addition to the ordinary carpenter who made wooden articles for domostic use, there were skilled workmen employed in building carts (Māmsa Jātaka No. 315) and chariots 2651 and in building dugouts, 2652 boats 2653 and ships, 2654 Among wooden articles for domestic use we find (1) paryanka, high class bed-stead 2655 (2) phalakāsana, 2656 bench (3) sayyāphalaka, 2657 ordinary wooden bed-stead (4) stool 2658 (5) benches long enough to accommodate three persons 2659 (6) āsandī 2660 (7) āsandaka (rectangular chair) 2661 (8) sofa (sattango) 2662 (9) sofa with arms to it 2662 (10) arm-chair 2664 (11) state chair (bhadda-pitham) 2665 (12) cushioned chair

<sup>9847</sup> Alamvuşi (No. 523); Mahijanaka (No. 539).

<sup>2648</sup> No. 484

viswantara Jataka (No. 547).

seep Ibid.

Spandana (No. 475); Pāraskara Grhyasūtra, I. S. 18; I. 10. 1-3; III. 14; Sāūkbyāyana Grhyasūtra, IV. 7, 32; Āśvālāyana Grhyasūtra, II. 6. 1, 9; III. 12. 2; I. 8. 1.

<sup>2012</sup> Champeys Jataka (No. 506).

sess Samudra-vāņij Jātaka (No 465).

sees Sankha Jataka (No. 442).

Devadbarma Jātaka (No. 7); Surāpāna (No. 81); Vairi (No. 103); Pafichaguru (No. 132); Grāmanichanda (No. 257); Manikundala (No. 351); Sivi (No. 499); Alam-

vuşā (No. 523); cf. Pallanka in Chuliavagga, VI. 141; VI. S. 1. etc.; Mahāvagga, V. 10. 3.

<sup>(</sup>No. 173); Kanšla (No. 31); Markata (No. 536).

Midulaksana Jataka (No. 66); Indrasamanagotra (No. 161).

Mahāsvapna (No. 77); Illisa (No. 78).

<sup>2050</sup> Chullavagga, VI. 13. 2.

Ibid., VI. 14. 1; VI. 8, 1 etc.; Mahävagga, V. 10. 3.

vagga, VI. 20. 2 and VIII. 1. 3.

page Ibid.

sass Ibid.

Bees Ibid.

sees Ibid.

(vithika) 9666 (13) chair raised on a pedestal (elaka-padaka pitham) 2667 (14) chair with many legs (amalakavantika-pitham) \$688 (15) cane-bottomed chair (koccham)2869 (16) straw-bottomed chair 2870 (16) litter or sedanchair 2671 (17) board to lean against (apassena-phalakam) 2672 (18) wooden plank (phalaka) used as a slate for writing 2873 (19) dice-board (akkhasas phalakam)2674 (20) wooden pestle and mortar 2675 (21) wooden spoon2676 (22) juhu, spoon 2677 23) upabhrt, a spoon 2678 (24) darvi, a spoon 2679 (25) sruk, a laddle 2680 (26) sruva, small sacrificial ladle 2881 (27) dhruva, big sacrificial ladle 1689 (28) agnihotrahavani, the ladle with which Agnihotra oblations were offered 2688 (29) a wooden vessel called patri 2684 (30) prasitraharana (the vessel into which the portion of the sacrificial food belonging to Brahman is put, 2885 (31) wooden dish 2686 (32) wooden sacrificial cup2687 (33) dropa or dropi, a vessel for measurement2688 (34) karisa, a vessel for measurement 2089 (35) amnana, a vessel for measurement 2690 (36) wooden tubs used in watering plants 2891 (37) wooden yoke for carrying loads (Pali kajo or kacho) 2 and (38) wooden boxes

```
vees Ibid.
```

seev Ihid.

sass Ibid.

acco Thid.

sero Toid.

vagga, V. 10, 2.

<sup>2672</sup> Mahavagga, I. 25. 15, 16.

sess Katabaka Jataka (No. 195).

Alamvuşā Jūtaka (No. 523). The commentator however takes akkha in the sense of gold : akkhasas ti suvaņņaphalakam viya visālā. Compare ākarā-phalaka in Pāraskara Grhyaslūtra, II. 10. 17 which according to the commentator Rāmakṣṇa was made of udumvara wood.

<sup>1475</sup> Nanachhando Jataka (No. 289).

tara (No. 547); cf. Aśvalfiyana Grhyaettra, IL 1. 2, 9.

<sup>\*\*\*\*</sup> Asvalayana Grhyasutra, IV. 3. 2.

<sup>2010</sup> Ibid., IV. 3. 3.

Paraskara Grhyasütra, III. 2, 2; Paraskara Grhyasütra, II. 14, 14, 20, 24,

<sup>2000</sup> Sankhyayana Grhynsüten, I. 9. 14

Sankhyāyana Grhyasūtra, IV. 3. 6; Sankhyāyana Grhyasūtra, I. 8. 74; I. 9. 4; I. 9. 13; I. 9. 14; Pāraskara Grhyasūtra, I. 1. 3.

<sup>3509</sup> Adváláyana Grhyasútra, IV. 3, 5.

<sup>\*\*\*\*</sup> Ibid., IV. 3. 4.

<sup>2004</sup> Ibid., IV. 3, 10.

<sup>\*\*\*</sup> Ibid., IV. S. 8.

<sup>2080</sup> Ibid., IL 1. 4.

<sup>1487</sup> Thid., IV. 3. 11.

<sup>2438</sup> Amra Jataka ( No. 124 ); Vikarnaka (No. 232).

<sup>2000</sup> Vartaka Jätaka (No. 35).

nenn Thid.

sees Aramadusaka Jataka (No. 46).

<sup>1000</sup> Midulaksaņa Jātaka (No. 66).

(peţikā).2603 The manufacture of wooden sandals is described in the Mahājanaka Jātaka2604; while razor of udumvara wood,2695 sphya (wooden sacrificial sword)2696 and wooden shields2697 are also mentioned.

In the construction of houses the carpenter obtained the full scope for his skill. The Alinachitta Jātaka<sup>2698</sup> tells us how the carpenters of a village near Benares would go up the river in a vessel and enter the forest, where they would shape beams and planks for house-building and put together the framework of one storey or two storey houses, numbering all the pieces from the main post onwards; these they then brought down to the river bank and put them all aboard; then rowing down-stream again they would build houses to order, as it was required of them. The palace of the King of Benares mentioned in the Kuśanāli<sup>2629</sup> and Bhadra-śāla Jātakas<sup>2700</sup> was a one-pillared one, probably like the famous one-pillared Durbar Hall of Fatepur Sikri, the pillar being made of wood.

(4) Grass and reed work—The worker in grass and reeds (nalakāra) made a large variety of articles for daily use among which the more important were (1) mat (kilinjaka), 2701 (2) basket (pachchi = kalopi), 2702

<sup>(</sup>No. 491). Box made of sandalwood is mentioned in Matsya Jätaka (No. 75).

No. 539.

<sup>28, 25.</sup> Khadira Gthyasütra, H. 3, 17,

On the different implements mentioned in the Grhyasützas, compare Prof. Max Muller's paper in Zeitschrift der Deutschen Morgenlandischen Gesellschaft, Vol. IX. pp. VII. seqq.; LXXVIII seqq. On the Präsitraharana compare Hillebrandt, Neu-and Vollmond-

sopfer, pp. 119 (with note 6), 120 and 131.

Svetaketa Jataka (No. 377).

<sup>24 95</sup> No. 156,

sass No. 121.

<sup>2700</sup> No. 465.

chanda (No. 257); Javanaharpsa (No. 476); Päraskara Gihyasütra, I. 5, 2,

Nanda (No. 39); Midulaksapa (No. 66); Illisa (No. 78); Surāpāna (No. 81); Sopa (No. 529); Pāraskara Gihyasūtra, II. 14. 11, 20; III. 3. 4; Āśvālāyana Gihyasūtra, IV. 3. 15; Khadira Gihyasūtra, III. 2. 6.

(3) small basket (changotaka)<sup>2703</sup> (4) winnowing basket (Pāli kullaka)<sup>2704</sup> (5) cage-like structure made of cane or bamboo-splints for catching fish (kumina)<sup>2705</sup> (6) cage-like structure made of straw for birds to live in<sup>2706</sup> (7) sandals made of grass<sup>2707</sup> (8) hand-punkha<sup>2708</sup> (9) umbrella made of leaves <sup>2709</sup> (10) string loop (sikya)<sup>2710</sup> (11) a ring made of straw over which coolies keep the load they are to carry on their heads (chumvataka)<sup>2711</sup> (12) broom-stick<sup>2712</sup> (13) rope<sup>2713</sup> (14) flute or pipe (venudanda).<sup>2714</sup> Receptacles were also made out of the leaves of trees (patraputa).<sup>2713</sup>

(5) Pottery: This industry was sufficiently developed to admit of localisation in particular places. The Jātakas<sup>2716</sup> repeatedly mention village of potters. According to the Uvāsagadasao<sup>2727</sup> there were 500 potter-shops outside the town of Polāsapura; apparently these formed a suburban village of potters. Among the vessels of earthenware<sup>2718</sup> we find (1) pitcher<sup>2719</sup> (2) jug<sup>2720</sup> (3) jar<sup>2721</sup> (4) a large water-jar<sup>2722</sup> (5) drinking pot<sup>2723</sup> (6) liquor-cup<sup>2724</sup> (7) sthāli<sup>2725</sup> (8) pot for keep-

vardhakistikara (No. 283); Nanachhando (No. 289); Mahajanaka (No. 539); Asvalayana Gihyastira, IV. 5. 7.

1705 Haritamāta Jātaka (No. 238).

\*\*\* Kapets (No. 42); Lols (No. 274).

2101 Dašaratha Jātaka (No 461).

Durvalakāṣṭha Jātaka (No. 105);
Sūkara (No. 153).

970 Pilamuşthi Jātaka (No. 252); Brahmadatta (No. 323).

1710 Ekarāja Jātaka (No. 303).

1711 Sammodamāna Jātaka (No. 33).

1719 Triparyasta Jataka (No. 16).

Gihyasütra, III. 1. 52.

2714 Chandrakinnara Jataka (No. 481).

9718 III. 376; III. 509.

1717 VII. 181. 184.

2710 Asvalayana Grbyasutra, IV. 7, 10.

2719 Vātamīga (No. 14): Mahāsvapna (No. 77); Indrasamānagotra (No. 161); Sānkhyāyana Gīhyasūtra, L. 13. 5; II. 17. 2; III. 4. 3; IV. 1. 3; IV. 3. 4; IV. 17. 4; Khadira Gīhyasūtra, I. 3. 5.

2720 Aśvālāyana Grhyasūtra, H. 1. 2, 9.

9721 Ibid., IV. 6. 4.

2790 Midulakana Jataka (No. 66).

ares Ibid.

1754 Illies Jataka (No. 78).

Mahilamukha (No. 26); Khulladhanurgraha (No. 374).

Potadājaka Jātaka (No. 28)); Matsyadāna (No. 288).

ing curds<sup>2,7,2,6</sup> and (9) vat (chāṭi).<sup>2,7,2,7</sup> The skill of the potter was exhibited in the preparation of earthen pots with female figures engraved on them and of earthen dolls for children mentioned in the Ku'a Jātaka.<sup>2,7,2,8</sup> In the Viśwantara Jātaka.<sup>2,7,2,9</sup> we are told that some of those dolls were representations of the images of elephants, horses, bulls, śyāma deer, monkey (kadalīmṛga), hare, owl, peacock, swan and birds like heron etc.

(b) Leather-work: The leather was tanned and softened by the application of kṣāra²<sup>730</sup> and the leather-worker manufactured oil flasks and "shoes of white leather very elaborately worked and high-heeled so as to make the wearer seem taller."<sup>2731</sup> The shoes of the Vrātyas are described in the Kātyāyana Śrautasūtra²<sup>732</sup> as black and pointed (karninyan). The Grhyasūtras²<sup>733</sup> and the Jātakas²<sup>734</sup> refer to shoes some of which had only one sole³<sup>735</sup> and were so stylish as to fetch 100, 500 and even 1000 pieces. <sup>2736</sup> Vašistha in his Dharmasūtras²<sup>737</sup> refers to objects made of leather among which the Jātakas mention (1) leather undergarment (chamma n'vāsana)²<sup>738</sup> (2) leather upper garment (chamma prāvaraṇa)²<sup>239</sup> (3) leather coverlet of chariot²<sup>740</sup> (4) leather-made fittings of chariots²<sup>741</sup> (5) leather by which the arm is protected against the bowstring²<sup>742</sup> (6) leather-belt for elephant²<sup>743</sup> (7) leather shoe for elephant²<sup>744</sup> (a) leather umbrella for elephant²<sup>745</sup> (9) leather strap to

```
2790 Sankhyayana Gihya-alia, 111. 2. 9.
```

Pullehäudha Jātuka (No. 55); Kumbha (No. 512).

<sup>\*\*\*\*</sup> No 531.

stas No. 547.

<sup>2730</sup> In the Mahaunmarga Jataka (No. 546) we have "Phalasatam chammam." According to the commentator phalasam=phalasatap pamapam wahu kate khadapetva midubhavamupanitim.

Arrian-Indica, 16.

<sup>9709</sup> XXII. 4.

<sup>9725</sup> Atvālāyana, III. S. 1; Khadira, II. 5. 16; III. 1, 25; III. 1, 41;

Päenskarn, II. 6. 30, 32; Sankhyayana, III 1. 10, 18.

ars. Upanaha Jataka (No. 231).

<sup>2705</sup> Tilamuythi Jataka (No. 256); Brahmadatta (No. 323).

aras Sankha Jataka (No. 42)

avar III. 49-63.

arse Brahmadatta Jataka (No. 323).

aras Ibid.

<sup>8740</sup> Kukkura Jataka (No. 22).

atta Ibid.

aras Asvalayana Grhyasutra, III. 12. 11.

avas sudadanta Jaiaka (No. 514).

aras Ibid.

area Mid.

bind a dog<sup>2746</sup> (10) net of leather-straps to catch deer<sup>2747</sup> (11) leather case for keeping sword<sup>2748</sup> (12) leather bag for keeping wealth (chamma pasivvaka)<sup>2749</sup> and (13) leather made vessel for sprinkling water on plants.<sup>2750</sup>

(7) Wine-distilling: The preparation of wine was an important industry as drinking was quite common in those days. The Surapana Jātaka 37 51 gives us the mythological origin of surā and vīruni wines and dilates on the evils of drinking. In the Ayogrha Jataka 1752 the uncertainty of human life has been compared to the uncertainty of the cloth of the drunkard which is liable to be exchanged at any moment for a glass of liquor. From the Sankhyayana Grhyasutra 2753 we find that on occasions of marriage four or eight women who are not widows drink wine and dance four times. The Jatakas 4754 also show that drinking formed an important part of all festive ceremonies. From the Surapīna Jataka 2755 we learn that there was a Drink Festival probably like the Greek Dionysia and the Roman Baccanalia. In the Gangamala Jataka 2738 we read of a daylabourer and his lady-love who decided to join a festival and to regale themselves with strong drink, garland and perfumes. We read of liquorshops (apina), 2757 liquor cups 4758 and of dried fish taken along with liquor. 2752 We find different varieties of wine like (1) sura 2750 (2) meraya maireya) 4761 (3) varuni 4764 (4) kapotika 2763 (5) kilala 4764 (=Sans.

<sup>8748</sup> Sunaka Jātaka (No. 244); şadadanta (No. 514).

<sup>&</sup>quot;147 Suvarpamiga Jataka (No. 359).

<sup>2748</sup> Asadréa Jataka (No. 181); Gandatinduka (No. 519).

vihachchhatra Jataka (No. 336); cf.

<sup>#750</sup> Arāmadījaka Jātaku (No. 46).

<sup>8783</sup> No. S1.

<sup>\*\*\*\*</sup> No. 510.

avas I, 11, 5,

<sup>\*\*\*\*</sup> Tapdila Jātaks (No. 388); Pādakušalsmāņava (No. 432).

<sup>3711</sup> No. 81.

<sup>9704</sup> No. 421.

BT 17 Anavirati Jataka (No. 65).

<sup>\*\*\*\*</sup> Illisa Jataka (No 78).

aras Ibid.

<sup>97 \*\*\*</sup> Illisa (No. 78); Surāpāna (No. 81); Pādakušalamāņava (No. 432); Tap.lila (No. 388); Sānkhyāyana Grhyasūtra, I. 11 5.

arat Viśwantara Jataka (No. 547).

<sup>27 82</sup> Varuni (No. 47); Surapana (No. 81).

stas Surāpāna Jātaka (No. 81).

Sankhyāyana Gthyasūtra, III. 3. 7; See Zimmer—Altindisches Leben, p. 281.

- (6) wine prepared out of the juice of sugarcane. <sup>2765</sup> (7) and wine prepared out of grapes for which Kapisa was famous in the days of Pāṇinī. <sup>2766</sup> Kapotikā wine was a rarity though the ordinary variety of wine seems to have been cheap for a glass was worth only one māṣā. <sup>2767</sup> Liquor of superior strength <sup>2788</sup> was however dear as appears from the Vāruni Jātaka <sup>2789</sup> where we are told of a wine-distiller who used to sell strong drink in exchange for gold and silver pieces.
- (8) Stone-work: In the Vabhru Jātaka<sup>2710</sup> we find a worker in stone (pāṣāṇa-kuṭṭaka) busy with his work of cutting stone in a ruined village and also hollowing out a cavity in a white crystal as a cage for a mouse. A crystal cave for a mouse is also mentioned in the Satyaṃkila Jātaka.<sup>2771</sup> Crystal palaces mentioned in the Jātakas<sup>2772</sup> some of which were seven-storeyed<sup>2773</sup> are probably exaggerations. In the Śūkara Jātaka<sup>2774</sup> we are told that the Gandhakuṭira monastery was furnished with a marble staircase (maṇisopāṇa). Stone images of hares<sup>2773</sup> and elephants<sup>2774</sup> were also manufactured. We have already referred to the crystal bowl and steatite vases discovered within the Piprawa stupa belonging to 450 B. C., an examination of which shows that they were turned on the lathe the use of which accounts for their high polish and beauty.
- (9) Ivory work: The worker in ivory (dantakāra) produced various articles including ornaments like bangles. According to Nearchos "the Indians wear earrings of ivory, those that are very well off." Benares was one of the principal centres of this industry which was developed enough to be localised in the ivory workers' ward (dantakāravīthi). 2779

```
2748 Samudravāņij Jūtaka (No. 465).
```

<sup>2744</sup> IV. 2. 99.

<sup>97 82</sup> Illisa Jätaka (No. 78).

ores Pārnekara Gibyastira, III. 4. 9.

STOS No. 47.

<sup>9770</sup> No. 137.

<sup>9771</sup> No. 73.

<sup>(</sup>No. 380); Chaturdvāra (No. 439); Nami (No. 541).

<sup>2778</sup> Lošaka Jūtaka (No. 41).

<sup>9774</sup> No. 153.

<sup>2775</sup> Ghata Jataka (No. 454).

<sup>977</sup> Matrposaka Jataka (No. 455).

Kāṣāya Jātaka (No. 221).

Fragments 9 and 10-Arrian-Indica, 16.

Silavannāga Jātaka (No. 72); Kāṇāya (No. 221).

- (10) Work in bone, horn, conch-shell and coral: Vasistha in his Dharmasūtras 2780 refers to objects made of bone and conch shells. The Jātakas 2781 frequently refer to the manufacture of bows from the horn of the sheep on account of its flexibility just as Homer's Illiad refers to the Greek custom of manufacturing box from the horn of the ibex. The mention in the Ghaṭa Jātaka 2789 of images of hares made of coral and of jewels (māṇikya) is corroborated by the find of ornaments made of coral and precious stones in the Piprawa stupa belonging to 450 B. C.
- (11) Salt industry: The preparation of salt by the evaporation of saline water is clearly referred to in the Bhūridatta Jātaka. The manufacture of salt by the lonakāra 2784 is also mentioned in the Kausāmvī Jātaka.
- (12) Sugar: Extraction of juice from sugarcane and preparation of molasses by thickening the juice by heating it on fire is described in the Mahāsvapna Jātaka. 2785 In this connection the following remark of Megasthenes will be found interesting: "Stones are dug up of the colour of frankincense, more sweet than figs or honey." 2786 These are probably sugarcandy which he took to be a kind of crystal.
- (13) Dyeing: We find monks dyeing their chivara<sup>2787</sup> and people using cloth dyed (1) in red colour (kāṣāya)<sup>2788</sup> (2) with safilower (kusumbha)<sup>2789</sup> (3) in yellow with karnikāra flower, <sup>2790</sup> (4) in blue with kanṭakuraṇda<sup>2781</sup> and (5) in golden colour.<sup>2792</sup>

In those days cloth was stiffened with 2795 starch and then polished with conch (sankha). The Khullanarada Jataka 2794 also refers to an

<sup>•</sup> TEO III. 49-63.

area Acadria (No. 181); Sarahhanga (No. 522); Khandahala (No. 542).

<sup>9789</sup> No. 454.

<sup>2783</sup> No. 543.

<sup>2764</sup> No. 428.

BT .. No. 77.

<sup>2706</sup> Fragment 10 = Strabo XV. O. 703.

<sup>\*\*\*\*</sup> Varupa (No. 71); Gupa (No. 157).

at \*\* Godhā (Nos. 138 and \$25).

<sup>\*\*\*</sup> Pusparakta Jätaks (No. 147).

<sup>2500</sup> Gupa (No. 157); Dardara (No. 172).

<sup>9191</sup> Dardars Jātaka (No. 172).

<sup>2112</sup> Kāşāya Jātaka (No. 221).

<sup>2792</sup> Vaks Jitaka (No. 38).

<sup>2704</sup> No. 477.

upper garment which was thus stiffened (ghattita) with starch. The Pusparakta Jātaka 2795 refers to the custom of wearing cloth after it has been curled into a thousand folds.

Architecture : - In the pratyutpannavastu of the Jatakas 2790 we find frequent mention of kuti-kara-siksapada (instruction to monks about the construction of houses) which is found in the Sütravibhanga of the Vinaya Pitaka. In the Gramanichanda Jataka 2797 we read of vastuvidyacarya who could find out the defects of building sites seven cubits underground and on whose advice the princes selected the sites for their palaces. The mason (itthaka-vaddhaki = Saas. istaka-vardhaki) 2798 was known and the Jatakas 2722 frequently refer to seven-storeyed houses (Sattabhūmaka-pāsāda). In India the use to which these seven-storeyed buildings were put was entirely private and had nothing to do with any worship of the stars like the seven-storeyed Ziggarats of Chaldma. The Jatakas also refer to a two-storeyed palace2800 and to a one-pillared palace.2801 A vivid description of an unfinished palace as preserved in the Kukku Jataka2808 corroborates the evidence of the Kuśanali 2803 and Bhadraśala Jātakas 2804 regarding the general use of wooden pillars in the construction of a house though the use of iron pillars was not altogether unknown. 2805 The Jatakas describe various other types of buildings, among which we notice (1) thatched houses for the ordinary people 306; (2) Dharmasala in which seats were provided and drinking water kept stored up in jars 2807; (3) Āsana-salā, resting place for travellers 2806; (4) Samsthāgāra (town-

<sup>9700</sup> No. 14".

aves Manikantha (No. 253); Brahmadatta (No. 323); Asthisena (No. 403).

<sup>2727</sup> No. 257.

arsa Mahaumarga Jataka (No. 546).

No. 514); Višwantara (No. 547).

<sup>2000</sup> Komāyaputra Jātaka (No. 299).

sao: Kušanāli Jataka (No. 121); Bhadrašala (No. 465).

<sup>\*\*\*\*</sup> No. 396.

seus No. 121.

No. 465.

<sup>28. 5</sup> Ayogiha Jataka (No. 510).

Sakuna (No. 38); Ašātamantra (No. 61); Mādalakšaņa (No. 66); Kuddāla (No. 70); Madhyama Nikāya, Sutra 81.

asor Kulayaka Jataka (No. 31).

asos Abhyantara Jataka (No. 281).

hall)2\*\*00; (5) Chaitya built on the relic of Bodhisattva as kapirāja; 2810 (6) kriḍāsālā which was constructed after the ground was levelled down and properly measured with a tape. 2811 A portion of this building was reserved for the reception of guests, a portion for the poor and helpless, a portion for the delivery of poor and helpless women who were carrying and a portion for the merchants to store up their wares. The building was decorated with paintings inside and beautified by the excavation of a tank near by and the construction of an adjoining garden in which fruit and flower trees were planted; and (7) a privy (vachehhatthāna) with doors in which a lamp was kept burning the whole night. 2812

The details of buildings are found in abundance in the canonical texts of the Buddhists. Buddha enjoined on his devotees the supervision of building construction as one of the duties of the order. 2313 We read even of a care-taker of houses known as avasika, 2814 The Bhikkhus were thus told by the Blessed One with respect to buildings: "I allow you, O Bhikkhus, abodes of five kinds-vihīra, arlhayoga, prīsāda, harmya and guhi."2615 Vihīra is the well-known Buddhist monastery, originally implying the halls where the monks met. Ardhayoga literally means half-joining and according to Buddhaghosa 9816 refers to suvarna-vangagrha which Professors Oldenburg and Rhys Davids have rendered as 'goldcoloured Bengal house'. Was it the much familiar Bengal house with gold-coloured straw-covering or thatch? It is called half-joining, for, both the halves of the roof are joined together at the ridge on the top of the roofing, looking like parted hair. Prasada is a residential storeyed building; harmya is a more pompous type of storeyed house. Gühā literally means cave and would refer to under-

Bhadrasala (No. 453);

Bhadrasala (No. 465).

<sup>3410</sup> Mahakapi (No. 407).

sen: Mahanmarga Jataka (No. 546).

<sup>1612</sup> Triparyasta Jataka (No. 16).

seis Chullavagga, VI. 17. 1.

Bisa Jataka (No. 488).

osis Vinaya texts: Mahavagga, f. 30. 4. Chullavagga, VI. 1. 2.

Buddhaghoşa's commentary on Mahāvagga I 30, 4 rons thus: Addayoga ti suvapņa-vangageham. Pāsādo ti dīghapāsādo. Hammi-yān ti upari ākāsatale patitihitaku-tāgāro pāsādo yava. Guhā ti itthakagahā silāguhā dāroguhā paņsuguhā

ground buildings. One of the Jatakas<sup>2617</sup> actually contains an elaborate description of an underground palace and such have been the rock-cut temples, as in the famous Ajanta caves.

One should carefully select the building site so that it might be "not too far from the town and not too near, convenient for going and for coming, easily accessible to all who wish to visit him, by day not too crowded, by night not exposed to too much noise and alarm." 2818

After the selection of the site houses, at least of the richer classes. were extensively built, for, we are told that "an upasaka (devotee) has built for his own use a residence, a sleeping room, a stable, a tower, an one-peaked building, a shop, a boutique, a storeyed house, an attic, a cave, a cell, a store-room, a refectory, a fire-room, a kitchen, a privy, a place to walk in a well a well-house, a yantragrha (which is supposed by Buhler to be 'a bathing place for hot sitting baths'), a yantragrha room, a lotus pond and a pavilion."2819 Other houses comprised "dwelling rooms and retiring rooms and store-rooms and service-halls and halls with fire-places in them, and store-house, and closets, and cloisters and halls for exercise, and wells and sheds for the well, and bath-rooms and halls attached to the bath rooms and ponds and open-roofed sheds (mandapas)".2890 The extensiveness of the buildings can be imagined from the length of time devoted to getting a house completely built. We are told that "with reference to the work of a small vihāra, it may be given in charge (of an overseer) as a navakarma (new work) for a period of five or six years, that on an addayoga for a period of seven or eight or twelve years". 28 21 That the long periods were not idled away will be clear from the detail of houses gathered mainly from the Vinaya texts. 9899

The whole compound is enclosed with ramparts (prākāra) of three kinds, namely, brick walls, stone walls, and wooden fences which are again surrounded with bamboo fences, thorn fences and ditches. 2823

Mahaumarga Jataka (No. 546).

<sup>3818</sup> Chullavagga, VI. 4. 8.

<sup>2011</sup> Mahavagga, III. 5. 9; also III. 5. 6.

<sup>8880</sup> Chollavagga, VI. 4 10.

<sup>1891</sup> Ibid., VI. 17. 1.

Ibid., VL 5.

<sup>\*\*\*</sup> Chullavagga, VI. 3. 7. 10.

Gateways are built with rooms and ornamental screen-work over them; 2824 and gates are made of stakes interlaced with thorny brakes. 2825

Five kinds of roofing are mentioned—brick-roofing, stone-roofing, cement roofing, straw-roofing and roofing of leaves. 28 26 The roof is first covered with skins and plastered within and without; then follow whitewash, blocking, red-colouring, wreath-work and creeper-work. 28 27 The wooden roof of the underground palace described in the Mahaunmarga Jataka 28 28 was covered with ulloka mattikā and painted white. Ulloka was an under-cloth used in the making of 'gadi'; so it appears that the wooden roof was covered with cloth plastered with mud over which whitewash was applied.

The floors were of earth, not of wood, and were restored from time to time by fresh clay or dry cowdung being laid down, and then covered with a whitewash, in which sometimes black or red was mixed. From the parallel passage in Mahnvagga (I. 25. 15) and Chullavagga (VIII. 3. 1) it would seem that the red colouring was used rather for walls, and the black one for floors. It appears, however, that with a view to removing the dampness 2829 gravel was spread over the floor. 2880

The doors are furnished with "door-posts and lintel, with hollows like a mortar for the door to revolve in, with projections to revolve in those hollows, with rings on the door for the bolt to work along in, with a block of wood fixed into the edge of the door-post, and containing a cavity for the bolt to go into (called the monkey's head), with a pin to secure the bolt by, with a connecting bolt, with a key-hole, with a hole for a

which excellent work in stone have been found at the Sanchi and Bharhut Topes.

<sup>2005</sup> Chollavagga, VI. 3. 10.

<sup>3.8; 3.3</sup> etc.

<sup>2027</sup> Ibid., V. 11. 6; the rendering of the term 'egampheti' which also

by 'skins' seems doubtful and unsuitable. Buddhaghosa in his note at the latter place says 'agum phiyantiti bhitti dandakādisu, vethetvā bandhāti.'

<sup>2009</sup> No. 546.

on Chullavagga, VI, 20, 2.

<sup>2830</sup> Compare Chullavaggs, V. 14. 5.

string with which the door may be closed, and with a string for that purpose."2831

The windows are stated to be of three kinds according as they are made with railings, lattices or slips of wood. The shutters are adjustable and can be closed or opened whenever required. 2888

There were stairs of three kinds viz., brick stairs, stone stairs and wooden stairs; and they were furnished with alambana-band or balustrades. The Gandhakutira monastery was adorned by a marble stair case. A detailed description of flights of stairs is given in the Mahasudassana Sutta: "Each of these had a thambha, evidently posts or banisters; suciyo, apparently cross-bars let into these banisters; and unhisam, either a headline running along the top of the banisters or a figure-head at the lower end of such headline." 2836

In the Vinaya Texts 1837 we find described another sort of building—the hot-air baths. "They were built on an elevated basement faced with brick or stone with stone stairs upto it, and a railing round the verandah. The roof and walls were of wood, covered first with skins, and then plaster; the lower part only of the wall being faced with bricks. There was an ante-chamber, and a hot-room and a pool to bathe in. Scats were arranged round a fire-place in the middle of the hot-room; and to induce perspiration hot water was poured over the bathers."

In the Digha Nikiya<sup>28 28</sup> there is a description of another sort of bath, an open-air bathing tank with flights of steps leading to it faced entirely of stone, and ornamented both with flowers and carvings. <sup>28 29</sup>

<sup>2851</sup> Chullavagga, VI. 3. 8; also 2. 1 and 17. 1.

Chullavagga, VI. 2. 2.

<sup>2805</sup> Mahāvagga, I. 25, 18; Chullavagga, VIII, 2, 2,

sans Chullavagga, VI. 11. d.

sees Sakara Jataka (No. 153).

Mahāsudassana Satta, I. 59. See also Rhys Davids — Buddhist Suttas, p. 262; Compare Chullavaggs, VI. 3. 3.

<sup>2851</sup> III. pp. 110, 297.

<sup>2003</sup> Rhys Davids—Baddhist Suttas, pp. 262 ff.

p. 76 refers to several ancient baths still to be seen at Ameridas-pura in a fair state of preservation inspite of the lapse of more than two thousand years that have clapsed since they were first constructed.

The Grhyasütras \$3 40 have also preserved many rules and rites on house-building. The building site we are told must be (1) even ground 2541 (2) inclined towards the south-west 2842 or a place from where the water flows off to the north-west \$8 48 or to the north 28 44 (3) non-saline soil of undisputed property 2845 (4) covered with grass, herbs and trees 2846 (5) having no plants with thorns and milky juice2847 (6) immune from destruction (by inundation etc.) 9848 (7) square in size2849 or an oblong qualrangle in size9850 or should have the form of a brick9851 or of a round island 2852 and (8) there should be natural holes in the ground on all directions. 2655 The building-site is also to be examined in the following ways: "He should dig a pit knee-deep and fill it again with the same earth (which he has taken out of it). If (the earth) reaches out (of the pit, the ground is) excellent; if it is level, (it is) of middle quality; if it does not fill (the pit it is) to be rejected. After sunset he should fill (the pit) with water and leave it so through the night. If (in the morning) there is water in it (the ground is ) excellent if it is moist, (it is) of middle quality; if it is dry, (it is) to be rejected". 2854 The arrangement not only of the posts but also of doors 9855 is carefully described. One should not, we are told, build a house with its door to the west. 2856 Let him construct a back-door so that it does not face the (chief) house-door; so that the householder or rather his valuable objects etc., which are in the house cannot be seen by passers-by. 2857

2340 Sánkhyáyana, III. 2-3; Aśväláyana,
II. 7-9; Páraskara, III. 4. 1-4;
10-14, 18; Khadira, IV. 2, 6-15;
Govila, IV. 7; Hirapyakuśin,
I. 27-28; Āpastamya, 17.

- 9841 Govila, IV. 7. 7.
- 2642 Apastamya, 17, 1.
- 2843 Khadira, IV. 2. 7.
- 1844 Govila, IV. 7. 3.
- asas Aśvālāyana, II. 7. 2; Khadira, IV, 2.6.
- 2044 Aśvalayana, II. 7. 3-4; Khadira, IV. 2. 6, 9-11; Govila, IV. 7. 2.
- 2547 Aśvaläyana, II. 7. 5-6; Khadira, IV. 2. 8; Govile, IV. 7. 4.

- 2548 Govila, IV. 7. 2.
- 2940 Asvālāyons, II. S. O.
- 28 80 Ibid., II, 8, 10.
- 10 51 Khadira, IV. 2. 12; Govila, IV. 7, 12,
- 2858 Govila, IV. 7, 18,
- 2053 Ibid., IV. 7. 14; Khadira, IV. 2. 13,
- 2024 Āśvālāyana Gthyasūtra, II. 8, 2-5 -S. B. E. Vol. XXIX. p. 212.
- Govila Grhyasütra, IV. 2, 14—15; Govila Grhyasütra, IV. 7, 15—21.
- 16 M. Govila Grhyagatra, IV. 7. 18,
- barg's soles on this passage in S. B. E., Vol. XXX. p. 121.

The temple of the gods is mentioned in Pāṇini. 2858 In the Mānava Grhyasūtra 2859 we are told "Let a daughter be married in a temple." The Sānkhyāyana Grhyasūtra 2860 also refers to god's houses which one is enjoined to walk round, keeping right side turned towards them.

Fortunately for us we have some extant remains of the buildings of this period. The Baithak of Jarzsandha and the walls of Rzjagrha the the ruins of which have been unearthed, were built according to Cunningham before the 5th century B. C. Many of the Buddhist caves like those of Khandagiri and Udayagiri in Orissa were anterior to the invasion of India by Alexander the Great (326 B. C.) The Dzgobas or topes were another class of monuments erected in the cemeteries. The solid dome erected by the Szkiyas over their share of the ashes must have been about the same height as the dome of St. Paul measured from the roof. Indeed much light is thrown on the fine masonry work of this period by the discovery in 1898 on the Nepal frontier of the Piprawa stupa about which Mr. V. A. Smith rightly observes "The construction and contents of the stupa offer valuable testimony concerning the state of civilisation in Northern India about 450 B. C. which is quite in accordance with that elicited from early literary sources."

Sculpture—The sculptor (Kundakāra)<sup>2864</sup> worked in wood, gold, coral and stone. The vivid description of the life-like images of many birds and beasts sculptured on the Vaijayanta chariot<sup>2865</sup> may be a poet's imagination but the image of Buddha made of red sandalwood which Ghosila, minister of king Udayana of the Vatsa country, a contemporary of Buddha caused to be made existed down to the time of Hiuen Tsang who saw it during his visit to Kausāmvī.<sup>2866</sup> In the Asātamantra Jātaka<sup>2867</sup> an ācārya of Taxila is said to have produced out of udumvara wood a life-like image of his own self.

<sup>255</sup>s V. 3, 96-100.

<sup>2840</sup> I 7. 10. 2840 IV. 12, 15.

<sup>2861</sup> Vînaya texts, IV. p. 308.

<sup>2002</sup> Rhys Davide.

ass Imperial Guartteer of India (new edition), Vol. II. p. 102.

<sup>2004</sup> Mahaunmarga Jataka (No. 546).

<sup>2000</sup> Sudhābhojana Jataka (No. 535).

Western world, Vol. I. p. 235.

<sup>2847</sup> No. 61.

In the Jatakas2868 we also read of a prince who agreed to marry only when a girl like the image of gold which he caused to be prepared could be found ont. In the Kuśa Jātaka 1869 we are told that the golden image of a princess which was made by prince Kuśa was far superior to the one prepared by the royal sculptor.2870 A life-like image of a lady and images of elephants made of gold as dolls for children 2871 are also mentioned.

A stone-image of Bodhisattva as elephant 2872 and images of hares made of coral9878 were also known.

Painting-Painting was well-known and the painters were organised into a guild.2674 The life-like paintings of elephants, horses, chariots and various objects of natural scenery on the walls of the underground palace described in the MahTunmtrga Jitaka 2873 may be a poet's imagination but when we find that Buddha prohibited the use of love-scenes painted in frescoes but permitted the representations of wreaths, creepers, fine ribbon and dragon's teeth in fresco-painting \$376 we may safely expect at least a sub-stratum of truth in the poetic exaggeration. Painted punkhas2877 and a picture-gallery (chittigIra) belonging to king Pasenadi of Kosala 9878 are also mentioned.

The occupations -The pursuit of agriculture in this period was associated neither with social prestige nor with social stigma. The stricter Brahmin tradition not only in the law-books but also in the Suttanipāta, the Majjhima Nikaya and the Jatakas expressly reserves the two callings of agriculture and trade for the vaisyas and judges them unfit for the brahmins and the kshatriyas. Thus, the brahmin Esukari of Sravasti considers tillage and dairy-farming as not less the property and province of the vaisya than are bow and arrow, endowed maintenance (by alms)

....

Ananusochaniya Jataka (No. 328); Udaya (No. 458),

nas No. 531.

Mahaunmarga Jataka (No. 546).

Mükapangu Jātaka (No. 538).

Mātrposaka Jātaka (No. 455). 2873 Ghata Jataka (No. 454).

<sup>2274</sup> Jātaka VI. 427.

BRTS No. 546.

Vinaya texts, Vol. II. p. 67; Vol. STE IV. p. 74.

Kusa Jātaka (No. 531).

Rhys Davids-Buddhist India, p. 68.

and sickle and yoke, the property and province of the kṣatriyas, brahmins and working classes respectively. 2879 The Vasettha sutta 2880 reveals the same exclusive spirit as correct. And in the Dasa-brīhmana Jātaka\*\*\* brahmins who engage themselves in tillage and other callings are declared to have fallen from braminhood. On the other hand in both the Jatakas 2882 and the Suttas 2883 not only are bramins frequently found pursuing tillage but also no reflection is passed upon them for so doing, nay the brahmin farmer at times, is a pious man and a Bodhisattva to boot.2884 Dr. Fick is disposed to think that the Udicca brahmins 2885 of the north-west inherited a stricter standard. 2886 Nevertheless it is not claimed for the pious ones just mentioned living near Benares and in Magadha that they were Udicea brahmins. As to the kshatriya clansmen of the tribal republics, they were largely cultivators of the soil. For instance in the Kunzla Jātaka\*887 it was the Sīkiyan and Koliyan peasants who began to quarrel over the prior turn to irrigate.

But agriculture though it remained the principal occupation of the mass of the population lost its attraction for the more arduous spirits who began to crowd into cities lured by the finery of city-life, by the chances of greater income by trade or employment and by other facililies. The diversity of occupations that sprang up in the Brahmana period became more pronounced in this epoch as is evident from the large number of functional groups.

<sup>9870</sup> M. II. 180.

<sup>9889</sup> M. No. 98; S. N. III, 9.

<sup>388</sup> E No. 495.

Somadatta Jataka (No. 211) ; Uraga. 2002 (No. 354); Suvarpakarkata (No. 389); Mabākapi (No. 516).

Brahmin peasant Varadwija in Suttanipāta.

Uraga Jātaka (No. 354).

Satyamkila (No. 73); Mahasvapna (No. 77); Bhimasens (No. 80);

Suripina (No. 81); Mangala (No.

<sup>87);</sup> Parasahasra (No. 99); Tittira

<sup>(</sup>No. 117); Akalaravi (No. 119);

Amra (No. 124); Langustha (No.

<sup>144);</sup> Ekaparna (No. 149); Sata-

dharmā (No. 179) ; Svetaketa (No. 377); Nalinikā (No. 526); Mahā-

vodhi (No. 528).

Socials Glisderang Indian, 138 L 国際日本

<sup>2057</sup> No. 536.

Among those who embraced learned professions we find (1) activas (teachers)2888 some of whom taught the children of villagers and were maintained by them; 2889 while others imparted higher instruction in reputed centres of learning like Benares and Taxila in the three Vedas and the conventional eighteen silpas 2890 and were paid either in advance by rich students2891 or after the completion of studies by poor students who collected their tuition fees by begging 2802 (2) vejjas (physicians) some of whom obtained a fee of 16,000 pieces by curing a merchant-prince's wife2893 (3) visavaidyas (curers of poisonous bites).2894 Then there was the army of (4) astrologers 2895 (5) soothsayers 9896 (6) nimittap thakas (omen-readers)2897 (7) angavidyApIthakas (those who can read the physical features of men and women) 9898 (8) magicians (mīvīkāra, māvāvī or aindrialika)2899 who came to be condemned by the Buddha as they preyed on the ignorance of the ordinary people. There were also besides the usual hotr, adhvaryu and udgatr various other classes of priests like those who officiated at the Ahina sacrifices, 2000 the sadasya, 2001 the samitri and the kāmasādhvaryavah. 2002

Besides the cultivator we find others who followed occupations allied to agriculture like the parnika (grower of green vegetables only), 2003 trus-

Varuna (No. 71); Längulija (No. 123); Upānaha (No. 231); Guptila (No. 243); Tilamuşthi (No. 252); Tūja (No. 338); Tittira (No. 438).

<sup>\*\*\*</sup> Losaka (No. 41); Takka (No. 63),

Shimasena (No. 80); Durmedha (No. 122); Asadria (No. 181); etc.

<sup>25 81</sup> Susima (No. 163); Tilamuşthi (No. 252).

<sup>2825</sup> Dyūta (No. 478).

<sup>1803</sup> Vinaya I. 272,

<sup>9804</sup> Vișavânta (No. 69); Bhūridatta (No. 543).

Brahmajāla Sutta ; Nakṣatra Jātaka (No. 49).

sere Ibid.

Mahamangala (No. 453); Garga (No. 135).

Pañcháudha (No. 55); Allnachitta (No. 156); Nanāchhanda (No. 289).

<sup>28.80</sup> Vidurapandita (No. 545); Viśwantara (No. 547); cf. Daśś; pa (No. 401); Amra (No. 474).

<sup>2000</sup> Scauta Sutra, IV. 1. 6. 7.

<sup>1011</sup> Indische Studien, X. 136, 144.

<sup>2002</sup> Max Mullers' A. S. L., pp. 450, 469 seq.

No. 103). Kuddāla Jataka (No. 70); Parņika

hīraka (grass cutter), 2904 gopīla (cowherd), 2905 ajapīla (goatherd), 2908 aśvapīlaka 2907 or aśvanivandhika 2908 (horsegroom) and hastipālaka (elephantkeeper). 2909

Of those engaged in the various arts the more important are:—(1) peśakāra (weaver)<sup>2910</sup> (2) karmīra (smith)<sup>2911</sup> (3) maņikīrı (jeweller)<sup>2912</sup> (4) vardhaki (carpenter)<sup>2913</sup> (5) iṣtaka-vardhaki (mason)<sup>2914</sup> (6) kundakara (sculptor)<sup>2915</sup> (7) rathakāra (chariot-maker)<sup>2916</sup> (8) kumbhakāra (potter)<sup>2917</sup> (9) carmakāra (tanner and leather-worker)<sup>2918</sup> (10) nalakāra (worker in reeds)<sup>2919</sup> (11) śoundika (wine-distiller)<sup>2920</sup> (12) dantakāra (ivory-worker)<sup>2921</sup> (13) lonakāra (salt manufacturer)<sup>2922</sup> (14) pāsīna-kuṭṭaka (stone-cutter)<sup>2923</sup> (15) sthapati (architect)<sup>2924</sup> and (16) citrakāra (painter). I pasīna-kuṭṭaka (stone-cutter)<sup>2923</sup> (15) sthapati (architect)<sup>2924</sup> and (16) citrakāra (painter).

Among those who followed non-industrial occupations we find: (1) fisher-men<sup>2926</sup> (2) poultry-farmer (vartakavyādha or śākunika)<sup>2927</sup> (3) niṣāda (butcher and hunter)<sup>2928</sup> (4) barber,<sup>2929</sup> (5) washerman (nirnejaka)<sup>2930</sup>

```
*** Chullakaśresthi (No. 4); Visabya (No. 340).
```

<sup>\*\*\*\*</sup> Surāpāna (No. 81); Ekaparņa (No. 149).

<sup>2000</sup> Dhūmakāri (N. 413).

<sup>2007</sup> Tirtha (No. 25); Surapāna (No. 81); Ekaparpa (No. 149).

<sup>9000</sup> Giridanta (No. 184).

Mahilamukha (No. 26); Ekaparna; (No. 149).

<sup>2010</sup> Suttavibhanga.

warge (No. 546). Mahaun-

Vidurapapdita Jātaka (No. 545); Kunāla (No. 536).

<sup>\*\*\*\*</sup> Anīlachitta (No. 156); Samudravāņij (No. 466); Mahānnmārga (No. 546).

<sup>\*\*14</sup> Mahannmarga Jataka (No. 546).

apra Ibid.

sere Suttavibhanga.

<sup>1017</sup> Ibid.

<sup>1010</sup> Ibid ; Mahanmarga (No. 546).

Ibid.; Grāmanichanda; (No. 257); Kuša (No. 531).

<sup>2000</sup> Vāruņi (No. 47).

<sup>\*\*\*\*</sup> Kāṣāya ( No. 221 ); Śūavannāga (No. 72).

<sup>3039</sup> Kausamvi (No. 428).

<sup>9930</sup> Vabhra (No. 137).

<sup>9094</sup> Kuru (No. 213).

Mahanmarga (No. 546).

<sup>2020</sup> Ubhatobhrasta (No. 139).

<sup>2027</sup> Vartaks (No. 118) ; Tittira (No. 319).

<sup>2000</sup> Mayūra (No. 159); Rohantamīga (No. 501); Syāma (No. 540); Khullabamsa (No. 533),

Mahākedāra (No. 9); Sīgāla (No. 152).

<sup>9980</sup> Ghata (No. 454); Vidurapandita (No. 545),

(6) sweeper (pupph-chhaddak)<sup>2951</sup> (7) tailor (tunnavīya)<sup>2932</sup> (8) ferryman (tīrthanāvika)<sup>2933</sup> (9) pilot (jalaniyāmaka)<sup>2934</sup> (10) land-pilot (sthalaniyāmaka)<sup>2935</sup> (11) forest-guard (aṭavī-pāla)<sup>2936</sup> (12) gardener (udyīna-pālaka)<sup>2937</sup> (13) garland-maker (mālā-kāra)<sup>2938</sup> (14) confectioner (modaka)<sup>2939</sup> (15) bhūtavaidya (conjurer of evil spirits)<sup>2940</sup> and (16) perfomer of spells.<sup>2941</sup>

Among those who performed menial work we find (1) cook (pachaka)<sup>2942</sup>
(2) boy-servant<sup>2943</sup> (3) attendant<sup>2944</sup> (4) bath-attendant (snapaka)<sup>2945</sup>
and shampooer (samvahaka) [D. 1. 51].

In addition to these there were others who earned their living by amusing the public. Such were (1) the musician<sup>2946</sup> (2) trumpet-blower (bherivādaka)<sup>2947</sup> (3) blower of conchshells (saṃkhavādaka)<sup>2948</sup> (4) blower of an instrument called mandraka<sup>2949</sup> (5) actor (naṭa)<sup>2950</sup> (5) wrestler (malla)<sup>2951</sup> (7) snake-charmer (ahituṇdika)<sup>2952</sup> and clown (soviya = souvika).<sup>2953</sup>

```
2001 Kunāla Jātaka (No. 536).
```

Mahaunmarga (No. 546).

<sup>2000</sup> Avārya Jātaka (No. 376).

<sup>2004</sup> Suparaga Jatuka (No. 453).

<sup>2286</sup> Vannupatha Jätaka (No. 2).

patha (No. 2); Jayardişa (No. 513).

Vātamīga Jātaka (No. 14); Paţadūşaka (No. 280).

vidurspapinda Jātaka (No. 414); Vidurspapdita (No. 545).

<sup>2550</sup> Viśwantara Jataka (No. 547).

<sup>2040</sup> Kāmanīta Jātaka (No. 228).

Jätaka (No. 48); Sarvadamsträ (No. 241); Vrhachchhatra (No. 336); Kharaputra (No. 386); Parantapa (No. 416).

<sup>(</sup>No. 274); Vidarapandita (No. 545).

vannupatha Jitaka (No. 2); Bhimasena (No. 80); Vilodaka (No. 183).

<sup>2044</sup> Chullakaśresthi Jataka (No. 4).

was Khandahāla (No. 542).

Vidurapaņdita Jātaka (No. 545); Višwantara (No. 547).

<sup>3047</sup> Bheriyadaka Jataka (No. 59).

soas Sankhadharma Jataka (No. 60).

vos Viswantara Jataka (No. 547).

Vidurapandita (No. 545); Panini IV. 3, 110, 129.

aves Vālodaka (No. 183); Ghaja (No. 454). of. Mutthika = muştika in Vidurapandita (No. 545).

<sup>2363</sup> Sflamimāņsā (No. 86); Ahituņdika (No. 265); Chāmpeya (No. 506).

<sup>2033</sup> Vidurapandita Jataka (No. 545).

We know further that with the growth of the state there arose a class of people who lived by accepting service under the king. Prominent among these were the royal high-priest, 2954 arthadharmīnuśāsaka, 2955 sarvārthachintaka, 2956 viniśchayāmātya (judge), 2957 arghakāraka (court-valuer), 2956 rajjuka (surveyor) 2959 droņamāpaka (measurer of corn), 2950 valipratigrāhaka (tax-collector), 2951 nagarapāla, 2952 hiraṇnyaka (cashier or officer of the treasury) 2953 etc.

Guilds—We have seen that in an earlier period some of the functional groups came to be organised into guilds; but it was during this period that the guilds came to play a prominent part in the various aspects of social life. The Mūkapangu<sup>2964</sup> and Mahāunmūrga Jātakas<sup>2965</sup> refer to the conventional number of eighteen guilds but it is to be regretted that only four of them viz., those of wood-workers, smiths, leather-dressers and painters are specially mentioned.<sup>2968</sup> On the evidence of the Jātakas and the law books of the period we get however the names of the following guilds:—(1) wood-workers<sup>2967</sup> (2) smiths<sup>2968</sup> (3) leather-dressers<sup>2969</sup> (4) painters<sup>2970</sup> (5) garland-makers<sup>2971</sup> (6) caravan-traders<sup>2972</sup> (7) herdsmen<sup>2973</sup> (8) moneylenders<sup>2974</sup> (9) cultivators<sup>2975</sup> (10) traders<sup>2976</sup>

Mahāsvapna (No. 77); Susima (No. 163); Tilamusthi (No. 252); Savaka (No. 309); Vandhanameksa (No. 120); Andhahhūta (No. 62); Kurudharma (No. 276); Nänächhanda (No. 289); Rathahtthi (No. 332); Hastipāla (No. 509); Susima (No. 411); Chedi (No. 422); Kimchhanda (No. 511).

Tirtha (No. 25); Khandahala (No. 542); Khandahala (No. 218).

sess Suhanu Jātaka (No. 158).

Khandhāle Jūtaka (No. 542); Kūţavāņija (No. 218).

Tandulanali (No. 5); Suhanu (No. 158); Nemi (No. 541). Palms of the Brethern, 25, 212.

avos Kurudharma (No. 276).

<sup>2040</sup> Ibid.

<sup>9301</sup> Gandatindu (No. 520). Garga (No. 155).

sees Kapavera Jataka (No. 318).

<sup>1003</sup> Silamimāmsā Jātaka (No. 86).

<sup>9944</sup> No. 538.

<sup>2245</sup> No. 545.

<sup>&</sup>quot;Vaddhaki-kammāra-chammakārachittakārldinānāsippa-kusalā."

Samudravāņij Jātaka (No. 496); Mahāunmārga (No. 546).

Suchi Jataka (No. 387); kuša (No. 531); Mahanamarga (No. 546).

<sup>3000</sup> Mahaunmarga Jataka (No. 546).

suro Thid

<sup>1971</sup> Kulmāşapiņda Jataka (No. 415).

<sup>3070</sup> Jarudapāna Jātaka (No. 256).

anys Gautama XI. 21.

sora Ibid.

Bors Ibid.

<sup>2076</sup> Ibid.

and (11) pilots. 2077 Similarly, the moss-troopers numbering 500 of a little robber village near the hills of Uttara Pāāchāla 2076 and the forest-police who escorted the travellers 2079 were organised under a Jeṭṭaka. These craftguilds had three characteristics: (1) an alderman at the head (2) heredity of profession and (3) localisation of industry. The position of the alderman of the guild is indicated in the Sūchi Jātaka 2030 where he is a great favourite of the king (rājavallabha) and in the Uraga jātaka 2081 where he is an important minister of the king (of Kośala). These heads of guilds were called pamukkha (chief or president) and also jeṭṭaka (elder, alderman), distinction between these two words being not apparent. In the Anguttara Nikāya we find the word pūga-gāmanika which means leader of a guild. There is one instance of all the guilds having a common chief who was also lord of the treasury of the kingdom of Kāśi. 2082 The centralisation in this case was perhaps due to quarrels between the foremen of the subordinate guilds such as those of Śrāsvasti. 2083

The necessity for interdependence among people following a particular profession or craft led them to live together in a particular locality. We thus find villages inhabited solely by fowlers, 2934 chandalas, 2935 brahmins, 2936 robbers, 2937 hunters, 2938 carpenters 2939 and smiths. 2990 This localisation of industry was also due, as we have already seen, to the policy of segregation adopted by the higher castes or the king with regard to the people following the hinasippa's and partly to the nearness of the market for their labour or product of their labour as the case may be. For these very reasons people following a particular profession or craft came to live together in special wards of the city. Thus we find the

sorr Suparage Jataka (No. 463).

<sup>2070</sup> Jataka I. 296; 297; II. 368; IV. 335.

<sup>9079</sup> Jätaka II. 335.

<sup>9000</sup> No. 387.

<sup>2001</sup> No. 154.

<sup>2002</sup> Nyagrodha Jataka (No. 445).

and Nakula (No. 165) Jatakas.

<sup>2004</sup> Khullahamsa Jataka (No. 533).

<sup>(</sup>No. 497); Chittasambhūta (No. 498).

Suvarna-kakkata (No. 276);

<sup>\*\*\*\*</sup> Saktigulma (No. 507).

Maytira Jātaka (No. 159); Rohantamīga (No. 501); Syāma (No. 540).

<sup>2000</sup> Alinachitta Jataka (No. 156); Phandana (No. 475).

suso Süchi Jätaks (No. 387).

ivory-workers' bazar, 2991 the weavers' ward 2999 and the vaisva ward 2993 of Benares and florists' quarter2994 and cooks' quarter2995 in Sravasti. Similarly in the Uvasagadasao we are told that the kshatriya quarter of Vestili was different from that of the brahmins,

Combined with this widespread corporate regulation of industrial life there was a general but by no means cast iron custom for the son to follow the calling of his father. Not only individuals but also families are frequently mentioned in terms of their traditional calling. Thus Sati the fisherman's son is Sati, the fisherman; Chunda the smith is called Chunda the smithson, 2996 Apastamva 2997 says "In successive births men of the lower castes are born in the next higher ones if they have fulfilled their duties." Gautama 9 998 says "Men of the several castes and orders who live according to their caste duties enjoy after death the rewards of their work." Apastamva2999 says "In successive births men of the higher castes are born in the next lower ones if they neglect their duties. Apastamva acco enjoins the king to punish those who have trangressed the caste laws. 3001 Gautama 3002 authorises the king to punish such transgressors of caste laws.

The functions of these guilds were legislative, judicial and executive. The Vinaya Pitaka lays down that a thief should not be ordained as a nun without the sanction of the guilds. 3003 From the Vinaya Pitaka 5004 we further learn that the guilds had the function of arbitrators to settle differences between members and their wives. And Gautamasoos lays down that they have legislative functions, for, he refers to the validity of the laws and customs established by guilds.

```
2001 Silavannaga Jataka (No. 72); Kaşaya
       (No. 221).
```

Bhīmasena Jātaka (No. 80).

<sup>2008</sup> Viswantara Jataka (No. 547).

see A Padma Jataka (No. 261).

<sup>100</sup> Mames Jataka (No. 315).

<sup>1004</sup> M. I. 256; D. II. 127 f; Jataka I. 98, 194, 312; II. 79; of. nisādo = luddaputto-luddo; Jataka III. 330 f. ; V. 356-8.

<sup>9907</sup> II. 2-3; 10-11.

<sup>2994</sup> XL 29.

<sup>....</sup> II. 11. 11.

<sup>8000</sup> H. 10, 12-16.

<sup>6001</sup> Cf. Apastamya II. 27, 18,

<sup>3000</sup> XI. 31.

Rājānam vā samgham vā gapam vā **高潮道** pugam vi srenim vi anapaloketa-

<sup>0004</sup> IV. 226.

<sup>5006</sup> XL 21.

The learner or apprentice (antevāsika, lit. the boarder) appears frequently in Buddhist books, one of which indicates the relative position of pupil and master woodwright. 3008 In the Mahavagga 8007 Buddha says "The ZeTrya, O Bhikkhus, ought to consider the anteväsika as a son; the anteväsika ought to consider the ZeZrya as a father. Thus these two, united by mutual reverence, confidence and communion of life will progress, advance and reach a high stage in the doctrine and discipline. The Vinaya Pitaka also gives elaborate rules regarding the duties of the of the pupil towards his teacher and vice versa and also rules regulating the relation between teacher and pupil and the conditions determining its admissibility or cessation. But these relate to the education in the sacred lore, religion and humanities and not to training in the crafts with which we are concerned. The apprentice in the industrial sense indeed appears frequently in the Jatakas though no conditions of pupilage are given. Thus in the Kusa Jataka 1008 a prince apprentices himself to a potter, basket-maker, florist etc., in succession. The senior pupil also acts as assistant master (prsthacarya).3009 We have also instances of fees being paid by apprentices to teachers. 3010 But the conditions of pupilage, though not given in the Buddhist books are roughly foreshadowed by Gautama<sup>3011</sup> who says "The apprentice may forsake his master either of his own motion (in which case he is liable to correction) or under instructions from his kinsmen who consented to his pupilage. In the latter case the deserted master can sue the pupil's guardians for a breach of contract."3012 But a contract cannot be onesided. Hence Katyayana who flourished in the third century B. C. 5018 fixed a penalty upon the teacher for employing the apprentice in other work. "He who does not instruct the pupil in the art and causes him to perform other work shall incur the first amercement and the pupil may forsake him and go to another teacher, released from the indenture."3014

N. 290 f. V. 290 f.

<sup>3007</sup> I. 32. 1.

<sup>3000</sup> No. 531.

Anabhirati Jätaka(No. 185); Mahāśrutasoma (No. 537).

<sup>3010</sup> Susima Jataka No. 163) ; Tilamuşthi

<sup>(</sup>No. 252); of. Dydia (No. 478).

<sup>0011</sup> II. 43-44.

Vol. II. p. 8.

<sup>2013</sup> Macdonell-History of Sanskrit Literature.

<sup>1014</sup> Ibid., Vol. II. p. 7.

Another interesting fact to be noticed is that though normally the crafts were organised on a hereditary basis and technical talent descended from father to son and was confined to particular family yet the way was still open to exceptions to that rule. Spiritual ministrations were the work of the brahmins and administration that of the kahatriyas and brahmins though some share of it was being appropriated by the vaisyas as in the case of the office of the king's treasurer3015 with which was coupled the judgeship of the guilds. But these distinctions did not hold good in the economic sphere where all castes seemed to have stood together. In the Dasabrahmana Jataka 3016 brahmins who followed the professions of a physician, charioteer, agriculturist, meat-seller, caravan-guard, hunter, dealer in fruits, ornaments etc., are condemned proving thereby, though indirectly, that some brahmins followed these occupations. In the Bhūridatta Jataka3017 we read "If the four-fold caste system was true then why do people other than kshatriyas conquer kingdoms, why do non-brahmins become proficient in the Vedic mantras, why do non-vaisyas carry on agriculture, why do not sūdras serve the twice-born castes? Indeed the choice of occupations was quite free. Thus in the Vinaya Pitaka 1018 we find parents discussing the best profession which their wards might choose without a reference being made to the the father's trades. In the Chullavagga3019 the monks are allowed the use of a loom and of shuttles. strings, tickets and all the apparatus belonging to a loom. We also read of brahmins as physicians, 3020 goatherds, 3021 merchants, 3022 hunters, 3023 snake-charmers, 3014 archers, 3015 robbers, 3016 cart-wrights, 3017 agriculturists, \$028 caravan-guard, \$029 hawkers, \$050 and even low caste trappers, \$031

```
2018 Nyagrodha Jütaka (No. 445).
```

<sup>5016</sup> No. 495.

nois I. 77; IV. 128.

BG19 V. 28.

soso Dašabrāhmaps Jūtaka (No. 543).

Diūmakāri Jātaka (No. 413); Dašabrāhmaņa (No. 543).

<sup>1000</sup> Daśabrāhmaņa Jātaka (No. 543).

Chullanandika Jataka (No. 222); Indriya (No. 423).

sosa Champeya Jataka (No. 506).

soss Sarabhanga Jataka (No. 522).

sose Mahakrapa Jataka (No. 469).

Spandana Jäinka (No. 475).

Somadatta Jātaka (Na. 211); Uraga (No. 354); Suvarņakarkata (No. 389); Mahākapi (No. 516); cf. the Brahmin peagant Bharadwāja in Sutta Nipāta.

<sup>2020</sup> Dašabrāhmaņa Jātaka (No. 495).

soco Garga Jataka (No. 155).

<sup>0081</sup> Dašabrāhmaņa Jūtaka (No. 495).

In the Kuśa Jātaka3032 a prince in his infatuation for a girl apprentices himself incognito in succession to the potter, basket-maker, florist and cook to his father-in-law, without a word being said as to his social degradation when these vagaries became known. Similarly a prince takes to trade3033 while another resigning his kingdom goes to the frontier where he dwells "with a rich merchant's family, working with his own hands. 5034 We also read of a prince who only consents to marry when a princess is found exactly like a golden image which he himself had fashioned and which was far superior to that made by the chief smith employed for the purpose. 30 35 The Sankha JItaka 5036 speaks of a Brahmin who takes to trade to be better able to afford charitable gifts. Brahmins engaged personally in trading without such pretext are also mentioned. 3037 Again we hear of a deer-trapper becoming the protege and then the inseparable friend of a rich young śresthi without a hint at social barriers; 3038 a weaver looking on his handicraft as a more makeshift and changing it offhand for that of an archer 30 59; a pious farmer and his son with equally little ado turning to the low trade of rush-weaving 3040; a young man of good family, but penniless, starting on his career by selling a dead mouse for cat's meat at a farthing, turning his capital and hands to every variety. of job and finally buying up a ship's cargo with his signet-ring as security and winning both a high profit in his transactions and the hand of a sresthi's daughter. "This freedom of initiative and mobility in trade and labour finds further exemplification in the enterprise of a settlement of wood-workers. 3041 Failing to carry out the orders for which prepayment had been made, they were summoned to fulfil the contract. But they instead of 'abiding in their lot' as General Walker the Economist 3042 said of their descendants 'with Oriental stoicism and and fatalism' made a mighty ship secretly and emigrated with their families, slipping down the Ganges by night and so out to sea till they reached a fertile island.

<sup>3035</sup> No. 531.

<sup>1055</sup> Jat, IV, 184.

<sup>1034</sup> Jat. IV. 169,

soss Kusa Jataka (No. 531).

No. 442.

BOAT Jataka V. 22, 471.

soss Jātaka III. 49 ff.

Jasa Jasaka II, 87.

sose Jātaka IV. 318.

<sup>\$041</sup> Jataka IV. 159.

<sup>2042</sup> The Wages Question p. 171.

Stories all these, not history : nevertheless they serve to show that in these times the division of easte was not quite rigid and was no bar to the mobility of labour, both vertical and horizontal."3043 Indee! social divisions and economic occupations were very far from coinciding. The fact that brahmins claimed credit if born of brahmins on both sides for generations back 3044 betrays the existence of many born from a less pure connubium. In the Kusa Jataka 2045 a Brahmin takes to wife the childless chief wife of a king without losing caste thereby. Elsewhere in the Jatakas princes, brahmins, śresthi's and even low castes are shown forming friendships. sending their sons to the same teachers and even eating together and intermarrying without any social stigma. 3046 Even in Apastamva sūtra 3047 we find that a Sudra can become a Brahmin and a Brahmin a Sudra according to their good or bad deeds. Panint 3048 mentions a celebrated grammarian Chakravarman who was a kshatriya by birth. All these evidences go to show that the dignity of labour was recognised though there were certain notable exceptions. Thus the Suttavibhanga 30 40 mentions certain low castes and certain low crafts. As instances of low castes are mentioned the Vena who according to Manu lived by beating drams etc., and whose prototype we find in the Bherivada 30 50 and Sankhadhma 3031 Jatakas; the Nisadas (hunters or trappers), Pukkasa 3032 whose occupation is said to be that of throwing away dead flowers 3053 and the Chandralas who are called the meanest men on earth 3054 who lived apart in their own settlements 3055 by hunting and were sometimes employed for street-sweeping 3056 and policing towns by night, 3057

Rapson—Cambridge History of India, Vol. I.

<sup>2044</sup> D. I. 93; M. II. 156.

<sup>2040</sup> No. 531 ( - Jataka V. 280).

<sup>\*\*\*</sup> Jātaka II. 319 f; III. 9—10; VI. 422; Jātaka I. 421, 422.

<sup>304\*</sup> IL 5-10.

<sup>2042</sup> VI. 1. 130.

soas Vinaya Pitaka IV. 6-10.

sess No. 59.

<sup>5081</sup> No. 60.

According to Mann the pukkasa was the son of a chandala by a fildra female. He lived by hunting animals like ignama, percuping etc., which live in holes.

oosa Jataka IV. 205,

<sup>3064</sup> Jātaka IV. 397.

sambhūta Jātakas (Nos. 474, 497 and 498 respectively).

<sup>0000</sup> Jataka IV. 390.

Jataka III. 80.

sight of a chandila we are further told forebodes evil 3038; contact with the air that touches his body is pollution 3059; partaking of his food even without knowledge leads to social ostracism3000 and even food seen by him is not to be taken. 3081 As examples of low crafts are mentioned those of the nalakara (worker in grass and reeds) kumbhakara (potter), pesakāra (weaver), charmakīra (leather-worker) and nīpita (barber). It should, however, be noted that the social stigms resting on these low trades was due sometimes to their very nature (as in the case of the butcher and the tanner) but chiefly to their association with the aboriginal non-Aryan tribes who followed them. Yet other despised callings were the black arts, explanation of signs, omens, auguries, dreams, foretelling events etc. 3063 Jitaka VI. 191 refers to the popular belief that even Nagas do not dance for shame before actors. Jataka II, 82 refers to Brethern who used to get a living by being physicians soes or runners, doing errands on foot ..... the 21 unlawful callings. It is very interesting to note that there is a substantial agreement between the Pali works and Sanskrit law books in this connection. Thus Vasistha3084 conderns actors; also Baudhayana 3065 who adds to them stage-players and teachers of dancing, singing, and acting condemned as upapatakins, 3066 It is thus evident that both the Buddhist and Hindu social opinions are practically at one in condemning certain crafts and professions on the basis of an absolute standard, determined on grounds of moral deficiency and in some cases of uncleanliness of the processes of operation involved in the craft.

Similar agreement between Hindu and Buddhist books is to be found with regard to the mobility of labour already mentioned. Thus all the

Matanga (No. 497); Chittasambhilta (No. 498)-

vatam yāhi—Svataketu (No. 377).

sees Matangs (No. 497).

soes Chittneamhhata (No 498).

Chullavagga XII. 1. 3; Mahasila Tevijja Sutta, ch. II.

sons Note the prohibition in the Hindu

<sup>3004</sup> III. 3.

nous E. 5, 10, 14

L S. 14; Gautama XVII. 17; Vadistha XIV. 2. 3.

Hindu law books authorise the twice-born classes to take to the occupation of an inferior caste in times of distress or on failure to obtain a living through lawful labour. 3067 Gautama in his Dharmasutra 3068 says that a brahmin can be a farmer and a trader, though trade in a cortain specified articles are forbidden by him 8069 as also by Apastamya, 3070 Baudhayana 8071 and Vasistha. 3073 Vasistha 3073 prohibits brahmins and kshatriyas from being usurers but BaudhTyana 8074 says that the vaisya may practise usury. Even the brahmin priest who neglects his duties may at the king's pleasure be forced to do the work of a sudra. 8078 But though brahmins lived not only as gentlemen farmers but also as humble ploughmen \$678 in this period a brahmin who persists in trade cannot be regarded as a brahmin nor can a priest who lives as an actor or physician. 3077 In fact. there were recognised customs, not approved in one part of the country but admitted as good usage because locally approved in other parts. For. in discussing usage, Baudhayana 3078 expressly enumerates customs peculiar to the south and certain others peculiar to the north and adds that to follow these practices except where they are considered right usage is to sin but that for each practice the local rule is authoritative, though Gautama denies this. 3079

The condition of the labouring classes: (a) Free labourers—There is very little evidence to prove that in India slavery ever became the basis of the economic life of the people. Labourers were mostly free and were paid for their work. The free labourers were called kammakara so so and their wages so at were settled by higgling and haggling as in the Gangamāla Jātaka so so In the Avārya Jātaka so so the ferryman is also

```
Gantama VIL 6; Vasistha II. 22;
3007
                                              8011
                                                    Thid, III. 3.
      Bandhayana II. 4. 16.
                                              8078
                                                    I. 1. 17 £
... S. Compare Vasistha II. 24 f.
                                              3978
                                                    Sacred Books of the East, Vol. II.
*** VIL 9-20.
                                                     p. XLIX.
*** I. 7. 20, 12-13.
                                                    Suvarņamīga Jātaka (No. 359);
BOT1 1L 1. 2, 27.
                                                     Vidurapapdita (No. 545).
BOYS II. 24-32.
                                              3081
                                                    Purisatthakaram in Mapikaptha
8073 II. 40.
sovs V. 10. 21.
                                                     Jätaka (No. 253).
2010 Baudhayans II. 4, 7, 15,
                                               2043
                                                    No. 421.
sove Vasistha III, 33,
                                               2003
                                                    No. 376.
```

advised to settle the fare by bargaining before taking a man to the other side of the river. The wage-carning class also existed in the days of Paninisosa who uses the words vetana and vaitanika. The Gangamāla Jātaka 3085 gives us an insight into the frivolous though gay life led by some of the free labourers of those days. We are told that there was a poor labourer who earned his livelihood by fetching water to others. He contracted questionable intimacy with a poor woman who also earned her living by fetching water. Learning that a great festivity is in progress in the city (of Benares) they decided to join it with their total savings of one masaka each which they spent in regaling themselves with garland, perfumes and wine. Though the wage-earner was no man's chattel yet his lot seems to have been very hard. In the Serivanij Jataka soss a free woman who earned her living by working as a domestic drudge in the house of a neighbour is described as living from hand to mouth and unable to save anything with which she could buy from the hawker articles for her only dependent, a grand-daughter. In the Kundakapupa Jataka 3087 a free labourer of Śrīvasti is described as making his both ends meet with great difficulty and when the other citizens decided to make a corporate gift to the monks he decided to present Buddha with cakes prepared with the fine husk of rice which only he could spare.

In addition to these there were the day-labourers whose lot was probably harder. He was to a great extent employed in the larger land-holdings and paid either in board and lodging or in money wages. In a list of callings given in the Buddhist books he ranks along with the mere hewers of wood and flower-gatherers and below the slave. In the Sutanu Jataka aday with which he is reported to have

<sup>0004</sup> IV. 4, 13.

sees No. 421.

sees No. 31.

seer No. 109.

Bhītika - Pāli Bhātaka in Sutta Nipāta I, 4; cf. S. I. 171; Jātaka III. 293; I. 468.

aoso Jataka III. 406; IV. 43; S. N. p. 12.

soss Gangamāla Jātaka (No. 421).

soos Sutanu Jataka (No. 398).

D. I. 51; of. Mil. 147; 331; A. I. 146, 206.

sess No. 398.

maintained himself and the only other dependent, his mother with great difficulty.

(b) Slaves-Next, there were slaves who were an adjunct in comparatively rich households. The male slaves sometimes served as a valet or footman to his master's son3094 or as a store-keeper to his master 3095; while the female slaves in royal establishments waited upon the queens and performed such duties as daily buying flowers for them 3006 and looking after the jewels of the ladies in the royal harem. 3097 In other households they had to husk paddy, soss pound rice soss and fetch water. \$100 They were sometimes put on hire to work for others, \$101 Slaves seem to have been recruited from all classes of society. Viswantara Jataka seems to point to the fact that the enslavement of highborn prince and princess was nothing which could shock the social ideas of the day. From the Vidurapandita Jatakas103 we learn that slaves were of four kinds :- (1) garvadīsa, born slaves (i.e., children of slaves) (2) kritadīsa or those sold for money (3) bhaktadāsa or those who voluntarily recognise others as their owners for food and clothing (4) or for protection. To the fifth class belonged the karamaras of Pali literature, those who were captured by the robbers that raided villages as in the Takka<sup>3103</sup> and Chullanarada<sup>3104</sup> Jatakas. These karamaras are akin to the dhvajāhrta class of slaves described by Manu. To the sista class belonged the dandadasa who were reduced to slavery as a judicial punishment. An instance of such degradation is furnished by the Kulayaka Jatakas108 where the king enslaves the tyrannical village headman for his crimes.

The slaves formed part of the property of wealthy householders. "Wives and children, bondwomen and bondmen, goats and sheep, fowl and swine, elephants, cattle, horses and mares, together with gold and coins of

<sup>\*\*</sup> Kaţābaka Jātaka (No. 125).

Boos Thid.

Dhammapada Commentary on verses 21-23.

<sup>9007</sup> Mahāsāra Jātaka (No. 92).

<sup>3000</sup> D. C. III. 321.

cooo Robini Jätaka (No. 45).

<sup>5100</sup> Vimānavattu commentary p. 45.

<sup>3101</sup> Namasiddhika Jataka (No. 97).

<sup>8109</sup> No. 545.

<sup>\$108</sup> No. 63.

<sup>0104</sup> No. 477.

<sup>\$108</sup> No. 31.

silver"3108 all those ties the householder is said to pursue with blind and avid appetite. But knowing that they are fetters and encumbrances, even the unconverted man when speaking in praise of Gautama might say "He refrains from accepting slavewomen or slave-men."8101 The Theragatha indicates that they were completely at their master's control and had no freedom except that given to them by their masters.3108 They could be gifted away 3100 or exchanged for another. 3110 For this loss of persona Vasistha exempts them from taxation. For this very reason the master's consent was necessary for the slave's marriage. Pasenadi, king of Kośala had to obtain the consent of the master before he could marry Mallika, daughter of a slave woman of one of the leading Sakya cheifs named Mahanaman. For the same reason the marriage of a slave with free women hardly improved his status. 3111 Similarly, sons born of a slave-girl by a free man were hardly regarded as free. Hence the Lichchhavis never recognised Vasavakhattiya as a member of the Sakya family since she was the daughter of a Sakya prince by the slave-girl Nagamunda. 3119

The slaves, however, might be manumiated \$113 or might free themselves by payment; \$114 but while still undischarged they were not even eligible for the pavajjā ordination. \$115 As Rhys Davids \$116 points out, although slaves might be admitted into some of the orders coexistent with the Buddhist sampha, Gotama restricted this custom, so that "whenever slaves were admitted to the Order they must have previously obtained the consent of their masters, and also, I think, have been emancipated". This is borne out by the story of the jealous woman who mutilated her female servant. \$117 When the outrage was brought to light and the woman and her husband had been reprimanded by Gotama, they were converted to the

<sup>3104</sup> Majjhima, I. 162.

Dialogues, I. p. 5.

Psalms of the Brothern, p. 360; of. Ibid., p. 22.

<sup>8108</sup> Asampradina Jataka (No. 131).

<sup>\$110</sup> Apastamva I, 20, 15.

str: Chullasresthi Jataka (No. 4).

<sup>\*119</sup> Hadraśila Jitaka (No. 465).

p. 117; Psalms of the Sisters, p. 117; Psalms of the Brethern, p. 22; Jataka V. 313 (dasajanam bhujissam katvā).

sus Viswantara Jataka (No. 557).

saas Mahavagga l. 47.

<sup>#11\*</sup> Dialogues I. p. 103.

Dhammapada Commentary on verse 314.

faith, and then and there they freed the female slave and made her a follower of the Dhamma. The Therightha commentary \$1118 tells us that Punna, daughter of Anathapindada's domestic slave, was given freedom by her master when she defeated a Brahmin in argument and then allowed to enter the order.

The lot of the slave seems to have been far better than that of either the Greek or the Roman slave. From the Śrikālakarni 8119 Gangamāla 8120 and Uragas 1 s 1 Jatakas we find that the slaves were treated as members of the family and lived virtuous lives like their masters. Some of them, however, were in the habit of stealing like Khujjuttara 182 though the influence of Buddha's dhamma had a splendid effect on their character. That the slaves remembered their happy personal relationship even when their former master had gifted them away to another and even tried to help their ex-master in his distress is evident from the Asampradana Jataka. \$123 It is no wonder, therefore, to find that a master, at the time of his death would show confidence in his slave by telling him only, where he had kept his secret treasure 3124 or would consult his slave-girl as to the nature of the boon he should ask of the king. 5125 In the Uraga Jataka 5126 a slavegirl did not weep for her dead master and when she was told that the reason for her conduct was probably her ill-treatment by the dead master she stoutly protested and remarked that she had nursed him up from his childhood with great for lness but did not mourn his death because a dead man cannot be brought back to life by crying aloud just as an earthen pitcher once broken cannot be mended. In the Katahaka Jatakas 127 we find the slave-girl's son petted and brought up along with the master's son and permitted to learn writing and handicrafts and was afterwards appointed as store-keeper by his master.

There was the other and darker side of the picture as well; for, in the same Jataka we find the slave saying to himself that if he remained as

siis pp. 199 f.

<sup>3119</sup> No. 382.

<sup>31</sup> so No. 421.

<sup>3131</sup> No. 354.

<sup>\*188</sup> D. C. I., 208 f.

<sup>8185</sup> No. 131.

Nandadāsa Jātaka (No. 39).

<sup>5126</sup> Nănāchhanda Jātaka (No. 289).

<sup>8120</sup> No. 354.

<sup>3137</sup> No. 125.

storekeeper he would have to spend his life feeding on a slave's fare and at the slighest fault might get beaten, branded and imprisoned. Cases of ill-treatment of slaves were not altogether unknown. Anathapindada's daughter-in-law used to illtreat and even beat her disa's and disi's. 3128 A slave girl Dhanapali by name was put on hire to work for others and one day on her failure to earn any wages her master and mistress beat her severely after throwing her down at the gate of their house. \$130 The Majjhima Nikāya3130 also gives us a painful instance of ill-treatment by the mistress of a house. A slave-girl named Kali was never lazy but in order to find out whether her mistress's fame for gentleness and mildness was true or not rose one day late in the morning. At this her mistress merely questioned and frowned. On the second day she rose up late and was rebuked. On the third day she rose up still very late and was beaten on the head by her mistress. In the Vimanavattu commentary \$181 we are told that once a slave-girl of a brahmin of Kośala while going to fetch water saw the Buddha sitting at the foot of a tree. Desirous of earning religious merit and being careless whether the brahmin will beat her or kill her, she offered a pot of water to the Buddha who drank water from it. In order to increase her faith in him the Buddha by his miraculous power made the pitcher full every time its contents were taken by his disciples and returned the pitcher full of water to her. The Brahmin master heard all about it and was very angry with her and beat her to death. The Vimanavattu commentary \$132 furnishes us with another pathetic picture of ill-treatment. A Brahmin disliked a slave-girl's daughter to whom she used to administer kicks and blows for no fault of hers. The fact was that at the time of Kasyapa Buddha the girl had been the mistress and she used to beat her maid who was now born as the Brahmin lady and the situation was reversed. As the Brahmin mistress pulled the hair of her head the slave-girl's daughter had the hair of her head shaven by a barber. At this the enraged mistress tied her head with a rope and punished her and thus the girl came to be known as Rajjumala. At last she went to a

<sup>\*12\*</sup> Sujātā Jātaka (No. 269).

<sup>3130</sup> Nāmasiddbika Jātaka (No. 97).

<sup>5150</sup> I. 125 f.

<sup>\*101</sup> pp. 45-47.

этээ рр. 206—09.

forest to commit suicide unable any more to bear the rude treatment of her mistress. We also read of run away slaves in the Jatakas. 3133

(c) Female Labourers-Among the comparatively well-to-do classes the great majority of women were supported by father, husband or children and did not do much, if any, work beyond their household tasks. But among the poorer people the case was different and there are various records which refer to self-supporting women who were engaged in a trade or profession. The Jatakas, for example, refer to a free woman working as a maid-servant in a neighbour's house, \$154 as female astrologer (mahaikakshanika), \$185 as water-carrier3155 and a guard over cotton-fields3537 where she used sometimes to spin fine thread from the clean cotton. \$138 Again it is said that a certain woman was the keeper of a paddy field and she gathered and parched the heads of rice. 3129 Women also appear to have been capable of functioning as keepers of burning grounds, though no mention is made of any wage they might have received. 3140 In the Dhammapada Commentary \$141 we read of a woman acrobat: "One day (at Rajagrha) a certain female tumbler climbed a pole, turned somersaults thereon, and balancing herself on the tip of the pole, danced and sang as she trod the air." The people "stood on bed piled on beds" to obtain a good view so that the tumbler earned "much gold and money."

A large number of women also earned their living by dancing and music 3143 while the courtesans formed a far from negligible portion of the

8288 Katihaka Jātaka (No. 125); Kalanduka (No. 127).

Suvarnahamsa (No. 136).

9100 Asilakshapa Jataka (No. 126).

Mahānāradakāšyapa (No. 421);

1157 Mahanmärga Jataka (No. 546).

3180 Ibid.

Dhammapada Commentary on verse 118.

Dhammapada Commentary on exxivi;

Dhammapada Commentary on verse 7—8.

Dhammapada Commentary on verse
348.

vagga I. 7, 1, 2; Dialogues I. pp. 5 and 7; II. 170; Rhys Davids—Buddhist Birth Stories, p. 171; Dhammapada Commentary III. pp. 166 and 297; Naccagita-vadita kusalā in Fausboll's Jātaka, II., p. 328; V. p. 249; Solasasu nāṭaki-sahassesu in Ibid., I. p. 437; Ibid., No. 263.

sight of a chandlla we are further told forehodes evil 3058; contact with the air that touches his body is pollution 3059; partaking of his food even without knowledge leads to social ostracism 3060 and even food seen by him is not to be taken. 3081 As examples of low crafts are mentioned those of the nalaktra (worker in grass and reeds) kumbhaktra (potter). pesakāra (weaver), char nakāra (leather-worker) and nīpita (barber). It should, however, be noted that the social stigms resting on these low trades was due sometimes to their very nature (as in the case of the butcher and the tanner) but chiefly to their association with the aboriginal non-Aryan tribes who followed them. Yet other despised callings were the black arts, explanation of signs, omens, auguries, dreams, foretelling events etc. 3068 Jataka VI. 191 refers to the popular belief that even Nagas do not dance for shame before actors. Jataka II. 82 refers to Brethern who used to get a living by being physicians soes or runners, doing errands on foot ..... the 21 unlawful callings. It is very interesting to note that there is a substantial agreement between the Pali works and Sanskrit law books in this connection. Thus Vasistha 3084 condemns actors; also Baudhīyana 3065 who adds to them stage-players and teachers of dancing, singing, and acting condemned as upapātakins. 3066 It is thus evident that both the Buddhist and Hindu social opinions are practically at one in condemning certain crafts and professions on the basis of an absolute standard, determined on grounds of moral deficiency and in some cases of uncleanliness of the processes of operation involved in the craft.

Similar agreement between Hindu and Buddhist books is to be found with regard to the mobility of labour already mentioned. Thus all the

Mātanga (No 497); Chittasambhūta (No. 498).

vātam yāhi — Svataketu (No. 377).

<sup>2000</sup> Mätanga (No. 497).

sees Chittasambhūta (No 498).

Tevijja Satta, ch. II.

Note the prohibition in the Hindu smṛti.

<sup>8004</sup> III. 3.

<sup>8008</sup> I. 5. 10, 14

I. I. 2, 13. Compare Apastamva
I. 6. 14; Gautama XVII. 17;
Vadistha XIV. 2. 3.

Hindu law books authorise the twice-horn classes to take to the occupation of an inferior caste in times of distress or on failure to obtain a living through lawful labour. 3067 Gautama in his Dharmasūtra 3068 says that a brahmin can be a farmer and a trader, though trade in a cortain specified articles are forbidden by him 5080 as also by Apastamva, 3076 Baudhayana 3071 and Vasistha. 3072 Vasistha 3073 prohibits brahmins and kshatriyas from being usurers but Baudhīyana3074 says that the vaisya may practise usury. Even the brahmin priest who neglects his duties may at the king's pleasure be forced to do the work of a sudra. 3075 But though brahmins lived not only as gentlemen farmers but also as humble ploughmen 3076 in this period a brahmin who persists in trade cannot be regarded as a brahmin nor can a priest who lives as an actor or physician. 4077 In fact, there were recognised customs, not approved in one part of the country but admitted as good usage because locally approved in other parts. For, in discussing usage, Baudhāyana 3078 expressly enumerates customs peculiar to the south and certain others peculiar to the north and adds that to follow these practices except where they are considered right usage is to sin but that for each practice the local rule is authoritative, though Gautama denies this, 5079

The condition of the labouring classes: (a) Free labourers—There is very little evidence to prove that in India slavery ever became the basis of the economic life of the people. Labourers were mostly free and were paid for their work. The free labourers were called kammakara 3030 and their wages 3031 were settled by higgling and haggling as in the Gangamāla Jātaka 3032 In the Avārya Jātaka 3083 the ferryman is also

```
soav Gautama VII. 6; Vasiatha II. 23;
                                               BOTT
                                                     Ibid., III. a.
      Baudhiyana II. 4. 16.
                                                     I. 1. 17 L.
sees X. 5. Compare Valighta II. 24 f.
                                                     Sacred Books of the East, Vol. II.
**** VIL 9-20.
                                                      p. XLIX.
3070 I, 7. 20, 12-13,
                                                     Savarpamiga Jataka (No. 359);
ROTE
     1L 1. 2, 27.
                                                     Vidarapandita (No. 545).
**** II. 24-32,
3073 II. 40.
                                               4011
                                                     Purisatthakaram
                                                                      in Manikantha
**** V. 10. 21.
                                                      Jataka (No. 253).
Baudhāyana II. 4. 7. 15.
                                               2000
                                                     No. 431,
sors Vasistha III, 33.
                                               5000
                                                     No. 376.
```

advised to settle the fare by bargaining before taking a man to the other side of the river. The wage-earning class also existed in the days of Panini 3086 who uses the words vetana and vaitanika. The Gangamāla Jātaka sons gives us an insight into the frivolous though gay life led by some of the free labourers of those days. We are told that there was a poor labourer who carned his livelihood by fetching water to others. He contracted questionable intimacy with a poor woman who also earned her living by fetching water. Learning that a great festivity is in progress in the city (of Benares) they decided to join it with their total savings of one māsaka each which they spent in regaling themselves with garland, perfumes and wine. Though the wage-earner was no man's chattel yet his lot seems to have been very hard. In the Serivanij Jataka 8086 a free woman who earned her living by working as a domestic drudge in the house of a neighbour is described as living from hand to mouth and unable to save anything with which she could buy from the hawker articles for her only dependent, a grand-daughter. In the Kundakapūpa Jātaka 1087 a free labourer of Śrīvasti is described as making his both ends meet with great difficulty and when the other citizens decided to make a corporate gift to the monks he decided to present Buddha with cakes prepared with the fine husk of rice which only he could spare.

In addition to these there were the day-labourers whose lot was probably harder. He was to a great extent employed in the larger land-holdings and paid either in board and lodging or in money wages. The list of callings given in the Buddhist books he ranks along with the mere hewers of wood and flower-gatherers and below the slave. The Sutanu Jataka aday with which he is reported to have

soss IV. 4, 12,

<sup>9008</sup> No. 421.

sons No. 31.

<sup>8067</sup> No. 109.

Nipāta I. 4; cf. S. I. 171; Jātaka III. 293; I. 468.

<sup>5000</sup> Jataka III. 406; IV. 43; S. N. p. 12.

sooo Gangamāla Jātaka (No. 421).

<sup>\*\*\*</sup> Sutanu Jätaka (No. 398).

D. L. 51; cf. Mil. 147; 331; A. I. 146, 206,

<sup>\*\*\*</sup> No. 398.

maintained himself and the only other dependent, his mother with great difficulty.

(b) Slaves - Next, there were slaves who were an adjunct in comparatively rich households. The male slaves sometimes served as a valet or footman to his master's son 30 94 or as a store-keeper to his master 3095; while the female slaves in royal establishments waited upon the queens and performed such duties as daily buying flowers for them 3096 and looking after the jewels of the ladies in the royal harem. 3097 In other households they had to husk paddy, 3098 pound rice 3099 and fetch water. 5 100 They were sometimes put on hire to work for others. 5 101 Slaves seem to have been recruited from all classes of society. Viswantara Jataka seems to point to the fact that the enslavement of highborn prince and princess was nothing which could shock the social ideas of the day. From the Vidurapandita Jatakas 102 we learn that slaves were of four kinds :- (1) garvadāsa, born slaves (i.e., children of slaves) (2) kritadīsa or those sold for money (3) bhaktadīsa or those who voluntarily recognise others as their owners for food and clothing (4) or for protection. To the fifth class belonged the karamaras of Pali literature, those who were captured by the robbers that raided villages as in the Takka3103 and Chullanarada3104 Jatakas. These karamaras are akin to the dhvajābrta class of slaves described by Manu. To the sixth class belonged the daudadasa who were reduced to slavery as a judicial punishment. An instance of such degradation is furnished by the Kulayaka Jataka 108 where the king enslaves the tyrannical village headman for his crimes.

The slaves formed part of the property of wealthy householders. "Wives and children, bondwomen and bondmen, goats and sheep, fowl and swine, elephants, cattle, horses and mares, together with gold and coins of

```
Katahaka Jataka (No. 125).
```

Dhammapada Commentary on verses

BODY Mahasara Jataka (No. 92).

<sup>0000</sup> D. C. III. 321.

aces Robini Jataka (No. 45).

<sup>5100</sup> Vimansvattu commentary p. 45.

s101 Namasiddhika Jataka (No. 97).

<sup>\$103</sup> No. 545.

<sup>\*10#</sup> No. 63,

<sup>0104</sup> No. 477.

<sup>3108</sup> No. 31.

silver"3108 all those ties the householder is said to pursue with blind and avid appetite. But knowing that they are fetters and encumbrances, even the unconverted man when speaking in praise of Gautama might say "He refrains from accepting slavewomen or slave-men." 3101 The Theragatha indicates that they were completely at their master's control and had no freedom except that given to them by their masters. 3108 They could be gifted away 5100 or exchanged for another. 3110 For this loss of persona Vasistha exempts them from taxation. For this very reason the master's consent was necessary for the slave's marriage. Pasenadi, king of Kośala had to obtain the consent of the master before he could marry Mallika, daughter of a slave woman of one of the leading Sakya cheifs named Mahanaman. For the same reason the marriage of a slave with free women hardly improved his status.3111 Similarly, sons born of a slave-girl by a free man were hardly regarded as free. Hence the Lichchhavis never recognised Vasavakhattiya as a member of the Sakya family since she was the daughter of a Sakya prince by the slave-girl Nagamunda. 3112

The slaves, however, might be manumisted 3113 or might free themselves by payment; 3114 but while still undischarged they were not even eligible for the pavajja ordination. 3113 As Rhys Davids 3116 points out, although slaves might be admitted into some of the orders coexistent with the Buddhist sampha, Gotama restricted this custom, so that "whenever slaves were admitted to the Order they must have previously obtained the consent of their masters, and also, I think, have been emancipated". This is borne out by the story of the jealous woman who mutilated her female servant. 3117 When the outrage was brought to light and the woman and her husband had been reprimanded by Gotama, they were converted to the

<sup>\*\*\*</sup> Majjhima, I. 162.

anor Dialogues, I. p. 5.

Psalms of the Brethern, p. 360; cf. Ibid., p. 22.

<sup>\* 100</sup> Asampradāna Jātaka (No. 131).

<sup>1110</sup> Apastamva I. 20, 15.

our Challasreathi Jataka (No. 4).

<sup>\$128</sup> Bhadrasala Jataka (No. 465).

p. 117; Psalms of the Sisters, p. 117; Psalms of the Brethern, p. 22; Jataka V. 313 (ddsajanan, bhujissam katvā).

<sup>3114</sup> Vidwantara Jataka (No. 557).

Mahayagga 1. 47.

sur Dialogues I. p. 103.

Dhammapada Communitary on versa 314.

faith, and then and there they freed the female slave and made her a follower of the Dhamma. The Therightha commentary 1118 tells us that Punnt, daughter of Anathapindada's domestic slave, was given freedom by her master when she defeated a Brahmin in argument and then allowed to enter the order.

The lot of the slave seems to have been far better than that of either the Greek or the Roman slave. From the Śrikālakarni, 3110 Gangamāla 3120 and Uragas 1 2 1 Jatakas we find that the slaves were treated as members of the family and lived virtuous lives like their masters. Some of them, however, were in the habit of stealing like Khujjuttara 1832 though the influence of Buddha's dhamma had a splendid effect on their character. That the slaves remembered their happy personal relationship even when their former master had gifted them away to another and even tried to help their ex-master in his distress is evident from the Asampradana Jataka. \*123 It is no wonder, therefore, to find that a master, at the time of his death would show confidence in his slave by telling him only, where he had kept his secret treasure 3184 or would consult his slave-girl as to the nature of the boon he should ask of the king. 3125 In the Uraga Jataka 126 a slavegirl did not weep for her dead master and when she was told that the reason for her conduct was probably her ill-treatment by the dead master she stoutly protested and remarked that she had nursed him up from his childhood with great fondness but did not mourn his death because a dead man cannot be brought back to life by crying aloud just as an earthen pitcher once broken cannot be mended. In the Katībaka Jātaka 197 we find the slave-girl's son petted and brought up along with the master's son and permitted to learn writing and handicrafts and was afterwards appointed as store-keeper by his master.

There was the other and darker side of the picture as well; for, in the same Jataka we find the slave saying to himself that if he remained as

<sup>\*110</sup> pp. 199 f.

<sup>3119</sup> No. 382.

<sup>31 30</sup> No. 421.

<sup>\*191</sup> No. 354. \*199 D. C. I., 208 f.

<sup>0133</sup> No. 131.

<sup>1114</sup> Nandadása Játaka (No. 39).

Nanachhanda Jataka (No. 289).

<sup>\*130</sup> No. 354.

<sup>3137</sup> No. 135.

storekeeper he would have to spend his life feeding on a slave's fare and at the slighest fault might get beaten, branded and imprisoned. Cases of ill-treatment of slaves were not altogether unknown. Anathapindada's daughter-in-law used to illtreat and even beat her dasa's and dasi's. 8128 A slave girl Dhanapali by name was put on hire to work for others and one day on her failure to earn any wages her master and mistress beat her severely after throwing her down at the gate of their house. 3190 The Majihima Nikīya3130 also gives us a painful instance of ill-treatment by the mistress of a house. A slave-girl named Kali was never lazy but in order to find out whether her mistress's fame for gentleness and mildness was true or not rose one day late in the morning. At this her mistress merely questioned and frowned. On the second day she rose up late and was rebuked. On the third day she rose up still very late and was beaten on the head by her mistress. In the Vimanavattu commentary3181 we are told that once a slave-girl of a brahmin of Kosala while going to fetch water saw the Buddha sitting at the foot of a tree. Desirous of earning religious merit and being careless whether the brahmin will beat her or kill her, she offered a pot of water to the Buddha who drank water from it. In order to increase her faith in him the Buddha by his miraculous power made the pitcher full every time its contents were taken by his disciples and returned the pitcher full of water to her. The Brahmin master heard all about it and was very angry with her and beat her to death. The Vimanavattu commentary 3139 furnishes us with another pathetic picture of ill-treatment. A Brahmin disliked a slave-girl's daughter to whom she used to administer kicks and blows for no fault of hers. The fact was that at the time of Kasyapa Buddha the girl had been the mistress and she used to beat her maid who was now born as the Brahmin lady and the situation was reversed. As the Brahmin mistress pulled the hair of her head the slave-girl's daughter had the hair of her head shaven by a barber. At this the enraged mistress tied her head with a rope and punished her and thus the girl came to be known as Rajjumala. At last she went to a

<sup>119</sup> Sujūtā Jātaka (No. 269).

<sup>\*\*</sup> Nāmasiddhika Jātaka (No. 97).

<sup>0100</sup> I. 125 f.

<sup>3151</sup> pp. 45-47.

<sup>&</sup>lt;sup>в 103</sup> рр. 206—09.

forest to commit suicide unable any more to bear the rude treatment of her mistress. We also read of run away slaves in the Jatakas. 31 as

(c) Female Labourers-Among the comparatively well-to-do classes the great majority of women were supported by father, husband or children and did not do much, if any, work beyond their household tasks. But among the poorer people the case was different and there are various records which refer to self-supporting women who were engaged in a trade or profession. The Jatakas, for example, refer to a free woman working as a maid-servant in a neighbour's house, 3134 as female astrologer (mahaikakshanikā), 3133 as water-carrier \$136 and a guard over cotton-fields \$3837 where she used sometimes to spin fine thread from the clean cotton. 3133 Again it is said that a certain woman was the keeper of a paddy field and she gathered and parched the heads of rice. 8189 Women also appear to have been capable of functioning as keepers of burning grounds, though no mention is made of any wage they might have received \$140 In the Dhammapada Commentary 3141 we read of a woman acrobat : "One day (at Rajagrha) a certain female tumbler climbed a pole, turned somersaults thereon, and balancing herself on the tip of the pole, danced and sang as she trod the air." The people "stood on bed piled on beds" to obtain a good view so that the tumbler earned "much gold and money."

A large number of women also earned their living by dancing and music 3 143 while the courtesans formed a far from negligible portion of the

9188 Katāhaka Jātaka (No. 125); Kalanduka (No. 127).

Suvarnahamsa (No. 136).

2100 Asilakshapa Jataka (No. 126).

ozas Gangamāla Jātaka (No. 421); Mahānāradakāšyapa (No. 544).

Mahaunmärga Jatuka (No. 546).

sass Ibid.

on verse 118.

Dhammapada Commentary on exxxvi;

Dhammapada Commentary on verse 7—8.

Dhammapada Commentary on verse

vagga I. 7, 1, 2; Dialogues I. pp. 5 and 7; II. 170; Rhys Davids—Buddhist Birth Stories, p. 171; Dhammapada Commentary III. pp. 166 and 297; Naccagita-vadita kusalā in Fausboll's Jātaka, II., p. 328; V. p. 249; Solasasu nātakisahassesu in Ibid., I. p. 437; Ibid., No. 263.

The interchange of commodities of various localities must have been considerable during this period. For, the products of industries which came to be localised in a particular place attained a reputation all their own and were, therefore, much prized abroad. Such were the scents, ivory-products, cotton and silk fabrics of Benares, the blankets of Gandhāra, the cloth of Sivi country, the linen of Kautumvara, the horses of Sind, the mules of Kamvoja and the swords of Daśarnaka.

Besides the big caravan-traders <sup>231</sup> we also notice the hawker (kach-chhapuṭavāṇijo) and the small traders who used to carry their goods from one village to another on the backs of asses <sup>232</sup> or on their own heads. <sup>5333</sup> Again some of the merchants specialised in the trade of single commodities. Of such the Jātakas refer to cloth-merchants, <sup>5234</sup> grain merchants <sup>5235</sup> and incense merchants <sup>3236</sup> while Pāṇini <sup>5237</sup> refers to salt merchants and spice merchants.

As to local trade both retail and wholesale, foodstuffs for the towns were apparently brought to the gates while workshop and bazar occupied their special streets within. Thus there was a fish-monger's village at a gate of Śrāvasti. See Greengrocery is sold at the four gates of Uttara-Pāūchāla see and venison at the crossroads outside Benares. Arrows, carriages and other articles for sale were displayed in the āpaṇa see or it might be stored up in the antarāpaṇa. There were taverns for the sale of liquors see also hotels for the sale of cooked mest and rice.

The act of exchange between producer and consumer or between either and a middleman was a free bargain, 3246 leading sometimes to

oss: Serivāpij Jātaka (No. 3).

sass Simbacarma Jataka (No. 189).

suss Garga Jātaka (No. 155).

sasa Vidarapandita Jataka (No. 545).

<sup>\*\*\*</sup> Ahitandika Jataka (No. 365).

<sup>\*</sup>s\*\* Andhabbūta Jātaka (No. 62).

<sup>1007</sup> Lavapika, salāluka in Papini IV. 4

asse Rhys Davids-Buddhist India, p. 76.

Paalma of the Brethern, 166; of, Janka I, 361.

<sup>3940</sup> Jätaka IV. 445.

<sup>1941</sup> Jātaka III. 49 ; cf. M. I. 58 ; III. 91.

<sup>104.</sup> Jātaka II. 267; IV. 488; Vinaya IV. 248.

<sup>\*\*\*</sup> Jataka I. 55, 350 ; III. 408,

Vinaya II, 267; IV. 248, 249; cf.
Dhammapada commentary, III. 66.

<sup>5548</sup> Vinnya I. 20; 1L 267; D. 22.

<sup>\*\*\*</sup> Jataka I. 111 f.; 195; H. 222, 289, 424 f.; HI. 282 f.

adulteration 2247 and the use of false weights. 3248 We notice not only local 'cornering' in hay 3249 but also the dealer's sense of the wear and tear of articles 3450 and a case of that more developed competition called 'dealing in futures.' 3251 Again in the Apannaka Jataka 3252 two traders agree who shall start first. The one thinks that if he arrive first he will get a better, because a non-competitive price; the other also holding that 'competition is killing work' prefers to sell at the price fixed by his predecessor and yields him a start. But though free competition was the rule, custom may well have fixed price to a great extent. The expression "my wife is sometimes as meek as a 100 piece slave-girl" 2258 reveals a customary price. Moreover, for the royal household prices were fixed by the court-valuer without appeal. 2254

The trade of the traders may well have been largely hereditary<sup>3255</sup>; but their organisations do not seem to have attained the same development as the craft-guilds. The reason seems to have been that the merchant was necessarily a wanderer while industrial organisation in these olden days depended largely upon settled relations and ties of neighbourhood. A Hansa League, for instance, can only grow in highly developed markets and seaports. Nevertheless, there is some significant evidence of corporate concerted action among the merchants. Thus the Chullakaśresthi Jātaka<sup>3235</sup> mentions hundred or so merchants offering to buy up a newly arrived ship's cargo. Five hundred traders were fellow-passengers on board the ill-fated ships mentioned in the Vālāhāśva<sup>3257</sup> and Pāndara<sup>3258</sup> Jātakas; seven hundred others were lucky enough to obtain the services of Supāraga as their pilot, <sup>3259</sup> thus showing co-operative chartering of the same vessel. Again caravan traders had a common chief <sup>3260</sup> who was to

```
anar Nemi Jataka (No. 541).
```

Dust Ibid.

<sup>5 44</sup> Chullakaśresthi Jūtaka (No. 4).

asso Apappaka (No. 1) = Jātaka I, 99,

o 262 Chullakuśrostki (No. 4) = Jūtaka I. 121 £.

<sup>5959</sup> No. 1.

<sup>3281</sup> Nanda (No. 39); Durājāna (No. 64).

<sup>1924</sup> Tapdalanāli (No. 5); Sahana (No.

<sup>158);</sup> Nemi (No. 541); Psalms of the Brethern, 25, 212.

aosa Jataka II. 287; III. 198.

No. 4.

<sup>5257</sup> No. 196.

<sup>5300</sup> No. 518.

osso Supāraga Jātaka (No. 463).

<sup>\*\*\*\*</sup> Mahavanij Jataka (No. 493).

give directions as to halts, waterings, precautions against robbers and in many cases as to routes, fords etc. 3261

Further, several partnerships are mentioned, e. g., in the deal in birds exported from India to Babylon<sup>\$252</sup> and in horses imported from the north to Benares.<sup>\$263</sup> We also notice the partnership of traders of Srāvasti who carried on joint business and set out with five hundred cartloads of merchandise, <sup>\$264</sup> of two other traders of Srāvasti who started joint business with five hundred cart-loads of merchandise, <sup>\$265</sup> of two merchants of Benares who took five hundred waggons of merchandise from Benares to the country districts with an equal interest of both in the stockin-trade and in the oxen and waggons. <sup>\$266</sup>

A concerted commercial enterprise on a more extensive scale appears in the Jarudapīna Jātaka<sup>3</sup> 267 where some traders of Śrīvasti carried on joint business and came upon rich finds of minerals of all sorts from iron to lapislazuli which they stowed away to a common treasure-house, giving food to the brotherhood on joint account.

Methods and media of exchange—Barter was not uncommon in this period. Its continuance was due to the ease with which ordinary people could exchange their goods readily. Brahmins who were not allowed to trade in articles of agricultural production were permitted to barter homegrown corn, food etc. 3 2 6 3 Barter was also prescribed for the Samgha in certain cases 3 2 5 9 to whom the use of money was forbidden. 3 2 7 0 Barter also emerged in certain contingencies e. g., when a potter buys fuel for 16 kahāpaņas and a few pots, 3 2 7 1 when among humble folk a dog is bought for a kahāpaṇa and a cloak 3 2 7 2 or when a wanderer obtains a meal

ases Apannaka (No. 1); Vannupatha (No. 2); Jarudapana (No. 256).

sass Bävern Jätaka (No. 339).

<sup>3903</sup> Suhanu Jafaka (No. 158).

assa Mahāvāņij Jātaka (No. 493).

Sees Kūțavāņija Jātaka (No. 98).

<sup>6247</sup> Jarudapāna Jātaka (No. 256).

VII. 16 f : Apasthamva I, 20. 9. 6.

<sup>8200</sup> Vinaya II. 174.

vinaya II. 294 f; III. 237; Patimokkha V, 18; V. 19.

<sup>\*\*\*</sup> Chullakaśreşthi Jātaka (No. 4).

sara Sunaka Jataka (No. 242).

from a woodlander for a gold pin. \*278 From the Sütras of Pāṇini\*\*\* we have a large number of words which prove the existence of barter in his time. Thus we have saurpa, anything purchased with sūrpa; vāsanam, anything purchased with vasana; maudgika, anything purchased with the exchange of mudga and so on.

Rice<sup>3275</sup> and cowry-shell (sippikā)<sup>3276</sup> were still standards of value when the Jātakas were composed. From Pāṇini<sup>3277</sup> we find that gopuchchha or bovine tail also acted as a medium of exchange. A more common standard of value was, however, the cow. Thus in illustration of Pāṇini's sūtra "Taddhitārthottara-pada-samāhāre ca"<sup>3278</sup> we have the word pañcagu which means anything bought in exchange for five cows. Similarly in the Dharmasūtras we find that all fines for murder are reckoned in cows. <sup>3279</sup>

But for the ordinary mechanism of exchange the value of every marketable commodity was stated in figures of a certain metallic medium of exchange. From the evidences furnished by the literature of this period we find the use of the following metallic media of exchange:—
(1) kākanika<sup>3250</sup> (2) ardhamāṣaka<sup>3251</sup> (3) māṣaka<sup>3252</sup> (4) quarter kārṣa<sup>3253</sup> (5) half-kāṛṣa<sup>3254</sup> (6) kārṣāpaṇa<sup>3355</sup> (7) pāda<sup>3256</sup> (8) paṇa<sup>3257</sup>

3473 Jataka VI. 519.

- 3275 Tapdulanāli Jātaka (No. 5).
- and Stella Jataka (No. 118).
- Arhāt-gopuchehha-samkhyā-parimānād thak—V. 1. 19; cf. Pāņinī IV. 4, 6.
- Date II, 1. 51.
- \*\*\* Apasthamva I. 21. 1—3; Baudhayana I. 10. 21—22.
- Chullakaśreythi Jūtaka (No. 4).

  Kākaņika ith māsaka (R. Syāma
  Sāstri's Eng. Trans. of Kautilya's
  Arthaifistra, p. 98 in. 6).

- Mahaunmarga Jataka (No. 546).
- Jātaka (No. 78); Matsyadāna Jātaka (No. 288); cf. Suvarņa māṣaka in Udayabhadra (No. 458) and Sankhapāla (No. 524) Jātakas.
- \*ses Gangamala Jataka (No. 421).
- 3366 Ibid ; Mahāsvapna (No. 77).
- Chullakaśresthi Jātaka (No. 4);
  Kṛṣṇa (No. 29); Nanda (No. 39);
  Durājāna (No. 64); Sīlāmīmāṇaā
  (No. 86); Ubhatobhrasta (No. 139);
  Grāmapicapda (No. 257);
  Supāraga (No. 463); Mahāunmārga
  (No. 546); Mahāawapna (No. 77);
  Pāpinī V. 1. 29.
- Papini, V. 1. 34; V. 2. 119.

Spar Ibid.

V. 1. 26; Satamānaviņšatika-sahaera-vasanādap—Pāņini V. 1. 27; Tens Kritam—Pāņini V. 1. 27.

(9) satamīna 3986 (10) niṣka 3289 (11) suvarņa 3290 (12) hiraņya 3291 (13) kaṃsa 3292 and (14) vista. 3298

Some of these were made of gold and silver, others of copper or base metal. With the single exception of vista which is hardly mentioned in later literature all of these were circulating media of exchange in later periods as well. According to Dr. Goldstucker see some of these even bore stamped impressions on them; and in support of his contention he quotes the following sutra of Panini: Rupādāhata prasamsayoryap. see Here we get the rule for the addition of the suffix yap on the word rupa to designate both a coin bearing impressions, and a man of fine appearance. Ahata has been explained by the Kāśikā commentary, as bearing impression by stamping: "Nighātina—tāḍanādinā, Dînārādiṣu rūpam yadutpadyate tadāhatamucyate." The Patimokkhassa also refers to this practice of stamping impressions on coins which therefore came to be known as rūpyas (or rupiyos in Prākṛt dialects.)

It is worthy of note that most of the names of these media of exchange refer to a certain weight of metal they contained. For example, karsapana contained one karsa in weight of the metal of which it was composed and was, therefore, called kārsapana. On the basis of the weight in metal the medium of exchange contained two systems of currency arose. The older one reckoned the weight at 100 kṛṣṇalas while the newer one that arose in this period reckoned the weight at 80 kṛṣṇalas. Following Manu<sup>3 2 9 7</sup> we get the following table of weights on which the newer standard was based:—

Stara XV. 181 and 182.

<sup>(</sup>No. 478); Kuśa (No. 531); Viśwantara (No. 547).

<sup>1900</sup> Vinaya III. 219; Illisa Jataka (No. 78).

<sup>\*\*\*</sup> Vinaya III. 219; of. Papini V. 2. 65; V. 2. 55.

<sup>2 20</sup> Papini V. 1. 25.

sees Told., V. 1. 31.

<sup>\*\*\*\*</sup> Numismata Orientalia, p. 39, fn. 3.

<sup>2204</sup> Păpini V. 2. 120

<sup>\*\*\*\*</sup> V. 18 ; V. 19.

<sup>\*\*\*\*</sup> VIII. 134-37.

## For gold :

5 krsnalas or

5 gunjaberry seeds or

5 ratis make

4 māsakas make 4 pādas or

80 krsnalas i. e.,

80 guñjaberry seeds i. e.,

80 ratis make 1 karsa makes 4 suvarņas make

1 pala makes

## For silver :

2 ratis make 16 māsakas make 1 Masaka

1 Pada

1 Karsa 1 Suvarna

1 Pala 1 Niska

1 Māsaka

1 Dharana

According to Kautilyas 298 1 silver māsaka was 88 white mustard seeds (gaura sarṣapa) in weight. Now 18 white mustard seeds are equal in weight to one kranala or gunjaberry seed; so that a silver dharana will be equal to 16-28 = 782 kṛṣṇalas. Hence a dharana was equal in weight (782 kṛṣṇalas) to one Suvarna or 1 Karsa (80 kṛṣṇalas)

## For Copper:

Five ratis make 4 māsakas make 4 pādas or 80 ratis make 1 Māsaka 1 Pada 1 Karsa.

The older Satamana standard still continued in some localities. From the Vinaya Piṭaka3399 we learn that in Rājagrha in the time of Ajātasatru or Vimbisara one pada was equal to five masakas so that in that locality the karsapana was equal in weight to 5 x 20 or 100 ratis (as against 4 × 20 or 80 ratis under the new standard). We have seen that according to the new standard four suvarnas make one nişka but according to the evidence of old Pāli literature3 300 five suvarņas make one niska so that

Arthasastra, Bk. II. ch. 19.

<sup>8 90 9</sup> III. 45.

Childers - Pali Dictionary, s. Nikkho.

like the pada of the Vinaya Pitaka the nisks was also based on the older Satamana standard.

We have at present very little evidence at our disposal to enable us to find out as to whether gold or silver was the accepted standard of currency. Both the standards seem to have existed side by side. As to the relative value of gold and silver in this period we are absolutely in the dark. According to Dr. Prananathasson "A careful study of the fines prescribed in the Arthasastra of Kautalya may possibly afford a clue to the value of gold and silver. In assessing fines the value of any stolen article was taken into consideration. According to Kautalya the fine should be ten times the value of the stolen article ..... Kantalya in section 76 assessed the fines payable for the theft of one mīsaka of gold and silver as 200 and 12 copper panas respectively. If these fines represent twelve times the value of the stolen article, then the value of the gold and silver pieces, each weighing 1 masaka comes to 16.6 and 1 copper pana respectively." On the basis of a very reliable evidence furnished by a second century inscription Dr. D. R. Bhandarakarassos has found out the ratio between gold and silver as 14.1 to 1.

Instruments of credit:—Though as yet we have no evidence to prove the existence of collective banking, instruments of credit were not altogether unknown, for, in the Jātakas we read of signet rings being used by merchants as deposit or security (satyankāra = Pāli satyakāra)<sup>3505</sup> and of I. O. U.'s (iṇṇapannani<sup>3304</sup> or likhita<sup>3305</sup>).

Weights and measures:—The tula (scales) mentioned in the White Yajurveda<sup>3508</sup> was in general use in this period as is evident from its use in similes.<sup>8307</sup> Besides udanka (= Pāli ulunka)<sup>8308</sup> a liquid measure (for water) we find the use of the following weights and measures in this

Ancient India, pp. 86-87.

sson Ancient Indian Numismatics.

<sup>2000</sup> Chullakaáresthi Jätaka (No. 4)

<sup>8264</sup> Khadirangara (No. 40); Ruru (No. 482).

anna Vasistha, XVI. 10.

<sup>3304</sup> XXX. 17.

<sup>8007</sup> Kukkura Jātaka (No. 22); Mahānārada Kālyapa (No. 544).

<sup>2008</sup> Kupdakapūpa Jūtaka (No. 109).

period\*\*\*\*\* (1) māsa\*\*\*\* (2) nālikā\*\*\*\* (3) āḍhaka\*\*\*\* (4) māna\*\*\*\*\* and (5) drona.\*\*\*\*

Purchasing power of money—the Jatakas furnish us with the daily earnings of some classes of labourers in money and with the purchasing power of money. But unfortunately it is difficult to find out whether the unit of money was of silver or copper. Moreover, the Jatakas contain not only exaggerations but also imaginary colourings of facts and as such on their evidence scientific calculations cannot be based. Nevertheless if we make due allowance for all such exaggerations the evidences furnished by them may throw a flood of light on the wealth and welfare of the people of those days. Thus the fee paid to a barber was eight karsapanas, presumably of copper. 3815 The fee of a high class courtesan was 1000 karsapanas per night. 3516 One thousand karsapanas were the usual tuition fee paid in advance to the Ecarya. 5317 Poorer students must have paid lower fees as they had to collect them by begging. In the Dyūta Jataka3318 a student after completing his education managed to collect only seven niskas which however, he lost on the way by a boat-accident. He then resorted to hunger-strike and obtained thereby from the king 14 niskas which he paid to his teacher. From the Gangamals Jataka 3312 we find that a male

measures may be obtained from the	2 adhakas mako 1 Mana 2 manas ur
following tables based on later	4 idhakas make 1 Dropa
authorities:— (a) According to Kantilya (Arthusütra Bk. IL ch. XIX):—	*** Papin! V. 1 33 *** Tapdulandl! (No. 5); Várapi (No. 47);
10 seeds of mass (Phraseolus Radiatus) or 5 guñjaberries make 1 Suvarpamasa	Salittaka (No. 107).  Salittaka (No. 107).  Asampradāna Jātaka (No. 131);  Pāņinī V. 1. 53.
16 savarpamājas make I savarpa or kariba	**** Asampra'iana Jataka (No. 131). **** Vikarnaka Jataka (No. 232)
4 kārsbas make 1 Pala  - (b) According to Sārangadhara Sam- hitā (pp. 10 — 13 ) :—	3518 Saparaga Jataka (No. 463) 3518 Kanavera (No. 318); Sulasi (No. 419);
5 x 16 x 4 = 320 gnűjaberries make 1 Pala	Tarkārika (No. 481).
4 palas make 1 Kudava 4 kudavas make 1 Prastha	Susima (No. 163); Tilamaythi (No. 262).
1 praetha makes 1 Nalika	8828 No. 478,
4 pälikäs make 1 Ädbaka	9010 No. 421,

and a female water-carrier used to earn half a māṣaka each per day, while from the Viṣahya Jātaka<sup>3320</sup> we learn that a śreṣṭhī, being reduced to bankruptcy took to the work of a grass-cutter and earned two mīṣakas a day out of which he intended to give away one māṣaka, keeping the other for himself, which he thought would fetch sufficient food for him and his wife for one day. In the Sutanu Jātaka<sup>3321</sup> a day labourer is described as earning one-half to one māṣaka a day with which he somehow maintained himself and his mother. Even if the māṣaka referred to in the above three Jātakas be a silver one it is apparent that the prices of necessaries of life must have been very cheap so that one-half māṣaka of silver was sufficient for one man for one whole day.

In fact the purchasing power of money was high. A big Rohita fish was worth seven mīṣakas. 3322 Half a māṣaka of meat was sufficient for one lizard. 3323 A small quantity of clarified butter or oil could be had for a copper kārṣāpaṇa. 5324 A cup of surā was worth one copper kārṣāpaṇa. 3325 Six kārṣas (kārṣāpaṇas ?) would buy coarse clothing for a monk and ten kārṣas for a nun. 8326 In the Bhikkhuṇi Pātimokkha two kārṣas and a half and four kārṣas are set down respectively as the price of small and big covering pieces for nuns. A pair of ox would cost 21 kārṣāpaṇas. 3327 Eight kārṣāpaṇas could buy a decent ass. 3328 A young calf was sufficient as house-rent (nivāṣa-vetana) for a certain period. 3329 Hire for an ox used in carrying a cart across a shallow river was two kārṣāpaṇas. 3330 Cart-hire from Benares city to the pattana (port) near by was eight kārṣāpaṇas. 3331 The price of a slave was 100 kārṣāpaṇas, presumably of silver. 3332 The price of slaves, however, varied with their accomplish-

<sup>\*\*\*\*</sup> No. 340.

<sup>\*\*\*\*</sup> No. 398,

ssee Matsyadāna Jātaka (No. 288)

Mahanmarga Jataka (No. 546).

<sup>\*\*\*\*</sup> Vinaya IV. 248-50

sasa Illisa Jatoka (No. 78)

patimokkha.

No. 257). Gramanichapda (No. 257).

assa Mahaunmarga Jataka (No. 545).

ssas Krapa Jātaka (No. 29).

areo Ibid.

<sup>3321</sup> Chullakasresthi Jataka (No. 4).

Nanda (No. 39): Durājāna (No. 64);
In the Viśwantara Jātaka (No. 547)
Amitratāpanā was given in lieu of
100 kārsāpaņas kept as deposit
with her father who spent it away.

ments, good birth or (if a woman ) beauty as is evident from the Saktubhasta 8 3 3 and Viśwantara 8 5 3 4 Jatakas.

Certain articles, however, were noted for their high price. Kapotikā wine was very dear. 3335 Strong drink was exchanged for gold and silver pieces. 3335 A gold necklace worth a thousand pieces presumably of silver 3337 and sāṭakas worth a thousand pieces presumably of copper 3338 are referred to. Essence of sandalwood, 3339 woolen blankets 3340 and Benares fabrics each worth a lac pieces presumably of copper 3341 are also mentioned.

Progress of capitalism:—(a) Hoarding—With the growth of trade and commerce and development of town-life luxury invaded society, gambling and want of thrift reduced many families to poverty and much of this wealth passed into other hands. Ordinary people hoarded their wealth either under the ground<sup>8342</sup> or deposited it with a friend.<sup>5343</sup> Rich people kept a register of the nature and amount of the wealth thus hoarded on inscribed plates of gold or copper.<sup>8344</sup>

(b) Usury—Nevertheless money was lent on interest. There is a tolerant tone concerning the moneylender in the Rohantamiga Jātaka<sup>33,45</sup> where moneylending together with tillage, trade and harvesting are called four honest callings. Gautama<sup>83,45</sup> is equally tolerant; though Vasistha<sup>33,47</sup> and Baudhāyana<sup>33,48</sup> condemn it. Hypocritical ascetics are accused of practising it.<sup>33,49</sup> In Pāṇini's sūtras<sup>33,50</sup> we find the words Dvaiguṇika, Traiguṇika and Daśaikādaśika which go to prove the exhorbitant rates of interest exacted

```
**** No. 402.

**** No. 547 (case of Prince Viśwantara and his sister).

**** Surāpām Jātaka (No. 61).

**** Suraufi Jātaka (No. 47).

**** Kurudharma Jātaka (No. 276).

**** Kurudharma Jātaka (No. 276).

**** Therigāthā, ch. XIV.

**** Kurudharma (No. 276); cf. Sandalwood worth 1 lac pieces in Mahāsvapas (No. 77).

***** Viśwantara Jātaka (No. 547).
```

3200 IV. 4, 30; IV. 4, 31; V. 1. 47.

<sup>\*\*\*\*</sup> Mahāśvāroba Jātaka (No. 302); Mahāunmārga (No. 546).

\*\*\*\* Jāt. I. 225, 235f., 424; II. 309; III.

24, 116.

\*\*\*\* Jāt. VI. 521; Vin. III. 237.

\*\*\*\* Jāt. IV. 7, 488; VI. 29; cf. IV. 237.

\*\*\*\* No. 501.

\*\*\*\* X. 6; XI. 21.

\*\*\*\* X. 6; XI. 21.

\*\*\*\* Mahākīṣņa Jātaka (No. 469)

by some of the moneylenders of those days. Debtors were often reduced to slavery for non-payment of debts. Thus in the Therigatha Isidasi, a nun narrates the story of her reduction to slavery in one of her previous births on account of her father's debts. 8351 Moreover, debtors were not allowed to enter the Buddhist Order. 3352 On the other hand the usurers seem to have organised themselves into guilds having customary laws governing their transactions. 3358 Vasistha 3354 and Gautama 3355 name six different kinds of interest viz., compound, periodical, stipulated, corporal, daily and the use of pledge. The legal rate is fixed at five masas a month 3856 for 20 karsapanas which comes to about 183%. Anybody who exacted more than this legal rate of interest is called Vardhusika. But according to Vasistha, 3357 two, three, four, five in the 100 is declared in the Smrti to be the monthly rate of interest according to caste. Again articles such as gold, grain, flavouring substance, flowers, roots, fruits, wool, beasts of burden without security could be lent at an enormous rate of interest which could be increased six or eight-fold. The interest, however, stopped with the death of the king in whose reign the transaction took place.

Loans were contracted either on notes of hand 3358 or on the deposit of pledges (adhi). 3359 It appears that the debtor got back his note of hand when the loan was repaid. 3360

The State in relation to Economic life—The science of Vartta which concerned itself with the various branches of production as understood in in those days formed a part of the curriculum of royal studies \$3.61 and the king was repeatedly asked whether he was paying proper attention to the prosperity of those who are engaged in cattle-rearing, agriculture and

<sup>3351</sup> See also D. 1, 71.

<sup>3882</sup> Vinaya 1 76.

ssss Gautama XI. 21.

<sup>3354</sup> II. 51

<sup>\*\*\*</sup> XII. 34-35

<sup>\*\*\*</sup> Gautama XII, 29, Baudhäyana I. 5. 10, 22.

<sup>\*\*\*</sup> II. 42-50.

<sup>\*\*\*\*</sup> Impapannani in Khadirangara (No. 40) and Rura (No. 48); likhita in Vasiatha XVI. 10.

soso Jātaka VI. 521; Therfgāthā, 404.

<sup>5560</sup> Khadirangara (No. 40); Buru (No. 48).

<sup>3561</sup> Rāmāyaņa, Bālakāņda.

trade. \$362 Kings seem to have kept granaries for emergencies like war and famine \$363 and to have provided persons with food and seed-corn to enable them to start farming. \$364 He was bound not only to protect the property of infants \$365 but also to maintain the śrotriyas, the weak, the aged, women without means and lunatics. \$366 Apastamva \$367 calls upon kings to build a hall open to guests of the first three varnas and to see that no Brahmin suffered from hunger in his realm.

In exchange for these and other services rendered by him the king had a right to a tithe on raw produce whose amount and method of assessment we have already described. Moreover, all property left intestate or owner-less reverted to the crown. Sac Gautama Gautam

Further the king was to proclaim by criers lost property, and if the owner be not found in a year, to keep it, giving 1th to the finder. All treasure-trove belongs to the king. An exception is made when a priest is the finder and some say that anybody who finds it gets 1th. 5373 The king could impose forced labour (raja-kariya) on the people but this may have been limited to the confines of his estates. Thus, the peasant-proprietors enclose a deer-reserve for their king so that they might not be summoned to leave their tillage to beat up game for him 3374 Gautama 5375 says that the king should force artisans to work for him for

```
sass Ibid , Ayodhyakanda, ch. 103.
```

sses Ind. Ant. 1895, p. 261.

<sup>2004</sup> D. 1. I35.

sses Gautama X. 25.

Nose Vasistha XIX. 35; Gautama X. 9-12; Apastamya II. 10. 4-12.

<sup>\*\*\*\*</sup> II. 10. 4-12.

<sup>\*\*\*\*</sup> Jataka. III. 302; cf. IV. 415. S. I. 89 (Kindred Sayings L. 115).

<sup>5540</sup> XXVIII, 41.

<sup>8870</sup> IL. 14. 5.

<sup>8571</sup> XVII. 83-86; af. XVI. 19.

<sup>3879</sup> I. 11. 14-16; of. I. 18. 16.

<sup>8373</sup> Gautama X. 31.

Nyagrodhamiga Jätaka (No. 12); Nandikamiga (No. 385); of. Mahasvapna (No. 77).

<sup>0878</sup> Gautama X. 31,

one day in the month. If the stock is merchandise, says Gautama, 3376 the tax according to some is 10th, if it be gold or cattle 10th, while 60th is the tax on roots, fruits, flowers, medicinal herbs, honey, meat, grass and firewood.

It may be noted in this connection that śrotriyas, ascetics forbidden to hold property, students, artisans, those who live by exploiting river, forest or hills, those earning less than a kārṣīpaṇa, slaves, servants, very old men, blind, dumb, deaf and diseased persons, those without protectors, children before puberty, women of all castes, wives of servants, widows who have returned to their families, unmarried girls and pradattā's (probably those girls whose marriages have been proposed)—all these were exempt from taxation. \$377

Regulation of prices and profits by the state came as a natural sequel to the ideal of co-operation on which Indian society, though apparently split up into castes, was based. Undue raising of prices came to be denounced \$378 and, as we have already seen, for the royal household prices came to be fixed by the court-valuer without appeal; and what was once done in the interest of the king came to be done in the next epoch in the interest of the public as well. The exactions of the vārdhūṣika came to be denounced, his food was regarded as impure \$3579\$ and the rate of interest, was fixed. \$380 On the same principle Vasiṣtha \$381 asks the king to guard against the falsification of weights and measures.

While exploitation of others by capitalists came to be denounced great emphasis was laid on the performance of duties assigned to individuals and castes. We have already seen how the Dharmasūtras not only condemned those who did not perform their caste-duties 3383 but also authorised the king to punish them. 3383 We similarly find in the Dharmasūtras rules for punishing herdsmen who left their work or persons in tillage who abandoned their work and thereby caused loss to the employer.

save Ibid., 25-27.

as: v Vasistha, XIX. 23-27; Apastamva II. 10. 10-17.

DOTO Vasiatha II. 50.

save Ibid., 40-42.

soso Ibid., 42-50; Gautama, XII. 29-35.

<sup>8381</sup> Ch. XIX.

sass Apastamva II. 11. 11.

<sup>27. 18;</sup> Gantama XI. 31.

Mendicancy and undue asceticism was regarded as a social evil except in the case of men in the decline of their lives. This appears not only from the trend of the conversation between the Buddha and Ajātaśatru but also from the Vāśiṣṭha Dharmasūtra<sup>3384</sup> where begging Brahmins have been denounced as thieves.

Thus, we see that already in this period there were a general tendency to state-interference in economic life which developed into an accredited policy of the state in the next epoch.

The general economic condition of the classes and the masses—
The hoarded wealth of the merchants, usually estimated in crores, their magnificent donations to the various religious orders, the establishment of almonaries, the excavation of tanks and other public benefactions of the rich, the existence of the actor, dancer, singer, acrobat, magician, story-teller, shampooer and dress-maker—all point to the prosperity of the upper classes. It is further proved by the rich festivities, large fees paid to courtesans, the high price of rich wines and the stories of betting with big sums. The luxury of the rich is equally evident from the existence of palatial buildings and the use of hair-dye, 3336 ointment (vilepana), 3357 scent called sarvasaphāraka, 3368 sandalwood oil, 3368 essence of sandalwood, 3360 aguru, 3361 guggulu, 3363 camphor, 3363 chaturjātīya gandha, 3364 kalka, 3365 specially sarṣapa-kalka (mustard

<sup>3334</sup> Ch. II.

Bharidatta Jataka (No. 543).

anna Amracora Jataka (No. 344).

assa Apannaka Jataka (No. 1)-

<sup>\*\*\*</sup> Mahäunmärga Jätaka (No. 546),

<sup>\*\*\*</sup> Kuśa Jātaka (No. 531).

<sup>5390</sup> Kurudbarma Jataka (No. 276).

Bhallātika Jātaka (No. 504); Khandahāla (No. 542).

Matanga Jataka (No. 497).

ansa Andhabhiita Jataka (No. 62).

assa According to the commentator

komkum (saffron), jātipuṣpa, turaṣka (a scent from Turkey myrrh f), yavāna (a scent from Yavana country)—these four made up chaturjātīya gandha referred to in Mahāilavaja (No. 51) and Mātanga (No. 497) Jātakas.

Pāli kukku in Kuša (No. 531).

According to the commentator powdered mustard, salt, earth, powdered sesamum and tarmeric—these five made up kalka.

powder used as face powder), 3396 snānachūrņa 3397 and sandal powder as toilette for the breasts. 3898

Men of the middle-class were also happy and often above the reach of want. They too lived a life of ease, indulged in charities, made gifts to the Order, raised money by subscription for charity or for works of public utility and joined in merriment and festivities.

There were, however, poor and too poor people too in villages as also in towns. In the Mahasara Jataka (No. 92) an inhabitant of a janapada says that he has never seen (i. e., possessed) in his life a chair or a bedstead. We have already seen that the lot of the wage-earner appears to have been hard most of whom could with difficulty make their both ends meet. Moreover, the poorer labourers often suffered from the exactions of the money-lenders which sometimes became so unbearable that a debtor would fly to the forest or even attempt to commit suicide to escape from the clutches of his creditors. Sago Forced labour also injuriously affected their position.

Oppressive taxation sometimes added to the misery of all classes. The Mahāśvāroha Jātaka³400 speaks of a king (of Benares) who trebled the taxes so that the people could not lift up their heads. Another king (of Benares) oppressed his subjects with taxes and fines (dandavali) and crushed them like sugarcane in a mill.³401 The Gandatindu Jātaka³402 refers to a Pānchīla king whose subjects being oppressed by taxation fled to the forest where they wandered like wild beasts.³403

Occasional famines also caused much distress among the people. The Matsya Jataka<sup>3404</sup> refers to the suffering caused by a famine in Kośala due to the failure of rains. In another famine in Kalinga due to draught the people suffered so terribly from want not only of food but also of drinking water that epidemics broke out and leaving their homesteads people had

assa Mahānāradakāsyapa Jātaka (No. 544).

sav? Vardhakistikara Jataka (No. 283).

sses Kuśa Jātaka (No. 531).

<sup>3500</sup> Bharidatta (No. 543); Rura (No. 482).

<sup>8400</sup> No. 302.

oso1 Uchchhum viya janam pilsei in Mahāpingala Jātaka (No. 240).

<sup>8409</sup> No. 520.

<sup>3403</sup> Mahasvapaa Jataka (No. 77).

<sup>5404</sup> No. 75.

to wander about the country with their children for food. The Viraka Jataka 106 refers to a famine in the kingdom of Kāši which was so intense in character than unable to find food all the crows left the kingdom. Another famine which overtook a Kāši village was so terrible that the villagers had to take from their headman a collective loan of an old ox on whose flesh all of them had to subsist for a day or two 1407 Records of such famine are also to be met with in the early canonical literature of the Buddhists. These evidences contradict the assertion of Megasthenes that famines were unknown in India, 1409 unless of course he meant a very general and protracted famine.

Inspite of these visitations India was rich. Stories of her great wealth and prosperity reached the ears of foreigners and roused their greed and this made them invade India. In the fifth century B.C. the small Indian satraphy of Darius was regarded the wealthiest province of his empire, yielding the vast annual tribute of 360 Eubolic talents of gold, worth fully £1,290,000. This supply of gold India obtained, not as did Europe from America by conquest and rapine but by her mining industries and by the more natural and peaceful method of commerce "by the exchange of such of her productions as among the Indians were superfluities but at the same time not only highly prized by the nations of western Asia, Egypt and Europe but also were obtainable from no other quarter except India or from the farther East by means of the Indian trade." 3411

## THE END OF VOL. I.

<sup>5406</sup> Kurudharma Jataka (No. 276).

<sup>2404</sup> No. 204.

<sup>8407</sup> Grhapati Jataka (No. 199).

otos Vinaya I. 21, 23f; III. 220, n. 1; compare the five iti's in Sudhābhojana (No. 535). In the Mahāsvapna (No. 77) a dream is interpreted as foreboding famine in Kalinga caused by draught. The

Manicora (No. 194) refers to the popular belief that famines are caused by the sins of rulers.

ose McCrindle-Ancient India as Described by Megasthenes, 32.

p. 487.

of Asia, p. 225.

# Index I. Sources with the Subjects

The references are to the pages of this work ]

#### A

Agni Purana—Translated into English by M. N. Dutt. in two vols. on the right of collecting grass, fuel and flowers enjoyed by Brahmins 82.

Aitareys Āraņyaka—Text with Eng. Trans. by A. B. Keith on spade 132; gold 123; polished mirrors 135; wooden sacrificial spade 136; seats made of adamvara wood 137; boats 138; ropemaker 149 f.n.; āvasatha ( abode for guests) 168.

Altaroya Brahmana-Text with Eng. Trans. by M. Haug in two vols. ou the story of Viswamitra and his fifty sons who were expelled by him 82-83; sale of Sunahsepha by his father Ajlgarta 83; ownership of land; story of Manu dividing his land among his sons 84; Vaiáya's peculiar function of being eaten up by the pricat and nobleman 85; law of inheritance 90; beefeating 111; race of chariots drawn by donkeys 112; vāsas (cloth) 116; dasā (fringe or border of cloth) 161; niska (a medium of exchange) 125, 165; necklace of nickas 128; wooden sacrificial posts 137 ; asandi (shining sent) made of udumvara wood 138; asandi square in shape 138; asandi rectangular in shape 138 ; asandi having four legs 138; stretching of hides with pegs 139; tigerskin as coverlet for isandr's 139-40; preparation of Soma sacrificial drink 141 : pillar (methi) 145; éreşthin (banker?) 152, 157; loss of status of the Vaisvas the mass of the industrial population who became tributary to another (anyasya valikit) and whose function was to be devoured by the priest and nobleman 152; gradual transition from human sacrifice to horse sacrifice during the pastoral stage, thence to the sacrifice of domesticsted animals ending with the offering of the fruits of the earth in the agricultural stage 154; Kayasha, son of a low caste woman 155-56; royal priests 156; King Viswantara sacrificing without the help of of priests 156; high-roads ( mahapatha ) 159; setu (raised bank for crossing inundated land) 160 fa-; best as food for royal and other distinguished guests 165; indebtedness 177.

Alberuni See under Enquiry into Indis-Alberuni,

Altindischen Leben—Zimmer on weatherprophet 150; ktläla 142, 227 fm.; gräms as a clar standing between the family and the tribe 25 fm.; verbal contest in the Vedic village council 23; grämant as president of the village council 25-26; pani 74; seasons 91 fm; harmyesthab prince 173-74.

Amarakoşa with the commentary of Kşîraswâmî un Aŭkotha (flower tree) - Aŭkola of Bhallatika Jataka? 236; Āephotā (- Aparājitā ) - Aphotaka of Viswantara Jātaka? 207 fn.

American journal of Philology (Vol. VII)

Bloomfeld on Sakadhumam (weatherprophet) 50 in.

Ancient Coins and Measures of Ceylon-Rhys Davids on pada meaning a fourth part of a certain gold weight and not a metallic standard 166.

Ancient Egyptians-Wilkinson on early trade between ancient India and Egypt 21.

Ancient and Medieval India—Mrs. Manning on elephants unknown to the ancient Egyptians 21; preparation of Soma drink 34 fu.

Ancient and Medieval Architecture—E.

B. Havell on the high antiquity and origin of townplanning in ancient India
146.

Ancient History of the Near East—Hall on the Mitanni and the Kassites of Syria and Sumer worshipping some of the oldest Vedic Gods 73.

Ancient India as Described by Megasthenes and Arrisn-McCrindle on the relations of King Cyrus of Persia with the tribes on the right bank of the Indus 163; 58 rivers of India 200; gold coming from Dardæ-Sans. Darada or Darada-modern Dardisthan in Kashmere 210; method of capturing elephants, the precursor of modern kheda system 212; stones sweeter than figs or honey (=sugarcandy?) 229; famines unknown in India 280.

Ancient India as Described by Classical Authors—McCrindle: Herodotus on vegetable wool (raw cotton) 202; the story of gold-digging ante 209-10; export of stones and dogs from India to Babylon 260, 262. Aristobulus ( Fragment 39) on the rains of over a thousand towns and villages in the Indus region 179 fn.; (Fragment 29) on rainfall in Taxila 199 : Strabe (XV. C. 693) on the ruins of over a thousand towns and villages in the Indus region 179 fu; (XV. C. 691) (cf. C. 697) on rainfall in Taxila 199; (XVC, 689) on India, a land of rivers 200; (XV. C. 706) on gold coming from Dorde - Darada or Darada - modern Dardisthan in Kashmere 210; (XV. 1. 41-43, pp. 704-705) on method of capturing elephants, the presureor of the modern khedā system 212 fn.; (XV. C. 700) on the primitive nature of Indian mining and metal industries 214 : (XV. C. 701) on Indians having not pursued accurate knowlege in any line except Medicine 214; (XV. C. 709) on stones sweeter than figs or honey (= sugarcandy?) 229; Theophrasius on India famous for ivory and ebony 70 fn. Nearchos (Fragments 9 and 10) on leather oil flasks and white leather shoes 226; on earrings of ivory 228.

Ancient Indian Numismatics (Carmichel Lectures, 1921)—D. R. Bhandakar on the relative value of gold and silver based on a second century inscription 271.

Annals and Antiquities of Rajasthan—Col. Torid (2 vols.) on the Hindu names of towns at the estuaries of the Gambia and Sengal rivers of the Tumba Cunia and of another Cundas 19.

Angustara Nikaya or the Book of the Gradual Sayings-Translated by M.

Hare in three vols. on the use of birds to guide pilots (In a cloudy day birds were let loose and the direction to which birds went, the mariners thought land lay that way) 262.

Antiquity of Hindu Medicine-Royle See under Esseay on the Antiquity of Hindu Medicine-Royle,

Anukramani to the Rgveds on royal seers who have composed Rgvedic hymns 155-56.

Arthasistra of Kautilya on corporate undertakings by villagers 189; kākaņika—‡ māņaka 268 fn.; l silver māņaka—88 white mustard seeds in weight 270; table of weights and measures 272 fn.

Artic Home in the Vedas-B. G. Tilak on the seasons in the Vedic Age 91 fn.

Atharvayeds-Text Edited by Roth and Whitney and revised by Lindenau connected terms tachnical with weaving like otu (woof), tantu (yarn) and mayukha (pegs to stretch the web on or shuttle) 115; vastra (cloth) 116; sic (fringe or border of cloth) 116; nivi (closely waven end of the cloth) 116; drapi (vest) 47-48, 118; pratidhi (a part of the bride's attire) 118; uspice (headdress) 118; kamvala (blanket) 119; sāmulya (undergarment of wool?) 119; attada (sprung from tada or mulberry i. e., silken?) 119; sans (hemp) 119; metals: gold, ayas, silver, tin, lead and syams 122; extraction of gold from earth (mines) 125; nisks (a medium of exchange) 125, 165; chips of gold used in sacrifice 125; gold on the priest's finger 125; gold given as fee to the priset 125 ; golden ornaments 127; ornaments of various kinds : tirlts, parihesta, pravarte, ring, golden amplet necklace of niskes, kurles, kumbs, opaia etc. 127-28; silver amplet 130; loba 131 : ivama 131 : a bair of shears with sharp blades 131; icon are 132; iron hook 132; rezor 132; iron het 132; fetters made of iron 133; sacrificial hatchet 132; sickle to out and trim the sacred grass 123; threads of iron used in amulet 132; armour 132; iron forte 132; iron pillars 133; dhruva (wooden having the largest sacrideial ladle bowl) 136; juhu (wooden ladle) 136; upabhyt (wooden ladie) 136; wooden mace used in sacrifice 136; wooden cover for sacrificial vessels 126; wooden mortar and peetle for pounding rice 136; 169; wooden pegs (used in stretching out skin or woven sloth and for other purposes) 126; wooden sacrificial posts 187; avera (timber post) 187; drupad (timber post) 137; vanaspati (timber post) 137; tälpa (naptial bedstead made of wood) 137 ; prosths (in prostha-saya) something like a high and broad bench 137; vahya (light coach that could be carried about when nacessary) 137; isand! (shining seat or occupier of a shining sent) 137; Vržtya chist's asandi described 138; rathakara 1.8; carriage 188; boat 138; black antelope-skin as the dress of the religious student 129; deer-skin as dress 189; deer-skin as coverings 139; black antelops-skin used in pressing some and bruising and hasking the rice used in oblations 139, 174; decorated and inlaid (pil) bowls like the starry night 142 and carriage in relief of gods inside the bowl 142; the ordinary type of a dwelling house 148, 168; various divisions of the dwelling house : store-house of some, agniśala, patninam sadana, store-room for corn, covered verandahs, sheds for cattle etc. 143; grha (either an actual house erected over or beside the grave in memory of the deceased or chambers and vaults of subterranean or rack-cut caves) 144; pillar (sthund) on Vedic grave 144-45; dvāra (door) 145 in.; duropa (door) 145 fn.; sthuna (pillar) 145 fn.; svaru (pillar) 145 fn.; methi with variants madhi, methi or methi (pillar) 145 fn.; husbandman 148; tast; (carpenter) 149; sakadhuman (weatherprophet) 105; kusidin (usurer) 152; alayes and their condition 153; female labour 153; 153 fn.; interchange of commodities of various localities 158; life of the merchant described 159; parirathya (road suitable for chariots) and cart-roads 159; charm to ensure a prosperous journey 159; parting traveller's address to the houses of his village 159, 168; references to sea and the use of sea by means of simile 160; existence of three seas 160; evaporation of seawater going to form the clouds 160; navaprabhramanam (sliding down of the ship) 161; pratipans (exchange of merchandise) 164; āvasatha (structure of some sort for the reception of guests) 168 fo.; ukhā (cooking pot) 169; sūrpa (winnowing basket) 169; wooden stirring prong 169; fork 169; brahma-udana 169; wife joining her husband in ceremonials and sacrifices 171; wife as queen of the household 171 fn. 171-72; cooking left to the wife 171; bride weaving the garment which the insband is to wear on the first day of his wedded life 172; girls as milkmaids of the family 172; liberality of princes 173; harmya 174; women winnowing grain 174; women collecting the alkaline droppings of the cow 174; attendants 174; läksä (lac) 176; rate of interest 177; prayers to deities in connection with debts 177; contraction of debt with the intention of non-payment 177; King Parikšhit realising the ideal of material welfare of his subjects during his rule 178.

Atharvaveda—Eng. Trans. by M. Bloomfield See under Hymns of the Atharvaveda by M. Bloomfield.

Atharvaveda-Eng. Trans. by R. T. H. Griffith in two volumes śāriśākā as cultivated rice 93 ; forests supplying materials for the construction of chariots 97; on the use of udumvara wood in making amulets, sacrificial posts and ladles 98; the use of the timber of the hard-wooded tree Aratu in making the axles of chariots and carts 99; Abayu as being poisonous in its natural condition but medicinal when cooked and properly prepared 105; on the use of the skin of the black antelops in pressing Soma and bruising and husking the rice used in oblations 139 fn.

Atthasalini (Buddhaghosa's commentary on Dhammasangani)—Trans, into Eng. by Maung Tin in two vols. on the relative position of the apprentice and the master craftsman 245.

Apasthamva Grhyasütra—Trans. into Eng. by F. Max Muller in the S.B.E. series vol. XXX. on the rules and rites of house-building 235.

Apasthamva Dharmasütra—Trans. into Eng. by George Bahler in the S. B. E. series vol. II. on forests as the abode of hermits 203 (n.; rigidity of the caste system 244, 277; the condemned professions 249; a fidra can become a Brahmin and vice versa according to good or bad deads 248; slaves could be exchanged for another 253; Brahmins permitted to barter homegrown corn, food, etc. 267; cow as a standard of value 268; the king's duty to maintain frotriyas, the weak, the aged, women without means and lunatics 276; king's daty to build a ball open to guests of the first three varnas and to see that no Brahmin suffered from hanger 276; property left ownerless reverting to the crown 276; those exempted from taxation 277.

Asatosa Silver Jubiles Volumes on Orientalia vol. III. (Article by Prof. K. M. Gupta) on the Land System and Agriculture of the Vedic Age 91—92.

Atvalayana Gibyasütra-Trans. into Eng. by H. Oldenburg in the S. B. E. series vol. XXIX. on vribi (rice) 200; yava (barley) 201; sesamum 202; armour 214; axe 215; copper implements 216; copper rezor 216; gold vessels 216; gold spoon 217; ornament 217; earring 218; charlot 222; wooden spoon 223; jahn (spoon) 223; aprhhrt (spoon) 223; sruva (small sacrificial ladle) 223; dhrava (big sacrificial ladle 223; agnihotrahavani 233; patri 223; prasitraharana 223; wooden dish 223; wooden sacrificial cap 223; sphys (wooden sacrificial sword) 224; basket 234; winnowing basket 225; earthen vessels 225; jag 225; jar 225; shoes 225; leather by which the arm is protected against the bow-string 226; rules and rites on house-building 235;

method of examining the building site 235.

Aśvalāyana Srauta Sūtra with the commentary of Gärgya Nārāyanī on kārpāsa (cotton) 120, 203.

#### B

into Dharmasttra-Trans. Baudhāyana English by George Bahler in the S. B. E. series in Vol. XIV. on the articles used in the prepration of the Some drink 141; condemnation of the enstom of N. Aryans participating in seatrade 163, 259, 260; condemnation of town-life 186; ideal economic holding 190: law of inheritance and succession 193-95; 1th as the royal share of the produce 196; forests on the habitation of hermits 203; condemnation of actors, stage-players and teachers of acting, singing and dancing 249; apaddharma 250; cow as a standard of value 265; condemnation of money-landing 274; ave masses a month for twenty karsapapas as the legal rate of interest 275; property left ownerless reverting to the crown 276.

Beginnings of South Indian History—S. Krishnaswami Iyenger on Babylonian influence on Hindu Astronomy 73.

Bibliography of Indian Geology (article on gold by La Touche) on Neolithic gold mining 4.

Biography of Words—F. Max Muller on the common knowledge of the arts of the weaver, the carpenter and the platter of grass and reeds among the peoples speaking the Indo-European group of languages 45; loha originally meaning copper but later on denoting iron 49. Black Yajurveda See Taittiriya Samhitä.

Book of the Kindred Sayings, The-Rhys Davids and F. H. Woodhard See under Kindred Sayings.

Brhadaranyaka Upanisad-Trans, into Eug. by F. Max Muller in the S. B. E. Series Vol. XV. on the crops grown 94; gold 123; silver 123; goldsmith 124; pådas of gold 125 fn.; golden vessel for Asvamedha called mahiman 126 fn.; ladle of pure gold 126; silver vessel for Asyamedha called mahiman 130; metal vessels 131; rasor 132; gruva (small wooden sacrificial ladle) 136; cup made of udumyara wood 136; 169; waggons 138; carriage 138; Kings Pravahans Javala and Ajatasatru disputing with and instructing Brahmins in the love of the Brahma 156; gapa 157; description of borses and salt as coming from the Indus regions 151; setu (raised bank for crossing inundated land) 160 fn.; pada as a metallic standard 167 fn.; liberality of princes 173; läkṣā (lac) 176.

Buddhaghoşa's Commentary on Mahavagga I. 30, 231.

Buddhist Birth Stories-Rhys Davids on female dancers and singers 256.

Buddhist India—T. W. Rhys Davids on corporate village life 186; Suppāraka city 183; Solasa mahājanapada in the Jātaka period 197; picture-gallery of King Pasenadi of Kośala 237; articles in which the merchants dealt 262; Suppāraka as a port of departure 262; retail and wholesale trade: its arrangements 265.

Buddhist Records of the Western world-Beal See under Si-Yu-Ki. Buddhist Suttne-Trans. into Eng. by T. W. Rhys Davids in the S. B. E. Series Vol. XI. on Säketa city 182; cattle-rearing (in Dhaniya Sutta) 211; detailed description of a flight of stairs 234; open-air bathing tank described 234; 2000 years old baths at Anuradhapura in Coylon still in a fair state of preservation described 234 fn.

#### C

Calcutta Review (April, 1933) Prof. Amalya Ch. Vidyabhasana (in his article on Social life in Jaina Literature) on 1000 pieces as the fee of a courtesan (Kāmadwajā Vanijagrāma) for one night 257; umbrella and yak tail granted to a courtesan as a mark of royal favour 257.

Cambridge History of India-Rapson, Vol. I. on Dasa chief living in paras 23; monarchy as a well-established institution in the Ravedic Age 25; rejection of Zimmer's view that the grama was a clan standing between the family and the tribe 25 fm; puras as meaning earthwork fortifications and not towns 28; no mention of the use of the horse in war in the Rgveda 38; Vedic Indian very little of a navigator 67, 68; origin of the story of the Ramayana in the later Brihmana period 61; the nature of royal ownership of land 83-87; no see-borne commerce with Babylon in the Brahmana period 162; relations of King Cyrus of Persia with the tribes on the right bank of the Indus 163; Indian tribes subject to Assyrian kings 163; different districts having different laws of inheritance 193-94; caste was no bar to mobility of labour both vertical and horizontal in the Jataka period 248;

the large size of ships mentioned in the Jātakas 260,

Chindogya Upanisad-Trans, into Eng. by F. Max Muller in the S. B. E. series Vol. I. on the dearness of ealt owing to its importation from a distant place 34, 158 fn.; house and fields as instances of private wealth 82; 85; transferrability of houses and fields 85; royal gift of a village to Raikks 89, 178; famine 96; vasana (cloth) 116; gold 123; other metals : silver, lead, tin and loba 123; lavana (borax) 123; softening of gold by means of borax 124-25; alankara 127 fn.; necklace 128-29; John 131; softening of silver by means of gold, of tin by means of silver, of lead by means of tin and of John by means lead 131; hatchet 132; pair of nail scissors (kārshnāyasam) 132; boll metal (kāmeya) vessels 133; parigha 145 ; fisherman 151 ; kings Aswapati and Pravahana Javala disputing with and instructing Brahmins in the love of the Brahma 156; a Brahmin imparting knowledge to a Suira, accepting his presents and taking his daughter for his wife 156; Satyakāma Jāvāla of humble origin was accepted by a priest as a pupil and afterwards became founder of a school of the Yajarveda 156; high-roads (mahapatha) 159; seto (raised bank for crossing inundated land) 160 fn.; avasatha (structure of some sort for the seception of guests) 168 fn.; perfumes 176; liberality of Janafruti 173.

Chips from a German Workshop—F. Max Muller, Vol. I. Vedic idol-worship (sculpture) 37; absence of the caste system in the Revedic Age 58. Chollavagga-Trans. into Eng. by T. W. Rhys Davids and Hermann Oldenburg in the S. B. E. series vols. XVII and XX. on the sale of land 192; description of farming operations 198; monks combing cotton and making the estton up into pillows 219; cholaka (handkerchief) 220; boleters of five kinds 230; mosquito curtain, etc. 220; pallanka (high class bedstead) 232; beach long enough to accommodate three persons leandf 222; Leandaka 222; sattango (sofa) 222; sofa with arms to it 292; arm-chair 222; bhadda-pitham (state chair) 222; vithikā (enshioned elaka-padaka-pitham chair) 223 : (obsir raised on a pedestal) 223; amalakayantika-pitham : (chair with many legs) 223; cocohham (canabottomed clair) 223; straw-bottomed chair 223; supervision of building construction as one of the duties of the Buddhist Order 281; five kinds of abodes allowed to Buddhist monks 231; selection of building site 232; extencircly built houses described 232; period taken in building some of the big houses 232; compound of houses enclosed with ramports of three kinds 233; description of gateways 233, five kinds of roofing 233; floors of houses 233, doors, 233-34; windows 234; adjustible shutters for windows 234; flight of stairs 234 fo.; monks allowed to use a loom and all the apparatus belonging to a loom 246; the despised callings 249.

Civic and National Ideals—Sister Nivedită on civic consciousness in the age of the Rămāyana 148.

Civilization in Ancient India-R. C. Dutt

on the derivation of Arya from a root (kis) which means to cultivate 28.

Comparative Grammar of the Dravidian Languages—Dr. Caldwell on Dravidian words in the Hebrew text of the Book of Kings and Chronicles of the Old Testament suggesting that the two words concerned formed the chief article of trade between the early Indians and the Jews 91; trade between early Indians and the Greeks 260.

Contributions to the History of the Hindu Revenue System—Dr. U. N. Ghosal on hiranya meaning cash charge upon certain special classes of crops 88.

#### D

Das Alte Indien-Von Bohlen, Vol. I on early trade between India and Arabia 71-72.

Der Rigveda—Ladwig Vol. I. on the judicial function of the village sabhā in the Rgvedic Age 26; paṇi's (merchants) 74; anūka as adverb and not as an ornament 51; hvārā in Rgveda 1. 180. 3. meaning a wooden vessel and not a snake or a thief 53 fn.

Dhammapada—Trans. into Eng. by F. Max Muller in the S. B. E. Series Vol. X. on channels dug for co-operative irregation of fields 200.

Dhammapada Commentary on cattle rearing 211; female slaves waiting upon
queens and performing such duties as
buying flowers for them 252; undischarged slave caunot enter into the
Buddhist order 253; woman working
as the keeper of a paddy field and
parching the heads of rice 256; woman
working as keeper of burning grounds

though no wages are mentioned 256; woman working as an acrobat 256; woman working as a dancer and singer 256; courtesans having their serving maids 257; taverns for the sale of liquor 256.

Dialogues of the Buddha—Trans. into Eng. by T. W. Rhys Davids in four Vols. on Ukkattha city 183; Buddha did not accept slaves from anybody 253; undischarged slaves not eligible for the pavajja ordination 253; female dancers and singers 256.

Die Indogermanen—Hermann Hert, Vol. I. on the original Aryan stock having acquaintance with agriculture long before their migration into different lands 22.

Digest of Hindu Law—Colebrooke on conditions of apprenticeship as given by Gantama 245; and by Katyayana 245.

Dighs Nikāya on the cities of Vārāṇasī, 180, Champā 180, Dantapura on the Kalinga coast 180-81. 262, Māhissati 181, Mithilā 182, Potana 182 and Roruka, capital of Sovira 182, 262; description of an open-air bathing tank 234; voyages out of sight of land 258.

Disquisition on Ancient India—Robertson on the Arabian-Indian branch of Phonician trade 10.

Divyāvadāna—Text critically edited by E. B. Cowell & Neil on the cities of Brahmottara 180, Nandana 182, Romanaka 182 and Sadāmatta 182.

Dwipavaméa on glass pinnacle placed on the top of the Ruanwelle dagoba by Suidaitissa in the second century B. C. and on a glass mirror in the third century B. C. 135. Early History of India-V. A. Smith on the origin of the city of Pataliputra 184.

Early History of Kansamvi-N. N. Ghosh on the identification of Sahajātī with the ruins now existing at Bhitā, about eight miles from Allahabad 264 fn.

Early History of the Spread of Buddhism and the Buddhist Schools-Dr. Nalinaksa Dutt on lands gifted away 192.

Enquiry into India, An-Albertani (Eng. Trans. by Sachau) on the identification of Suvarna island with the islands of the Malaya Archipelago 162 fn.

Epigraphica Indica (vol. I) on pada as a metallic standard 167; (vol. II) on forests as elephant-preserves 204 fn.

Essay on the Antiquity of Hinds Medicine

-Royle on Myrrh-Egyptian bal =
Sans. bela 21-22; Arabian-Indian
branch of the Phonician trade 70.

Explorations in Sind—N. G. Mazumdar on Limbi in Kathiawar as an outpost of Indus civilisation 16; wider diffusion of Indus civilisation in Western Sind between the Indus and the Khirthar range 11.

#### G

Gantama—Trans. into Eng. by George Bahler in the S. B. E. series vol. II. on unenclosed land used by all for grazing cattle, obtaining firewood, gathering flowers and getting fruits 190; private ownership of land 191; modes of aquisition of property 191; acquiring property by usage 192—93; law of inheritance and succession 194— 95; royal share of the produce 196; forest as the habitation of hermits 203; all treasure-trove belongs to the king 210, 276; exception to this rule 210-11, 276; guild of herdsmen 242, of money-lenders 242, 275, of cultivators 242 and of traders 242; rigidity of the carte system 244, 277; legislative. functions of guilds 241; conditions of apprenticeship 245; the condemned professions 249; Apaddharma 250; Brahmins permitted to barter homegrown corn, food etc., 267; teleration of money-lending 274; six different kinda of interest 275; five māṣā's a month for twenty kārtāpaņas as the legal rate of interest 275; king's duty to protect the property of infants and also to maintain the strotriyas, the weak, the aged, women without means and lunstics 276; property of a Brahmin who leaves no issue to be divided among the Brahmins but the king appropriates in such cases the property of men of other castes 276; anybody who finds a treasure-trove gets onesixth 276; artisans to work for the king for one day in the month 276-77; scale of royal taxation 277.

Geography-Ptolemy on the identification of Yavadwipa with Java 162 fn,

Gopatha Brahmana (and the Atharvaveda)

—M. Bloomfield on beef-eating 111;

Kansamveya, one belonging to the city
of Kosamvi 181 fo.

Govila Gibyasutra—Trans. into Eng. by F.

Max Muller in the S. B. E. series
vol. XXX on the rotation of crops 91,
200; depisting life in the village 186;
ceremonies connected with agriculture
199; rules on house-building 235.

- Growth and Vicissitudes of Commerce— J. Yeats on the high antiquity of the silk industry of China 162.
- Guide to Taxin-Sir John Marshall on circumstances leading to the growth of the city of Taxila 184.

#### H

- Herodotus—Rawlinson on 360 Eubolic talents of gold-dust paid as tribute by the Indian satrapy of Darius 280; Indian army of Xerxes armed with iron-headed arrows 214.
- Hibbert Lectures for 1837 on the Origin and Growth of Religion among the Babylonians—Dr. Sayoe on commerce between India and Babylon as early as 800 B. C. 17.
- Hiranyakesin Crhynsutra—Trans. into Eng. by F. Max Muller in the S. B. E. Series Vol. XXX. on rules and rites on house-building 235.
- Historians' History of the World (Vol. I) on trade and the articles of trade between India and the Western world (Assyria, Babylon etc.) ·163—64; (Vol. II) on the Arabian-Indian branch of the Phomician trade 70.
- Historical Researches—Heeren on the derivation of Abyssinia from Aboasin, a classical name of the Indus 19; trade between ancient India and Egypt 20; trade between ancient India and Arabia 71.
- History of Ancient Sanskrit Literature— F. Max Muller on various kinds of priests 239.
- History of Ancient Del Orient-Eng. Ed. (Vol. II) on trade between ancient India and Egypt via Yemen 18, 72; trade

- hetween ancient India and Arabia 71-72.
- History of Antiquity—MaxDuncker on trade between early Indians and Sabous on the coast of S. Arabia before the tenth Century B. C. 72.
- History of Aryan Rule in India—E. B. Havell on the antiquity and origin of town-planning in ancient India 145-46; growth of villages into towns 183-84.
- History of Commerce—Dr. Day on Phonician commerce and its Arabian-Indian branch 69.
- History of Sanskrit Literature—A. Macdonald on the absence of horse-riding in the Egyedic age 38; brahmans in the sense of a man of the first warps occuring only eight times in the Egyeda while in the sense of sage or officiating priest occuring forty-six times 59; composition of the Ramayana before 500 B. C. 81; date of Kātyāyana 245.
- Hymns of the Atharvaveda—M. Bloomfield on opasa as a coverlet for women (ornā) 51 fn.

#### I

- Hinstrated London News (Feb. 27 and March 7, 1926; Jan. 7 and 14, 1928) on Prehistoric Civilisation of the Indus valley 12—16.
- Imperial Gazeteer of India (Vel. II) on Neolithic graves 6; Piprawah stupa (450 B. C.) 214, 236,
- India in Greece—Pococke on colonisation of Ethiopia by Indians 18—19; on the points of similarity between the sculpture and architecture of ancient India and ancient Egypt 20.

India and the Western World—Rawlinson on supposed Babylonian influence on Hindu Astronomy 73.

Indian Antiquary (Vol. VIII)-T. Foulkes on trade between Ancient Indians and the Jews 71; trade between ancient India and Egypt 21; existence of a sea-route between India and Persian coasts in the days of the Buddha 261. (Vol. XI) Prof. Ball on trade between early Indians and the Jews 70-71; explanation of the story of the gold-digging ants 210. (Vol. XIII) on trade between Ancient India and Egypt via Yemen 18. (Vol. XXX) Mr. Fawcett on the sculptures on the Edakal Cave, Wynaad 5 fo. (Vols. XXXIV and XXXVI) V. A. Smith on no Bronze Age in India 7 : on the copper and prehistoric implements of India 7; (Indian Antiquary, 1896) kings seem to have kept granaries for emergencies like war and famine 276.

Indian Village Community—Baden Powell on Aryan lands being cultivated by the conquered aborigenes 64.

Indica—Ktesias on dogs, onyxes and other precions stones as articles of trade between India and Babylon 162-63; description of the Indian lähjä (cochineal) 164; karpion (= karpura) 260.

Indica—Arrian on fifty-eight rivers of India 200; method of capturing elophants, the precursor of the modern 'khedi' system 212; oilflacks made of leather 226; white leather-shoes 226; earring made of ivery 228.

Indische Alterthamskunde—C. Lassen Book I. on early trade between India and Arabia 71—72; on the Sanskrit name ibha reaching Egypt through Tyre and becoming Egyptian ebu 21; elephants neither used nor tamed in ancient Egypt 21.

Indische Studien-Weber on the absence of caste in the Rgvedic Age 58; on liberality of princes in the Brühmana period 178; sadasys (a priest) 239.

Industrial Competition of Asia—C. Daniell on the nature of ancient Indian foreign trade 280.

Introduction to the History of Religion— Jevone on the cultivation of plants as one of women's contributions to civilisation 154.

J

Jaiminlya Brāhmaņa—text edited with Eng. Trans, by H. Oertel on paryanka 138; methi (pillar) 145 in.; king becoming a seer 153.

Jatakas, the (Fausball's edition) :-

Abhayantara: (No. 281) on iron nets 216; resting place for travellers 230.

Abitupdika (No. 365) on snake-charmor 241; grain merchants 265.

Akālarāvi (No. 119) on Udicea Brahmine 288,

Akirti Jālaka (No 480) on Kāveripattanam in the Drāvida country 181; leaves of Indravaruni tree 201.

Alamyusā (No. 523) on golden comb 218; gonako (blankets made of goat's hair) 222; paryanka 221; dice-board 223.

Alinachitta (No. 156) on village of carpenters 187, 224, 243; forests supplying

- tuel and timber 203; sātaka 219; kṣauma 221; angavidyāpāṭhakas 239; carpenter 240.
- Ananusocaniya (No. 328) on a life-like golden image of a girl 217, 237.
- Anabhirati (No. 185) on pearls 212; liquorshops 227; senior pupils arting as assistant master 245.
- Andhabhūta (No. 52) on camphor 203, 278; camphor tree 204; golden diceboard 217; golden dice 217; royal high priest 242; incense merchants 265.
- Adipta (No. 424) on Roruks, capital of Sovira 182; Raurava (=Roruka) as a port of departure 262.
- Amra (No. 124) on dropa, drow 223; Udieca Brahmins 238; magician's tricks 239; Chandala village 243, 248.
- Amra (No. 474) on Chandala village 186. Amracura (No. 344) on hair-dye 278.
- Aramaduşaka (No.46) on watering of plants by the gardener 213; wooden tubs or buckets for watering plants 223; leather made receptable for sprinkling water on plants 227.
- Avīkspa (No. 27) on gates of Srāvasti 182. Apaņņaka (No. 1) on Vārāņasi 180; neck-
- lace of gems 218; coverlet 219; caravan traders: their organisation, mode and habits of life etc. 262-63, 267; dealer's sense of the wear and tear of articles 266; selling at a price fixed by his predecessor 266; cintment 278.
- Asadréa (No. 181) on adjustible sword 214; gold plates worth a lac pieces 217; sanghāti 219; kanchuka (overcoat) 219; screen (śani) 220; leather-case for (keeping) sword 227; bows made from the horn of sheep 229; coventional 18 silpa's taught 239.
- Asampradana (No. 131) on slaves being gifted away 253; slaves helping their

- ex-masters in distress 254; adhaka (a kind of measure) 272; mana (a kind of measure 7272.
- Asstarupa (No. 100) on drainage of Benares 180.
- Afilak sapa (No. 126) on a woman working as an astrologer 256.
- Asitābhu, Asikābbū, Asītānublūtā (No. 234) on krakaca (saw) 215.
- Asthisena (No. 403) on kuţikāra-sikṣāpada 230.
- Aśvaka (No. 207) Potali city in Kaśi kingdom and its gates 182.
- Avarya (No. 376) on payment of tax in cash 197; ferryman 241; ferryman advised to settle the fare by bargaining 250-51.
- Ayogina (No. 510) on the uncertainty of human life compared to the uncertainty of the cloth of the drunkard 227; ironpillars used in the construction of a house 230.
- Bāveru (No.1339) on India's trads with Babylon earlier than 400 B. C. 162; golden cage 217; expert of peaceck by Indian merchants to Babylon 260, 262; the use of disakaka for the guidance of pilots 262; partnership in the deal in birds from India to Babylon 267.
- Bhadrasala (No. 465) on town-planning of Kosala capital 185; iron net 216; one pillared palace 224; use of the wooden pillar in the construction of houses 230; samsthagara (town hall) 231; seas born of a slave girl by a free man hardly regarded as free 253.
- Bhallātika (No. 504) on aguru (alos) 203, 278, Sāla tree 204; flower trees and plants like Karņikārā 206, Aŭkola 206; Sattali, Navamallikā, Mūdhavī 206, Yuthikā 206, Kuruvaka 207, Pātali 207; Sindhuyāra (= Niṣindā) 207.

- Bherlvids (No. 59) on trumpet-blowers 241.
- Bhimasena (No. 80) on gates of Benares 180; Benares famous for scents 180; Benares famous for textile fabrice 180, 220; town-planning of Benares 185; weavers' ward in Benares 220, 244, Udicea Brahmins inheriting a stricter standard 231; conventional 18 filpa's taught at Benares and Taxila 239; boy-servant 241.
- Bhojājāneya (No. 23) on swords 214; armour 214; gold plate worth a lac pieces 217; canopy decorated with golden stars 220; screen made of raktakamyala 221.
- Bhuridatta (No. 543) on earring 218; uspita 219; masuraka, seat covered with gadi 230 fn.; shoes made of cloth woven with threads of different colours and decorated with gold 221; preparation of salt by the evaporation of seawater 229; visavaidyas (curer of peisonous bites) 239; people not following casts professions 246; betting with big sums 278; debtors flying to the forest or attempting to commit suicide to escape from the clutches of their oreditors 279.
- Biss (No. 488) on āvāsika (carstaker of houses) 231,
- Brahmadatta (No. 323) on umbrella made of leaves 225; one-soled shoe 226; leather undergarment 226; leather upper garment 226; kutikāra-sikṣāpada 230.
- Chakravāka (No. 451) on Rohita fish 212; Pāthīna fish 212; Vāluka (- Bele ?) fish 212; Pāvuṣa (- Kālavāyuṣa) fish 212; Munja (Mirgela ?) fish 212.

- Chandrakinnara (No. 485) on puspapata (cloth with flowers embroidered on it) 200; flute or pipe 225.
- Chaturdvāra (No. 439) on crystal palace 228; dangers of son-voyages described 258; ship striking a hidden rock in mid-ocean 258.
- Champeya (No 506) on Sala tree 204; Karnikara flower tree 206; Patali flower tree 207; Amra tree 207; Jamvu (blackberry) tree 208; earring set with jewels 218; keyūra (bracelet on the upper arm) 218; dug-outs 272; snakecharmer 241; Brāhmaņa as snake-charmer 246.
- Chedi (No. 423) on Svätivati city in the Chedi kingdom 183; royal high priest 242.
- Chitrasambhüta (No 498) on Avanti city 183; Chandala village 186, 243, 248; coverlet for chariot with designs on it 219; eight of a Chandala forebodes evil 249; even food seen by a Chandala is not to be taken 249.
- Chullakaśresthi (No. 4) on linen flaz 202; chivara (dress of the Buddhist monks) made by the monks themselves 219; kāyavandhana 219; tent 221; grasscutter 240; attendant 241; marriage of a slave with a free woman hardly improved his status 253; navigability of the Ganges by crafts of considerable size right up to Benares 264; cornering in hay 266; dealing in futures 266; corporate purchase of a ship's cargo by many merchants 266; case of barter 267; kākaņika (a medium of exchange) 268; kārsāpaņa (a medium exchange) 268; signet rings as deposit or security (satyalikāra) 271; sight kārsāpaņas as cart-hire from Benares to the port mear by 273.

- Chullanandika (No. 322) on Brahmin working as hunter 246.
- Chullapadma (No. 193) on gates of Benares 180.
- Dadhivāhana (No. 187) on parašu (axe) 215; vāsi-parašu 215; screen made of silk-cloth 221.
- Durddada (No. 180) on corporate life in Benares 186; Karņikāra flower tree 206; Kaptakuraņda flower tree 206; cloth dyed in yellow with karpikāra flower 229; cloth dyed in blue with kaņtakuraņda flower 229.
- Dafabrāhmaņa (495) on fruit trees; Amra 207, Jamvu 208, Vilva 208, Vadarī 208, Haritaki 208, Āmalaki 208, Vibblitaka 208; Piyāla 208, and Lakuca 209; condemnation of Brahmins engaged in tillage and other callings 238, 246; forest-guard 241; Brahmins working as physician, goatherd, merchant, charioteer, agriculturist, meat-seller, caravan-guard, hunter, dealer in fruits, ornaments etc., 246; caravans electing their chief and appointing caravan-guard for safety 263.
- Dafaratha (No. 461) on sandals made of grass 225.
- Dasarpa (No. 401) en Dasarpaka famous for her swords 215; magician's tricks 239,
- Devadharma (No. 6) on Vārāņasī city 180; tent 221; paryanka 222,
- Dharmadhvaja (No. 384) on sufferings of mariners due to shipwrick in midocoan 258; the use of disakaka for the guidance of pilots at sea 262.
- Dhünkârî (No. 413) on enclosed pasture 190; goatherd 240; Brahmin working as goatherd 246.
- Darājāns (No.64) on customary fixed price: meek as a 100 piece slave-girl 266; kārṣāpaṇa 268; 100 kārṣapaṇas, pre-

- sumably of silver as the customary price of a slave-girl 273.
- Durmedha (No. 123) on conventional 18 silpa's taught 239.
- Durvalakāştha (No. 105) on crowbar 215; band-punkhā 225.
- Dyuta (No. 260) on gold vessels 216; golden bedstead 217; payment of tuition fees after the completion of studies obtained by begging 239; 14 nights as the paid to the teacher 245; 272; nights (a medium of exchange) 269.
  - Ekaparna (No. 149) on Vaisali city, 183; Udicca Brahmina 238; cowherd 240; asvapālaka 240; hastipālaka 240.
  - Ekarāja (No. 303) on string loop (šikya 225.
  - Gapdatindu (No. 520) on rājakammika (tax-collector) 117; leather-case for (keeping) sword 227; Valipratigrāhaka (tax-collector) 242; half a māṣaka as the daily wage of a female water-carrier 272—73; oppressive taxation 279,
- Gangamila (No. 421) on a daylabourer and his ladylove drinking wine together 227; wages of free labourers settled by higgling and haggling 250; the gay though frivolous life of the day labourer described 251; day labourers were sematimes paid in board and lodging 251; slaves treated as members of the family and living virtuous lives 254; woman working as water-carrier 256; quarter karsa and half a karsa as media of exchange 268.
- Carga (No. 155) on omen readers 239; valipratigrabaka 242; Brahmin as hawker 246; small traders carrying their goods from village to village on their own heads 265.

- Gandhara (No. 406) on Mithila 182; caravan trade 262-63.
- Ghata (No. 454) on Asitāfijana city 180; Uttara Mathurā 183; hares made of brass, silver and gold 216; hare made of stone 228; hare made of coral and precious stones 229, 237; washerman 240; wrestler 241; Dvārāvatī as a port of departure 262.
- Giridanta (No. 184) on asvanivandhika 240.
- Godbā (No. 325) on ādraka (ginger) 202; jīraka (cumin-seed) 203; marica 202; pippali (pepper) 202; cloth dyed red 229.
- Gidhra (No. 164) on walls surrounding Benares city 180.
- Grhapati (No. 199) on the misconduct of a village headman 188; corporate loan by villagers 189; sufferings caused by famine in a Kasi village 280.
- Grāmapiehaņda (No. 257) on paryanka 223; mat 224; vāstu-vidyācārya 230; nalakāra 240; kārņāpaņa 263; 54 kārņāpaņas as the price of a pair of ox 273.
- Gupa (No. 157) ou nivăsana 219; prăvaraņa 219; seate made of cloth 220; padapunchhanam 220; Benares cotton cloth fetching a 1000 pieces 220; monks dying their chivara 229; cloth dyed in yellow with karpikāra flower 229; sātakas worth 1000 pieces of copper 274.
- Guptila (No. 243) on acarya 239; caravan trade 262-63.
- Harimata Haritamanduka (No. 239) ion catching fish in a cage-like structure of came or bamboo-splints called kumina 212, 225.
- Hastipāla (No. 509), on royal high priest 242.
- Illies (No. 78) on Sarkard, a nigama near Rājagīha 182; bhastā (cloth-made bags

- to store up grains) 231; stool 232; basket 224; changotaka (small basket) 225; liquor-cup 225, 227; dried fish taken along with liquor 237; sură 227; a glass of ordinary wine was worth only one mășă 228; seven-storyed houses 230; mășaka and suvarpa as media of exchange 268, 269; a cup of sură was worth only one kărşāpapa 273.
- Indrasamānagotra (No. 161) on sayyāphalaka 223 ; pitcher 225,
- Indriya (No. 423) on Brahmin working as hunter 246.
- Jarudapāna (No. 256) on metals: iron, copper, lead, tin, silver and gold 209; vaiduryamaņi 209; pearls 212; guild of caravan traders 242; concerted commercial enterprise by merchants of Srāvastī 267.
- Javanahaman (No. 476) on mat 224.
- Jayaddvisa (No. 513) on foundation of Khullakalmasa city by a king 183; increase of royal domain by colonisation 191; forests as the habitation of Ataviyas 203—04; forest-guard 241.
- Kakkara (No. 202) on Asvakarpa tree 204; Vibhitaka tree 208; catching birds in traps with the help of decoy birds 212; traps made of wool for catching birds 221.
- Kalanduka (No. 127) on run away slaves 236.
- Kalingavočhi (No. 479) on Dantapura city 181, 262; Sākala city 183; länchhanamudrā (seal) 216.
- Kandagalaka (No. 210) on Khadira tree 204.
- Kapavera (No. 318) on nagarapāla 242; the serving maids of courtesans 257; 1000 kārņāpaņas per night as the fee of a courtesan 272.

Kapota (No. 42) on Adraka (ginger) 202; jiraka (cumin seed) 232; colander 215; cage-like structure made of straw for birds to live in 225; cook 241.

Karkata (No. 267) on fork 215

Kajāhaka (No. 125) on wooden plank used as a slate for writing 223; ran away slaves 256; wooden spoon 223; slaves as valet or footman to his master's son or as store-keeper to his master 252: slave-girl's son patted and permitted to learn writing and handicrafts 251; slaves fed on a slave's fare and at the slightest fault beaten, branded and imprisoned 254-55.

Kausamvi (No. 428) on lonakara (manufacturer of salt) 229, 240.

Kaka (No. 140) on gold vessels 216.

Kālavāhu (No. 329) on golden cage 217; golden sup for a bird 217.

Kāma (No. 466) on the extension of arable land by fresh clearance of forests 190; survey of the fields by royal officers uparājjam (viceroyalty) 197 : valisādhaka (tax-collector) 197; irrigation 200.

Kämanita (No. 228) on gold plate worth a las pieces 217; bhūtavaidya (conjurer of evil spirits) 241.

Kāmavilāpa (No. 297) on Penares famous fabrics 189; Benares textile for famous for satakas 220.

Kāṣāya (No. 221) on town-planning of Benares city 185; corporate life of the citizens of Rajagtha 186; decision of the majority prevailed in the village council 189 fn.; ivory 203; gandha-kāşāya sātaka 219-20; ivory bangles 228; ivory-workers' ward] in Benares 228; 244; cloth dyed in golden colour 229; dantakára (ivory-worker) 249.

Kästhähäri (No. 1) on finger-ring 218.

Ketava (No. 346) on scented rice (fali) 2 14. Khadirangara (No. 40) on gates of Benares city 190; brazen vessels 216; sevenstoreyed houses 230; innapannani (= I.

O. U.) 271; 275; the debtors getting back the I. O. U. when the loan was

paid back 275.

Khandapāla (No. 54) on Benares famous for her textiles 180, 220; agora 203; 18; Karnikara flower plant 206; Asoka flower tree 207; Pātali flower tree 207; Amra tree 207; sword 214; golden trappings for horses 217; earring 218; keytira (bracelet for the upper arm) 218; golden banglas set with pearls and precious stones 218; how made from the born of sheep 229; snapaka (bath-attendant) 242; arthadharmannsasaka 242; viniscayāmātya (judge) 242.

Kharamvara (No. 79) on a border village in Kolala 187; village headman appointed by the king 183; misconduct of the village; headman 188; revenue collector of a frontier village 197.

Kharaputra (No. 386) on performer of spalls 241.

Khulladhanurgraha (No. 374) on kāmsya sthäll 216; sthäll 225.

Khullahamsa (No. 533) on villages inhabited solely by hunters 186; nigida 24); villages inhabited solely by fowlers 243.

Khullakalinga (No. 301) on Dantapura city on the Kalinga coast 181, 262; Potali city in the Aswaks kingdom 182.

Khulinarada (No. 477) on Simula or cottonsilk 202; Simula or cotton-silk tree 204; cloth stiffened with starch 229-30; karamara, a person captured by robbers. and reduced by them to slavery 252.

Khullavodhi (No. 443) on chivera (dress of the Buddhist monks) made by the monks themselves 219.

Kimehhando (No. 511) on Nips (-Kadamva) flower tree 206; kirita (tiara for the head) 217; keyüra (bracelet for the upper arm) 218; angada (bracelet for the upper arm) 218; royal high priest 242.

Kimsakopama (No. 248) on Kimsaka flower tree 206.

Komāyaputra (No. 299) on a two-storeyed palace 230.

Kouseyi (No. 130) on copper vessels 216.

Kṛṣṇa (No 29) or kārṣāpaņa as a medium of exchange 268; 24 kārṣāpaṇas as the price of a pair of or 273; a young calf sufficient for house rent for a certain period 273; two kārṣāpaṇas as the hire for an ex in carrying a cart across a shallow river 273.

Kespa (No.440) on the leaves of Indravarunt tree 201.

Kṛṣṇadvaipāyana (No. 444) on the drainage system of Kosambi city 181; krakaca (a saw) 215.

Kahantivadi (No. 313) en lakat (lac) 203.

Kaburapra (No. 265) on foreste as the habitation of the Ataviyas 203-04; caravans appointing forest-guards for safety 263.

Kuddāla (No. 70) on parņika (growar of green vegetables) 201, 239; alāvu (goard) 201; kuşmānda (pampkin) 201; cusumber 201; šāka (potherbs) 201; spade 215; thatched house 230.

Kukku (No. 396) on wooden pillars used in the construction of houses 230.

Kukkura (No. 22) on leather coverlet for chariots 226; leather-made fittings of chariots 226; tult (scale) used by way of a simile 271. Kulâyaka (No. 31) on the corporate life of villagers 188—89; tent 221; phalakāsana (banch) 222; dharmasālā 230; persons reduced to slavery for their crimes 252.

Kulmāņapiņda (No. 415) on garland-maker 241; guild of garland-makers 242.

Kambha (No. 512) on chāţi (vat) 226.

Kumbbakāra (No. 408) on Dantapura city 181, 262; Kāmpilya city 181; Mithilā city 182.

Kundaka-kuksi-saindhava (No. 254) on gold sthäll 216; sätaka 219; canopy decorated with golden stars 220; screen 220; sthavikā (purse) 220; šānī (screen) 220; carpets 221.

Kuņāla (No. 536) on rivers dammed for purposes of irrigation 200; maluva (a kind of sweet potatoes) 201; sandalwood 203; trees: Tiefta, Kutaja, Sāla, Tilaka, Bhurjja, Muchilinda 204; Kuravaka, Chetasa, Bajuda, Punniga, Priyaka, Asana, Sarala, Karagula, Padmaka, Davadáru, Kakudha - Kakubha - Arjuna, Kachchikara, Tuna, Kanavera, Koranda, Kovidāra, Anangana, Anavajja, Surichir, Bhagini, Dhanakārika, Tālisa, Kotta 205; Cocha 206; flower trees: Karnikara, Kiménka, Aŭkola, Atimukta, Yodhi (- Yuthikā). Ketaki and Vakula 206; Champaka, Nagarukha (=Nagakelara), Asoka, Vanamalliki, Tagara, Bhandi (= Ghento), Jati and Sumana 207; Sandalwood, Priyanga and Usira (-Khaskhas) 200; silver 209; haritala (yellow orpiment) 209; manahálá 209; hingulaka 209; manikāra 217, 240 ; phalakāsana (honeh). 222; papph-chbaddak (sweeper) 241.

Kundaka-pupa (No. 100) on the corporate life of the citizens of Sravasti 185-86; on free labourers living from hand to mouth 251; udanka (= Pali Ulunka), a measure for liquids 271.

Kuranga-miga (No. 2I) on methods of bunting 211.

Kuru - Bharu (No. 213) on architect 240.

Kurudharma (No. 276) on Dantapura city on the Kalinga coast 181, 282; Indapattha city 181; Brahmic village 187, 243; land of ordinary landholders as distinguished from royal domain 191; royal share of the produce 196; survey of fields by royal officers 196; public granary 197; essence of sandal-wood 203; golden necklace worth 1000 pieces 218, 274; royal high priest 242; rajjuka (surveyer) 242; messurer of corn 242; essence of sandal-wood worth a lac pieces 274, 278; suffering caused by famine in Kalinga 279—80.

Kuin (No. 531) on Sakala city 182; sandalwood powder as a toilette for the breasts 203, 279; sandal-wood oil 203, 278; golden image of a girl 217, 237; necklace of nicks coins 218; mekhalā 218; cloth embroidered with gold 219; earthon pots with female figures engraved on them 226; earthen dolls for children 236; painted punkha 237; karmāra (smith) 240; malakāra 240; guild of smiths 242; industrial apprentice 245; prince apprenticing himself in succession as a potter, basket-maker, florist etc., without any social degradation 247; prince fashioning a golden image 247; Brohmin taking as his wife the childless wife of a king without losing his caste 248; nişka 209; kalka 279, 276 fs.

Kusanāli (No.121) on an one-pillared palace 224; use of the wooden pillar in the construction of houses 230. Kūtavānij (No. 218) on arthadharmānušāsaka 242; vinišcayāmātya (judge) 242; partnership of two traders of Srāvasti 267 and of two traders of Benares 267.

Lakşana (No. 11) on protection of the crops 199; method of hunting 211,

Länguleşä (No. 123) en änärya 239.

Linguitha (No. 144) on Udicoa Brahmins 238.

Lola (No. 274) on cage-like structure made of straw for birds to live in 225; eook 241.

Losaka (No. 41) on Gambhirapattana 181, 262; corporate life in the village 189; kānsāra 216; a seven-storayed crystal palace 228; ācārya being maintained by the gnardians of the children taught 239; distress of mariners when their ship struck a rock in mid-ocean 258.

Louhakumbhi (No. 314) on iron jar 215.

Madiyaka (No. 390) on Benares famous for her textile fabrice 180, 220.

Mahahamsa (No. 534) on Benares famous for her textile fabrics 180, 220; golden seat (Pali kochchha) 217; changotaka (small basket) 225.

Mahājanaka (No. 539) as Champā city surrounded by a wall piercod with gates with towers over them 180; Mithilā city 182; town-planning of Mithilā 185; description of the manufacture of arrows 214; illf (small sword) 215; brucelet on the lower arm 218; Kautamvara famous for her cloth 221; blankets made of goat's hair 222; description of wooden sandals 224; winnowing basket 225; ship containing seven caravans with their beasts 259; sea-voyage to Suvarnabhūmi (= Burma ?) 261; pearls, gems and diamonds as exports from India to Burma 262; navigability of

the Ganges by crafts of considerable size from Champa down to the sea 264.

Mahakapi (No. 516) on Prahmin peasant 238, 243.

Mahākapi (No. 467) on chaitya 231.

Mahikrapa (No. 469) on Brahmins working as robbers 246.

Mahamangala (No. 453) on Samthagara (town hall) 231; omen-readers 239.

Mahāmayūra (No. 491) on peţikā (wooden boxes) 223—24.

Mahapingala (No. 240) on hammer 215; orushing the subjects with taxation like sugarcane in a mill 279.

Mahānāradakāšypa (No. 544) on women working as water-carriers 256; merchantship going to the bottom of the sea 258; tulā (scale) used by way of a simile 271; sarṣapakalka 278—79.

Mahāsāra (No. 92) on female slaves looking after the jewels of the ladies in the royal harem 252; a man who has never seen (i.e., used) in his life a chair or a bed-stead 279.

Mahasilavaja (No. 51) on gates of Benares city 180; sword 214; gold drinking-pot 216; gold vase 216; gold box for keeping scents 217; pillows 220; chaturjätiva gandha 278, 278 fn.

Mahasudariana (No. 95) on Kusinara city surrounded by a wall 181.

Mahasutasoma (No. 537) on Indapatha 181, Kammasadamma city growing out of a village 183; king's right of increasing the taxes at will and of remitting them 196; senior pupil acting as assitant master 245.

Mahāswapna (No. 77) on the different divisions of a kingdom 197; vrihi (rice) 200; yava (barley) 201; godbūma (wheat) 201; mudga 201; māsa 201; Madhuka tree yielding Mahui flower 207; bell-metal vessels 216; gold plate worth a lac pieces 217; stool 222; rope 225; pitcher 225; manufacture of molasses from sugarcane juice 229; Udicoa Brahmins inheriting a stricter standard 238; royal high priest 242; half kārṣa and kārṣāpapa as media of exchange 268; sandal-wood worth a lac pieces 274 fn.; king's right to impose forced labour limited to the confines of his estates 275; oppresive taxation 279; a dream interpreted as foreboding famine in Kalinga 280 fn.

Mahāśwāreha (No. 302) on Benares famous for her textile fabrics 180, 220; a border village in Kāši 187; corporate life of villagers 189; gold vessels 216; gold vase 216; Benares cotton cloth fetching a lac pieces 220, 274; oppressive taxation 279.

Mahanmarga (No. 546) on Benares famous for her textile fabrics 180, 220; townplanning of Mithila 185; foundation of village for military purposes 188; corporate life of villagers 189; Pathina (Voyāla) fish 212; armour 214; iron helmet 214; sikāya-samayā (a sword of high quality) 215; Benares cloth fetching a lac pieces 220; tanning and softening leather by the application of kṣāra 226 ; mason 230 ; kṛdāśāla 231 ; underground palace 232; wooden roofing of the underground palace described 233; golden image of a girl made by the royal sculptor 237; woman working as a guard over a cotton-field and spinning thread from clean cotton 256; life-like paintings of elephants, horses, chariots. and various objects of natural scenery 297; karmara (smith) 240; carpenter

240; mason 240; kundakāra (seulpter)
236, 240; carmakāra 240; painter 240;
tunnavāya (tailor) 241; conventional 18
guilds 242; guild of wood-workers, of
smiths, of leather-workers and of paintors 242; ornaments of prostitutes 257;
Dyārāvatī as a port of departure 262;
building of 300 ships 259; ardhamāraka
and kārāpapa as media of exchange 268;
half a mājaka of meat was sufficient food
for a lisard 273; eight kārāpapas as the
price of a decent as 273; Benares
fabrics worth a lac pieces 274; scent
called sarvasauhāraka 278.

Mahāvaņij (No. 493) on Benares famous for her textile fabrics 180, 220; blankets 221; woolen shawl 221—22; uddiyāne ca kamvala (blankets made of the hair of udbitāla F) 222; caravantraders having a common chief 266; partnerhip of the traders of Srāvasti 267.

Mahayodhi (No. 528) on Udicoa Brahmina 238.

Mahilāmukha (No, 26) on ethāli 225; hastipālaka 240,

Mahotkrośa (No. 456) on Kadamya flower tree 206; tortoises 212.

Makhādeva (No. ?) on Mithilā city 182; pair of pincers made of gold 217; barber 240.

Manicora (No. 194) on the popular belief that famines are caused by the sins of rulers 280 fn

Mangala (No. 87) on estaka 219; peţikă (wooden boxes) 223—24; Udicea Brahmins 238; omen readers 239.

Manikantha (No. 253) on Alavi city 180; kutikārasiksāpada 230.

Manikundala (No. 351) on carring set with jewels 218; paryanka 222.

Manoja (No. 397) on methods of hunting 211; hunting lion from a machan 213; gold plate worth a lac pieces 217; golden sandals 217.

Markata (No. 173) en Tala tree 208; phalakāsana (bench) 222.

Mašaka (No. 44) on a border village in E36 kingdom 187; tent 221.

Matsya (No. 34) on catching fish from tanks and rivers in note 212; kayavandhana 219; bathing cloth 219.

Matsya (No. 75) on box made of sandalwood 224 fa.; suffering caused by famine due to the failure of rains 279.

Matsyadana (No. 298) on receptacles made out of the leaves of trees 225; maraka as a medium of exchange 258; seven marakas as the price of a big Robita fish 273; kutimvaka or kutumvika (private landowner) 191.

Maytra (159) on villages inhabited solely by hunters 186, 243; catching peacocks in traps with the help of decoy hirds 219; nighds (hunter and batcher) 240.

Mansa (No. 315) on town planning of Sravasti 185, 244; hunters going to the market with cart-loads of flesh to sell 211; carts 222; cooks' quarter in Sravasti 244.

Mātṛpoṣaka (No. 455) on trees : Sallaki, Kaṭaja and Visa 204, Kuruvinda (= Muthā or Vādāma tree) 208; keyūra (bracelet on the upper arm) 218; elephants made of stone 228; stone image of Bodhisattva as elephant 237.

Mātanga (No. 497) on Chandāla village 183, 243, 248; guggulu (bdellium) 203, 27d; gold vessels 216; gold pitcher 216; gold stick 217; gold sandals 217; seven-storied house 230; sight of a chandāla foreboding evil 249; partaking of bis food even without knowledge leads to social ostracism 249; chaturjitiya gandha 278, 278 fn.

Mitramitra (No. 197) on cloth-made bags for keeping shoes 221.

Mitravinda (No. 82) on a crystal palace 228.

Midulaksanā (No. 66) on spade 215; sātaka 219; sayyāphalaka 223; wooden yoke for carrying loads (Pāli kācho or kājo) 223; basket 224; large water jar 225; drinking pot 225; thatched house 230.

Munika (No. 30) on pig-culture 211.

Naksatra (No. 49) on astrologers 230; sootheayers 239; omen-reader (nimittapāthaka) 239.

Nakula (No. 165) on frepi-bhandana (quarrel among the guilds) 243.

Nalinikā (No. 526) on Sāla, Tilaka and Bhūrjja trees 204; flower trees: Karnikāra 206, Pāṭali 207; fruit trees: Amra 207; Jamvu (blackberry) 208; earring set with jewels 218; neoklace 218; mekhalā 218; Udioca Brahmins 238.

Nanda (No. 39) on spade 215; basket 224; enstomary fixed price: meek as a 100 piece slave-girl 266; kārṣāpaṇa 266; on elaves enjoying much confidence of their masters: they were told where the master's secret treasure was kept 254.

Nandikamiga (No. 385) on the corporate life of the villagers 189 fn.; king's right to impose forced labour confined to the limits of his estates 276.

Namesiddhika (No. 97) en slave-girls put on bire to work for others 252; and on failure to earn; any wages were beaten 255.

Nanachhanda (No. 289) on earring set with stones 218; wooden pestle and mortar 223; winnowing basket 225; angavidyāpāthakas 239; royal highpriest 242; slaves consulted as to the nature of the boon the master should beg of the king 254.

Nemi (No. 541) on a crystal palace 228; adulteration of food stuffs 266; use of false weights 266; for the royal household prices were fixed by the courtvaluer without appeal 242, 266.

Nyagrodha (No. 445) on tunnaväya (tailor)
241; guilds having a common chief
who is also the royal treasurer 243;
Vaisya taking part in administration
246.

Nyagrodhamiga (No. 12) on the corporate life of the villagers 189 fn.; lac 203; tail of a yak 203; methods of hunting 211 fn.; king's right to impose forced labour limited to the confines of his estates 276.

Padma (No. 261) on town-planning of Sravasti city 185, 244; florists' quarter of Sravasti 244.

Paláis (No. 307) on tress: Aivattha and Paláis 204.

Palāśa (No. 370) on *trees*: Palāśa 204 and Tinduka 208.

Paläyi (No. 229) on gates of Taxila 183.

Pafichāudha (No. 55) on mūlā (radish) 201; ohāţi (vat) 226; anguvidyā-pāţhaka 239.

Panchaupasatha (No. 490) on forests as the habitation of sannyasius 203.

Parantapa (No. 416) on flager-ring 218; performer of spells 241.

Parņika (No. 702) on parņika (grower of green vegetables) 201, 239; alāvu (gourd) 201; kuşmāņda (pumpkin) 201; šāka (pot berbs) 201; forests supplying pot berbs 203; changotaka (small basket) 235.

Parasahasra (No. 99) on Udicoa Brahmins 238,

- Padakuśala-minava (No. 432) on drinking wine forming part of festive ceremonies 227; Surž 227.
- Pandara (No. 518) on town-planning 184—85; sufferings of mariners due to ship-wreck in mid-occan 258; Karamvika-pattana as a port of departure 263; 800 merchants as fellow-passengers in a ship 266.
- Paniya (No. 459) on village headman powerless before villagers 188.
- Picumanda (No. 311) on Picumanda (-Neem) tree 204-05.
- Pürnapätri (No. 53) on finger-ring 218.
- Pusparakta (No. 147) on cloth dyed with safflower (kusumbha) 229; custom of wearing cloth after it has been curled into a thousand folds 230.
- Putadūsaka (No. 280) on receptacles made out of leaves of trees 225; gardener 241.
- Rathalatthi (No. 332) on royal high-priest 242,
- Robentamigs (No. 501) on villages inhabited solely by hunters 186, 243; earring set with stones 218; golden kinkini 218; nizādā 240; money-lending as can of the four honest callings 274.
- Robini (No. 45) un female slaves pounding rice 252,
- Romaka (No. 277) on jiraka (cumin seed) 202; marica 203.
- Rura (No. 482) on golden basket 217; Innapanani (-I. O. U.) 271, 275; the debter getting back his I. O. U. when the loan was paid back 275; debters flying to the lorests or attempting to commit snicids to escape from the clutches of his creditors 279.
- Saddanta (No. 514) on alava (goard) 201; kuşmanda (pompkin) 201; ervaraka (a kind of ensumber) 201; Kadali tree

- 208; method of capturing elephants, the precursor of the modern Kheda system 212; vas (adm) 215; hammer 215; crowbar 215; spade 215; grass-cutter's knife 215; anger 215; singhataka 215; leather-belt for elephant 226; leather-shoe for elephant 226; leather umbrella for elephant 226; leather strap to bind a dog 227; leather bag for keeping wealth 227; seven-storeyed house 230.
- Saktigulma (No. 503) on a village of 500 robbers 187, 243; Madhuka tree yielding Mahua flower 207; Tinduka tree 208; Piyala fruit tree 208; Kāra, a shrub 209; robbers looting the caravans 263.
- Saktubhastri (No. 402) on fishermen casting their net in high seas 258 fm.; prices of slaves varied according to their accomplishments, good birth and beauty 274.
- Sakuna (No. 36) on a border village in Kożala 187; successive stages of agriculture 198; thatched house 230.
- Samgramavacara (No. 183) on the walls surrounding the city of Benares 180; watch-towers over the gates of Benares 180.
- Samkalpa (No. 251) on trees: Aévattha 204 and Madhaka 207; Nyagrodha flower tree 207; Udamvara fruit tree 208.
- Sammodamina (No. 33) on chamvataka (a ring made of straw over which coolies keep the load they are carrying on their head) 225.
- Samiddhi (No. 167) on antaraväsaka (219 ; uttaräsanga 219.
- Samudravāņij (No. 466) on boats 222; wine prepared out of the juice of sugarcane 228; carpenter 240; guild of wood-

workers 242; miseries of mariners shipwrecked on an island 258; ship accommodating 1000 families of carpenters 259; navigability of the Ganges by crafts of considerable size from Benares down to the sea 264.

Sandhibheda (No. 349) on forests as pastures 202-03.

Sankha (No. 442) on ships 222; shoes fetching 500 and even 1000 pieces 226; Brahmin as trader 247; sufferings of mariners due to shipwreck in midocean 258; a ship 1120 cubits in length, 560 cubits in width and 140 cubits in depth 259; ship having three masts (kupaka) 259.

Sankhapāla (No. 524) on suvarņa māņaka (a medium of exchange) 268.

Sankbadhma (No. 60) on blower of conchshells 241,

Sarabhanga (No. 522) on armour 214; Kanchuka (overcoat) 219; bow made from the horn of sheep 229; Brahmins as archers 246.

Sarvadamstrå (No. 241) on performer of epells 241.

Sats (No. 316) on iron-rod used in reasting meat 215; tent 221.

Satadharma (No. 179) on Udioca Brahmins 238.

Satapatra (No. 279) on Kutimvaka or Kutamvika (private landholders) 191.

Satyanikila (No. 73) on golden cage 217; orystal cave for a mouse 228; Udicca Brahmine inheriting a stricter standard of life 238.

Sayaka (No. 909) on mango tree yielding fruits in all seasons 207-08; royal high-priest 243.

Salittaka (No. 107) on nalika (a kind of measure) 272.

Salaka (No. 286) on pig-culture 211.

Sāketa (Nos. 68 and 237j on Sāketa city 182.

Salikedāra (No. 484) on large holdings (of 8000 acres) 190; royal domain 190—91; land gifted away 193; protection of the crops 159; catching birds in traps made of the hair of horse's tail 213, 222.

Serivanij (No. 3) on Andhapura city 180; gold plate worth a lac pieces 217; free labourers living from hand to mouth 251; maid-servant 256; hawkers (kachchhaputo vāņijo) 265.

Silamimāmai (No. 86) on ahitundika (snake-charmer) 241; hirannyaka (cashier or officer of the treasury) 242; kārsāpaņa 268.

Silānišamsa (No. 190) on sufferings of mariners due to shipwreck in midocean 258; ship having three masts (kūpaka) 259; the navigability of the Ganges by crafts of considerable size right up to Benares 264.

Silavannaga (No. 72) on town-planning of Benares 185; saw 215; blankets 221; ivory-workers' ward in Benares 228, 244; ivory-worker 240.

Simhacharma (No. 189) on small traders carrying their goods from one village to another on the backs of asses 265.

Sivi (No. 499) on Aristapura city in the Sivi country 180; four gates of Aristapura 180; coverlet for elephants inlaid with gold 219; cloth of the Sivi country famous for its high quality 220.

Somadatta (No. 211) on Brahmin peasants 238, 246.

Sepaka (No. 229) on ill (small sword) 215; coverlet for elephant inlaid with gold 219; basket 224; sufferings of mariners due to shipwreck in midocean 258.

Sopananda (No. 532) fon Benares famous for textile fabrics 180, 220; uspiga 219; piloting a ship in an ocean (mahārņava) 257, 258.

Soumanasya (No. 505) on alavu (gonrd) 201; kuşmanda (pumpkin) 201.

Spandana (No. 475) on a village of carpenters 187, 243; Dhava tree 205; chariots 222; Brahmin working as a cartwright 246.

Sigula (Nos. 113 and 142) on the drainage of Benares 180; barber 240; cowryshell as a standard of value 268.

Sigāla (No. 148) on key (Pāli avāpuraņa) 215-16.

Srikalakarul (No. 382) on slaves treated as members of the family and leading virtuous lives 254.

Suchi (No. 387) on a village of 100 families of smiths 187, 243; corporate life of villagers 188; spear 214; parasu (axe) 215; vāsi (adze) 215; fishing hook made of iron 215; iron goad 215; fine needles with case 215; kāmsya sthālī 216; guild of smiths 242; alderman of a guild 243.

Sudhabhojana (No. 585) on vrihi (rice) 200; chinaka (- Sans. vrihibhoda) 201 fn. tandula 201 fn.; syamaka 201 fn.; harenukā 201 fn.; māluvā (a kind of sweet potatoes) 201; Bhanga, Asvattha, Sala, Tilaka, Soubhanjana (- Sajinā). Varaņa, Bhūrija, Vedisa, Veņu and Muchakunda trees 204; Sthalapadma and Karnikara flower plants 206; flower trees: Ludhra and Ketaki 206; Madhuka, Nyagrodha, Patali and Sindhuvara 207; fruit trees: Jamyu and Keks - Koka ? - Kharjura, Tinduka (Gaya or Ebony), Kadali and Mocha (= Astikadali) 208; Kuša and Usira (- Khaskhas) 209 ; fishes : Rohita, Pāthīna (Voyāla), Sakula (Sol), Singi (Singi), Kākiņņa (kālikley?), Aligargara,

Savakra, Kākamatsya and Satavakra 212; coarse cloth made from the threads spun out of the roots of trees; dangers and risks of maritime trade described 258; the five iti's 280 fm.

Suhanu (No. 158) on sarvarthachintaka 242; court-valuer 242 fixing prices of articles for the royal household without appeal 266; partnership in the deal in horses imported from Sind to Benares 267.

Sujāta (No. 252) on kuṭimvaka or kuṭamvika (private landholders) 191 fn.; gold plate 216—17; slavos ill treated and even beaten by Anāthapiņdaka's daughter-in-law 255.

Snkara (No. 153) on hand-punkhā 235; marble stair-case 228, 234.

Sukhavihāri (No. 10) on Anupiya city in Malladesa 180; mat 221.

Sulast (No. 419) on 1000 karsapanas as the fee of a courtesan for one night 272.

Sunaka (No. 242) on leather strap to bind a dog 227; barter 267.

Suparaga (No. 463) on Bhygukachahha (-Broach) city 180; diamond 209; kyhuramāla fish (-sword-fish ?) 212; corals 212; jalaniyāmaka (pilot) 241; guild of pilots 243; distress of mariners when their ship tossed aimlessly for four months, attacked by a seagale 258; ahip accommodating 70) merchants 259; Bhigukachahha as a port of departore 262; 700 merchants combining to obtain the services of one pilot 268; eight kārṣāpaṇas as the fee of a barber 272.

Surapina (No. 81) on paryanka 222; basket 224; mythological origin of sura and varuni wines 227; evils of drinking wine 227; Drink Festival in India 227; sura 227; varuni wine 227; kapotika

- wine 227; Udicea Brāhmins 238; gopāla (cowherd) 240; ašvapālaka 240; dearness of kapotikā wine 274.
- Susima (No. 163) on decision of the majority prevailing in the village council 189 fn.; corporate life of the citizens of Sravasti 186; athavikā (purse) 220; 1000 kārṣāpaṇas as the advance tuition fee paid to an ācārya 239, 272; royal high-priest 242; fees paid by apprentices to teachers 245; safety of the great N. route to Taxila 264.
- Susima (No. 411) on royal high-priest 242.
- Sušropi (No. 360) on Bhygukachchha city 180; sea-voyage from Bhygukachchha to Suvarpabhūmi (= Burma ?) 261; Bhygukachchha as a port of departure 262.
- Sutanu (No. 395) en day-labourers being sometimes paid in money wages 251; day-labourers earning balf a māṣaka to one māṣaka a day 273.
- Savarpahamsa (No. 186) on garlio 201; woman working as a maid-servant 256.
- Suvarnakakkala (No. 369) on Brahmin villages 187, 243; large holdings (of 8000 acres) 190; Tala tree 203; Brahmin peasant 238, 245.
- Suvarpamiga (No. 859) on lac 203; methods of hunting 211 fn.; net of leather-straps to catch deer 227; kammakara (free labourers) 250.
- Svetaketu (No. 377) on wooden shields 224; Udicea Brahmins 238; contact with air that touches a chandala's body is pollution 249.
- Syama (No. 540) on nişada 240 ; nişada village 243,
- Tailapatra (No. 96) on Vārāpasī city 180; parašu (axe) 215; multi-coloured cover-

- let for beddings 219; canopy decorated with golden stars 220.
- Tandulanāli (No. 5) on Vārānasī city 180; court-valuer 242, fixing prices for the royal household without appeal 266; rice as a standard of value 268; nālikā (a kind of measure) 272.
- Takka (No. 63) on corporate life of villagers 189; Acarya maintained by the guardians of children they taught 239; karamaras, persons captured by robbers and reduced by them to slavery 252.
- Takkala (No. 446) on bulbous roots of different kinds 201-03.
- Tarkārika (No. 481) on the serving maids of courtesans 257; out of 1000 pieces as fee for one night charged by a courtesan (Kali by name) 500 went to cover the price of clothes, perfumes and garland used for the night 257, 272.
- Tilamuşthi (No. 252) on umbrella made of leaves 225; one-soled aboe 226; ācārya 239; 1000 kārṣāpaṇas as the fee paid in advance to an ācārya 239, 272; royal high priest 242; fees paid by apprentices to teachers 245; safaty of the great N. route to Taxila 264.
- Tindaka (No. 177) on Tindaka tree (Gava or Ebony) 208.
- Tittira (No. 37) on the cities of Sravasti 182, Rajagtha 182 and Vaisali 183; Tittira (No. 117) on Udices Brahmins 238.
- Tittira (No. 319) on poultry-farmer 240; entching birds with the help of decoy birds 242.
- Tittira (No. 438) on acarya 239.
- Tirtha (No. 251) on aśvapālaka 240; arthadharmānušāsaka 242.
- Teiparyyastamīga (No. 16) on Ālavī city 180; broom-stick 225; privy (vachchhatthāna) 231.

- Trišakuna (No. 521) on stbavikā (purse) 220.
- Tandila (No. 388) on a cotton-field near Benares 220; drinking wine forming part of festive ceremonies 227; sura 227.
- Tues (No. 338) on gold plate worth a lac pieces 217; ācārya 239.
- Tvaksāra (No. 368) on Tvaksāra (bamboo) 204.
- Ubhatobhraşta (No. 139) en febermen 240 ; kārṣāpaṇa 268,
- Uchehhista bhakta (No. 212) on actor 241. Udahehani (No. 106) on bucket 215.
- Udaya (No. 458) on Surandhana city in the Kasi kingdom 182; iron vessels 215; silver vessels 216; gold vessels 216; life-like golden image of a girl 237; suvarpa-māyaka (a medium of exchange) 268.
- Udumvara (No. 298) on Yagdummura (a kind of fig) 201.
- Uddālaks (No. 487) on tent 221.
- Unmadayanti (No. 527) on four gates of the city of Aristapura 180; earring set with jewels 218.
- Upānaha (No. 231) on shoes 226; āsārya 239.
- Uraga (No. 354) on Brahmin peasants 238, 246; no odium on a Brahmin following the occupation of a peasant 238; alderman of a guild 243; quarrel among guilds 243; slaves treated as members of a family and leading virtuous lives 254; slaves possessing knowledge of higher philosophical truths 254.
- Utsanga (No. 67) on sätskas worth 1000 pieces of copper 274.
- Vabhru (No. 137) on worker in stone (pāsāņakuṭṭaka) 228, 240; white orystal cage for a mouse 228.
- Vairi (No. 103) on paryyanka 222.

- Vaka (No. 38) on bill-book 215: chivara (dress of the Buddhist monks) made by the monks themselves 219; cloth stiffened with starch 229.
- Vālāhādva (No. 196) on forests supplying rice 203; sufferings of mariners due to shipwreck in mid-ocean 258; ship accommodating 500 merchants 259; voyages to Caylon 261.
- Vandbanamoksa (No. 120) on royal high pricet 242,
- Vandhanagara (No 201) on iron fetters 216; iron chairs for prisoners 216.
- Vannupatha (No. 2) on Varanasi 180; hammer 215; spade 215; sthataniyamaka (land-pilot) 241; forest guard 241; pilots who noted the directions by marking the position of the San by day and of stars by night 262; caravan trade 263; caravans travelling through deserts at nights only 263; organisation of caravans 263.
- Vardhakisakara (No. 283) on payment of a tax in cash 197; winnowing basket 226; enanacharas 279.
- Variaka (No. 35) on karisa a vessel for measurement 223; amnana, a vessel for measurement 223.
- Vartaka (No. 118) on poultry-farming 211; šikunika (poultry-farmer) 540; Vartaka -vyldha (hunter of birds) 240,
- Varuna (No. 71) on the right gathering firewood by the learned 21; arbours of tree in parks 213; chivara (dress of the Buddhist monks) made by the monks themselvs 219; active 220.
- Vahya (No. 108) on woman serving as maid -servant 256,
- Valodaka (No. 193) on makaci, a kind of fibre 202; boy-servant 241; wrestler 241.

Vätamīga (No. 14) on silver box for keeping ornaments 216; litter or sedan chair 223; pitcher 225; gardener 241;

Vāruņi (No. 47) on vāruņi wins 227; dearness of wins of superior strength 228, 274; monks dying their chlvara 229; wins distiller 240; nālikā (a kind of measure) 272.

Vedavbhs (No. 48) on performer of spella 241,

Vidurapandita (No. 545) on lac 203; treat Tilaka 204, Muchakunda 204, Bhagintmāla 205, Saptaparņi 205, Uparibhadra 205, 205 fn.; flower trees: Karpikāra 206, Ketaki 206, Champaka 207; 207, Sindhuydra Nagnmallika 207 ; fruit treas : Amra 207. Jamva 208; Saha (= Sahakara, scented mango) 208; fishes: Robita, Pāguja and Pathina 212; Mapikara 217, 240; magicion 230; washerman 240; garlandmaker 241; cook 241; musician 241; notor 241; wrestler or boxer (mutthika) 241 fo.; clown (sobbiya or soubhika) 241 : kammakara (free labourer) 250 ; four kinds of slaves 252; shipwrecked pilot taking shelter in an island 258; cloth marchant 265,

Vikarnaka (No. 233) on drona, droni 223, 272.

Vinflaka (No. 160) on Tala tree 203.

Visa (No. 488) an the unenviable lot of the village headman 189 in.; Benares famous for cotton cloth 220.

Visavanta (No. 69) on visavaidya (curer of poisonous bites) 239.

Visahya (No. 340) on grass-cutter's knife 215; grass-cutter 240; a grass-cutter earning two masakas a day 273.

Viswantara (No. 547) on Benares famous for her textile fabrics 180, 220; Jetuttara city in the Sivi country 181;

Jetuttara surrounded by wall pierced with gates 181; town-planning of Benares 185; valibha (pumpkin) 201; garlic 201; maluva (a kind of sweet potato) 201; karoti (= Beng. varvati) 201; kalamyi 201; bulbons roots of different kinds 201-02; mustard 203; Nill 202 fn.; forests supplying (wild) rice 203; wild rice of two kinds 203 fa.; agura 203; guggula 203; naladi 203; compher 203; liquerice 203; kustha (costus) 203; ivory 203; trees: Sallaki, Camphor, Khadira, Asvakarna, Asvattha, Palasa, Kotaja and Sala 204; Aksiva (- Sajinā) 204 fn.; Sovālijana (-Sajina) 204 fa.; Kareri (Varana) 204 fn. Punnaga, Asana, Ajukaraa, Sarala, Padmaka, Kakudha, Karapdaka, Kovidāra, Tālisa, Saptaparņi, Karabja. Dhava, Dhatri, Putranjiva, Kosamva, Somaviksa and Pačjara 205; Mahināma 205—06 ; Svetaparpa, Jatāmāmai Nilapuspi, Svetavari and Kateruha 206 : Asltarn 206, 206 fn.; Katamála and Phanijjak 206; Vallika 205, 205 fn; Tulasi plant 206 ; flower trees : Karqikara, Karandaka, Kiménka, Kiménka. latikā, Nips (=Kadamvs), Ankola, Yodhi (- Yodhika - Yathikā) Sthalapadma. Ketaki and Vakula 206; Ašoka, Nigakefara, Tagara, Nāgavalli, Pātali, Nirgupdl (- Nisinda), Bhandi (- Ghentu), Jeti, Madbugandhikā, Swetschohba, Baktamāla, Simsapā, Asphotaka, Sūryyavalli, Anoja, Väsanti, Kiménkalatika. Padmotters, and Elimvard 207; Sirlsa (= Ghentu) 107 fm.; fruit trees : Amra. Jamva, Vadari, Kapittha, Kharijura, Tala, Vibhedaka (-Tala); Cocoanut, Haritaki Vibbliaka, Panasa, Lavoja, Timvaru and Drakaa 208; thrubs and plants yielding scente : Turmeric.

Aguru, Kustha (costus), Nalada (spikenard), Guggula and Liquorice 208: Sandalwood, Priyanga, Gandhadila, Bhadramuşti, Satapuşpa, Jhamaka, Tungavinta, Hrivera, Choraka, Kalinga, Unnaka and Lolopa 209; grass and reede : Kāša, Kuša, Potakila, Pavajja, Munis and Usira (-Khaekhae) 209; Rohita fish 212; silver pot for milching cows 216; ornament for the neck set with jewels 218; ornaments: mukhaphulla 216-17, kahauma, unnata, keyura angada, mekhala, gingamaka, pālipāda and adghattana 218; Kautamyara famous for her cloth specially linen 221; Gandhara famous for her blankets some fetching a lac pieces 222; wooden spoon 223; earthen dolls for children which were representations of the images of elephants, horses, bulls, deer, hare, monkey, peacock, swan, birds etc., 226; meraya (= maireya) wine 227; sevenstoreyed house 230; magician 239; confectioner 241; musician 241; mandraka-blower 241; weavers' ward in Benares 244; enslavement of a prince and a princess not shooking to the social ideas of those days 252; slaves freeing themselves by payment 253; sacrifice of cooks (panthasakuna) for the safety of the caravan-263; niska 269; Amitratapana's enslavement due to her father's debt 273 fn.; price of slaves varied with their accomplishments, good birth, beauty etc. 273, 274; woolen blankets worth a lac 274.

Viświsabhanjana (No. 93) on forests as pastures 202-03.

Viraka (No. 204) on the sufferings caused by famines in the Kasi kingdom 280. Vihachehhatra (No. 336) on leather bag for keeping wealth 227; performer of spells 241.

Journal Asiatique—(Vol. IV): Renaud on the identification of Yayadvipa and Suvarpadvipa with Jāvā and Sumātrā 162 fn.

Journal of the Bihar and Orissa Research Society—(1920): on prehistoric symbols on punch-marked coins 10.

Journal of Literature and Science, Madras —(1858): Mr. Elliot on the punch-marked coins in the graves of Coimbatore 10.

Journal of the Oriental Society of Germany—(Vol.XXII): Dr. Ballensen on references in the Vedas to images of gods 57.

Journal of the Royal Anthropological Institute—(Vol. XVIII): Gowland on Neolithic gold-mining centres in the Decean 4; (Vol. LIV), E. H. Hunt on Copper Age remains in graves discovered in the Nizam's dominions 9; E. H. Hunt on Hyderabad pottery of the Copper Age resembling early forms of the "Ka" mark pottery of Egypt 18; Richard on some iron graves in North Arcot district 9 fn.

Journal of the Royal Asiatic Society—
(Vol. VII): N. G. Walhouse on Copper
Age remains in Coimbatore 8; (1888):
Hewitt on the export of teak from the
Malabar coast to Babylon 72, 163;
(1889): John Cockburn on the cavepaintings in the Kymore ranges 5;
(1898): Kennedy on trade between India
and Babylon in the seventh and sixth
centuries B. C. 163; (1925): E. Mackay
in his article on Sumerian connections
with Ancient India on points of
similarity between ancient Indian and
Sumerian civilisation 17.

Journal of the Royal Economic Society— (1910): Mrs. Rhys. Davids on all exchange in the Vedic Age as done by barter 75.

Kapişthala Samhitā on metals: gold, ayas, lead, tin, syāma and loha 123; washing for gold 125; syāma 131; ointments 176.

Kansika Sütra of Atharvaveda with extracts from the commentaries of Darila and Kesava edited with valuable notes by M. Bloomfield on charms to avert inundation 96; Tishtägha tree 100; syämäka 107; parihasta used as a bracelet 127 fn.; weather-prophet 150 fn.

Kausika Sütra on canal irrigation and the practical part of the ceremony of letting in the water 93.

Kangitaki Brahmana (and Aitareya Brahmana)—Trans, into Eng. by A. B. Keith on a double crop 91; wooden sacrificial post 137; ritual shoes made of bore skin 140; freethin 152, 157. gambling as one of the causes of indebtedness 177.

Kangitaki Sütra on palüla (straw) 143 fn.; the necessity of proving one's descent from three generations of sais before one can serve as a priest 155.

Kanşitaki Upanişad—Trans, into Eng. by F. Max Muller in the S. B. E. series Vol. I. on vasana (cloth) 116; ranor 132; razor case 132; asandi having four legs 138; paryyanka (bed-stead) 138; aresthin 152, 157; King Ajāta-satru disputing with and instructing Brahmins in the lore of the Brahma 156; perfumes 176.

Kathopanisad—Translated into English by F. Max Muller in the S. B. E. series Vol. XV. on gold 123; śrinkā, an ornament 128; razor 132; sword 132; polished mirrors 135; pictures (light and shade) 142; painter's brush 142.

Kāšikā (commentary on Pāṇini's Sūtras) by Pandita Vāmana and Jayādityācārya Edited by Panditas Gangādhara Sāstrī and Ratnagopāla Bhattāchārya: Pāṇini's Sūtra IV. 2. 68 tena niverittam referring to the foundation of Kaušāmvī by prince Kušāmva 181 fn.

Kāthaka Samhitā-Edited by L. Schreder in four vols. CD well-irrigation 93; tautu (yarn) 115; vemān (loom) 115; nfvi (closely woven end of the cloth) 116; praghāta (long and loose unwoven fringe with swaying tassels) 116; tūşa (shorter fringe of the cloth corresponding to the modern chilkā) 116; vātapā (lengthwise border of the cloth which kept the web together from becoming threadbare by fluttering in the wind) 116; arokāh (spotty patterns embroidered all over the cloth) 116-17; uspisa (a head dress) 118; threads of wool 118; barāsi (a barken stuff) 119; metals : gold, syas, lead, tin, syama and loha 123; washing for gold 125; syams 131; methi (pillar) 145; knowledge not descent making a Brāhmapa 155; setu (raised bank for crossing inundated land) 160fn. : satamans (a medium of exchange) 165; hiranya kanala (a medium of exchange) 125, 167; ointment 176; salali (annointing instrument used by males) 176.

Kātyāyana Srautasūtra on uspisa 118; tārpya (silk or linen garment) 119; preparation of soma drink 141; black and pointed shoes of the Vrātyas 226; Satamāna (a medium of exchange) 269.

Kevaddha Satta on the tas of birds to gaide pilots 262. Khādira Gihyaestra—Trans. into Eng., by
H. Oldenburg in the S. B. E. series
vol. XXIX. on rotation of crops
91, 200; darvi (a spoon) 223; razor of
udamwara wood 224; basket 224;
rules and rites on house-building 235;
sesamum 202; razor made of metal
215; brazen vessels 216; brazen bowls
216; ornaments 217; golden ornaments
217; wreath of gold 216; rope 225;
pitcher 225; shoes 226.

Kindred Sayings (-Sanyotta Nikāya)—
Translated into Eng. by Mrs. Rhys
Davids and Mr. F. H. Woodward in
three parts on all property left
intestate or ownerless reverting to the
erawn 276.

La Doctrine du Sacrifics-Sylvain Levi on the story of Manu dividing his property among his sens 84 fm.

Land system in South India between 800

A. D. and 1200 A. D.—Dr. K. M. Gupta
(Punjab Oriental series, Vol. No. XX.)
on two-field and three-field systems of
cultivation 92—93.

Latyayana Scautacutra with the commentary of Agni Swami on the necessity of proving one's descent from three generations of this before one can serve as a preist 155.

Literary History of India—R. W. Frazer on the Purusasukta hymn 61; ms not unknown to the early Indo-Aryans 67.

Manchester Memoirs Vol. LX. Part 1, (1915) on Neolithic graves 6.

Mahāhhāsya of Patanjali critically by edited by Kielhorn: the commentator Nāgojibhaṭṭa's wrong interpretation of the Mauryas as idol-manufacturers 165—66.

Mahiniddesa on Tamraparpi dwips 261 in.; (commentary) on the difficulties of caravans figuratively described 263.

Mahāparinibbāna Suttauta—Trans. into Eng. by T. W. Bhys Davids in the S. B. E. series vol. XI. on the six great cities and the small city of Kusinagara 179-80; foundation of a fortress in Pāteligrāma which along with the fortress grew up into the town of Pāteliputra 184.

Mahasudassana Suttanta—Trans. into Eng. by T. W. Rhys Davids in the S. B. E. series vol. XI. on town-planning of Knsavati 155; detailed description of a flight of stairs 234.

Mahavagga-Trans. into Eng. by T. W. Rhys Davids and Hormann Oldenburg in the S. B. E. series in vols. XIII. & XVII, on cultivation of lands by tenants 198; use of scare-crows to protect the crops 100; channel dag for po-operative irrigation likened to a patchwork robe of the monks 200; Simula cotton used in quilts 202; forests. as elephant-preserves 204; coverlets dyed with figures of animals 220 fp.; high quality of the cloth of the Sivi country 22); various kinds of woolens 221; pallanka (high class bed-stead) 222; Ssandl 222; litter or sedan chair 223; apassona phalakam (board to lean against) 223; five kinds of abodes allowed to Buddhist monks 231; extensively built houses of the richer classes described 292; ogumpheti ( - ekins ?) 233 fm.; adjustible shutters for windows 234; relation between the antevāsika and the ācāsya 245; undischarged slaves not eligible for the pavajjā ordination 253; one hundred pieces for one night as fee of a courteean (Salavati by name) 257.

Mahāvaņša—Edited by W. Geiger on frontier villages in Vanga country 187 and 187 fn.

Maitrāyana Brāhmaņa Upanişad—Translated into English by F. Max Muller in the S. B. E. series in Vol. XV. on plantain tree 105 fn.; the work of the black-smith described 131; bell 132; vessels made of brass 133; painted wall 142; karmāra (blacksmith) 149; mṛtpaca (potter) 150; public dancer 151; actor 151 fn.; magician 151 fn.; prizefighter 151; catching fish with a net 170-71.

Maitrāyanī Samhitā—Edited by L. Schreder, on vemāna (loom) 115; nspisa 118; threads of wool 118; tārpya (silk or linen garment) 119; kṣhauma (linen) 119; metals: gold, ayas, lead, tin, dyāma and loha 123; washing for gold 125; hirapyakṣṣṇāla (a medium of exchange) 125; opaša 129; šyāma 131; prāvepa (according to Goldner looking glass); potter 140, 150; knowledge and not descent making a Brāhmaņa 155; ointment 176; šalalī (annointing instrument used by males) 176.

Majjhima Nikāya (the first 50 discourse)

—Translated into English by Bhikkhu
Silacara in two parts on the city of
Attaka in Anga 180: Assapura, a
nigama in Anga 180; Halidda-vamsa,
a nigama in the Koliya country 181;
Kitagiri, a nigama in the Kāši kingdom
181; forests as elephant-preserves 204;
thatched house 230; slaves forming
part of a householder's property 5253; beating a female slave (Kāli by
name) 255; female dancers and singers
256; voyages out of sight of land 258.

Manchester Memoirs (Vol. LX.)—Elliot Smith on the causes that led to the establishment of Neolithic settlements in particular localities 6.

Manusmrti with the commentary of Medhatithi-Translated into English by Dr. Ganganatha Jha complete in ten vols. on the sharing of lands by the conquering persons 24; fines on piercing fine gems like diamonds and rabies and for boring pearls or inferior gams improperly 133 fn. ; kranala as a metallic standard 167, 167 fn.; Vena caste 248; Pukkasa caste 248 fn.; Dhvajāhīta class of slaves 252 : Dandadāsa class of slaves 252 ; table of weights and measures on which the standard of exchange was based 269.

Manual of Indian Buddhism-Kern on the sale of land to Anathapindada 192 fn.

Mayamatam on the growth of villages into towns 183 fn.

Mānava Grhyasūtra on temple 236,

Myth, Ritual and Religion—Andrew Lang on the similarity in the primitive mode of accounting for creation from the sacrifice of a fabulous monsterman, a Purusa 61.

Natural History—Pliny on Indian glass as superior to all others from the circumstances of its being made of pounded crystal 135; fifty-eight rivers of India 200.

Nen und Vollmondsopfer-Hildebrandt en prasitraharana 224 fn.

Nirukta-Yāska on Devapi as royal priest 156.

Notes on the Age and Distribution of the Foote collection of Indian Prehistoric and Protohistoric Antiquities (Madras, 1916)—Bruce Foote on Neolithic pottery 3-4; Neolithic iron industry 4 fn.; painted figures on rocks in the Neolithic eite of Kapgallu in the Bellary district 5.

Numismata Orientalia-Goldstneker on stamped impressions on the media of exchange 269.

Omina et Portenta-Weber on charms to avert inundation 96; Sakadhūmam (weather-prophet) 150 fu.

Origin of the Brahmi Alphabet—Bahler on references to navigation in the Bayeda 67.

Origin and Growth of Religion among the Habylonians—Dr. Sayce See under Hibbort Lectures.

Original Sanskrit Texts—Muir on kulyd in the Rgveda meaning artificial water-ways 29; on the probable use of cotton cloth in early Vedic Age 49; leather work in the Rgvedic Age 54; absence of caste system in the Rgvedic Age 58.

Oxford History of India—V. A. Smith on the non-existence of the golden age at poets in the primitive times 1; Paraşasükta hymn 61; voyage of Skylax down the Indus into the Indian Ocean 261.

Pali Dictionary-Childers on kutimyaka or kutamyika (private landowners) 191 fn.; Nikkho-five suvarpas 270.

Pali Dictionary—Rhys Davids on kutimvaka or kutamvika (private landowners) 191 fn.

Pañchavigisa Brahmapa—Trans. into Eng. by Dr. Caland on mapi being work on the neck by means of a thread 52; goat's skin as clothing 112; this (a shorter frings of cloth corresponding to the modern chilkā) 116; uşņīşa 118; barāsi (barken stuff) 116; opaša 128; necklace of silver niņkas 128, 130, 165; prākāša (according to Geldner looking

glass) 134; bage for holding milk, wine and other liquids made from cow-hide 110, 140, 160; mothi (pillar) 145 fo.; vayitri (female weaver) 149 fo. 153; royal seers 155; royal priest 156; badvan (causeways) 160; goat's skin as clothing 112; gambling as one of the causes of indebtedness 177.

Papini See under Sütras of Papini.

Päraskara Grhyasütra-Trana. into Eng. by H. Oldengurg in the S. B. E. series vol. XXIX. on kiläla (a variety of sura) 142: parisent (a drink from flowers) 142 : position of women in relation to agriculture 153 : mudga 201 ; sesamum 202; mustard 202; tortoises spear 214; axe 215; copper rasor 216; brazen vessels 216; an instrument of gold used in giving honey and clarified butter to the newborn child in the medicipanana ceremony 217; ornaments 217 : kupdala (earring) 218 ; chariots 222; ākarsa phalakam (dics-board) 223 fa.; darvi (spoon) 223; sruva (small sacrificial ladle) 223; mat 224; basket 224; shoes 226; wine of superior strength 228; rules and rites on housebuilding 205.

Patimokkhs—Trans, into Eng. by T. W. Rhys Davids and Hermann Oldenburg in the S. B. E. series vol. XIII. on employment of weavers to weave cloth for monks 219; silk fabrics 22I; use of money forbidden to the Sangha 267; practice of stamping impressions on media of exchange 269; a kārēs (=kārēnaņa) enough for buying coarse clothing for a monk and ten kārēs's for a nun 273.

Pliny's Natural History See under Natural History-Fliny, Periplus of the Erythrean Sea (Schoff's Eng. Trans.) on the discovery of the monsoon 74; the export of abony from Barygasa 70 fn.

Prehistoric Antiquities—Schreder on ayas as pure dark copper 49; loha as originally meaning copper but later denoting

iron 49, 131.

Prehistoric India—Dr. Pafichanana Mitra (Second edition, 1927) on Neolithic pottery 4; rock-carving in Manbhandar village of Singhbhum 5—6; prehistoric rock-painting near Singanpur in the Reigath district of C. P. 4—5.

Proceedings of the Asiatic Society of Bengal (1867): Mr. H. E. Blanford on the existence of man in India at a much earlier period than in Europe 1.

Psalms of the Brethern on channels dag for co-operative irrigation likened to a patchwork robe of the Buddhist monk 200; court-valuer 242, 266; alaves having no freedom except that given by their masters 253; manumission of slaves 253; courtesans 257; fichmonger's village at a gate of Sravasti 265;

Pealms of the Sisters-See under Theri-

Ptolemy's Geography-See under Geography-Ptolemy.

Ramiyapa—Valmiki (with the three commentaries of Tilaka, Siromani and Bhusana) complete in seven vols. on crops grown 94—95; importance of agriculture 95; famine 96-97; forests supplying resin, alos, musk, sandalwood, lac, hides, honey and fuel and the materials for the construction of bonses and sacrificial implements 97; different kinds of trees 98—105; beautiful avenues of Sala trees in the city of

Ayodhya 101 fn.; mango-gardens of Kośala 105 fn.; groves of cocoanut trees along S. coast of the Decean 105 fn.; groves of plantain trees 105 fn.; art of gardening 103; dung of buffaloes used as fuel 112; Kamvoja, Bahllika and Sind famous for their horses 112, 158; flash of sheep as food 112; cloth made of sheep's wool 113; large size and great strength of the elephants of the Himalayan and Vindhyan regions 113, 158; hides of elephants 113; hunting the deer and the antelope with the bow and the arrow 114; weaving industry 120-22: linen 120-21, woolen 121, silk 121-23; metals 123-24; mineral products like gairika, lime, mica, crystal and diamonds 124; goldsmith 124, 149 fn.; mining gold, gems and precious stones 125; silver mines 124; metal industries 126-133; various articles made of gold 126-127, various ornaments 129-30, various articles made of silver 130, metal vessels 131; spade 132; hee 132; bill-book 132; iron axe 132, iron box or trunk 133; 169; collyrium pots 133; blade of an arrow 132; sword 132; armour 132; armour for elephants and horses 132; ornaments made of iron 133; images of tiger made of various metals 183; bellmetal milk-pots 183; brass 133; alchemy 133; jeweller 134, 149; jewellery 134; polished mirror 135; wooden sacrificial post 157; specialised carpenters 139; manufacturer of boxes 139, 169; wooden sandals 139; artificial hills made of wood 139; deer-skin used as seat-spreads 139; tiger-skin as coverlet for chariots 139-40; lion-skin as coverlet for chariots 140; leather-worker 140, 149; pote like kumbhi, karambhi and sthall 140, 169; liquor-pots 140 169; alters and seats made of ivory and gold 140; pillars and windows made of ivory 140; images of ivory placed in chariots 140; sura that oozes spontaneously from trees (-tadi ?) 142; varual and maireya wines 142; painters 142; rooms adorned with pictures made by skilful artists 142; images of horses, birds, serpents and of Lakymi with her elsphants carved on a chariot 142; townplanning of the city of Lanka 146-47; town-planning of the city of Ayodhya 147 : civic consciousness of the citizens in keeping with town-planning 148; weaver of rugs 149; scent-maker 149; potter 150; astrologer 150; physician 150; cook 150, 174; servant 150; washerman 150; musician 151; public dancer 151; actor 151; artist 151; painter 151; merchant 151; mason 151; a brahmin earning livelihood by ploughing 156; Välmiki, a Südra was the composer of the Ramayana and a rsi 156; recognition of the position held by trades and crafts in society 158; references to sea-voyages 161-62; reference to preparations for a naval fight 162; India's trade in silk with China 162; flesh of goat, sheep and of hunted animals like black antelope and wild boar as food 170; dried meat as food 170; flesh of buffalo, cock, peacock, hare and various kinds of ktkala as food in Ravana's kitchen 170; asava and its preparation 171; luxury and the improvement of art in the age of the Rāmāyana 174-76; gambling as one of the causes of indebtedness 177; duty of the state to promote the material welfare of the subjects 178; foundation of Kausamyi by prince Kusamya 111 fn.;

inclusion of Vartta (which concerned itself with the various branches of production) in the royal curriculum of stadies 275; king advised to pay proper attention to the property of traders, cultivators and the cattle-farmers 275—278.

Reallexicon der Indegermanischen Altertumskunde—Otto Schreder on the original Aryan stock having acquaintance with agriculture long before their migration into different lands 22; on the common knowledge of the arts of the weaver, the carpenter and the plaiter of grass and reeds among the people speaking the Indo-European group of languages 45.

Records of the Geological Survey (Vol. I):

Dr. Oldham on the Godavari flake being
"formed from a compact light-coloured
agate" 2; (Vol. XXXVII): Dr.
Keith on the Berma find containing
implements showing distinct traces of
having been worked by man 1.

Report of the Archelogical Survey of India, Madras (1914-15): Longhurst on Copper Age remains in Kurnool burial sites S; the western (Egyption) influence on the Copper Age pottery of S. and W. India 9.

Report of the Archmological survey of India, Southern Circle (1902-08) Mr. A. Rea on Copper Age remains in the burial sites at Adichanallur in Tinnsvelly 8.

Rgveda Samhitā with the commentary of Sāyanācārya critically edited by F. Max Muller in a vols. on cow as the medium of exchange 9—10; growth of landownership and agricultural life 22—24; Aryans charing among themselves the conquered land of the Dasyus 24; no

royal ownership of land 24-25; corporate village life 25-26; growth of towns 26-28; clearance of forests for purposes of agriculture 28; origin of the art of sowing seeds and of the use of the plough 28-29; agricultural operations 28-29, 31-32; use of manure 29; irrigation by wells ceremonies connected 29-30, 93; with agriculture 30-31; nature of the grains grown 32; food of the people 32-35 ; demesticated animals 35-41 ; various kinds of trees 42, grass 43 and plants 43; economic importance of forests 41; hunting and fishing 43-44; weaving industry 45-49; dress 47-48; metal industry 49-52; various kinds of ornaments 51-52; carpentry 52-53; pottery 53; leather-work 54; manufacture of liquor 54; housebuilding 54-57; painting and soulpture 57-58; caste system in relation to mobility of labour 55-62; different occupations 62-64; domestic labour 64-65; internal or domestic trade 65-66; means of communication : roads and rest houses for travellers 66, 159, beasts of burden etc., 66-67; navigation 67-69; combination between merchants 74-75; methods and media of exchange 75-77; general economic condition of the masses and the classes indebtedness 79; rate of 77-80; interest 79, 177 fn.; famine 80; hospitality and liberality 80; law of inheritance 89; prostha (in prosthasays), something like a high and broad bench 137 fn.; asecana, vessel to hold liquids such as meat-jaice 140, 169; ayasthuna (pillar made of ayas) 145 fn. ; anja or anji meaning ornameats 127 fu.; grha, either an actual house

erected over or beside the grave in memory of the deceased or chambers and vaults of subterranean or rock-out caves 144; pillar (sthunk) on Vedic grave 144-45; upalapraksini (woman employed in grinding corn) 148 fn.; vaptr (barber) 151 fn.; kusidin (usurer) 152 fn.; high status of the rathakuras 152; slavery 64, 153; dasa denoting a non-sacrificer, a heterodox and not always a slave 153, 153 fm.; aritr (rower of a boat) 161; harmya 173-74; harmyesthah prince 137-74; prayers for freedom from debt 177 fn.; protection of crops from birds by making din and noise 199.

Rgveda—Translated into English by R. T.

H. Griffith in two vols. on Kākamvara, some umbrageous tree 42;
uses of Valvaja (Elensine Indica) 43:
Pātā or Pāṭbā, a climbing plant having
medicinal properties 43; hunting lion
from a place where men lie in wait to
capture him or where a pitfall has been
prepared to entrap him 44; Rgveda
IV. 24. 10 and VIII. 1. 5 referring to
images of gods 57; Rgveda IV. 32. 33
referring to carved images of girls on
wooden posts 57-58, 142; Rgveda IV.
24. 9 suggesting haggling over prices
65-66.

Rgveds, the oldest literature of the Indians by A. Knegi—Translated into English by R. Arrowemith on race of chariots drawn by horses as "the peaceful preparation for the decisive struggle on the battle-field" 39; lowest stage of development of arts and crafts in the Rg vedic Age 44.

Rgveda—Eng. Trans. by H. H. Wilson, on puras as cities 26, 27-28; references to weaving in the Rgveda 46; Rgveda IV. 24. 2 suggesting a contract for sale 65; Rgveds III. 31. I-2 suggesting law of inheritance and Sayana's interpretation on it 89 fn.

Rgvedic Culture—A. C. Das on cultivaof rice in the Rgvedic Age 32 fg.

Sarangadhara Samhita (Nirpaya Sagara Press) on table of weights and measures 272 fp.

Satapatha Brahmana (Ajmere edition) on secrifice described figuratively as ploughing, sowing and reaping 31; garmont of kusa grass used by the wife of the secrificar 43 fa.; alankara used for the first time in the, 51 fn., 127, rukma being worn on the breast by mesus of a chain (rukmapāśa) 52, 128 talpa 53: nature and construction of gtha (a memorial structure) 56 fn. : cities of Asandhivat and Parivakra 81-82 : feeling against land-transfer 85 ; gifts of lands to Brahmins 85; Kabatriya clansmen apportioning land given to them by a king with the mutual consent of all 85; every one being fit to be eaten up by the king 85; grant of (public) land by the king with the consent of the clan 86; agricultural operations 92; raid of cattle 109; various articles of food prepared from cow's milk 110, 171; besf-cating 111; growing feeling against cow-slaughter 111; goat's skin as clothing 112; origin of boar, its fat and the sandals made of its skin 113; tortoise 114; anuchada (forward stretched web) 115; sic (border or frings of cloth) 116; dasa (border or fringe of clath) 116 fn.; nivi (closely woven and of the cloth) 116; praghāta (lang and loose unwoven fringe of swaying tassels) 116; arokāh (spotty patterns embroidered all over the cloth) 116-17; adhivasa (garment to cover the upper part of the body) 117; usnita 118; tārpya (silk or linen garment) 119; metals : gold, ayas, load, tin, syams and loha 123; washing for gold 125; suverpa 125 fn.; padas of gold 125 fn.; fatamana 125 fn.; gold on the priest's finger 125 fn.; karpasobhana 128; silver plates 130; lohamaya 131; lobāyasa 131 ; prākāša (according to Geldner looking glass) 134; asandi (shining seat) made of Udumvara wood 138 ; asandi made of Khadira wood 135 ; Asandi square in shape 138; a span high asand! 138; knee high frand! 138; navel high desuit 138; naumanda (radder of a boat) 139; goatskin as the ritual dress of the priest 139; gost-skin, tiger-skin and black antelope skin as coverlet for aspndl's 139-40; ritual shoes made of boarekin 113; 140; burnt (pakva) bricks mentioned for the first time in, 143 fn.; imasana (funeral and memorial structure) and its three varieties-vasta, grha and prajulanam 114; stone and timber pillars on smasana 145, 145 fn.; dvar (door) 145 fn.; sthung (pillar) 145 fn.; sthūņa-rāja 145 fn.; methi (pillar) 145 fp.; smelting of ores (sáman) 148 fo. ; female weaver 142 fo., 153 ; stonecarving 149 fn.; position of women in relation to agriculture 153-54: royal seers 156; kings Janaka and Asvapati disputing with and instructing brahmapas in the lore of the Brahma 156; horses imported from the Indusregions 158; setu (raised bank for crossing inundated land) 160 fn.; reference to sea and sea-navigation by Manu, the Indian Noah 161; menoravacarpanam (sliding down of the ship) 161

fn.; ship having two rudders 161; nāvāja (pilet) 161; tūla (balance) 164; intamana (a medium of exchange) 165-86 : a śatamana was vrtta (i.e., round) in shape 166; suvarna (a medium of exchange) 166; pads (a medium of exchange) 166; avasatha (structure of some sort for the reception of guesta ) 168 fa.; Yājūavalkya's fondness for beef 170; liberality of princes 173; cintment 176; gambling as one of the causes of indebtedness 177; sareşika, a reed stalk with a tuft as annointing instrument 176; Kaustm. veya, one belonging to the city of Kodámyi 181 fn.

Satapatha Brāhmaņa—Trans. into Eng. by J. Eggeling in five vols. (in the S. B. E. series) on Prof Eggeling's acceptance of Sāyana's interpretation of a satamāna as having been 100 mānas or gunja-berries in weight 166.

Samaveda—Eng. Trans. by Stevenson on the preparation of Soma sacrificial drink 141.

Sankhyāyana Āraņyaka Upaniṣad—Trans. into Eng. by A. B. Keith on paryyanka (bed-stead) 138; asandi having four legs 138;

Sankhyāyana Grhyasūtra—Trans. into English by H. Oldenburg in the S. B. E. series vol. XXIX. on kilāla (a variety of surā) 142, 227; pariārut (a drink from flowers) 142; vrīhi (rice) 200; yava 201; mudga 201; sessmum 202; mustard 202; indigo 202; šana (Crotalaria Junica) 202; consecration ceremony of a garden 213; sword 214; axe 215; copper razor 216; gold vessels 216; gold spoon 217; golden ornaments 217;

earring 218; chariot 222; sruc (ladle) 223; sruva (small sacrificial ladle) 223; pitcher 225; pot for keeping cards 225—26; shoes 226; women drinking wine at marriage festivals 227; sura 227; rules and rites on house-building 235; temples 236.

Sanyutta-Nikaya-See under Kindred Sayings.

Sayana's commentary on the Rgveda—on the fowler's wife cutting a bird evidently for food (in Rgveda 1. 92. 10) 33; tridhata and trivaratha (in Rgveda VI 45. 9) 56; Rgveda III. 31. 1—2 referring to customs or laws of succession to property 89.

Si-yu-ki (Buddhist Records of the Western World) by Hinen Tsang-Trans. into English by S. Beal on the story of the maritime adventures of the lion-prince Simhala 261; kingdom of women 261; red sandal-wood image of the Buddha caused to be made by the minister of king Udayana, a contemporary of the Buddha 236.

Sociale Gliederang Indien—Fick on Udicoa Brahmins-inheriting a stricter standard of life 238.

Some Aspects of the Earliest Social History of India—S. C. Sarkar, London, 1928 on opasa as a style of hair-dressing 51 fn.; kurira as a style of hair-dressing 52 fn.; building activities developing through the needs of social and corporate life of the Vedic Aryans [as in the case of Vedic gorthi (club) vidatha (royal audience hall), sabha and the like ] 57; uttada (sprung from tuda or mulberry tree i.e., silkan) 119; kumva and kurira as a kind of hornshaped coiffure 127 fn., 128 fn.

St. Petersburg Dictionary—on dama 55 fn.; pastyasad 55 fn.; pasi 74; andka as an adverb only (and not as an ornament) 51; opasa as hair-tape or hair-net 51; khādi as an ornament of three kinds 52; šyāmā, name of various plants 107 fn.

Study in the Economic Conditions in Ancient India, A-Dr. Prananatha on the relative value of gold and silver in Kantalya's time 271.

Sütras of Püpini on ükhana (=a pit artificially made where the hunter could lie in wait at a convenient distance for shooting) 114 fn.; pāda as a metallic standard 167; Salatura city 182; Takksasīlā 193; šana (Crotalaria Junica) 202; grāmah filpini (oraftsmen attached to a village) 213; gramakantābhyām ca taksana (carpenters attached to a village) 213; bell-metal 216; kantha 220; kauseya cloth 221; carpets 221 fn.; Kapiša famous for grapes out of which wine was prepared 228; temple of the gods 236; actor 241; Chakravarman, a Kahatriya was a grammarian 248; vaitanika (wageearner) 251; dvaipyo vanika (merchante trading with islanders) 259; salt merchants 265; spice marchants 265; saurpa, visanam and mandgika proving the existence of barter 265; bovine tale as a standard of value 268; cow as a standard of value 268; karsapana 268, pada 268, papa 268, satamana niska 269, hirapya 269, kamen 269 and vista 269 as media of exchange; stamped impressions OIL media of exchange 269; milja (as a kind of weights) 272; adhaka (a kind measure) 272; dysignpika, traigupika

and dasaikadasika proving the exhorbitant rates of interest 274-75.

Suttanipāta—Translated into English by
V. Fausboll in the S. B. E. series
Vol. X. on cattle-rearing by Kāšī
Bharadwāja, a Brahmin 211; Brahmin
peasant Bharadwāja 238, 246 fn.;
bhātaka (day-labourer) 251 fn.; route
from Srāvastī to Patithāna described
264; (commentary) on Sirimā, a courtesan whose mother was also a courtesan whose mother was also a courtesan 257.

Suttavibhanga on pešakāra (weaver) 240; rathakāra 240; low castez and trades 248-49.

Taittirlya Āraṇyaka with the commentary of Bhāskara—Edited by Mahādeva Sāstri in three vols. on the slanghter of the cow as an invariable accompaniment of the Rājasūya, Vājapeya and the Aśvamedha ceremonics 110.

Taittiriya Brahmana with the commentary of Sayanacarya in three vols. on sura as a drink of ordinary life 35 fn., 54; talpa (son born on the nuptial bedstead i. e., legitimate son) 53; Janaśruteys as a nagarin 82; two kinds of rice : aśu and mahavrihi 94; domestic animals to be sacrificed in Asvamedha 110; beef-eating 110, 111; sacrifice of buffaloes 111; vemana (loom) 115; tilsa (a shorter fringe of the cloth corresponding to the modern chilkā) 116; tārpys (silk or linen garment) 119; hirapya-krapala prakasa (according to Geldner looking glass) 134; kšcha (glass or jewellery) 133, 135; tālpa (nuptial bedstead) made of Udamvara wood 137; prostha (something like a high and broad bench) 137; mantras for the preparation of Soma drink 142; freethin 152, 157 fn.;

loss of the former high status of the rathakara through devotion to a mechanical art 152, 154; position of women with regard to agriculture 153—54; vanij (merchant) 158; setu (raised bank for crossing inundated land) 160 fn.; satamana (as a medium of exchange) 167; cattle driven out to graze thrice a day 167; avasatha (structure of some sort for the reception of guests) 168 fn.; liberality of princes 173.

Taittiriya Samhitā (-Black Yajurveda) with the commentary of Sayandearya on separate ownership of land 82; ownership of land 82-84; story of Manu dividing his property among his sons 84; rise of landed aristocracy 88; law of inheritance 90; use of six or twelve exen to drive the plough 90-91; plough-share 90-91; seasons bearing on agriculture 91; well-irrigation 93; crops grown 94; different kinds of trees 99, 103, plants 107 and grass 109; cow as a medium of exchange 111; use of bullocks in ploughing land and in drawing waggons and carriages 111; camel as an object of sacrifice 112; goat's milk as the highest form of draught 112, 112 fn.; bad effects of accepting the gift of a sheep 113; sheep used in drawing the plough 113; ass as "the best burden-gatherer of animals" 113; pits artificially made where the bunter could lie in wait 114; tortoise 114 pracinatana (forward stretched web) 115; vāsas (cloth) 116; nīvi (closely woven end of the cloth) 116; pragbita (long and loose unwoven fringe with swaying tassels) 116; tilsa (a shorter trings of the cloth corresponding to the modern chilkā) 116; vātapāna (lengthwise border of the cloth which keep the web together from becoming threadbare by fluttering in the wind) 116; uspisa 111; tarpya (silk or linen garment) 119; kshauma (linen)119; metals: gold, ayas, lead, tin, syama and loha 123; origin of silver 123; washing for gold 125; hiranyakṛṣṇala 125; fatamāna 125; hirapyagarbha 125; various kinds of ornaments like opasa, sraj, pundarisraj and bhoga 128; silver plates 130; loha 131; śyāma 131; sickle to cut and trim the sacred grass 132; dhrava (wooden sacrificial ladle having the largest bowl) 136; juhu (wooden ladle) 136; upabhft (wooden ladle) 136; wooden mace used in sacrifice 136; wooden Soma reservoir 136, 169; wooden instrument called sphys 136; wooden sacrificial posts 137; vapaspati (timber post) 137; pitha (in pithasarpin), a wooden seat 137; asandi (shining sent) whose use in ritual by a priest ensures sămrājya for his client 13S; waggon 13S; bost 13S; hidedresser 139; dry skin-bag as sacrificial fee 140, 169 fn.; ritual shoes made of black antelope skin 140; mantras for repetition at every stage of the mannfacture of Soma sacrificial drink 141; intoxicating effects of Soma drink; the story of Viśwarūpa 141; various kinds of altar-bricks 143-44; durya (door) 145 fn.; methi (pillar) 145 fn.; bhisak (physician) 150 fn.; physicians already came to be disliked 152, 152 in., 154-55; knowledge not descent making a brāhmaņs 155; setu (raised bank for crossing inundated land) 160 fa.; satsmina (as a medium of exchange) 165; milehing cows thrice a day ukhā (cooking pot) 169; brahma-udana

169; cooking left to the wife 171; ointment 176; Isika (annointing instrument) 176; origin of collyrium 176; gambling as res of the causes of indebtedness 171.

Taittirlya Samhita—Keith's Eng. Trans. on separate ownership of land 82; father making common property with the son 83.

Tandya Maha Brahmana with the commentary of Sayanacarya critically edited by Pandits A. Chinnaswami Sastri 1935, on base-eating 110; golden sraj (an ornament) 128,

Theogony of the Hindus—Count Bjornstjirns on the points of similarity between the religious systems of Ancient India and Egypt 19—20.

Therigatha on Benares cloth fetching 1000 pieces 220; Benares famous for her silk fabrics 221; manumission of slaves 253; Vimala, a courtesan whose mother was also one 257; satakas worth 1000 pieces of copper 274; Isidas! reduced to slavery in one of her previous births on account of her father's debts 275; addit (deposit of pledges on which loan was granted) 257.

Therigatha commentary on Puppa's admission into the Buddhist samples only after she was emencipated by her master 254; woman working as keeper of burning ground though mo wages are mentioned 256.

Times of India Illustrated Weekly (7th March, 1926) on the prehistoric civilisation of the Indus valley 12-16.

Tod's Rajasthana—See under Annals and Antiquities of Rajasthana—Col. Tod.

Travels of Marco Polo-Sir Heary Yale revised by Cordier on Indian dogs 164. Uvāsagadasao—Eng. Trans. by A. F. R. Hoerale on the cities of Alavi 180, Vārāpasi 180, Champā 180, Indapatha 181, Kampilya 181, Košāmvi 181, Kušinārā 181, Mithilā 112, Polāsapura 182, Pātalipattaka 182, Rājagiha 182, Sānkāšya 182, Sāketa 182, Setavya 182, Sagala 182, Sumsumāra 183, Takkeašilā 183, Ukkattha 183 and Vaišāli 183; Vaišāli was known as Vāniyagāma with Kulings and Kundagāma as its suburba 183; town-planning of Veiāli 185, 244; village of potters near Polāsapura 187, 225.

Vaijayanti-Yadavaprakasa on the growth of villages into towns 183 fn.

Vāšistba Dharmasūtra-Trans. into Eng. by George Buhler in the S. B. E. series vol. XIV, on the imposition of fines on village as a whole 190; village elders administering justice 190; distinction of royal domain from land of the ordinary landbolders 191; mode of acquisition of property 191; proofs of title to property 192; provisions on the right of way and evidence in disputes regarding immovable property. 192; acquiring property by usage 192 -93; state management of the property of widows and minors 193; laws of inheritance and succession 193-95; one-sixth as the royal share of the wealth of the subjects 196; exemption from taxation 198; objects made of leather 226; objects made of bone and conchabell 220; actors condemned 240; the other condemned professions 249 fn; apaddharma 250; slaves exempted from texation owing to loss of persona 253; Brahmins permitted to barter homegrown corn, food etc., 267; likhita (=I. O. U.) 271, 275; money-leading

condemned 274; six different kinds of interest 275, 277; two, three, four and five in the hundred is the monthly rate of interest according to caste 275, 277; interest on articles like gold, grain, beasts of borden etc., without security could be increased six or eightfold 275, 277; interest stopped with the death of the king in whose reign the transaction took place 275; king's duty to maintain śrotriyas, the weak, the aged, women without means and luns. ties 275; property other than a Brahmin's left ownerless reverts to the crown 193, 276; undue raising of prices condomned 277; those exempted from taxes 277; food of the money-lender who exacted mere than the legal rate of interest was impure 277; king's duty to guard against the falsification of weights and measures 277; begging Brahmins denounced as thieves 278.

Vajasaneyi Samhitā-See under White Yajurveda.

Veda of the Black Yajur School-Keith's See under Taittiriya Samhita-Keith's Eng. Trans.

Vedio Index—Macdonell and Keith on Aryans having acquaintance with agriculture in the Indo-Iranian period 22; dasa chiefs ruling ever puras 23; private ownership of land 24, 82 fm.; vis and jana 24; monarchy as a well-established institution in the Revedic Age 25; rejection of Zimmer's view that the gramani was the president of the village council 25-26; use of eak; (manure) in the Revedic Age 29-30; Yava meaning any kind of grain and not barley 82; cow, though its flesh was taken was gradually sequiring aspectity

even in the Rgvedic Age 33; salt in the Rayadic Age 34; Vedic sura (as opposed to Soma) being a drink of ordinary life \$5 fm., 54; no mention of horse-riding in war in the Rgveda 38; high social status of the rathakara and the taksan 45; vaya (weaver) 63; lobs originally meaning copper later denoted iron 49; Agoi and the sages as pathikrt (pathmakers ) 66; ota 46 fa.; existence of longer vessels with many oars for sea voyages in the Rgvedic Age 68-99; pani 74; niska as a sort of currency 76; story of Mann dividing property among his sons 84 fn.; the epithet devourer of the subjects applied to the king indicates king's political superiority and not his ownersip of the soil 85, 85 fn.; king's right to apportion the land with the consent of the clan as containing the germ of the later stateownership of the soil 86 fn.; vali (king's revenue) 87-88, 88 fn.; only five seasons in the year 91 fa.; drapi as a cost of mail 117 fo.; gold obtained from the bad of rivers 125 and from mines 125; vaya (weaver) 149; urdāra (a wooden vessel of definite size used in measuring grain) 164; kṛṣṇala, māṣa and other grains used as standards of weight in measuring precious metals 164; Vedio village 167 ; ksatty : his functions 174 ;

Vedic India—Ragozin on early cultivation of the cotton plant or tree by the Indo-Aryans 49; navigation anknown to the Rayedic Aryans 67.

Vedic Mythology—Macdonall on the cure of Ghori's skin-disease 63; well-irrigation in the Ryvedic Age 29-30; story of Manu dividing property among his cons 84 in. Vedische Mythologie—A. Hillebrandt, revised and enlarged in two vols. 1927—29, on the preparation of Soma drink 34 fn,

Vedische Studien—Geldner on anüka as an ornament 51; the existence of the caste system in the Rgvedic Age 58; prävepa (looking glass) 135; harmyesthah prince 173-4.

Vedische Studien—Pischel (Vol. II.) on patsyasad [patsya (n) meaning a house] 55.

Vimānavattu commentary on the cities of Ayojjha 180, Vārāņasi 180, Kāmpilya 181, Košāmvī 181, Madhurā 181, Mitbilā 182, Sāgala 182, Sāketa 182 and Vaiššīī 183; female slaves fetching water 252; a slave-girl beaten to death 255; story of a slave-girl flying to the forest to commit snicide, nuable to bear rude treatment 255—56; trade-route from Kaušāmvī through Sind to Sovīra 264.

Vinaya Texts-Translated into English by T. W. Rhys Davids and Hermann Oldenburg in the S. B. E. series vols. XIII., XVII. and XX. on large holdings (of 8000 acres) 190; channels dug for co-operative irrigation likened to patchwork robe of the monks 200; hot-air baths 234; dagobie or topes 236; fresco-painting 237; physician's fee of 16,000 pieces for curing a merchantprince's wife 239; a thief not to be ordained as a nun without the sanction of the guilds 244; guilds as arbitrators 244; parents discussing the best profession for their wards without a reference to the father's trade 246; low castes and low trades 248; fifty kahapanas for one night as the fee of a courtesan (Amvapall) 257; a Hindu merchant's seventh trading voyage on high seas 259; navigability by seagoing ships of the Ganges and the Yamuna 264; taverns for the sale of liquor 265; hotels for the sale of cooked meat and rice 265; barter prescribed for the Buddhist Sampha in certain cases 207; suvarpa and hiranya as media of exchange 269; one pada was equal to five masakas in Rajagrha in Ajatasatru's time 270; the purchasing power of a copper karsapana 273; debtors unfit for admission into the Buddhist Sampha 275; famino 280.

Wages Question, The-Walker on Indians abiding in their lot with oriental stoicism and fatalism 247.

Western Origin of Chinese Civilisation— La Conperie on maritime intercourse between:India and China from about 680 B. C. 162; foundation of an Indian colony about the present Gulf of Kiao—tchoa called Langga (after the Indian name of Lanka or Ceylon) 162.

White Yajurveda (together with the Kanva recension) on crops grown 93-94; forests supplying wild rice (alvara) 97, bdellinm 97, animals 97 and honey 97; different kinds of trees 99, 100, 103, 104, 106, 107, 108; 609 animals brought for the Horse-sacrifice 109-10; ballocks carrying loads 111; sacrifice of buffaloes 111; horses given as sacrificial tee 112; camel as an object of sacrifice 112; asses drawing the car of the Aswins 113; boar as an object of sacrifice to Indra 113; elephant-keepers 113; fishing in rivers and lakes 114; fishvendor 114; technical terms connected with weaving like otu (woof), vemān (loom) and maynkha (wooden pegs to stretch the web on or shuttle) 115; vasas (cloth) 116; threads of wool

3 14

118; metals: gold, ayas, syama, loha, lead, tin and silver 122-23; goldsmith 124, 128 fn.; gold pieces 125 fn.; a circular gold disc or plate with 21 knobs used in sacrifice 125; gold needles used in sacrifice 125; hiranyagarbha 125; sacrificial cauldron with golden handles 126; golden ornaments 127, 128; various ornaments like neckchain, opasa, gold worn as amulet trappings for horses 128 : golden 128; silver needles used in sacrifica 130; loha 131; śyāma 131; iron-131; blacksmith 131; smolter formed hammered OF receptacle with a tool of ayas 131; metal jug 131; sickle to cut the ripened grain 131; knife 131; iron axe 132; rasor 132; fetters made of iron 132; lend needles used in sacrifice 132; armour 132; iron castles (used figuratively) 132; srava (small wooden sacrificial ladle) 136; sruc (large wooden ladle) 136; wooden sacrificial spade 136; wooden Soma reservoir 136, 169; fourcornered sacrifical cups of Khadira wood 136; mortar-shaped cup of Palasa wood 136; wooden Soma cups 136, 169; wooden mortar and pestle for extracting Soms juice 136, 169; wooden needles used in stitching together the folding doors of the cart-shed 136; fire shovel or poker made of Palais wood 136, 169; wooden instrument called sphya 136; wooden sacrificial posts 137; drupad (timber post) 187; thrones made of Khadira wood 137; pitha (in pithasarpin), a wooden seat 137; asandi (shining seat) 137, 138; rājāsandī (shining seat for kings) 138; war-chariots 138;

carte 138, carriage 138; potter 140; mrnmaya ukhā (sarthen cooking pot) 149, 169 ; dvār (door) 145 ; darya (door) 145; durona (door) 145; principal occupations of the people 148 fn., 148-51, 174; women splitting cane, working in thorns, doing embroidery work, dealing in love charms, washing and dyeing cloths and making scabbards and ointments 153; gapa and gapapati 157; vanij (merchant) 158; -references to the sea 161; aritram (oar) 161; ship propelled by 100 cars 161; tilla (balance) 164, 271; women fetching water 172; birth of industrious women, a blessing which the Horse-sacrifice will bring to the king 172; ointment-maker (usually a female) 176, 153; duty of the state to protect the life and property of the subjects as also to promote their material welfare 176-77; ideal of happiness which the king prays to the gods for his country to attain 178.

White Yajarveda—Eng. Trans. by R. T. H. Griffith on different crops grown 94; the use of the timber of Karshamarya tree (Gmelina Arbora) in making sacrificial ladles 100; Kımuka tree as furnishing kindling sticks for sacrificial purposes 100; goat as an object of sacrifice to Vâyu 112.

Yājnavalkhya Samhitā on the right of collecting grass, fraits and flowers enjoyed by Brahmins 82.

Zeitschrift der Deutschen Morgen landischen Gesellschaft (vol. IX.): Max Muller on the different implements mentioned in the Gihyasütras 224 fn.; (vol. LI.): Oldenburg on the existence of the caste system in the Rgvedic Age 58.

# II. Subject Index.

## [ The references are to the pages of this work ]

#### A

Agriculture, clearance of forests for purposes of, 28; implements for, 28-29; application of manure for, 29, 92-93; irrigation for, 12, 29-30, 93, 260; rainfall a necessity for, 11, 30, 199-200; prayers and charms for esinfall 30, 96; charms to avert inundation 93, 96; prayer for a bumper harvest 96; troubles the agriculturist had to contend with 95-96; agricultural operations 31-32, 92-93, 198-99; successive stages of, 198-99; rotation of grops 91; khila system of, 91-22; cultivation of land by peasant-proprietors 197-98; cultivation of lands belonging to others 198; measures for the protection of the crops 199; ceremonies connected with, 30-31, 96, 199; products of, 32, 93-94, 95, 200-02; position of woman in relation to, 153-54.

Agriculture, not known to the Palsolithic Indians 1; in the Neclithic Age 3; in the Indus Valley in the Chalcolithic Age 11-12; known to the Aryans in the Indo-Iranian period 28; in the Revedic Age 23-24, 28-32; in the Brahmana period 90-96; in the Age of Gautama Buddha 197-202.

Agricultural products, in the Rgvedic Age 32; in the Brahmana period 93-94; in the Age of the Ramayana 95; in the Age of Gautama Buddha 200-02, Age 64; change for the worse in the Br4hmana period 152, cf. 85.

Alchemy ? (in the Age of the Ramayuna )

Arboriculture - See under Gardening, art of.

Architecture, in the Neolithic Age : thatched huts 3; prehistoric cometries 6; in the Copper Age : megalithic monuments of Coimbatore and Hyderabad Cairn burials 89; in the Chalcolithic Age: dwelling houses of Mohenzo Daro with brick-filling bath rooms and paved washing places near wells 14-15; a temple with a bath at Moheaso Daro 15-16; the dwelling houses of Harappa, one of which had narrow walls and corridors 16; brick-structures like Hindu Samidhi's 16; in the Revedio Age : giba (a memorial structure erected or beside the grave) 56; the harmya 56, 173-74; the widatha (royal audience hall) etc. 57; in the Brahmana period: the ordinary dwelling house in which bamboo-work predominated 143; smasina (memorial structures) of three kinds viz., vāsta, giha and praghanam usually made of bricks or stones 144 ; timber architecture 145 ; fivaentha (a temporary structure for the reception of guests) 168; in the Age of the Elmiyapa : Kaikeyl's Mahala with its krodhāgāra, citragiha, latāgiha etc.

174 ; Yovarāja Rāma's Mabala 174 — 75 ; Ravapa's palace with its krodhagdra, kāmagīha, divāvihāragīha, oitragīha, latagiba, artificial mountains made of wood etc. 175; in the Age of Gautama Бореня 230; Buddha: thatched seven-storied buildings 230; dharmasala 230 ; isana-sala (resting place travellers) 230; samsthägåra (townball) 230-31; chaitya 231; kṛḍāśālā, of which a portion was reserved for the reception of guests, a portion for the poor and the helpless and a portion for the delivery of helpless women 231; a privy with doors in which a lamp was kept burning the whole night 231; buildings of fee kinds in which monks were permitted by the Buddha to live via. vihāra, ardhayoga, prisāda, harmya and goha 231-32; hot-sir baths 234; tanke with bathing nie open flights of steps 234; temples 236 ; Vaithaka of Jarasandha and the walls of Rajngtha 236; Khapdagiri and Udayagiri caves 236 ; Dagobūs or Topes 236 ; Piprawa Stupa 236.

Arts and crafts, in the Palssolithic Age ; work in stone ; work in bone 2 ; in the Neolithic Age : work in stone 3 ; pottery 3-4; gold-mining 4; pearl and cunobshell industry 6; architecture : huts 3 and cametries 7 | painting 4-5; sculpture 5-6; in the Copper Age : work in branse 7, 8; work in silver 7; work in iron 8,9; work in gold 8; pottery 8, 9; architecture ; tombs of Cyclopean style in Tinnevelly, Kurnool, Coimbatore and Anantapar districts 8-9; Hyderabad cairn burials 9; in the Chalcolithic Age: weaving 12; work in shell and terracetta 13; work in silver 13; work in gold 13; work in precious stones 13; work in ivory 13; work in copper 13 ; work in bronze 13 ; pottery 13-14 ; architecture 14-16; towa-planning in Mohenzo Daro 14 and in Harappa 16; in the Ravedio Age: weaving of wool 45-48 and of cotton 49; work in ayas 49-50; work is gold 50-52; carpentry 52-53; pottery 53; leather-work 54; manufacture of liquor 54; architecture 54-57; painting 57; sculpture 57; in the Brahmana period : weaving 115-22; mining 122-24; work in gold 124-30; work in silver 130; work in ayas and lobe 130-33; work in bellmetal 133; work in brass 133; alchemy? 133; art of the jaweller 133-34; glass work ? 134-35; carpentry 136-39; leather-work 139-40; pottery 140; work in ivory 140; manufacture of liquor 141-42; painting 142; sculpture 143-45; town-planning 145-48; orboriculture 103-04; in the Age of Gautama Buddha: work in iron 214-16; work in copper 216; work in silver 216; work in bell-metal 216; work in brass 216; work in gold 216-17; art of the jeweller 217-18, 214; weaving 218-22; carpentry 222-24; work in grass and reads 224-25; pottery 225-26; leather-work 236-27; wine distilling 227-28; work in stone 228; work in ivory 228; work in bone, conchabell and coral 229; preparation of salt 229 and of molasses 229; dyeing 229; stiffening cloth with starch and polishing it with couch 229-30; curling cloth into a thousand folds before wearing it 230; architecture 230-36; sculpture 236-37; painting 237.

Articles of foreign trade, in prehistoric times 17-18; 20-21, 72; in the Revedic Age 71; in the Brahmana period 163-64; in the Age of the Ramayana 162; in the Age of Gautama Buddha 260, 262.

Articles of domestic trade in the Egyedic Age 65; in the Brahmana period 158; in the Age of the Ramayana 158; in the Age of Gantama Buddha 265.

Aryans acquainted with agriculture in the Indo-Iranian period 22-23.

Asava 171.

Ayas, in the Revedic Age 49-50; in the Brahmana period 130-31.

#### B

Barter, in the Egyedic Age 75; in the Brahmana period 164; in the Age of Gantama Buddha 267—68.

Beef-eating, in the Chalcolithic Age 12; in the Egwedie Age 33; in the Brahmans period 110-11.

Bell-metal industry, in the Age of the Rāmāyaṇa 133; in the Age of Gautama Buddha 216.

Borax 123, 125.

Brass industry, in the Brahmans period 133; in the Age of the Ramayans 133; in the Age of Gautama Buddha 216.

Bronze industry in the Copper Age 78; in the Chalcolithic Age 13.

Burms find 1, 2,

## C

Canal irrigation, in the Rgvedic Ago 29; in the Brahmana period 93.

Carpentry, in the Rgvedic Age 52-53; in the Brahmana period 136-39; in the Age of the Ramayana 139; in the Age of Gautema Buddha 222-24. Caste system in relation to mobility of labour, in the Rgvedio Age 58-63; in the Brabmana period 154-56; in the Age of Gautama Buddha 244, 246-50.

Cattle-rearing, in the Chalcelithic Age 12; in the Egyedic Age 35—41; in the Brahmana period 109-13; in the Age of Gautama Euddha 211.

Ceremonies connected with agriculture, in the Rgvedic Age 30-31; in the Britmaps period 96; in the Age of Gautama Buddha 199.

Chalcolithic civilisation of the Indus Valley, its affinity with Samerian culture 11, 16-17; prosperous agriculture on a flat plain subject to floods 11; ampler rainfall than today: evidences for it 11 -12; crops grown: wheat and cotton 12; hunting, fishing and weaving industries 12; dress and ornaments of the people 12-13; work in shell and terracotta, in silver, in gold, in precions stones, in bronze and copper 13 ; pottery 13-14; dwelling houses at Mohenzo Daro 14-15 and at Harappa 16; a temple and a public bath at Mohenzo Daro 15-16; town-planning at Mohenzo Daro and Harappa 14, 16; internal trade 16-21.

Character of foreign trade in Ancient India 280.

Civic consciousness in the Age of the Ramayana 148,

Civilisation of the Copper Age: work in copper 7, 9; in bronze 7, 8; in silver 7; in iron 8; in gold 8; pottery 8, 9; architecture: Cyclopean style of construction of the tombs 8-9; probable Egyptian influence on the pottery and on the construction of the tembs of this age 8-9; methods and media of exchange 9-10.

Classification of villages 186-57.

Combination between merchants, in the Rgvedio Age 74-75; in the Age of Gautama Buddha 242, 263, 257.

Competition determining prices, in the Rgvedio Age 65-66; in the Age of Gautama Buddha 265-66.

Conshshell industry, in the Neolithic Age 6; in the Chalcolithic Age 13, 16; in the Age of Gantama Baddha 229.

Copper Age antiquities 7-9.

Copper industry, in the Copper Age 7.8, 9; in the Chalcolithic Age 13; in the Rgwedic Age 49-50; in the Brāhmaņa period 130-31; in the Age of Gautama Buddha 216.

Corsl, work in, in the Age of the Ramayana 124, 134; in the Age of Gautama Buddha 212, 220.

Cornering 266.

1.

Corporate life in the towns (in the Age of Gantama Buddha) 185-86.

Corporate life in the villages, in the Rgvedic Age 25-25; in the Age of Gautama Buddha 188-90.

Cotton, cultivation of, in the Chalcolithic Age 12; in the Egyedic Age 49; in the Brahmans period 119-20; in the Age of Gantama Buddha 220.

Cotton industry, in the Chalcolithic Age 12; in the Rgvedic Age 49; in the Brāhmaņa period 119-20; in the Age of Gautama Buddha 219-20.

Cow as a standard of value, in the Rgvedic Age 9-10, 75; in the Age of Papini 268; in the Sutra period 268. Cowry-shell as a standard of value (in the Jataka period) 268,

Craft-guilds-Ses under Guilds,

Currency, in prehistoric times 9-10; in the Rgvodic Age 75-77; in the Brähmann period 164-67; in the Age of Gautama Buddha 268-71. For details See under Methods and Media of exchange.

Custom influencing prices 200.

D

Dealing in futures 266.

Dignity of labour, in the Revedic Age 61-62; loss of this dignity in the Brahmana period 152, 154-55 and in the Age of Gautama Buddha 245-49.

Domestic furniture, in the Ryvedic Age 58; in the Brahmana period 168; in the Age of the Ramayana 169; in the Age of Gautama Buddha 217, 222-23.

Domestic economy, in the Egyedic Age 64-65; in the Brahmana period 153-54, 171-73.

Domestic trade, in the Chalcolithic Age 10; in the Revedic Age 65-67; in the Brahmana period 158-60; in the Age of Gantama Buddha 262-67.

Domestic utensils, in the Neolithic Age 3; in the Copper Age 8; in the Chalcolithic Age 13; in the Egyedic Age 50, 53, 54; in the Brahmana period 168—69; in the Age of Gantama Buddha 215-17.

Domesticated animals—See under Cattlerearing.

Drainage system, (in the towns of Mohenzo Daro and Harappa in the Chalcolithic Age) II and in Benares in the Age of Gantama Buddha 120. Dress of the people, in the Chakolithic Age 12—13; in the Rigwedia Age 47—48; in the Brahmana period 117—18; in the Age of Gautama Buddha 319, 229—30.

Dried fish as food 227.

Duties levied by the king 277.

Dyeing industry 229.

### E

Economic condition of the classes and the masses—See under General economic condition of the classes and the masses.

Excavations at Mohenso Daro and Harappa 11-16.

Exemption from taxation 277.

Extent of Aryan expansion in the Revedic Age 22; in the Brahmana period 81.

## F

Falsification of weighte and measures condemned 277.

Famine; in the Egyedic Age 80; in the Brähmana period 96-97; in the Aga of Gautama Buddha 279-80.

Famine relief 278.

Female labour, in the Rgvedic Age 64-65; in the Brahmana period 153-54 171-72; in the Age of Gantama Buddha 256-67.

Fishing, in the Chalcolithic Age 12; in the Revedic Age 33, 44; in the Brahmana period 114, 170-71; in the Age of Gautama Buddha 212.

Food of the people, in the Palmolithic Age 2; in the Neolithic Age 3; in the Copper Age 8; in the Chulcolithic Age 12; in the Revedic Age 32—33; in the Brahmana period 169—71.

Forced labour 276-77, 279.

Foreign trade of India, in the Chalcelithic Age 16—21; in the Rgvedic Age 69—74; in the Brühmaps period 162—64; in the Age of Gautama Buddha 26:—62, 280. For details See under Trade of India, Articles of foreign trade and Maritime trade-routes

Forests and their economic importance, in the Egyedic Age 41—43; in the Brahmana period 97—109; in the Age of Gautama Buddha 202—09.

Free labourers, their dignified status in the Rgvedic Age 61-62; loss of their former status in the Brihmuna period 152, 154-55 and in the Age of Gantama Buddha 248-49; their frivolous though gay life 251; their general economic condition 251.

Fruits, in the Rgvedic Age 33; in the Brahmans period 105; in the Age of Gautama Buddha 207-08.

#### G

Gardening, art of, in the Age of the Rāmāyana 103-04; in the Jātaka period 213; in the Sūtra period 213.

General economic condition of the classes and the masses, in the Egyedic Age 77—80; in the Brahmana period 167—77; in the Age of Gautama Buddha 278—80.

Geographical mobility of labour 247.

Glass industry? (in the Brahmana period)

Godavari flake 1, 2,

Gold industry, in the Palseolithic and Neolithic Ages 4; in the Chakolithic Age 13; in the Revedic Age 50-52, in the Brahmana period 124—29; in the Age of the Ramayana 129—30; in the Age of Gautama Buddha 216—17.

Grass: its different varieties, in the Rgvedic Age 43; in the Brāhmana period 108; in the Age of Gautama Buddha 200.

Grass, work in, 224-25.

Guilds, in the Revedic Age 74-75; in the Brahmana period 156-58; in the Age of the Ramayana 258; in the Age of Gantama Buddha 242-43; their organisation 157, 243, 245; their three principal characteristics: (1) an Alderman at the head 243, (2) heredity of profession 244 (3) localisation of industry 243-44; their legislative, judicial and executive functions 244.

Gungeria hoard 7.

## H

Haggling over prices 65-66, 265.

Herbs, in the Rgvedio Age 43; in the Brahmans period 105-07; in the Age of Gautama Buddha 208-09.

Hearding of wealth 274,

Horse-racing (in the Egyedic Age) 39.

Horse-riding (in the Revedic Age) 38-39.

Horticulture-See under Gardening, art of,

Honse-building: thatched hats in the Neolithic Age 3; in the Chalcolithic Age 14-15, 16; in the Ravedic Age 54-57; 173-74; in the Brahmana period 143-45, 167-68, 174-75; in the Age of the Ramayana 174-75; in the Age of Gantama Buddha 2:0—34, 235. For details See under Architecture.

Hunting, in the Paleolithic Age 1; in the Neolithic Age 3; in the Chalcolithic Age 12; in the Revedic Age 43-44; in the Brahmana pariod 113-14; in the Age of Gantama Buddha 211-12.

#### I

Indebtedass of the people-See under

Indian trade or commerce with Arabia,
Assyria, Babylon, Burma, Caylon,
Chaldes, China, Egypt, Mesopotamia,
Porsia and Phoenicia—See under Trade
of India.

Inheritance-See under Law of inheritance.

Inland trade routes, in the Chalcolithic Age 16; in the Egyodic Age 66; in the Brahmana period 159-60; in the Age of Gantama Buddha 263-64.

Internal trade-See under Domestic trade.

Instruments of credit 271, 271 fa.

Iron, in the Neolithic settlement in the Bellary district 4 fn.; articles made of iron found in the barial sites of Adichanallur in Tinnevelly 8; in the Rgvedic Age ? 49-50; in the Brāhmaņa period ? 131; in the Age of the Rāmāyaņa 131-33; in the Age of Gautama Buddha 214—16.

Irrigation, in the Chalcolithic Age 12; in the Egwedic Age 29-30; in the Brahmaya period 93; in the Age of Gantama Buddha 260,

Ivory, work in, in the Age of the Ramayana 140; in the Jataka period 228.

#### J

Jewellery, in the prehistoric burial sites at Adichanallar in Tinnevelly 8; in the Chalcolithic Age 13; in the Brahmana period 133; in the Age of the Ramayana 133-34; in the Age of Gantama Buddha 217-18; in the Piprawa stupa 214.

#### 瓦

Khila system of cultivation 91-92. Kilâle, a variety of sură 142, 227.

#### L

Labour-See under Free labourers and Slavery.

Land-ownership-See under Land system.

Land revenue, the amount of the royal share in the Brahmaps period 88 and in the Age of Gautama Buddha 195—96; payable either in cash or in kind 88, 197; land survey 196; land revenue administration 193—97.

Land system : division of land into vastn. arable land, pasture and forests; vastu and arable land in individual ownership and pasture and forests in communal ownership 23-24, 82, 191-93; land belonged to the members of the joint family in common 82-84; transfer of land 84; feeling against land-transfer in the Satapatha Brahmapa 65; no state-landlordism in the Revedic Age 24-25, in the Brahmaps period 85-87 and in the Age of Gautama Buddha 190-91; royal domain 190-91; land revenue in the Rgvedic Age 25, in the Bribmana period 87-88 and in the Age of Gautama Buddha 195-97; land tenure 197-98; rise of landed aristocrats and its causes 88-89, 173; an ideal economic holding according to Baudhayana 190.

Land tenure: peasant-proprietorship 197-98; bhāgolāņa 198; Zamindari system 88-89, 173. Landed aristocracy, causes favouring the growth of, (in the Brahmans period) 88-89, 173.

Law of inheritance in the Ravedic Age 89; in the Brahmana period 82-90; in the Age of Gautama Buddha 193-95.

Leather-work, in the Rgvedic Age 54; in the Brahmana period 139-40; in the Age of Gastama Buddha 226-27.

Linen industry, in the Brahmapa period 119; in the Age of the Ramayana 120-21; in the Age of Gautama Buddha 220-21.

Loans, in the Revedic Age 79-80; in the Brahmans period 177; in the Age of Gautama Buddha 274-75, 279.

Localisation of arts and crafts 243-44, cf. 185.

Low castes and low trades 243-49.

## M

Manufacture of liquor, in the Rgvedic Age 34-35, 54; in the Brahmana period 141-42; in the Age of the Ramayana 143; in the Age of Gautama Buddha 227-29.

Manure in the Rgvedic Age 29; in the Brahmana period 92-93.

Maritime trade - See under sea-borne trade.

Maritime trade-routes, in the Revedic Age 70, 73-74; in the Brahmans period 163; in the Age of Gautama Buddha 261.

Meat-eating, in the Palmolithic Age 2; in the Neolithic Age 3; in the Chalcolithic Age 12; in the Rgvedic Age 33; in the Brahmana period 110-13, 170.

Mendicancy, condemnation of, 278.

Merchante' guild-See ander Guilde.

Methods and Media of exchange, in prehistoric times: during the pastoral stage cow as the medium of exchange 9-10; in the agricultural stage when commerce developed itself garments and coverlets served as measures of value 10; panch-marked coins with prehistoric symbols on them 10; finds of coins of the Chalcolithic Age at Mohanso Daro and Harpppa 11; in the Ravedio Age: cow as a medium of exchange 75; niska 75-77, mana 77 and hiranyapinda as metallic media of exchange; was the niska a coin ? 76; in the Brahmana period : barter 164 ; nitka 164-65, satamāus 165-60, mayarya 166, pada 166-67; krspala 167 as metallic media of exchange; in the Age of Gautama Buddha : barter 267-08; rice, cowry-shell and the cow as media of exchange 268; kākapika, ardhamijaka, mājaka, quarter kārja, hall karşa, karşapans, pada, pana, satamana, niska, suvarpa, hiranya, kamsa and vista as metallic media of exchange 269-70; stamped impressions on some of the media of exchange 269.

Milk and preparations from milk, in the pgyodic Age 34, in the Brähmaga period 110, 171.

Mining and metal industries, in the Copper Age 7—9; in the Chalcolithic Age 12—13; in the Egyedic Age 49—52; in the Brahmana period 122—35; the Age of Gantama Buddha 209—10, 214—18.

Mixed metal industries: bell-metal: in the Brahmana period 133; in the Age of the Ramayana 133; in the Age of Gautama Buddha 216; brass, in the Brahmana period 133; in the Age of the Ramayana 133; in the Age of Gautama Buddha 216; bronss, in the Chalcolithic Age 13.

Mobility of labour-See under Caste system in relation to mobility of labour.

Molasses, preparation of, 229,

Moneylending-See under Loans.

Monsoons, discovery of, 74.

### N

Navigation in the Revedic Age 67-74; in the Brahmana period 160-63; in the Age of Gautama Buddha 256-59, 262.

Neolithic civilisation: knowledge of agrioulture: its evidences 3; articles for
domestic use betraying fascination for
colore 3; polished work in stone 3;
pottery 3—4; gold-mining 4; rockpaintings near Singapur in C. P. 4—5,
in Kapgallu in Bellary district 5 and the
cave-paintings in the Kymore ranges 5;
coulpture in the Edakal cave, Wynnad
5—6; knowledge of thatched hate 3;
use of cemetries and graves 6; pearlfishery and conch-shell industry 6.

No Bronze Age in India 7. No Copper Age in South India 7. No Golden Age in prehistoric times 1.

No state-landlordism in the Rgvedic Age 24-25; in the Brähmann period 55-87; in the Age of Gantama Buddha 190-91.

#### 0

Occupations of the people, in the Rgvedic Age 62-64; in the Erähmana period 148-52; in the Age of Gautama Buddhe 237-42. Origin of villages, in the Rgvedic Age 25; in the Age of Gautama Buddha 186—88.

Ornaments, in the Copper Age 7, 8; in the Chalcolithic Age 12—13; in the Rgvedic Age 51—52; in the Brahmans period 127—29; in the Age of the Ramayana 129—30, 133, 133—34; in the Age of Gantama Buddha 217—48.

#### P

Painting in the Neolithic Age 4-5; in the Egredic Age 57, In the Brahmana period 142; in the Age of the Ramayana 142; in the Age of Gantama Buddha 237.

Paleolithic civilisation: Paleolithic settlements not only near rocks suitable for fashioning tools but also near rivers and lakes 2; no private property in land, no division of labour, no knowledge of metals or of pottery 1; stone tools and weapons 1; hone weapons and implements in the Billa Surgam caves of Karnaul 2; smoked flesh as food 2.

Pātna, an întoxicating drink 35, 54. Parierut, 142.

Partnership 267.

Pearlishing in the Neolithic Age 8; in the Rgvedic Age 44; in the Brahmana period 114—15; in the Age of the Ramayana 124, 129, 134; in the Age of Gautama Buddha 212, 217, 218.

Pig-culture 211.

Piprawa Stupa : excellence of its construction and of the jewellery it contains 214.

Plants in the Rgvedic Age 43; in the Brahmana period 105-08; in the Age of Gautama Buddha 206-07, 208

Ports of departure from India 262.

Poultry-farming 211.

Precious stones, in the Chalcolithic Age 13, 16; in the Rgvedic-Age 71, 72; in the Brahmann period 163-64; in the Age of the Ramayana 124, 129, 134; in the Age of Gantsma Buddha 214, 218, 262.

Prices, influence of competition on, 65-56, 265-66; influence of custom on, 266; state control of, 277.

Private ownership of land, in the Egyedie Age 23-24; in the Brahmana period 82-S5; in the Age of Gautama Baddha 191-93.

Protection of the crops 199.

Parchasing power of money (in the Jataka period) 272-74.

Purnea Schta hymn, dealing with a theory of creation, not of casts 60-31.

## R

Raising of prices, condemnation of, 277.

Rate of interest, in the Egyadic Age 79;
in the Brahmana period 177; in the
Sütra period 274—75.

Reeds, in the Rgvedic Age 43; in the Brahmana period 108-09; in the Age of Gautama Baddha 209,

Regulation of prices 265, 277.

Relative value of gold and silver 271.

Rice as a standard of value (in the Jätaka period) 268.

Rotation of crops 91, 91 fa.

Royal revenue, in the Brahmana period 67—88; in the Age of Gautama Buddha 195-97, 210-11, 276-77, 279.

#### 8

- Salt industry, in the Egyedic Age 33-34; in the Brahamana period 34; in the Age of Gautama Buddha 229.
- Scalpture, in the Neolithic Age 5-6; in the Egyedic Age 57-58; in the Brahmana period 142; in the Age of the Eamayana 142; in the Age of Gautama Buddha 236-37.
- Sea-borne trade, in the Rgvedic Age 67—
  74; in the Brahmana period 160—64; in the Age of Gautama Buddha 257—62.
- Seasons in the Vedic Age 91 fu.
- Ship-building industry, in the Rgvedic Age (a vessel with 100 cars) 68; in the Brahmana period (vessels having two rudders) 139, 161; in the Jataka period 259—60.
- Silk industry, in the Brahmana period 119; in the Age of the Ramayana 121-22; in the Age of Gautama Buddha 221.
- Silver, work in, in the Copper Age 7; in the Brahmana period 130; in the Age of the Ramayana 130; in the Age of Gautama Buddha 216.
- Shavery, in the Rgvedic Age 64, 153; in the Brahmana period 153; in the Age of Gantama Buddha 252-56.
- Slaves, the classification of, 252; causes of slavery 252, 79; status of, 252—54, 153, 64; usual duties of, 153, 252; manumission of, 253; their lot fir better than that of the Greek or Roman slaves 254—56; no slave-market 153; slavery

- did not become the basis of husbandry 64, 152.
- Soma drink, in the Rgvedie Age 34-35, 54; in the Brahmana period 141-42,
- State control over prices 277.
- State protection to the scotrigue, the weak, the aged, women without means and the lunatics 276.
- State protection of the property of infants 276.
- Stone, work in, in the Palssolithic Age 1, 2; in the Neolithic Age 3; in the Age of Gantama Buddha 228.
- Successive stages of agriculture 198-99.
- Surā, in the Rgvedic Age 35, 54; in the Age of the Rāmāyana 143, 171; in the Age of Gautama Buddha 227.
- State help to the famine-stricken 276.
- State in relation to economic life, in the Brāhmaņa period 177-78; in the Age of the Rāmāyaņa 178; in the Age of Gautama Buddha 275—78.

### T

- Tin, in the Chalcolithic Age 13; in the Brahmana period 122, 123; in the Age of the Ramayana 123.
- Tools and weapons, in the Palsolithic Age 1-2; in the Neolithic Age 3; in the Copper Age 7; in the Chalcolithic Age 13; in the Revedic Age 50; in the Brahmana period 131-32; in the Age of Gautama Buddha 215.
- Towns, origin of, 183-84; division into wards 185; parks in, 183; avenues of trees in, 101 fn., 147; arbours of trees in, 213, 147; town-hall 230-31; main buildings in, 147; town-planning 16,

145-47, 184-85; corporate life in, 185-86,

Towns in the Chalcolithic Age 14-16; in the Rgvedic Age 26-28; in the Brahmana period 81-82; in the Age of Gautama Buddha 179-86.

Town-planning, in the Chalcolithic Age (at Harappa, specially at Mohenzo Daro) 16; in the Brahmans period 145-47; in the Age of the Ramayana 147; in the Age of Gautama Buldha 184-85.

Trade of India, with Arabia in prehistoric times 72, in the Age of the Ramayana 161; with Assyria in the Brahmana period 163, in the Age of Gautama Buddha 260; with Babylon in prehistorio times 16-17, 72-73, in the Brahmana period 162-63, in the Age of Gautama Buddha 260; with Burma (Suvarnabhūmi) 261; with Coylon 261; with Chalden 72; with China 161-62; with Egypt in prehistoric times 17-21, 70-71; with Mesopotamia in prehistorio times 16-17, 70-71; with Persia in prohistoric times 16-17, 69-70, in the Brahmapa period 163, in the Age of Gautama Buddha 261; with Phoenioia in prehistoric times 69-70.

Trade-routes in the Chalcolithic Age 16; in the Egyedic Age 66, 70, 73-74; in the Brahmpa period 159-60, 163; in the Age of Gantama Buddha 261, 263-64.

Trees, in the Rgvedic Age 42; in the Brahmana poriod 98—105; in the Age of Gautama Buddha 204—08.

U

Use of the horse in war in the Rgvedic Age 38-39,

Usury, 275; usurers organised into guilds 275; their exactions condemned 277.

V

Villages, origin of, 25, 183—58; classification of, 196—87; administrative machinery of, 25—26; corporate activity in, 25—26, 188—90.

W

Weaving industry, in the Chalcolithic Age 12; in the Rgvedio Age 45—49, in the Brahmana period 115—20; in the Age of the Ramayana 120—22; in the Age of Gautama Buddha 218—22. For details See under cotton, linen, silk and woolen industries.

Weights and measures, in the Egyedic Age 77; in the Brühmana period 164, 271; in the Age of Gautama Buddha 271-72.

Wine-distilling-See under Manufacture of liquor.

Woolen industry, in the Rgvedie Age 48; in the Bramana period 118—19; in the Age of the Ramayana 121; in the Age of Gautama Buddha 221—22.

Work in bones, in the Palmolithic Age 2; in the Age of Gautama Buddha 229.

Work in corals - See under Coral, work in.

Work in grass and reeds-See under Grass, work in.

Work in born 229.

Work in stone-Ses under Stone, work in.

## Index III. Proper Names.

## [ The references are to the pages of this work ]

#### A

Aboasin (= the Indus) 19.

Abyesinia 19.

Abyssinians 20.

Aciravati river 183.

Aden 7.

Adielmoaller 8, 18.

Adityas 80.

Ælian 210.

Agastya 105 fn., 111.

Agni 26, 37, 66, 83, 125, 153 fn., 159, 177.

Agra 27, 33, 135.

Ahina sacrifices 239.

Ajanta caves 232.

Ajātašatru, King 156, 184, 278.

Ajigarta 82.

Akhurāja 199.

Akkad 72, 73.

Akkadian 77,

Al-Uhaid 17. Alexander 77, 236,

Alexandria 73.

Allahabad 181.

Alavi 180.

Amara (simha) 206, 207 fo.

Amenophie 19.

America 280.

Amitratāpanā 273 fm.

Amulya Ch. Sen 257 fn.

Amyapali 192, 257.

Anantapara 4, 8, 18.

Anathapindaka 192, 254, 255.

Andhapara 180.

Andhens 81.

Andrew Lang 61,

Anga 95, 97, 180.

Angirasas, the 168.

Anghā 199.

Angul 2,

Anopiya city 180.

Annrådbapura 234 fn.

Anandskumära 259.

Apola 24.

Apasthamya 186, 192 fn., 193 fn., 194, 195, 203 fn., 244, 244 fn., 249 fn., 250, 267fn.,

268 fa., 276, 276 fa., 277 fa.

Āptaryāma 141.

Arabia 70, 72, 74, 163.

Arabian Sea 69, 70.

Arada 199.

Aradus, isle 70.

Aramic script 73.

Arāti 47.

Arcot 9 fn.

Aristapura city 180.

Aristobulus 199.

Armenia 73.

Arrian 77, 163, 200 fm, 212 fm, 226 fm,

228 fn.

Asitanjana city 180.

Asmodeus 106.

Asoka forest 103, 123, 147.

Assakenoi, the 163.

Assapura 180.

Assyria 72, 153.

Assyrian 163, 260.

Astakenoi, the 163.

Asvamedha 110, 111, 126.

Asyapati, King 156. Aswini 28, 40, 96, 112, 113, 154. Asangs 78. Asandhiyat 81. Atithigva 78. Atiratra rite 141. Atri 24 Attaka city 180. Attock 19. Atavi 180. Avanti 183, Ayodbyā kingdom 95, 120, 124, 143. Ayodhya city 95, 101 fn., 105 fn., 121, 122, 133, 146, 147, 148, 180, 182. Ayojjha city - Ayodhyā 180. Ayomukha mountain 124, В Babylon 17, 21, 70, 71 fn., 146, 163, 260, 262, 267. Babylonians 164, Beccanelia 227. Bectring 163. Baden Powell 64. Bahllika 112, 158. Balfour S. H. 49. Balkh 74. Ball, V. 70, 210, 210 fn. Ballensen, Dr. 57. Barker 19 fn. Barley island 162 fn. Baroda 4, Barygaza 164. Baudhāyana 141, 163, 186, 190, 193 fn., 194, 195, 196, 203 fn., 248, 250, 250 fn. 260, 268 fn., 274, 275 fn., 276. Bah 124. Beal 236 fn. Bellary 3, 4, 4 fn., 5.

Beluchisthan 4, 11, 14, 17.

265, 267, 273 fn., 274, 279.

Benares 27, 179, 180, 181, 185, 186, 187,

220, 221, 224, 228, 238, 239, 251, 264,

Bongal 231. Besara 183. Bhadravätikā 180. Bhaga 137, 157 fn., 199. Bhandagama 264. Bhápdárkára D. R. 9. Bharnt Topes 233 In. Bharadwāja 33, 56, 121. Bharata 95, 121, 122, 124, 133, 158, 178, Bhava 79. Bhajya 68. Bihar St. Bijnai river 2. Billa Sangam 2. Birs Nimrod 163. Bjornstjirna, Count 20 fn. Blanford H. F. 1 In. Bloomfield 51 fn., 150 fn. Blue river 19, Bodhisattva 231, 237. Bohlen Von 71. Bobtlingh 166. Book of Genesis 20. Brahma 147. Brābmi alphabet 260. Bihadratha 153 fn. Brahmottara city 180. Brhaspati 30, 172. Brosch 16, 164, 260, 261, Bruce Foote 3 to , 4 fn., 5 fn. Bryn 79. Buddha, the 179, 181, 192, 200, 219, 231, 236, 239, 245, 251, 254, 255, 261, 278, Buddhaghoşa 231 fn., 233 fn. Buhler 67, 260. Barma 261, 262. Burma find 1. Byzantine 76.

C

Calcutta 27. Caldwell, Dr. 71, 71 fn., 260. Cambay 16.

Cary 214 fn. Caspian Sea 73. Cathedral Cave of Billa Surgam 2. Cevlon 162, 261, 264. Caylonese 135. Chakravarman 248. Chakradharpur 2. Chaldea 72, 230. Champa city 179, 180, 261, 264. Chandragupta Manrya 82. Chavadipaleiyam 10. Chedi 78, 183. Chik Mulangi lake 2. Childers 191 fn., 270 fn. China 162, 163. Chitra, king 79. Chitrakūta bill 123. Chunda 244. Chrysostom 210. Cockburn J. 5, 6. Coimbatore 8. Colebrooke 245 fn. Cretan 16. Ctesias See under Ktesias. Cuddapah 2, 4. Cunningham 181, 183, 236. Cutch 11. Cuvier 19. Cyavana 43 fn., 63, Cyrus, king 163.

D

Daksināpatha 95.
Dandaka forest 120, 121.
Daniell C. 280 fu,
Dantapura city 180—81, 263.
Darada 210.
Darāda 210.
Dardisthān 210.
Darina 108.
Darina 74, 163, 209, 210, 261, 260.
Darás rite 141.

Dasaratha 120, 121, 122, 129, 133. David 70. Day, Dr. 69. Dayarama Sahni 11. D'Anville 73-Deccan, the 71, 99 fm, 104 fm, 105 fm, 124, Dedan 70. Deir-el-Bahari 17, 72. Delhi 27. Desaka city 181. Dayadatta 181. Devapi 156. Dhanapali 255. Dhanwantari 42. Dhenkenal 2. Digha Kārayana 185. Dionysia 227. Diescorides 114. Divodāsa 27, 78. Dīrgha Cārāyapa 185. D. R. Bhandarkar 76, 271. Dravida country 95, 181, 207 fa. Dravidians 163. Draadvati, river 81. Durgácarya 5%. Dutugaimuna 135. Dvärävati, port 262.

D

Eabani 17.
East End 185.
Edakal cave 5.
Edda 40.
Eggeling, Professor 166.
Egypt 9, 14, 17, 18, 19, 20, 21, 61, 71, 72, 74, 280.
Egyptians 20, 21, 69, 135.
Elam 17.
Elliot 10.
Elliot Smith 6.
Erythral 210.
Esubins 18, 19.

Esukari 237.
Estaja 39.
Ethiopia 18.
Ethiopians 19.
Euphrates 72, 73 fn., 77.
Ezion—Gaber 70.

F

Faizabad district 182.
Farakkabad District 182.
Fatopur Sikri 224.
Fansboll 256 fn.
Fawcett, F. 5 fn.
Forgusson 10.
Fick, Dr. 228, 257.
Finidis (-Phoenicia) 69.
Foulkes, T. Rev. 21, 71, 261.
Fraser 3.
Fraser, R. W. 61, 67.

Gambia, river 19.

G

Gandhakutira monastery 228, 234. Gangs 22, Ganges canal 10, Gautama Buddha 253. Gautama, law-giver 191, 192, 194, 195 fa., 196, 203 fp., 210, 244, 249 fn., 250, 250 fn., 267 fn. 274, 275, 275 fn., 276, 276 fn., 277, 277 fm. Gaya 264. Gandbara 48, 222, 261, 265. Gandharans 40. God rosia 74. Goldnor 26, 51, 58, 135, 156. Ghat mountains 164 Chatsila 2. Ghosa 63, Ghoşila 236. Gilead 20.

Girivraja 149 fa., 184.

Gambhirapattana, port 181, 262,

Godavari, river 105 fn. Godavari flake 1. Golden Forest 121. Golden Chersonese 261 fm. Goldstocker 119, 269. Gomal river 22. Gomati, river 22. Gonaddha 264. Gonda District 182. Gorskhpur 131. Gotama (-the Buddha) 253, Gowland 4 fp. Greece 9, 21, 61, 153. Greeks 199, 210. Griffith 42 fa., 43 fa., 57, 57 fa., 58 fa., 65, 66 fn., 68 fn., 93, 93 fn., 94 fn., 98 fn., 99 fn., 105 fn., 109, 112 fn., 139 fn. Gantar 2,

H

Hakra, river 11. Hall 73 fp. Halidda-vanysa, nigama 181. Hannmans 121, 122, 124, 148, 175. Hansa League 266. Harappa 11, 13, 16, 28, 73 fu. Hatasu 18, 72. Hattigama 234 Hang 34 fn., 141 fn. Havell, E. B. 145, 145 fo., 146, 183, Hazra, mountain 184. Hājipura 183. Hebrew 21, 71, Hears lake 2. Heeren 19 fn., 20, 71. Herodotas 179, 202, 209, 209 fn., 210, 210 fn., 214, 214 fn., 260, 262 fn., 289 fn. Hewitt 72, 163, Hibbert Lectures 17, 72, Hillebrandt 34 fn., 224 fn. Himalayan regions 113. Hindukush mountain 73.

Hippalus 74.

Hiram 70, 71.

Hirt, Hermann 22 fn.

Hinan Tsang 286.

Hoevale A. F. R. 180 fn., 182 fn., 183 fn.

Homes 229.

Hopkins 67, 85 fn., 157.

Horace 70 fn.

Humboldt 163 fn.

Hant E. H. 9, 9 fn., 18.

#### 1

Iarchus 19. Idamena 70. Illiad 229. Illusa 155. Indapattha city 181. Indian Ocean 162, 261. Indra 9, 10, 21, 23, 24, 26, 27, 30, 31, 33, 34, 26, 39, 40, 47, 48, 53, 55, 56, 57, 62, 69, 75, 77, 80, 82, 87, 113, 147, 153 fn., 159, 176, 179. Indrani 118 fn. Iroquois, the 61. Isa 19. Ishmelites 20. Isidas! 275. Isis 19.

#### J

Jacob 21.
Jahnus, the 156.
Janaka, 120, 121, 156, 166, 167, 173.
Janas ruti 89, 173.
Janas ruti 89, 173.
Janas ruti 82.
Janas ruti 82.
Janas ruti 836.
Java 152 fo.
Javala Pravahana 156.
Javala Satyakāma 156.
Jelosphant 71.
Jetavana 213.

Jetattura city 181.
Jevons 154, 154 fn.
Jivaka 192.
Joseph 20.
Jubbalpur 2.
Judea 163.
Julius Africanus 18.
Jumna, river 23, 181, 264.
Jyotistoma 141.

## K

Kabul, river 22. Kaikeyl 174. Kaegi 26, 44. Kaira 2. Kajangala, city 181. Kálábagh 19. Kalinga 18, 262, 279, 280 fa. Kamboja 112, 158, 265. Kammasadamma, city 183. Kanita 19. Kapilāvastu 181, 200, 264. Kapgallu 3, 5. Karayandra 74. Karnool 2, 4. Kathiawar 4, 11, 16. Kashmere 213, Kassites, the 13 fm., 146. Kasu 78. Kaurama, King 173. Kansalyā 32, 120, 121. Kansamyeya 82. Kansamyi 179, 236, Kautalya 271. Kautamvara 221, 265. Kantilya, 189, 208 fu., 270, 272 fn. Kayasha 155. Kākşīyan 78. Kali, river 182. Kali, slave-girl 255, 257. Kampila 81. Kampilya 81, 181,

Kāšī Bharadwāja 198, 211. Kāšī kingdom 95, 156, 181, 182, 187, 197

243, 230.

Kāsia 181. Kāsyapa Baddha 181, 255.

Katyāyana 141, 245.

Käveri, river 00 fn., 124.

Kāveripattana 181.

Keith, A. B. 1 fn.

Kekaya kingdom 122.

Kekayas, the 156.

Kennedy 163, 163 fn.

Kern 192 fn.

Khandagiri 236.

Khara 133.

Khorasan 13, 17.

Khujjuttarā 254.

Khullakalmāşa, city 183.

Kidorlmohan Son Gupta 92 fn.

Kişkindlıyâ kingdom 95.

Kitagiri, nigama 181.

Kikata (- Magadha) 22.

Knoz, H. 5.

Koli city 181,

Keliya country 181.

Koliya city 200.

Koliyans 200.

Kośala 8, 95, 105 fu., 185, 187, 192, 237, 243, 253, 255; 263, 279.

Kofam 181.

Kośamyi 181, 264.

Kosiyagotta 121, 192.

Krumn, (= Kurrum) river 22.

Ktesias 163, 164, 260, 260 fn.

Kubhā, river 22.

Kukundhaa, the 139.

Kakurabhas, the 139.

Kalli (fabrics) 16.

Kullega 183.

Kumbbakarpa 147,

Kundagama 183

Kundiya city 181.

Kurnool 8.

Kurram, river 22.

Kurunga 78.

Kurupanchala country 166.

Kurus, the 81.

Kuśs, prince 237.

Kusanagara 181.

Kusinagara 180, 181.

Kusinārā 181, 264.

Kuvers 147.

Kymore (cave paintings) 5.

### L

La Coperie 162.

Ladak 210.

Ladders, the 73.

Ladismit 142,

Lang-pa 162,

Lanka, city 103, 121, 146, 148, 162.

Larkana, district 11.

Lassen, C. 21, 21 fn. 71.

Leormant 18, 72.

Levant 69.

Liebchbavis, the 252, 257.

Limbi 16.

Lomapada, King 97.

London 115, 214 fn.

Longhurst 8 fn., 9 fn.

Ludwig 26, 51, 52 fn. 74.

Lydekker, R. 210.

## M

Mackay, E. 17 fn.

Macdonell 22 fn., 23 fn., 25 fn., 26, 29, 32,

33 fn., 34, 34 fn., 35 fn., 38, 36 fn., 44, 45 fn, 46 fn., 49, 49 fn., 54 fn., 50, 63 fn., 66

fn., 67, 68, 74 fn., 81, 84 fn., 91 fn., 88 91 fn., 125, 157, 164 fn., 166 fn., 174 fn.,

fn., 245 fn.

Madhurā city 181.

Madbyadeśa 81.

Madras, the 182.

Magadha S1, 95. 181, 184, 190, 191, 192, 238.

Mahanama 198, 253.

Mabāpāreva 147.

Mahidhara 107, 132.

Mahagovinda 184.

Mahārāştra 76.

Mahavira 76.

Mahandra 264.

Malabar Coast 72, 163.

Malnyachala bill 124.

Malaya Archipelago 162 fn.

Malladesa 180.

Mallika 253.

Manee, King 19.

Manthará 121.

Mann, King 191, 147.

Manu, the Great 28.

Manu as Adam of the race 84 fu., 89, 90.

Manu, law-giver 133, 248 fn. 252, 269.

Manu, the Indian Noah 181.

Margo Polo 164.

Margalla spur 184.

Marshall, Sir John 11 fn., 184 fn.

Maski 4.

Mathura city 181.

Matsya 95.

Manbhandara (rock carvings) 5-6.

Mauryan 145, 166.

Mauryas the 165, 166.

Max Duncker 72.

Max Muller 45, 57, 58, 94 fm., 119, 135 fm., 2 24 fm., 239 fm.

Maya 121, 147.

Madura 56 fn.

Magadhl, river 95.

Mahissati city 181, 264.

Marats 30, 48, 75.

Mc Crindle 70 fn., 163 fn., 202 fn., 210 fn., 262 fn., 280 fn.

Medbyatithi 78.

Medhajanana coromony 217.

Madiantish 21.

Mediterranean Sea 69.

Megasthenes 200, 210, 210 fn., 229, 280, 280 fn.

Mehi 16.

Mesha inscriptions 260.

Mesopotami 11, 14, 17.

Mihran, river 11.

Mirsapur 6.

Mithila city 182, 185.

Mitra (god) 24.

Mohenzo Daro 11, 12, 14, 15, 16, 17, 18, 28,

73 fn., 120.

Montgomery 11.

Morhana Pahar 2.

Mrs. Manning 21 fn., 34 fn.

Mrs. Rhys Davids 74 fn , 193, 360.

Muir 29, 49, 49 fn., 54 fn., 58.

Mojavant mountain 34.

Murrae ridge 184.

Mutibas 81.

Mysore 4.

N

N. Dutt 192 fn.

N. G. Mazumdar 11.

N. N. Ghosh 264 fn-

Nachiketas 121.

Naisadas SI.

Nandanakanana 147.

Nandana, city 183.

Nara canal, Eastern 11.

Navagvas 30.

Navavāstva 153 fu.

Nābhānediştha 94, 40.

Nagamunda 253.

Nagojibhatta 165.

Nalanda 264.

Nearchos 74, 210, 226 fu., 228.

Nebonidus 17, 72, 163;

Nebachadaeszar 17, 72, 163.

Nellore 2.
Nepal 214, 236.
Nerbuda find 1.
Nilab, river 19.
Nilgiri 4.
Nivedită, Sister 148 fn.
Nonh, Indian 161.
North America 61.
Nungarh 2.

0

Obermaier 1.
Oldenburg 51, 83, 231, 233 fn.
Oldham 2 fn.
Ophir 71,
Grissa 205, 236.
Oaborn 1 fn.
Oudh 81.
Oxus 73.

P

Paippaläda 107 fn. Paithan 182. Pajra 78. Palmyra 74. Pampa, river 95. Panchavati Forest 105 fa., 122. Pañchaśāradīya ceremony 110. Pafichanana Mitra 4 fn , 5, 5 fn., 6 fn. Paravrj 63. Parivakra city 82, Parjanya (god) 31, 79, 178, 199. Parikshit 178. Parsu 78. Partabgunj 2. Pasenadi, King 185, 237, 253. Patițthâna city 182, 264. Patna Museum 7. Pākasthāman Kaurayān 78. Panchala 81, 82, 156, 181, 279, Papdakulis 10.

Papini 114 fn., 167, 202, 213, 216, 221, 228, 236, 248, 251, 259, 265, 268, 268 fn., 269, 269 fn., 274, Paruani, country 40, 48, Pāṭaligrāma 184. Pāţaliputra 184, 264, l'ațaliputtaka 182. Percy Brown 5 fn. Persia 17, 73, 163. Persian Gulf 69, 70, 72, 73, 260, 261. Panis, the 74, 79, Persians 114, 135, 200 fn , 210. Philostratus 18, 19. Phoenicia 69. Phœnicians 69, 70. Pijavana 78. Pipra 26. Piprawah Stupa 214, 218, 229. Pischal 26, 65. Pliny 114, 135, 200 fn., 210, Posocke 19 fn., 20. Polasapura 182, 187, 225. Potali city in Kasi kingdom 182. Potali city in Asmaka kingdom 182. Potana city 182. Prajāpati 114, 125. Prasasta 147. Prastoka 78. Prapanatha, Dr. 271. Prakrta dialects 269. Prthusravas 79. Ptolemy 162 fn. Pulindas 81. Pun 72. Punna 263. Punna 258. Pundras 81. Punt 18. Purpa 259. Purukuten 153, Purpamasi rite 141. Püşhan (god) 35, 36, 40, 48, 112.

R

R. Syama Sastri 268 fn. Ragozin 49, 49 fn., 67. Raigath 4, 5, 5 fn. Raikka 89, 129, 173. Rajjumālā 255. Ramapaka. city 182. Ramesa Dutt 28 fn. Ramses 19.

Rapson 23 fn., 25 fn., 38 fn., 67 fn., 68 fn. 81, 87 fm., 193 fm., 248 fm., 266 fm.

Rassam 17, 72, 163. Rathavimocaniya oblations 165. Raurava (= Roruka), city 262. Rawalpindi 264. Rawlinson 73 fn., 209 fn., 210 fn., 280 fn. Rajagaha 182. Rājagiha 182. Råjagtha 179, 180, 182, 186, 191, 192, 236, 256, 263.

Rajasuya 110, 165, 174. Rakhāladāsa Banerji 11.

Rima 19, 95, 105 fa., 120, 121, 122, 124, 125, 133, 142, 159, 174, 178.

Rāmakṛṣṇa, commentator 223 fn.

Rapti, river 182.

Rāvaņa 120, 121, 122, 124, 130, 140, 143, 170, 171, 175.

Rea 7, 8 fn.

Red Sea 69, 74, 162,

Reinaud 162 fn.

Rhinocolura 70.

Rhys Davids 166, 182 fn., 183 fn., 188, 191 fm., 197 fm., 231, 233 fm., 234 fm., 236 fn., 237 fn., 253, 256 fn., 262, 262fn., 263, 265 fm.

Ribhus 24.

Richard, F. J. J fn.

Ridgeway, Prof. 9. Rijrāšva 24, 63.

Robertson 70 fn.

Rohini, river 181, 200. Roman 66, 254. Rome 21, 153, Roruka, city 182, 262. Roth, Von 40, 51, 52, 55, 128, 156, 166. Royle, Dr. 20, 70. Ruanwelle Dagobā 135. Rudra (god) 36, 75, 76, 84. Rusamas 78, 173.

S. Krishnaswami Iyenger 73. Sabaras 81. Sabeans 72. Sadāmatta city 182. Sagula, city 182. Sahajāti 264. Sahara, desert 19. Sahri-Sokhta 16. Sakula 187. Salt Range 34. Samarra 17. Sambalpur 2. Sambara, an asura 26, 27. Samkissa city 182, Samkiás 182 Sangai, river 2. Santal Parganas 205. Saptagu, a sage 55. Sarkarā, nigama 182. Saraju, river 22, 182. Saraswati, river 22, 38, 81. Sarsswati 27. Sasarpari SO. Satvats 81. Saunaka, a sage 177 fn. Sautramāņi, rite 141. Savitar, (god) 161. Saxony 122.

Sayce, Dr. 17, 72.

Sagala, city 182, 264.

Sākala (= Sialkot) 182.

Sakete, city 179, 182, 264. Sakyas 200, 236, 253. Salavati 257. Salatura, city 182, Salindiya, villago 191. Samkasya, city 182. Sanchi Topes 233 fn., Santano 156. Sati 944. Sayana 28 fn., 33, 46, 56, 79, 84, 89, 89 fn., 90, 100, 114, 128, 165, 166, Schiern, Dr. 210. Schoff 70 fm., 74 fm. Schrader, Otto 22 fn., 24, 45, 49, 49 fn., 50. 130, 131. Scotland 10. Senegal, river 19. Setavya, city 182. Seth Mahetha 182.

Shalmanesar 163.

Sheftovitch 146.

Sielkot 182.

Sidon 69, 74.

Simrock 98 fn.

Simhavāhu, King 187.

Simbala, lion-prince 261,

Sind 11, 12, 48, 66, 95, 112, 120, 158, 264, 265.

Sindon 11, 120.

Sindha, river 38.

Singapper 4.

Singhbhum 5.

Sirim4 257,

Sistan 14, 17.

Siva 20.

Sivi, country 180, 181, 220, 265,

Sita 105, 120, 122, 123, 124, 161, 175,

Siti (goddess of Furrow) 199.

Skylaz 74, 261.

Smith, Elliot 6,

Smith, V. A. 1 fn., 7, 7 fn., 61, 184 fn. 236, 261 to.

Soma, King 118.

Sourdsten 95.

Souvira, 95.

Sovira kingdom 183, 264.

Sravasti, city 179, 180, 182, 185, 186, 192, 213, 237, 243, 244, 251, 250, 263, 264, 265, 267.

Srukta, an armen 27,

St. Paul 236.

Stein, Acriel Sir 11, 14.

Stevenson 34, 141 fu.

Strabo 70 fn., 199 fn., 200 fn., 163, 212 fn., 214 fn.

Subimal Sarkar 51 fn., 52, 57 fu., 119, 127 fn., 128.

Sudas 78, 156.

Sudarfana hill 124.

Suez 14.

Speriva 161.

Suidoitiana 135.

Sumatra 162 fa.

Sumer 13, 17, 72, 73, 260.

Sumsumara city 182-83. Sumva kingdom 181.

Sunshiepha 83.

Sandas 19.

Supere, city 260.

Suparaga, a pilot 266.

Suppăraks, city 183, 260, 262, 263.

Surasenas, the 181,

Surundhana, city 182.

Susa 14, 17,

Savarpabhūmi (= Barma) 261, 261 fn , 264.

Suvarpadwips 162, 162 fn.

Sovarparekbi, river 2.

Savästa ( - Swat), river 22.

Strye 39.

Suryarikā (= Sahara desert) 17.

Syanadratha 78.

Syanaya 78.

Svativati 183.

Swat, river 22,

Sylvain Levi, 84 fn. Syncellus 19. Syria 73, 260.

T

Takkahasila 183. Talchir 2. Tan ba Sunda 19. Tanjore M fn. Tarabis 71. Taxila 60, 82, 183, 194, 199, 239, 264. Thmralipti 264. Temraparul, river 6, 16. Tilmraparpidwipa ( - Ceylon) 261, 261 fn. Telavãha river 180. Tennet 135 In. Tepel, Musyan 17. Thebas 17. Theobald 10. Thore 40. Tigris, river 72, 73 In. Tilak, B. G. 91 fn. Tinnevelly cemetries 6, 8. Tinnevelly 4, 16, 18. Tirbut 81. Tirindra 78. Tirthikas 186. Tobit 106. Touche La 4 fn. Trasadasya 78, 153. Trisanku 133. Trita 30. Tagra 68. Turveses 153 fo. Twastr 62. Tvastu 141. Tylos, isle 70.

U

U. N. Ghosal 86, 88 fn. U. S. A. 155.

Tyre 74.

Udayagiri 236.
Udayana, King 181, 236.
Udicca Brahmins 235.
Ugrajit 177.
Ugrampasya 177.
Ujjain 183, 187, 264.
Ukkattha, city 183.
Ukthya, rite 141.
Ur 13, 17, 72, 163.
Usinaras, tho 81.
Uttarakośala 182.
Uttarakurus 81.
Uttara Madras 81.
Uttara Madras 81.
Uttara Pańchála 248, 265.

Vaidarva 82.

Vajjis, the 184.

V

Vala (Asura chief) 69. Valarimapur 189. Vanga 95, 187. Vanijagama 183, 257. Varapavati, river 158. Varups (god) 24, 56, 67, 79. Vasae, the 81. Vasistha 68, 122, 191, 191 fp., 192, 193, 193 fm., 194, 195, 196, 226, 229, 249, 249 fm., 250, 250 fm., 267 fm., 271 fm., 274, 275, 276, 270 fn., 277, 277 fn., Vateya, country 236. Vajapaya, ceremony 110, 141. Valmiki 106 fn., 156. Vall 129. Varanasi 180. Vasavakhattiya 253. Vāyu (god) 34, 112. Vodisa 264. Vendidad 23. Vesali 183, 185, 192, 244, 264, Vibhigapa 147, Videha 81, 156, 166,

Vidura 258. Vimala 257. Vincent, Dr. 20. Vindhyan regions 113, 158. Virgil 70 fn. Visna 80. Visakha 182, 217. Vispala 63. Viswantara, King 156. Viswantara, prince 274 fn. Viswamitra 61, 64, 82, 156. Viswakarman 147. Viśwarupa, a sage 141. Vivinda 78. Vratyas 130, 137, 138, 165, 226, Vrisahlgir 94. Vitra, asura chief 30, 69, 96, 176, Vitras 26.

#### W

Walker 247.

Walker 247.

Wasiristhan 14.

Weber 58, 98 fm., 150 fm., 172, 173 fm.

West End 185.

Wilkinsen 21.

Wilson 27, 27 fm., 28 fm., 65, 77, 79, 89 fm., 210.

Winekler, Dr. 163, Woolney 13, 17. Wynaad 4, 5.

X

Xerxes, King 214.

Y

Yama 119, 128, 174.

Yamanā 23.

Yaśodharā 181.

Yavadwipa 162, 162 fm.

Yādava prince 66.

Yādavas, the 78, 153 fm.

Yādavaprakāša 183 fm.

Yājūabalkya 111, 170.

Yāska 89 fm., 156.

Yeats, J. 162.

Yemen 18, 72.

Yimir, giant 61.


Yudhājit, Kekayarāja 120, 121.

Z

Zagros Ranga 73. Ziggarata 230. Zimmer 25, 25 fn., 53, 58, 74, 91 fn., 127, 142 fn., 150 fn., 227 fn.



CATALOGUED.





D.G.A. 80.

# CENTRAL ARCHAEOLOGICAL LIBRARY NEW DELHI

Issue Record

Catalogue No. 330.934/Das - 34731.

Author-Das, S.R.

Economic History of . Title-Ancient India

Borrower No.

Date of Issue Date of Return

A book that to

ARCHAEOLOGICAL

GOVT. OF INDIA

Department of Archaeology

DELHI.

Please help us to keep the book clean and moving.

5. 8. 148. N. DELHI.